

Appendix 1: Recommended IPI Provisions in Response to Submitter Evidence and Matters Raised During the Hearing

Upper Hutt City Council

Intensification Planning Instrument (IPI) for the Upper Hutt City District Plan

9 June 2023

Contents

HOW TO READ THIS DOCUMENT	5
PROPOSED AMENDMENTS TO THE DISTRICT PLAN	6
PART 1 – INTRODUCTION AND GENERAL PROVISIONS	6
1 INTRODUCTION	6
1.1 Contents	6
2 HOW THE PLAN WORKS	7
2.2 General Approach.....	7
3 INTERPRETATION	8
3.1 Definitions	8
3.2 Abbreviations	19
4.1 National Policy Statements.....	19
PART 2 - DISTRICT-WIDE MATTERS.....	20
STRATEGIC DIRECTION	20
UFD - Urban Form and Development	20
ENERGY, INFRASTRUCTURE AND TRANSPORT	27
NU - Network Utilities	27
REG – Renewable Energy Generation.....	34
TP - Transport and Parking	36
HAZARDS AND RISKS	40
NH – Natural Hazards	40
Natural Environment Values.....	41
ECO - Ecosystems and Indigenous Biodiversity	41
NFL – Natural Features and Landscapes.....	43
SUBDIVISION	43

SUB-GEN – General Subdivision Provisions that Apply in All Zones.....	43
SUB-RES – Subdivision in Residential Zones	46
SUB-HRZ – Subdivision in the High Density Residential Zone	69
SUB-CMU – Subdivision in Commercial and Mixed Use Zones	86
SUB-COM – Subdivision in Industrial Zones.....	96
SUB-SAZ - Subdivision in the Special Activity Zone	108
SUB-DEV1 - Subdivision in Development Area 1	110
DFC – Development Financial Contributions	110
GENERAL DISTRICT WIDE MATTERS	117
AIR - Air	117
EW - Earthworks.....	119
LIGHT - Light	121
PK – Papakāinga	123
PK – Papakāinga amendments – multi-zone	131
NOISE - Noise	132
SIGN - Signs	135
TEMP – Temporary Activities	139
PART 3 – AREA SPECIFIC MATTERS	141
RESIDENTIAL ZONES	141
GRZ – General Residential Zone	141
GRZ – Precinct 1 - Indigenous Biodiversity Precinct	166
HRZ – High Density Residential Zone	179
Precinct 2 – St Patrick’s Estate Precinct	201
RURAL ZONES	203
GRUZ – General Rural Zone	203

RLZ – Rural Lifestyle Zone.....	203
COMMERCIAL AND MIXED USE ZONES.....	204
COMZ – Commercial Zone.....	204
NCZ – Neighbourhood Centre Zone.....	221
LCZ – Local Centre Zone	246
MUZ – Mixed Use Zone	274
TCZ – Town Centre Zone	307
CCZ – City Centre Zone	335
Outdoor Living Space.....	360
INDUSTRIAL ZONES	373
GIZ – General Industrial Zone	373
OPEN SPACE AND RECREATION ZONES	377
OSZ – Open Space Zone.....	377
SPECIAL PURPOSE ZONES	378
SAZ – Special Activity Zone	378
DEVELOPMENT AREAS.....	388
Development Area 1 - Wallaceville Structure Plan Development Area	388
PART 4 – APPENDICES AND MAPS.....	395
APPENDICES.....	395
Appendix 1 – Medium and High Density Design Guide	395
Appendix 2 – City Centre Zone Design Guide	437
Appendix 3 – Precinct 2 – St Patrick’s Estate Precinct Structure Plan	458

HOW TO READ THIS DOCUMENT

The text in this section is for explanatory purposes and does not form part of the Intensification Planning Instrument (IPI).

The following formatting conventions are used to identify proposed changes to the District Plan:

1. Text that is black and struck through (~~example~~) was notified in the IPI as text proposed to be deleted from the District Plan.
2. Text that is black and underlined (example) was notified in the IPI as text proposed to be inserted into the District Plan.
3. Text that is shown in red underlined or struck through (example1, ~~example2~~) identifies recommended amendments to the IPI in response to decisions requested by submitters. For each recommended amendment the relevant submission point is identified as a comment.
4. Text that is shown in blue underlined or struck through (example1, ~~example2~~) identifies recommended amendments to the IPI in response to matters raised during the hearing.
5. Text that is required by Section 80H of the RMA to identify the provisions that incorporate, or are replaced by, the Medium Density Residential Standards (MDRS) is still present within relevant provisions. This text does not form part of the IPI and will be removed as provided for by Section 80H(2)(b) of the RMA once the IPI becomes operative.
6. Text that is for explanatory purposes that does not form part of the IPI is preceded by the following or similar wording: *This section/paragraph is explanatory only and does not form part of the IPI.*

PROPOSED AMENDMENTS TO THE DISTRICT PLAN

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
PART 1 – INTRODUCTION AND GENERAL PROVISIONS			
1 INTRODUCTION			
1.1 Contents			
1	1.1 Contents	Add new chapters	<p>PART 1 – INTRODUCTION AND GENERAL PROVISIONS</p> <p>3 Interpretation</p> <p>3.1 Definitions</p> <p>3.2 Abbreviations</p> <p>PART 2 – DISTRICT-WIDE MATTERS</p> <p>Subdivision</p> <p>SUB-GEN – General Subdivision Provisions that Apply in All Zones</p> <p>SUB-RES – Subdivision in <u>the General Residential Zones</u></p> <p><u>SUB-HRZ – Subdivision in the High Density Residential Zone</u></p> <p>SUB-RUR – Subdivision in Rural Zones</p> <p><u>SUB-CMU – Subdivision in Commercial and Mixed Use Zones</u></p> <p>SUB-RES – Subdivision in Commercial <u>Industrial</u> Zones</p> <p>General District-Wide Matters</p> <p><u>PK - Papakāinga</u></p> <p>PART 3 – AREA SPECIFIC MATTERS</p> <p>Residential Zones</p> <p>GRZ – General Residential Zone</p> <p>Precinct 1 – Residential Centres Precinct <u>Indigenous Biodiversity Precinct</u></p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>Precinct 2 – Residential Hill and Residential Conservation Precinct</p> <p>HRZ – High Density Residential Zone</p> <p>Precinct 2 – St Patrick's Estate Precinct</p> <p>Commercial and Mixed Use Zones</p> <p>COMZ – Commercial Zone</p> <p>NCZ - Neighbourhood Centre Zone</p> <p>LCZ – Local Centre Zone</p> <p>MUZ - Mixed Use Zone</p> <ul style="list-style-type: none"> Precinct 2 – St Patrick's Estate Precinct <p>TCZ – Town Centre Zone</p> <p>CCZ - City Centre Zone</p> <p>PART 4 – APPENDICES AND MAPS</p> <p>Appendix 1 – Design Guide for the Residential Centres Precinct <u>Medium and High Density Design Guide</u></p> <p>Appendix 2 – City Centre Design Guide</p> <p>Appendix 3 – Precinct 2 – St Patrick's Estate Precinct Structure Plan</p>
2 HOW THE PLAN WORKS			
2.2 General Approach			
2	2.2 General Approach	Add new zones	<p>Zones</p> <p>The technique of zoning is used as the principle method for managing the effects of activities to enable sustainable management of resources. Zoning recognises the different environments within the City and the effects that different activities have on those environments.</p> <p>The District Plan contains the following core zones:</p> <ul style="list-style-type: none"> • General Residential Zone • High Density Residential Zone • General Rural Zone

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<ul style="list-style-type: none"> • Rural Production Zone • Rural Lifestyle Zone • Commercial Business Zone • <u>Neighbourhood Centre Zone</u> • <u>Local Centre Zone</u> • <u>Mixed Use Zone</u> • <u>Town Centre Zone</u> • City Centre Zone • General Industrial Zone • Open Space Zone • Special Activities Zone
	2.2 General Approach	Delete Section 2.4.7	<p>2.4.7 Specific information accompanying applications for a Comprehensive Residential Development</p> <p>An application under the Comprehensive Residential Development provisions of the Plan must include an assessment of the proposed development against the Design Guide for the Residential Centres Precinct. The design guide is detailed within Appendix 1.</p>
	2.2 General Approach	Delete Section 2.4.8	<p>2.4.8 Specific information accompanying applications for subdivision or development within a the Residential Centres Precinct that is not a Comprehensive Residential Development where any allotment has a minimum net site area of less than 400m²</p> <p>Where the proposed development includes an allotment under a minimum net site area of less than 400m², an assessment of the proposed development must be provided using the section on small site design and development contained in the Design Guide for the Residential Centres Precinct. The design guide is detailed within Appendix 1.</p>

3 INTERPRETATION

3.1 Definitions

3.1 Definitions	Replace definition for Accessory building	<p>Accessory building means a detached building, the use of which is ancillary to the use of any building, buildings or activity that is or could be lawfully established on the same site but does not include any minor residential unit.</p> <p>NPS a building which is accessory to the main use of the site. On residential sites, this includes garages, carports, workshops, garden sheds, swimming pools, spa pools and glasshouses that are not used for commercial purposes other than home business. It also includes walls, fences and retaining walls defined as buildings.</p>
-----------------	---	--

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			For the purposes of the Southern Hills Overlay Area, accessory buildings do not include any building in the General Residential Zone or Residential Hill Precinct which exceeds 36m ² in floor area and/or 3 metres in height. (See definition of “ building ”)
	3.1 Definitions	Add definition for Ancestral Land	Ancestral Land Means land that belonged to tipuna/tupuna .
	3.1 Definitions	Add definition for Commercial and Mixed Use Zones	<p>Commercial and Mixed Use Zones</p> <p>Means the following:</p> <ul style="list-style-type: none"> • City Centre Zone • Town Centre Zone • Local Centre Zone • Neighbourhood Centre Zone • Mixed Use Zone
	3.1 Definitions	Add definition for Commercial Service Activity	<p>Commercial Service Activity</p> <p>means any activity that provides commercial services rather than goods. It includes:</p> <ul style="list-style-type: none"> (a) bank; (b) commercial indoor fitness centres/gymnasiums/play areas; (c) professional and financial services; (d) commercial sexual services; (e) dry cleaner; (f) funeral director premises; (g) beauty and appearance industries; (h) real estate agent; (i) show home; (j) travel agent; and (k) veterinary clinic.

Commented [MM1]: Consequential amendment to provide definition for a term used in the IPI. Amendments recommended pursuant to clause 99(2), Part 6 of Schedule 1 of the RMA.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	3.1 Definitions	Delete definition for Comprehensive residential development	<p>Comprehensive residential development a residential development of at least three residential units, on a site within a the Residential Centres Precinct, at a density greater than the minimum net site area requirement for the General Residential Zone.</p> <p>Note: A Comprehensive Residential Development may include an existing residential unit.</p>
	3.1 Definitions	Add definition for Drive-through activity	<p>Drive-through activity means any activity with a substantial focus on drive-through transactions, including service stations and drive-in or drive-through retail and services outlets and restaurants.</p>
	3.1 Definitions	Add definition for Drive-through restaurant	<p>Drive-through restaurant means any land or building on or in which food and beverages are prepared, served and sold to the public inclusive of a facility designed to serve customers in their vehicles, for the consumption on or off the premises and may include an ancillary cafe or playground area.</p>
	3.1 Definitions	Add definition for Driveway	<p>Driveway means an access way designed and constructed for use by motor vehicles, pedestrians or cyclists.</p>
	3.1 Definitions	Add definition for Dwelling	<p>Dwelling means residential unit.</p>
	3.1 Definitions	Add definition for Emergency service facility	<p>Emergency service facility means places occupied by organisations that respond to and deal with accidents, emergencies, or urgent problems such as fire, illness, or crime.</p> <p><u>Includes:</u></p> <ul style="list-style-type: none"> (a) <u>police, fire and ambulance stations;</u> (b) <u>surf lifesaving activities;</u> (c) <u>administration related to emergency services;</u> (d) <u>storage and maintenance of emergency vehicles and equipment; and</u> (e) <u>personnel training.</u> <p><u>Excludes:</u></p> <ul style="list-style-type: none"> (f) <u>healthcare activities;</u> (g) <u>hospitals; and</u>


IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			(h) <u>private security companies.</u>
	3.1 Definitions	Add definition for Entrance strip	<u>Entrance strip</u> has the same meaning as <u>driveway</u> for the purposes of the <u>MDRS height in relation to boundary standard.</u>
	3.1 Definitions	Add definition for Entertainment and hospitality activity	<u>Entertainment and hospitality activity</u> means any <u>activity</u> where the primary business is providing entertainment or hospitality.
	3.1 Definitions	Add definition for Entertainment facility	<u>Entertainment facility</u> means any <u>commercial</u> facility used for leisure, entertainment or hospitality. It includes: <ul style="list-style-type: none"> (a) <u>cinemas;</u> (b) <u>theatres;</u> (c) <u>concert venues;</u> (d) <u>conference centres; and</u> (e) <u>private function facilities.</u>
	3.1 Definitions	Add definition for Food and beverage activity	<u>Food and beverage activity</u> means any <u>activity</u> where the primary business is selling food or beverages for immediate consumption on or off-site. <p>It includes:</p> <ul style="list-style-type: none"> (a) <u>restaurants;</u> (b) <u>cafes;</u> (c) <u>bars;</u> (d) <u>taverns; and</u> (e) <u>take-away food bars</u> <p>It excludes:</p> <ul style="list-style-type: none"> (f) <u>retail activities;</u> (g) <u>supermarkets; and</u>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			(h) <u>drive-through restaurants.</u>
3.1	Definitions	Insert definition for General Title Land (in relation to Papakāinga)	General Title Land (In Relation to Papakāinga) means <u>land</u> that is owned by Māori but which is not held under Te Ture Whenua Māori Act 1993.
3.1	Definitions	Delete definition for Gang fortification	Gang fortification any <u>building</u> or <u>site</u> which is used by groups for accommodation as a base or headquarters, and which is typified by high fencing and other fortification.
3.1	Definitions	Add definition for General Residential Zone	General Residential Zone means the areas identified as General Residential Zone on the Planning Maps.
3.1	Definitions	Add definition for Healthcare activity	Healthcare activity means the use of <u>land</u> and/or <u>buildings</u> for providing physical or mental health or welfare services, including: <ul style="list-style-type: none"> (a) <u>medical practitioners;</u> (b) <u>dentists and dental technicians;</u> (c) <u>opticians;</u> (d) <u>physiotherapists;</u> (e) <u>medical social workers and counsellors;</u> (f) <u>midwives;</u> (g) <u>paramedical practitioners;</u> (h) <u>alternative therapists;</u> (i) <u>providers of health and wellbeing services;</u> (j) <u>diagnostic laboratories; and</u> (k) <u>ancillary office activities;</u> <u>but excluding hospitals.</u>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	3.1 Definitions	Add definition for High Density Residential Zone	High Density Residential Zone means the areas identified as High Density Residential Zone on the Planning Maps.
	3.1 Definitions	Add definition for Hydraulic Neutrality	Hydraulic neutrality means managing stormwater runoff from all new subdivision and development through either on-site disposal or storage, so that stormwater is released from the site at a rate that does not exceed the pre-development peak stormwater runoff for the 10% and 1% rainfall Annual Exceedance Probability event.
	3.1 Definitions	Delete existing definition for Hydraulic Neutrality	Hydraulic Neutrality the principle of managing stormwater runoff from all new allotment or development areas through disposal or stored on site and released at a rate that does not exceed the peak stormwater runoff when compared to the pre-development or subdivision situation.
	3.1 Definitions	Add definition for Indigenous Biodiversity Precinct	Indigenous Biodiversity Precinct means the areas identified on the Maps as Precinct 1 - Indigenous Biodiversity Precinct .
	3.1 Definitions	Add definition for Iwi Authority	Iwi Authority means the same as in the Resource Management Act 1991.
	3.1 Definitions	Add definition for Large format retail activity	Large format retail means any individual retail activity with a store or individual tenancy exceeding 500m ² gross floor area .
	3.1 Definitions	Add definition for Light industrial activity	Light industrial activity means industrial activity that does not involve the use of heavy machinery and does not generate objectionable odour, dust or noise .
	3.1 Definitions	Add definition for Medium Density Residential Standards	Medium Density Residential Standards (MDRS) means the requirements, conditions and permissions set out in Schedule 3A of the Resource Management Act 1991.
	3.1 Definitions	Amend definition for Minor Structures to address an unanticipated	Minor structures means any structure of less than 5m ² in area with a height of less than 1.2m. <ul style="list-style-type: none"> Any fence or wall with a height of less than 2m. Any retaining wall with a height of less than 1.5m above the finished ground level. Any tank or pool, and any structural support:

Commented [MM2]: S58.14 - Kāinga Ora: Homes and Communities.

Commented [MM3]: Consequential amendment. Clause 99, Schedule 1 RMA.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
		consequence of giving effect to MDRS.	<ul style="list-style-type: none"> Which has a capacity of less than 25,000 litres and is supported directly by the ground. Which has a capacity of less than 2,000 litres and is supported at a height of less than 2.0 metres from the base of its structure. Which has a capacity of less than 500 litres and is supported at a height of less than 4.0 metres from the base of its supporting structure. Any non-enclosed and uncovered decks with a height of 1.0m or less above ground level.
	3.1 Definitions	Add definition for Nationally Significant Infrastructure	<p>Nationally Significant Infrastructure means the same as in the National Policy Statement on Urban Development 2020.</p>
	3.1 Definitions	Replace definition for Net site area	<p>Net site area <u>NPS</u></p> <p>the area of a site excluding:</p> <ul style="list-style-type: none"> Any access allotment, driveway or right of way in the case of a rear allotment. Any common area, access allotment, driveway or right of way where there is more than one residential unit on a site.  <p>means the total area of the site, but excludes:</p> <ol style="list-style-type: none"> any part of the site that provides legal access to another site; any part of a rear site that provides legal access to that site; any part of the site subject to a designation that may be taken or acquired under the Public Works Act 1981.

Commented [MM4]: S53.2 and S53.9 - New Zealand Defence Force.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	3.1 Definitions	Add definition for Office activity	Office activity means an activity conducted within a building and focusing on business, government, professional or financial services and includes the personal service elements of these activities .
	3.1 Definitions	Add definition for Papakāinga	Papakāinga means housing and ancillary activities (including social, cultural, educational, recreational, and commercial activities) for tangata whenua on their ancestral land .
	3.1 Definitions	Add definition for Passenger Car Unit (PCU)	Passenger Car Unit (PCU) means the conversion of different types of vehicles into their equivalent passenger cars in terms of operating characteristics. A car or other light vehicle is 1 PCU, while a heavy vehicle or bus is 2.0 PCU. A car entering and leaving a site generates 2 PCU, while a heavy vehicle or bus generates 4 PCU.
	3.1 Definitions	Add definition for Public Street	Public Street has the same meaning as road with respect to the Outlook Space (per residential unit standard).
	3.1 Definitions	Add definition for Qualifying matter	Qualifying matter means a matter referred to in section 77I or 77O of the RMA.
	3.1 Definitions	Add definition for Qualifying matter area	Qualifying matter area Means a qualifying matter listed below: <ul style="list-style-type: none"> (a) flood hazard extents identified on the Planning Maps comprising the: <ul style="list-style-type: none"> (i) River Corridor; (ii) Stream Corridor; (iii) Overflow Path; and (iv) Erosion Hazard Area; (b) Ponding areas; (c) Pinehaven Flood Hazard Extent; (d) Mangaroa Flood Hazard Extent; (e) 1% (1 in 100 year) flood extent of the Hutt River; (f) Fault band identified on the Planning Maps; (g) Significant Heritage Features listed in Schedule HH-SCHED1;

Commented [MM5]: Consequential on S69.1 - RACE Inc.

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<ul style="list-style-type: none"> (h) <u>Notable Trees listed in TREE-SCHED1;</u> (i) <u>Urban Tree Groups listed in UTG-SCHED1;</u> (j) <u>Indigenous vegetation</u> that is not on an <u>Urban Environment Allotment;</u> (k) <u>Rare or Threatened Indigenous Vegetation</u> and Fauna in ECO-SCHED-2 where not on an <u>Urban Environment Allotment;</u> (l) <u>The areas within 20 metres of the bank of any waterbody with an average width of 3 metres or more;</u> (m) <u>The widths specified for esplanade reserves and esplanade strips in SUB-GEN-S1;</u> (n) <u>The areas within 20 metres of a high voltage (110kV or greater) electricity transmission line;</u> (o) <u>The areas within 12-32m of a high voltage (110kV or greater) electricity transmission line;</u> (p) <u>The Open Space Zone as identified on the Planning Maps;</u> (q) <u>The Natural Open Space Zone as identified on the Planning Maps;</u> (r) <u>The Sport and Active Recreation Zone as identified on the Planning Maps.</u> 		
	3.1 Definitions	Add definition for Relevant residential zone	<table border="1"> <tr> <td><u>Relevant Residential Zone</u></td> <td>means the General Residential Zone and the High Density Residential Zone.</td> </tr> </table>	<u>Relevant Residential Zone</u>	means the General Residential Zone and the High Density Residential Zone.
<u>Relevant Residential Zone</u>	means the General Residential Zone and the High Density Residential Zone.				
	3.1 Definitions	Delete definition for Residential Centres Precinct	<table border="1"> <tr> <td><u>Residential Centres Precinct</u></td> <td>an area identified on the planning maps as Residential Centres Precinct.</td> </tr> </table>	<u>Residential Centres Precinct</u>	an area identified on the planning maps as Residential Centres Precinct.
<u>Residential Centres Precinct</u>	an area identified on the planning maps as Residential Centres Precinct.				
	3.1 Definitions	Replace definition for Retail	<table border="1"> <tr> <td><u>Retail</u></td> <td>refers to any land, building or part of a building means activities where goods, merchandise, equipment or services are sold, displayed or offered for sale or direct hire to the public. The definition does not include the sale and hire of motor vehicles, boats, caravans, motor homes and accessories and motor vehicle spare parts, home business, restaurants or service stations.</td> </tr> </table>	<u>Retail</u>	refers to any land, building or part of a building means activities where goods, merchandise, equipment or services are sold, displayed or offered for sale or direct hire to the public. The definition does not include the sale and hire of motor vehicles, boats, caravans, motor homes and accessories and motor vehicle spare parts, home business, restaurants or service stations.
<u>Retail</u>	refers to any land, building or part of a building means activities where goods, merchandise, equipment or services are sold, displayed or offered for sale or direct hire to the public. The definition does not include the sale and hire of motor vehicles, boats, caravans, motor homes and accessories and motor vehicle spare parts, home business, restaurants or service stations.				
	3.1 Definitions	Add definition for Reverse sensitivity	<table border="1"> <tr> <td><u>Reverse sensitivity</u></td> <td>means the vulnerability of an existing lawfully established activity to other activities in the vicinity which are sensitive to adverse environmental effects that may be generated by such existing activity, thereby creating the potential for the operation of such existing activity to be constrained.</td> </tr> </table>	<u>Reverse sensitivity</u>	means the vulnerability of an existing lawfully established activity to other activities in the vicinity which are sensitive to adverse environmental effects that may be generated by such existing activity , thereby creating the potential for the operation of such existing activity to be constrained.
<u>Reverse sensitivity</u>	means the vulnerability of an existing lawfully established activity to other activities in the vicinity which are sensitive to adverse environmental effects that may be generated by such existing activity , thereby creating the potential for the operation of such existing activity to be constrained.				

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	3.1 Definitions	Replace the definition for Service station	<p>Service station means a vehicle orientated facility, any land and buildings where the principal predominant activity is the refuelling of motorised vehicles and retail sale of products and services associated with fuels and/or motor vehicles, fuels (including petrol, LPG, CNG and diesel) and including lubricating oils, kerosene, LPG, spare parts, carwash facilities. It may also include as ancillary activities: such as car wash facilities, trailer hire and the sale of food and beverage.</p> <ul style="list-style-type: none"> • The mechanical repair and servicing of motor vehicles (other than panel beating, trimming or spray painting, heavy engineering such as engine restoring and crankshaft grinding). • The sale or hire of any goods, including the preparation and sale of food and beverages. • Car wash facilities. • The hire of light trailers and motor vehicles.
	3.1 Definitions	Add definition for St Patrick's Estate Precinct	<p>St Patrick's Estate Precinct means the area identified as St Patrick's Estate Precinct on the Planning Maps.</p>
	3.1 Definitions	Add definition for Supermarket	<p>Supermarket means a retail shop selling a wide range of foodstuffs and non-food grocery items for consumption and use off-site, where foodstuffs comprise more than 90 percent of the total retail floor space. Foodstuffs include:</p> <ul style="list-style-type: none"> • <u>fresh produce, meat, fish and dairy; and</u> • <u>chilled, frozen, packaged, canned and bottled foodstuffs and beverages.</u> <p>Non-food grocery items include:</p> <ul style="list-style-type: none"> • <u>cooking, cleaning and washing products;</u> • <u>kitchenwares; and</u> • <u>toiletries.</u>
	3.1 Definitions	Add definition for Tikanga/Tikanga Māori	<p>Tikanga/Tikanga Māori means Māori customary values and practices.</p>

Commented [MM6]: S33.4 - Fuel Companies; and S32.4 - Z Energy Limited.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	3.1 Definitions	Add definition for Tino Rangatiratanga	Tino Rangatiratanga means self-determination, sovereignty, self-government, Māori governance by Māori over Māori affairs.
	3.1 Definitions	Add definition for Tipuna/Tupuna	Tipuna/Tupuna means ancestors.
	3.1 Definitions	Add definition for Trade supplier	Trade supplier means a business engaged in sales to businesses and institutional customers (but may also include sales to the general public) and consists only of suppliers of goods in one or more of the following categories: (a) <u>automotive and/or marine suppliers;</u> (b) <u>building suppliers;</u> (c) <u>catering equipment suppliers;</u> (d) <u>farming and agricultural suppliers;</u> (e) <u>garden and patio suppliers;</u> (f) <u>hire services (except hire or loan of books, videos, DVDs and other similar home entertainment items);</u> (g) <u>industrial clothing and safety equipment suppliers; and</u> (h) <u>office furniture, equipment and systems suppliers.</u>
	3.1 Definitions	Add definition for Walkable catchment	Walkable catchment means areas within the High Density Residential Zone that are specified in Urban Form and Development Policy UFD-P2 within a 10 minute walk of a train station, and the City Centre Zone based on average walking speeds.
	3.1 Definitions	Amend definition for Warehouse	Warehouse Means any building or part of a building , or land , where materials, articles or goods are stored. A warehouse may include offices and showrooms. Wholesale outlets may be included if incidental to, and a part of, the principal use of the site as a warehouse.
	3.1 Definitions	Add definition for Whakapapa	Whakapapa means genealogy.

Commented [MM7]: S5.4 - Bob Anker

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
---	---------	--------	--------------

3.2 Abbreviations

#	Chapter	Change	Track Change	
			Abbreviation	Meaning
3.2 Abbreviations	Amend abbreviations table		Abbreviation	Meaning
			CON	Controlled activity
			DIS	Discretionary activity
			<u>MDRS</u>	<u>Medium Density Residential Standards</u>
			NC	Non-complying activity
			NESS	National Environmental Standards
			NPS	National Planning Standards
			NPSs	National Policy Statements
			<u>NPS-UD</u>	<u>National Policy Statement on Urban Development</u>
			NZCPS	New Zealand Coastal Policy Statement
			RDIS	Restricted Discretionary activity
			PER	Permitted activity
			PR	Prohibited activity
			RMA	The Resource Management Act 1991

4.1 National Policy Statements

#	Chapter	Change	Track Change
4.1 National Policy Statements	Amend		<p>National policy statements and New Zealand Coastal Policy Statement</p> <p>National policy statements (NPSs) and the New Zealand Coastal Policy Statement (NZCPS) form part of the Resource Management Act's policy framework and are prepared by central government. NPSs and the NZCPS contain objectives, policies and methods that must be given effect to by policy statements and plans. NPSs and the NZCPS must also be given regard to by consent authorities when making decisions on resource consent applications, alongside other considerations.</p> <p>The following table provides an overview of whether any relevant review/s of the Upper Hutt District Plan has been undertaken in relation to NPSs and the NZCPS.</p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			National Policy Statement on Urban Development 2020 The plan has not yet been reviewed <u>in part</u> .
PART 2 - DISTRICT-WIDE MATTERS			
STRATEGIC DIRECTION			
UFD - Urban Form and Development			
	UFD – Urban Form and Development Residential	Add UFD-01	<p><u>Objectives</u></p> <p><u>UFD-01</u></p> <p>A well-functioning urban environment that enables all people and communities to provide for their social, economic, and cultural wellbeing, and for their health and safety, now and into the future.</p> <p>[s80H(1)(a)(ii) note: this provision incorporates the objectives in clause 6 of Schedule 3A of the Act]</p>
	UFD – Urban Form and Development Residential	Add UFD-02	<p><u>UFD-02</u></p> <p>Relevant residential zones provide for a variety of housing types and sizes that respond to</p> <ol style="list-style-type: none"> 1. <u>Housing needs and demand; and</u> 2. <u>The neighbourhood’s planned urban built character, including 3-storey buildings.</u> <p>[s80H(1)(a)(ii) note: this provision incorporates the objectives in clause 6 of Schedule 3A of the Act]</p>
	UFD – Urban Form and Development Residential	Add UFD-03	<p><u>UFD-03</u></p> <p>The High Density Residential Zone provides for higher density housing types and sizes that respond to:</p> <ol style="list-style-type: none"> 1. <u>Identified housing needs and demand.</u> 2. <u>The proximity and walkability to the following train stations and zones:</u> <ol style="list-style-type: none"> (i) <u>Silverstream Station</u> (ii) <u>Heretaunga Station</u> (iii) <u>Trentham Station</u>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(iv) <u>Wallaceville Station</u></p> <p>(v) <u>Upper Hutt Station</u></p> <p>(vi) <u>City Centre Zone</u></p> <p>(vii) <u>Town Centre Zone</u></p> <p>(viii) <u>Local Centre Zone</u></p> <p>(ix) <u>Neighbourhood Centre Zone</u></p> <p>3. <u>The planned urban built character of the zone including buildings up to 8 storeys.</u></p>
	UFD – Urban Form and Development	Add UFD-O4	<p><u>UFD-O4</u></p> <p><u>Qualifying matters</u> continue to be provided for via <u>qualifying matter areas</u> to:</p> <p>(i) <u>ensure the ongoing recognition and provision for Matters of National Importance under Section 6 of the RMA;</u></p> <p>(ii) <u>give effect to national policy statements;</u></p> <p>(iii) <u>ensure the safe and efficient operation of nationally significant infrastructure; and</u></p> <p>(iv) <u>open space is provided for public use.</u></p>
	UFD – Urban Form and Development Residential	Add UFD-P1	<p><u>Policies</u></p> <p><u>UFD-P1</u></p> <p><u>Provide for and encourage medium and high density residential development that is:</u></p> <p>a) C<u>consistent with the Council's Medium and High Density Design Guide in Appendix 1.</u></p> <p>b) <u>Accessible by active and public transport</u></p>
	UFD – Urban Form and Development Residential	Add UFD-P2	<p><u>UFD-P2</u></p> <p><u>Provide for heights and densities of urban built form that enable more people to live in, and more businesses and community services to be located in, the City's urban environments, by:</u></p> <p>1. <u>enabling the greatest building heights and densities, including unlimited height of buildings, to occur within the City Centre Zone;</u></p>

Commented [MM8]: S5.5 - Bob Anker-P

Commented [MM9]: S5.5 - Bob Anker.

Commented [MM10]: S5.5 - Bob Anker.

Commented [MM11]: S53.2 - New Zealand Defence Force.

Commented [MM12]: S50.8 - Waka Kotahi - New Zealand Transport Agency.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>2. <u>enabling building heights up to of at least 20 metres and greater densities within the High Density Residential Zone. The High Density Residential Zone comprises areas within a walkable catchment of the following train stations and centres:</u></p> <ul style="list-style-type: none"> a. <u>Silverstream Station;</u> b. <u>Heretaunga Station;</u> c. <u>Trentham Station;</u> d. <u>Wallaceville Station;</u> e. <u>Upper Hutt Station;</u> f. <u>City Centre Zone;</u> g. <u>Town Centre Zone;</u> h. <u>Local Centre Zone;</u> and i. <u>Neighbourhood Centre Zone;</u> <p>3. <u>enabling greater building heights and densities, including building heights of up to 22 metres, to occur in the Town Centre Zone and Local Centre Zone;</u></p> <p>4. <u>enabling increased building heights and densities, including building heights of up to 12 metres, to occur within the Neighbourhood Centre Zone; and</u></p> <p>5. <u>enabling a variety of building heights and densities, including 3-storey buildings, to occur within the General Residential Zone;</u></p> <p><u>while avoiding inappropriate locations, heights and densities of buildings and development within qualifying matter areas as specified by the relevant qualifying matter area provisions.</u></p>
	UFD – Urban Form and Development Residential	Amend existing Strategic Direction relating to Residential	<p>The residential areas within the City are characterised by ...</p> <p>Demand for higher density residential development is increasing in the City and the manner in which the District Plan provides for higher density residential development is important to the character and amenity of existing established neighbourhoods <u>medium density housing within the General Residential Zone</u>. Higher density residential development is becoming more desirable to certain sectors of the community and it is also desirable in establishing a variety of housing types and styles, thereby providing a greater variety to the housing stock of the City.</p>

Commented [MM13]: S58.27 - Kāinga Ora: Homes and Communities

Commented [MM14]: Consequential amendment in response to S5.26 - Bob Anker.

Commented [MM15]: S5.4 - Bob Anker.

Commented [MM16]: S5.4 - Bob Anker.

Commented [MM17]: S5.4 - Bob Anker

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>Higher density residential development is best located provided for within walkable catchments of in close proximity to retail, service and public transport centres specifically near the City Centre Zone (central business district), neighbourhood centres and major transport nodes. Higher density residential development is provided for in these areas via the High Density Residential Zone in the form of Comprehensive Residential Development and by way of an increased density for residential development.</p> <p>Within the General Residential Zone and High Density Residential Zone existing qualifying matter areas may limit the amount of permitted medium density development possible on an allotment, the Residential Conservation and Residential Hills reflect the particular environmental and topographical characteristics of those areas.</p> <p><u>The Indigenous Biodiversity Precinct contains the City's urban significant natural areas within urban environment allotments. This Precinct contains areas of continuous significant indigenous vegetation and significant habitats of indigenous fauna that have been identified in accordance with the requirements of the Regional Policy Statement for the Wellington Region.</u></p> <p><u>The Indigenous Biodiversity Precinct puts in place additional policy direction and guidance to encourage the maintenance of indigenous biodiversity values. This is in response to the increased risk placed on these areas resulting from the greatly increased permitted activity development enabled through the incorporation of the Medium Density Residential Standards into the District Plan.</u></p> <p><u>As a Matter of National Importance under section 6(c) of the Resource Management Act 1991, the inclusion of the Indigenous Biodiversity Precinct acts as a placeholder and an acknowledgement of the Council's function to maintain indigenous biodiversity under the RMA until the Council progresses its comprehensive significant natural areas plan change. In the meantime, the relevant Urban Environment Allotment and Urban Tree Group indigenous vegetation clearance rules continue to apply under chapters ECO-Ecosystems and Indigenous Biodiversity, and UTG – Urban Tree Groups.</u></p> <p>The City's residential areas are ...</p> <p>The amount of land suitable for urban use ...</p> <p>The primary role of the General Residential Zone is to provide opportunities for residential activity in a way that enables all people and communities to provide for their social, economic, and cultural wellbeing and for their health and safety. Residents want a range of living styles to reflect their various needs, while maintaining high levels of amenity and residential character. In the General Residential Zone, the provisions of the Plan seek to ensure that new development will be provided for in a manner that will respect existing forms responds to is consistent with the planned urban built form character, including 3-storey buildings.</p> <p>Certain non-residential activities are ...</p> <p>Within the General Residential Zone of the City are environments with special character. The Residential Conservation Precinct includes the areas adjoining Trentham Memorial Park, Palfrey Street, Chatsworth Road and parts of Pinehaven. These areas have a mature landscape and townscape, contain native flora and fauna, natural watercourses, as well as larger sections. They also include</p>

Commented [MM18]: S5.4 Bob Anker.

Commented [MM19]: S43.6 - KiwiRail Holding Ltd.

Commented [MM20]: S43.6 - KiwiRail Holdings Ltd.

Commented [MM21]: Consequential on S58.106 - Kāinga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>residential development on the hills surrounding the urban area. These areas require a lower density of development in order to maintain their important landscape and ecological values.</p> <p>In contrast, the Residential Hill Precinct is ...</p> <p>Higher density housing may suit the needs of certain groups of the community. It is important to locate higher density housing in appropriate areas. The Plan identifies areas where higher density housing is specifically encouraged due to the proximity of these areas to retail and service centres and transport nodes.</p> <p>To ensure that new higher medium and high density residential development, including Comprehensive Residential Development, is well designed, use of and achieves a high degree of amenity, assessment against the design outcomes identified within the Medium and High Density Design Guide (Appendix 1) for Residential Developments will be encouraged for permitted activity medium density residential development, and will be a matter of discretion for medium and high density residential development that requires a resource consent required.</p>
	UFD – Urban Form and Development Commercial and Industrial	Delete existing Strategic Direction relating to Commercial and Industrial	<p>Businesses within the City are located in the Central Business District (CBD), commercial and industrial areas, and suburban areas. Some parts of the business areas include hotels, tourist facilities and other activities.</p> <p>Historically, the location of industry in Upper Hutt has been influenced by two factors, land availability in southern and eastern Upper Hutt and the close proximity of transportation links.</p> <p>Business activities in general, while vital to the well-being of the community, may have a range of adverse effects on the surrounding environment, including residential areas. These effects need to be identified and managed to ensure that amenity values are not diminished.</p> <p>The efficient use of the existing infrastructure and resources of the commercial and industrial areas, including new development, is considered to be an important resource management matter.</p> <p>The variety of activities which exist in the commercial areas contributes to the vitality and convenience of the City. A number of distinct commercial and industrial areas are found in the City.</p> <p>Some commercial areas within the City are characterised by pedestrian orientated activities and amenities. Large scale industrial, warehousing and storage facilities, which are vehicle orientated, may adversely impact on the pedestrian environment of the CBD. It is therefore important to recognise the particular elements which affect the amenity values of an area.</p> <p>The business areas within the City are divided into three specific zones to reflect the Plan's policies:</p> <ul style="list-style-type: none"> • The Commercial zone focuses on retail and service functions which support the local community. This includes suburban centres which provide for a limited range of shopping and business needs. Local shops and dairies provide day to day convenience shopping.

IPI - PROPOSED AMENDMENTS																	
#	Chapter	Change	Track Change														
			<ul style="list-style-type: none"> The CBD accommodates a variety of activities in a compact, convenient layout which is characterised by pedestrian-orientated traffic. Commercial activities are also provided for at Silverstream and other suburban areas. These areas provide for a limited range of shopping and business needs. The smaller neighbourhood shops, including dairies, provide for day-to-day convenience shopping. <p>The Industrial zone incorporates land which is used for a range of business activities, but in particular larger scale industrial, warehousing, storage and commercial activities which are vehicle rather than pedestrian orientated. There are limited retail activities within these areas and the environmental standards are less stringent than those within the Commercial zone.</p>														
	UFD – Urban Form and Development Commercial and Mixed Use	Introduce new Strategic Direction relating to Commercial and Mixed Use – Well-functioning Urban Environments	<p>For the Commercial and Mixed Use Zones the following Strategic Objectives apply:</p> <table border="1"> <thead> <tr> <th colspan="2">Strategic Objectives – Commercial and Mixed Use</th> </tr> </thead> <tbody> <tr> <td>CMU-01</td> <td>Well-functioning Urban Environments</td> </tr> <tr> <td colspan="2"><u>The Commercial and Mixed Use Zones are well-functioning urban environments that enable all people and communities to provide for their social, economic, and cultural wellbeing, and for their health and safety, now and into the future.</u></td> </tr> </tbody> </table>	Strategic Objectives – Commercial and Mixed Use		CMU-01	Well-functioning Urban Environments	<u>The Commercial and Mixed Use Zones are well-functioning urban environments that enable all people and communities to provide for their social, economic, and cultural wellbeing, and for their health and safety, now and into the future.</u>									
Strategic Objectives – Commercial and Mixed Use																	
CMU-01	Well-functioning Urban Environments																
<u>The Commercial and Mixed Use Zones are well-functioning urban environments that enable all people and communities to provide for their social, economic, and cultural wellbeing, and for their health and safety, now and into the future.</u>																	
	UFD – Urban Form and Development Commercial and Mixed Use	Introduce new Strategic Direction relating to Commercial and Mixed Use – Business Land Capacity	<table border="1"> <thead> <tr> <td>CMU-02</td> <td>Business Land Capacity</td> </tr> </thead> <tbody> <tr> <td colspan="2"><u>Sufficient feasible commercial and mixed use land development capacity is available to meet Upper Hutt’s anticipated business land needs in the short, medium and long term</u></td> </tr> </tbody> </table>	CMU-02	Business Land Capacity	<u>Sufficient feasible commercial and mixed use land development capacity is available to meet Upper Hutt’s anticipated business land needs in the short, medium and long term</u>											
CMU-02	Business Land Capacity																
<u>Sufficient feasible commercial and mixed use land development capacity is available to meet Upper Hutt’s anticipated business land needs in the short, medium and long term</u>																	
	UFD – Urban Form and Development Commercial and Mixed Use	Introduce new Strategic Direction relating to Commercial and Mixed Use – Centres Hierarchy	<table border="1"> <thead> <tr> <td>CMU-03</td> <td>Centres Hierarchy</td> </tr> </thead> <tbody> <tr> <td colspan="2"><u>Upper Hutt has a hierarchy of centres that</u></td> </tr> <tr> <td colspan="2"><u>(i) Promote a diverse and thriving economy;</u></td> </tr> <tr> <td colspan="2"><u>(ii) Are the preferred location for shopping, leisure, cultural, entertainment and social experiences;</u></td> </tr> <tr> <td colspan="2"><u>(iii) Support the establishment and consolidation of well-functioning urban environments;</u></td> </tr> <tr> <td colspan="2"><u>(iv) Provide for the community’s employment and economic needs;</u></td> </tr> <tr> <td colspan="2"><u>(v) Contribute to meeting the community’s housing needs; and</u></td> </tr> </tbody> </table>	CMU-03	Centres Hierarchy	<u>Upper Hutt has a hierarchy of centres that</u>		<u>(i) Promote a diverse and thriving economy;</u>		<u>(ii) Are the preferred location for shopping, leisure, cultural, entertainment and social experiences;</u>		<u>(iii) Support the establishment and consolidation of well-functioning urban environments;</u>		<u>(iv) Provide for the community’s employment and economic needs;</u>		<u>(v) Contribute to meeting the community’s housing needs; and</u>	
CMU-03	Centres Hierarchy																
<u>Upper Hutt has a hierarchy of centres that</u>																	
<u>(i) Promote a diverse and thriving economy;</u>																	
<u>(ii) Are the preferred location for shopping, leisure, cultural, entertainment and social experiences;</u>																	
<u>(iii) Support the establishment and consolidation of well-functioning urban environments;</u>																	
<u>(iv) Provide for the community’s employment and economic needs;</u>																	
<u>(v) Contribute to meeting the community’s housing needs; and</u>																	

Commented [MM22]: S50.10 - Waka Kotahi - New Zealand Transport Agency.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(vi) <u>Contribute to the City’s social wellbeing and prosperity; and</u></p> <p>(vii) <u>Are well serviced by existing or planned public and active transport.</u></p>
	UFD – Urban Form and Development Commercial and Mixed Use	Introduce new Strategic Direction relating to Commercial and Mixed Use – Centre Zones	<p>CMU-04 Centre Zones Hierarchy</p> <p>Upper Hutt establishes a hierarchy of centres as follows:</p> <ul style="list-style-type: none"> • <u>The City Centre Zone is the principal centre and main focal point of the city and provides for a wide range of commercial, cultural, community, recreational, civic and residential activities that serve the city’s employment, economic and social needs.</u> • <u>The Silverstream Town Centre is a commercial centre that provides key services to the immediate and neighbouring suburbs and accommodates a wide range of commercial and community activities as well as residential activities.</u> • <u>The Local Centres Zones provide goods and services mainly to surrounding local residents while also accommodation community and residential activities.</u> • <u>The Neighbourhood Centre Zones are smaller in scale than the other centre zones and provides for the day to day needs of their immediate residential neighbourhoods, and includes provision for residential activities.</u>
	UFD – Urban Form and Development Commercial and Mixed Use	Introduce new Strategic Direction relating to Commercial and Mixed Use – Mixed Use Zone	<p>CMU-05 Mixed Use Zone</p> <p>Upper Hutt’s Mixed Use Zone complements the centres hierarchy by providing for a wide range of activities including residential activities, and activities that are less compatible with the character of other commercial centres such as vehicle oriented activities, large format retail and light industrial activities.</p>
	UFD – Urban Form and Development Special Activities	Amend Strategic Direction relating to Special Activities	<p>SPECIAL ACTIVITIES</p> <p>The main characteristics of the Special Activity Zone are</p> <p>Major activities in the Zone include ...</p> <p>The area adjoining and including St Patrick’s College covers approximately 65 hectares of land, 45 hectares of which is undeveloped. This land is referred to in the Plan as the St Patrick’s Estate Area. The land borders the Hutt River and forms part of the flood plain.</p>

Commented [MM23]: S50.10 - Waka Kotahi - New Zealand Transport Agency.

Commented [MM24]: S50.10 - Waka Kotahi - New Zealand Transport Agency.

Commented [MM25]: S64.10 - Retirement Villages Association of New Zealand.

IPI - PROPOSED AMENDMENTS															
#	Chapter	Change	Track Change												
ENERGY, INFRASTRUCTURE AND TRANSPORT															
NU - Network Utilities															
	NU – Network Utilities	Amend NU-P9	<p>Policies</p> <p>NU-P9 Ensure that network utilities are designed, developed, constructed, located, upgraded, operated and maintained to avoid, remedy or mitigate any actual or potential adverse effects on the environment.</p> <p>There are a range of different network utilities with different potential adverse effects on the environment. For instance, above ground network utilities can have adverse effects including visual, noise, traffic, odour and amenity, depending on their size, location, frequency and their scale in comparison with the character of a particular environment. A different activity status applies to some network utilities in the Southern Hills Overlay Area, Open Space, and General Residential Zones, and High Density Residential Zone to reflect that these zones have special environments that are more vulnerable to adverse effects and associated loss of amenity.</p>												
	NU – Network Utilities	Consequential Amendment	<table border="1"> <thead> <tr> <th colspan="2">Permitted Activities</th> <th colspan="2">Zone</th> </tr> </thead> <tbody> <tr> <td colspan="4">Radiocommunication, Telecommunication and Electricity Distribution and Transmission</td> </tr> <tr> <td>NU-R9</td> <td>Masts with or without associated antennas</td> <td>PER</td> <td>General Rural Rural Production Rural Lifestyle Commercial <u>and</u> <u>Mixed Use</u> City Centre General Industrial Special Activity Development Area1 (Gateway Precinct only) Development Area 2</td> </tr> </tbody> </table>	Permitted Activities		Zone		Radiocommunication, Telecommunication and Electricity Distribution and Transmission				NU-R9	Masts with or without associated antennas	PER	General Rural Rural Production Rural Lifestyle Commercial <u>and</u> <u>Mixed Use</u> City Centre General Industrial Special Activity Development Area1 (Gateway Precinct only) Development Area 2
Permitted Activities		Zone													
Radiocommunication, Telecommunication and Electricity Distribution and Transmission															
NU-R9	Masts with or without associated antennas	PER	General Rural Rural Production Rural Lifestyle Commercial <u>and</u> <u>Mixed Use</u> City Centre General Industrial Special Activity Development Area1 (Gateway Precinct only) Development Area 2												
	NU – Network Utilities	Consequential Amendment	<table border="1"> <tbody> <tr> <td>NU-S3</td> <td>Maximum Height above ground level of Network Utilities</td> </tr> </tbody> </table>	NU-S3	Maximum Height above ground level of Network Utilities										
NU-S3	Maximum Height above ground level of Network Utilities														

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change																									
			<p><i>Policy NU-P9</i></p> <ul style="list-style-type: none"> The maximum height above ground level of any utility structure listed in the table below shall include any antenna and support structures and exclude any lightning rod <table border="1"> <thead> <tr> <th>Network utility</th> <th>City Centre</th> <th>Commercial Neighbourhood Centre Local Centre Mixed Use Town Centre General Industrial Development Area 1 (Gateway Precinct only)</th> <th>General Residential High Density Residential Development Area1 (excluding Gateway Precinct)</th> <th>Special Activity</th> </tr> </thead> <tbody> <tr> <td>Masts, antennas, lines and single-pole support structures</td> <td>20m</td> <td>25m</td> <td>n/a</td> <td>20m 15m in the St Patrick's Estate College Area</td> </tr> <tr> <td>Masts and antennas (where there are two or more providers)</td> <td>25m</td> <td>30m</td> <td>n/a</td> <td>25m (other than in the St Patrick's Estate College Area)</td> </tr> <tr> <td>Maximum height above ground level of an antenna and support structure measured from the highest point of the building to which it is attached.</td> <td colspan="2">5m</td> <td colspan="2">3.5</td> </tr> <tr> <td>Cabinets, and network utility structures located within road reserve, that are not otherwise provided for</td> <td colspan="2">2.0m</td> <td>1.8</td> <td>2.0</td> </tr> </tbody> </table>	Network utility	City Centre	Commercial Neighbourhood Centre Local Centre Mixed Use Town Centre General Industrial Development Area 1 (Gateway Precinct only)	General Residential High Density Residential Development Area1 (excluding Gateway Precinct)	Special Activity	Masts, antennas, lines and single-pole support structures	20m	25m	n/a	20m 15m in the St Patrick's Estate College Area	Masts and antennas (where there are two or more providers)	25m	30m	n/a	25m (other than in the St Patrick's Estate College Area)	Maximum height above ground level of an antenna and support structure measured from the highest point of the building to which it is attached.	5m		3.5		Cabinets, and network utility structures located within road reserve, that are not otherwise provided for	2.0m		1.8	2.0
Network utility	City Centre	Commercial Neighbourhood Centre Local Centre Mixed Use Town Centre General Industrial Development Area 1 (Gateway Precinct only)	General Residential High Density Residential Development Area1 (excluding Gateway Precinct)	Special Activity																								
Masts, antennas, lines and single-pole support structures	20m	25m	n/a	20m 15m in the St Patrick's Estate College Area																								
Masts and antennas (where there are two or more providers)	25m	30m	n/a	25m (other than in the St Patrick's Estate College Area)																								
Maximum height above ground level of an antenna and support structure measured from the highest point of the building to which it is attached.	5m		3.5																									
Cabinets, and network utility structures located within road reserve, that are not otherwise provided for	2.0m		1.8	2.0																								

IPI - PROPOSED AMENDMENTS															
#	Chapter	Change	Track Change												
			<p>Cabinets, and network utility structures, that are not otherwise provided for.</p>	3.5m											
			Anemometer masts	15m	30m	12	12								
			Maximum height above ground level of an extreme adverse weather measured from the point of attachment.	4m											
	NU – Network Utilities	Consequential Amendment	<p>NU-S4 <i>Policy NU-P9</i></p>	<p>Maximum Size and Diameter of Network Utilities</p> <p>(1) The maximum size and diameter of network utilities for each zone is outlined in the table below.</p> <table border="1"> <thead> <tr> <th>Network utility</th> <th>City Centre</th> <th>Commercial Neighbourhood Centre Local Centre Mixed Use Town Centre General Industrial Development Area 1 (Gateway Precinct only)</th> <th>General Residential High Density Residential Development Area1 (excluding Gateway Precinct)</th> <th>Special Activity</th> </tr> </thead> <tbody> <tr> <td>Masts</td> <td>Diameter of mast <600mm from 6m in height</td> <td>Diameter of mast 1.5m</td> <td>n/a</td> <td>Diameter of mast 1.5m Except in the St Patrick's Estate College Area: Diameter of mast</td> </tr> </tbody> </table>		Network utility	City Centre	Commercial Neighbourhood Centre Local Centre Mixed Use Town Centre General Industrial Development Area 1 (Gateway Precinct only)	General Residential High Density Residential Development Area1 (excluding Gateway Precinct)	Special Activity	Masts	Diameter of mast <600mm from 6m in height	Diameter of mast 1.5m	n/a	Diameter of mast 1.5m Except in the St Patrick's Estate College Area: Diameter of mast
Network utility	City Centre	Commercial Neighbourhood Centre Local Centre Mixed Use Town Centre General Industrial Development Area 1 (Gateway Precinct only)	General Residential High Density Residential Development Area1 (excluding Gateway Precinct)	Special Activity											
Masts	Diameter of mast <600mm from 6m in height	Diameter of mast 1.5m	n/a	Diameter of mast 1.5m Except in the St Patrick's Estate College Area: Diameter of mast											

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change				
					<600mm from 6m in height		
			Masts (where there are two or more providers)	Diameter of mast <600mm from 6m in height	Diameter of mast 1.5m	n/a	Diameter of mast 1.5m
			Antenna attached to masts	Antenna located within a horizontal diameter circle of 750mm around the mast	Antenna located within a horizontal circle of 5m around the mast	n/a	Antenna located within a horizontal circle of 5m around the mast Except In the St Patrick's Estate College Area – Antenna located within a horizontal circle of 750mm around the mast
			Antenna attached to buildings	Antenna diameter of 2m or area of 1.8m ²	Antenna diameter of 1m or area of 0.8m ²		Antenna diameter of 2m or area of 1.8m ²
			Cabinets, and network utility structures located within road reserve (not otherwise provided for)	2m ²	1.4m ²		2m ²
			Cabinets and other network utility structures (not otherwise provided for) that are not located within road reserve	15m ²			

IPI - PROPOSED AMENDMENTS															
#	Chapter	Change	Track Change												
			<table border="1"> <tr> <td>Cabinets located within the road Reserve containing an electricity Distribution substation</td> <td>5m²</td> </tr> <tr> <td>Meteorological enclosures and buildings</td> <td>30m²</td> </tr> <tr> <td>Extreme adverse Weather warning devices</td> <td>No greater dimension than 2.5m x 1.5m</td> </tr> </table>	Cabinets located within the road Reserve containing an electricity Distribution substation	5m ²	Meteorological enclosures and buildings	30m ²	Extreme adverse Weather warning devices	No greater dimension than 2.5m x 1.5m						
Cabinets located within the road Reserve containing an electricity Distribution substation	5m ²														
Meteorological enclosures and buildings	30m ²														
Extreme adverse Weather warning devices	No greater dimension than 2.5m x 1.5m														
	NU – Network Utilities	Consequential Amendment	<p>NU-S5 <i>Policy NU-P9</i></p> <p>Separation distance and setbacks from boundaries</p> <p>(1) No network utilities shall be located within an esplanade reserve or esplanade strip.</p> <p>(2) The following table applies to masts and antenna attached to masts and any cabinet or other network utility structure that is over 5m2 in area with a height of more than 1.2m that are not located in the road reserve or rail corridor:</p> <table border="1"> <thead> <tr> <th>Zone</th> <th>Setback distance or setback for masts and antenna attached to masts</th> <th>Setback distance or setback for cabinets and other network utility structures</th> </tr> </thead> <tbody> <tr> <td>All</td> <td colspan="2">Not located within an esplanade reserve or strip</td> </tr> <tr> <td>Commercial and Mixed Use City Centre General Industrial Development Area 1 (Gateway Precinct only)</td> <td>No less than 10m from a General Residential Zone or High Density Residential Zone boundary</td> <td>No less than 2 metres to any boundary in a General Residential, High Density Residential, General Rural, Rural Production, Rural Lifestyle, Open Space and Special Activity Zone and to a road or service lane boundary.</td> </tr> <tr> <td>General Rural Rural Lifestyle</td> <td>No less than ...</td> <td>No less than ...</td> </tr> </tbody> </table>	Zone	Setback distance or setback for masts and antenna attached to masts	Setback distance or setback for cabinets and other network utility structures	All	Not located within an esplanade reserve or strip		Commercial and Mixed Use City Centre General Industrial Development Area 1 (Gateway Precinct only)	No less than 10m from a General Residential Zone or High Density Residential Zone boundary	No less than 2 metres to any boundary in a General Residential, High Density Residential, General Rural, Rural Production, Rural Lifestyle, Open Space and Special Activity Zone and to a road or service lane boundary.	General Rural Rural Lifestyle	No less than ...	No less than ...
Zone	Setback distance or setback for masts and antenna attached to masts	Setback distance or setback for cabinets and other network utility structures													
All	Not located within an esplanade reserve or strip														
Commercial and Mixed Use City Centre General Industrial Development Area 1 (Gateway Precinct only)	No less than 10m from a General Residential Zone or High Density Residential Zone boundary	No less than 2 metres to any boundary in a General Residential, High Density Residential, General Rural, Rural Production, Rural Lifestyle, Open Space and Special Activity Zone and to a road or service lane boundary.													
General Rural Rural Lifestyle	No less than ...	No less than ...													

IPI - PROPOSED AMENDMENTS																			
#	Chapter	Change	Track Change																
			<table border="1"> <tr> <td></td> <td>Rural Production Development Area 2</td> <td></td> <td></td> </tr> <tr> <td></td> <td>General Residential <u>High Density Residential</u>, Open Space Special Activity Development Area1 (excluding Gateway Precinct)</td> <td>No less than 10m from a General Residential, High Density Residential, or General Rural, Rural Production or Rural Lifestyle Zone boundary.</td> <td>No less than 2 metres to all boundaries</td> </tr> </table>		Rural Production Development Area 2				General Residential <u>High Density Residential</u> , Open Space Special Activity Development Area1 (excluding Gateway Precinct)	No less than 10m from a General Residential, High Density Residential , or General Rural, Rural Production or Rural Lifestyle Zone boundary.	No less than 2 metres to all boundaries								
	Rural Production Development Area 2																		
	General Residential <u>High Density Residential</u> , Open Space Special Activity Development Area1 (excluding Gateway Precinct)	No less than 10m from a General Residential, High Density Residential , or General Rural, Rural Production or Rural Lifestyle Zone boundary.	No less than 2 metres to all boundaries																
	NU – Network Utilities	Consequential Amendment	<table border="1"> <thead> <tr> <th colspan="2">Restricted Discretionary Activities</th> <th colspan="2">Zone</th> </tr> </thead> <tbody> <tr> <td colspan="4">Radiocommunication, Telecommunication and Electricity Distribution and Transmission</td> </tr> <tr> <td>NU-R21 <i>Policies NU-P5, NU-P6, NU-P9</i></td> <td> Masts with or without associated antennas which meet the following criteria (1) Have a maximum height above ground level of 12m (2) The diameter of the mast is <600mm, from 6m in height above ground level (3) The antenna are located within a horizontal circle of 750mm (4) Are located no less than 10m from a General Residential, High Density Residential, or General Rural, Rural Lifestyle or Rural Production Zone boundary Council will restrict its discretion to, and may impose conditions on: (5) Risks to ... </td> <td>RDIS</td> <td><i>General Residential High Density Residential Open Space Development Area1 (excluding Gateway Precinct)</i></td> </tr> <tr> <td>NU-R22 <i>Policies NU-P5, NU-P6, NU-P9</i></td> <td> Masts, with or without associated antennas that do not comply with the standards to be a permitted activity. Council will restrict its discretion to, and may impose conditions on: </td> <td>RDIS</td> <td><i>General Rural Rural Production Rural Lifestyle Commercial <u>and</u> Mixed Use City Centre</i></td> </tr> </tbody> </table>	Restricted Discretionary Activities		Zone		Radiocommunication, Telecommunication and Electricity Distribution and Transmission				NU-R21 <i>Policies NU-P5, NU-P6, NU-P9</i>	Masts with or without associated antennas which meet the following criteria (1) Have a maximum height above ground level of 12m (2) The diameter of the mast is <600mm, from 6m in height above ground level (3) The antenna are located within a horizontal circle of 750mm (4) Are located no less than 10m from a General Residential, High Density Residential , or General Rural, Rural Lifestyle or Rural Production Zone boundary Council will restrict its discretion to, and may impose conditions on: (5) Risks to ...	RDIS	<i>General Residential High Density Residential Open Space Development Area1 (excluding Gateway Precinct)</i>	NU-R22 <i>Policies NU-P5, NU-P6, NU-P9</i>	Masts , with or without associated antennas that do not comply with the standards to be a permitted activity. Council will restrict its discretion to, and may impose conditions on:	RDIS	<i>General Rural Rural Production Rural Lifestyle Commercial <u>and</u> Mixed Use City Centre</i>
Restricted Discretionary Activities		Zone																	
Radiocommunication, Telecommunication and Electricity Distribution and Transmission																			
NU-R21 <i>Policies NU-P5, NU-P6, NU-P9</i>	Masts with or without associated antennas which meet the following criteria (1) Have a maximum height above ground level of 12m (2) The diameter of the mast is <600mm, from 6m in height above ground level (3) The antenna are located within a horizontal circle of 750mm (4) Are located no less than 10m from a General Residential, High Density Residential , or General Rural, Rural Lifestyle or Rural Production Zone boundary Council will restrict its discretion to, and may impose conditions on: (5) Risks to ...	RDIS	<i>General Residential High Density Residential Open Space Development Area1 (excluding Gateway Precinct)</i>																
NU-R22 <i>Policies NU-P5, NU-P6, NU-P9</i>	Masts , with or without associated antennas that do not comply with the standards to be a permitted activity. Council will restrict its discretion to, and may impose conditions on:	RDIS	<i>General Rural Rural Production Rural Lifestyle Commercial <u>and</u> Mixed Use City Centre</i>																

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(1) The degree, extent and effects of the non-compliance with the Permitted Activity Standards</p> <p>(2) Risks to public health and safety</p> <p>(3) The maximum height above ground level of the mast and area or diameter of any antenna</p> <p>(4) The maximum height above ground level, area or diameter of any antenna</p> <p>(5) Any effect on heritage and cultural values</p> <p>(6) Visual effects including impacts on:</p> <p>(a) The residential and recreational use of land in the vicinity of the proposed utility;</p> <p>(b) The existing character, landscape, streetscape and amenity values of the locality;</p> <p>(c) Key public places, public viewing points and significant recreational areas</p> <p>(7) Amenity effects, including noise, vibration, odour, dust, earthworks and lighting</p> <p>(8) Cumulative effects</p> <p>(9) Any potential interference with public use and enjoyment of the land and the operation of land uses in the near vicinity</p> <p>(10) Measures to mitigate the bulk and scale of the utility, including screening, colour and finish treatment, earth mounding and / or planting, viewing distances, the location of support structures.</p> <p>(11) Whether the size and scale of the proposal is generally compatible with other development in the area.</p> <p>(12) Any adverse effects on traffic and pedestrian safety including sight lines and the visibility of traffic signs.</p>

General Industrial Special Activity Development Area1 (Gateway Precinct only) Development Area 2

IPI - PROPOSED AMENDMENTS											
#	Chapter	Change	Track Change								
			<p>(13) The extent to which alternative locations, routes or other options have been appropriately considered.</p> <p>(14) The extent to which it is technically, economically and practically reasonable for the masts or antennas can be co-sited with similar structures or other buildings.</p> <p>(15) The extent to which the affected persons / community has been consulted with.</p>								
REG – Renewable Energy Generation											
	REG- Renewable Energy Generation	Consequential Amendment	<table border="1"> <thead> <tr> <th colspan="3">Permitted Activities</th> <th>Zone</th> </tr> </thead> <tbody> <tr> <td>REG-R5</td> <td>Temporary renewable energy assessment and research structures</td> <td>PER</td> <td> <i>General Rural Rural Production Rural Lifestyle Commercial and Mixed Use City Centre General Industrial Open Space Development Area 1 (Gateway Precinct only) Development Area 2</i> </td> </tr> </tbody> </table>	Permitted Activities			Zone	REG-R5	Temporary renewable energy assessment and research structures	PER	<i>General Rural Rural Production Rural Lifestyle Commercial and Mixed Use City Centre General Industrial Open Space Development Area 1 (Gateway Precinct only) Development Area 2</i>
Permitted Activities			Zone								
REG-R5	Temporary renewable energy assessment and research structures	PER	<i>General Rural Rural Production Rural Lifestyle Commercial and Mixed Use City Centre General Industrial Open Space Development Area 1 (Gateway Precinct only) Development Area 2</i>								
	REG- Renewable Energy Generation	Consequential Amendment	<table border="1"> <thead> <tr> <th colspan="3">Standards for permitted activities</th> <th>Zone</th> </tr> </thead> <tbody> <tr> <td>REG-S2 <i>Policy REG-P2</i></td> <td> Any solar panel mounted to any building (1) The permitted building height may ... (2) The sunlight access <u>or height in relation to boundary</u> standard may be exceeded by no more than 1m. </td> <td></td> <td><i>All</i></td> </tr> </tbody> </table>	Standards for permitted activities			Zone	REG-S2 <i>Policy REG-P2</i>	Any solar panel mounted to any building (1) The permitted building height may ... (2) The sunlight access <u>or height in relation to boundary</u> standard may be exceeded by no more than 1m.		<i>All</i>
Standards for permitted activities			Zone								
REG-S2 <i>Policy REG-P2</i>	Any solar panel mounted to any building (1) The permitted building height may ... (2) The sunlight access <u>or height in relation to boundary</u> standard may be exceeded by no more than 1m.		<i>All</i>								

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
				(3) *Where located on a heritage building ...	
	REG- Renewable Energy Generation	Consequential Amendment	REG-S3 <i>Policy REG-P2</i>	Roof-mounted small scale wind turbines (1) The sunlight access, height in relation to boundary, setback and noise standards for the zone in which the site is located shall be complied with (2) The permitted building height may ... (3) There shall be no more than ... (4) *Shall not be located ...	<i>All</i>
	REG- Renewable Energy Generation	Consequential Amendment	REG-S4 <i>Policy REG-P2</i>	Freestanding small scale wind turbines (1) The sunlight access, height in relation to boundary, setback and noise standards for the zone that the site is located in must be complied with. (2) The permitted building height for ... (3) There shall be no ... (4) *Shall not be located on ...	<i>All</i>
	REG- Renewable Energy Generation	Consequential Amendment	REG-S5 <i>Policy REG-P3</i>	Temporary renewable energy assessment and research structures (1) Shall comply with the following New Zealand Standards as well as any others relevant to emissions: (a) NZS6808:2010 Acoustics – Wind Farm Noise (b) NZS 2772:1999 Radiofrequency Fields (2) Must comply with the .. (3) Shall not be located ... (4) Any anemometer must not ..	<i>All</i>

IPI - PROPOSED AMENDMENTS															
#	Chapter	Change	Track Change												
			<p>(5) All structures shall comply with the sunlight access <u>height in relation to boundary</u>, height control plane and setback requirements for the zone in which they are located.</p> <p>(6) ...</p>												
	REG – Renewable Energy Generation	Consequential Amendment	<table border="1"> <thead> <tr> <th colspan="2">Restricted Discretionary Activities</th> <th colspan="2">Zones</th> </tr> </thead> <tbody> <tr> <td>REG-R9</td> <td>Land based structures that support in-stream hydro or marine energy generation provided that they are not located:</td> <td>RDIS</td> <td><i>General Rural Rural Production Rural Lifestyle Commercial and Mixed Use City Centre General Industrial Open Space Development Area 1 (Gateway Precinct only) Development Area 2</i></td> </tr> <tr> <td><i>Policies REG-P1, REG-P3, REG-P4, REG-P5</i></td> <td> <p>(1) On a site containing an item listed in the Schedule of Significant Heritage Features HH-SCHED1</p> <p>(2) Within an esplanade reserve or strip</p> <p>(3) Within any riparian setback</p> <p>(4) On any legal road (formed or unformed)</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <p>(5) All those matters under REG-MC1, and:</p> <p>(6) Traffic effects</p> <p>(7) Effects on public access</p> <p>(8) Effects on natural character</p> </td> <td></td> <td></td> </tr> </tbody> </table>	Restricted Discretionary Activities		Zones		REG-R9	Land based structures that support in-stream hydro or marine energy generation provided that they are not located:	RDIS	<i>General Rural Rural Production Rural Lifestyle Commercial and Mixed Use City Centre General Industrial Open Space Development Area 1 (Gateway Precinct only) Development Area 2</i>	<i>Policies REG-P1, REG-P3, REG-P4, REG-P5</i>	<p>(1) On a site containing an item listed in the Schedule of Significant Heritage Features HH-SCHED1</p> <p>(2) Within an esplanade reserve or strip</p> <p>(3) Within any riparian setback</p> <p>(4) On any legal road (formed or unformed)</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <p>(5) All those matters under REG-MC1, and:</p> <p>(6) Traffic effects</p> <p>(7) Effects on public access</p> <p>(8) Effects on natural character</p>		
Restricted Discretionary Activities		Zones													
REG-R9	Land based structures that support in-stream hydro or marine energy generation provided that they are not located:	RDIS	<i>General Rural Rural Production Rural Lifestyle Commercial and Mixed Use City Centre General Industrial Open Space Development Area 1 (Gateway Precinct only) Development Area 2</i>												
<i>Policies REG-P1, REG-P3, REG-P4, REG-P5</i>	<p>(1) On a site containing an item listed in the Schedule of Significant Heritage Features HH-SCHED1</p> <p>(2) Within an esplanade reserve or strip</p> <p>(3) Within any riparian setback</p> <p>(4) On any legal road (formed or unformed)</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <p>(5) All those matters under REG-MC1, and:</p> <p>(6) Traffic effects</p> <p>(7) Effects on public access</p> <p>(8) Effects on natural character</p>														
TP - Transport and Parking															
	TP - Transport and Parking	Introduce permitted activity relating to site access for commercial zones	<table border="1"> <thead> <tr> <th colspan="2"><u>Permitted Activities</u></th> <th colspan="2"><u>Zone</u></th> </tr> <tr> <th colspan="4"><u>Site Access</u></th> </tr> </thead> <tbody> <tr> <td>TP-R3</td> <td>Activities and buildings and structures if site access is compliant with TP-S1</td> <td>PER</td> <td><i>Commercial and Mixed Use</i></td> </tr> </tbody> </table>	<u>Permitted Activities</u>		<u>Zone</u>		<u>Site Access</u>				TP-R3	Activities and buildings and structures if site access is compliant with TP-S1	PER	<i>Commercial and Mixed Use</i>
<u>Permitted Activities</u>		<u>Zone</u>													
<u>Site Access</u>															
TP-R3	Activities and buildings and structures if site access is compliant with TP-S1	PER	<i>Commercial and Mixed Use</i>												

Commented [MM26]: Clause 16(2) Schedule 1 RMA, correction of minor error.

IPI - PROPOSED AMENDMENTS															
#	Chapter	Change	Track Change												
	TP - Transport and Parking	Introduce permitted activity relating to loading for commercial zones	<table border="1"> <thead> <tr> <th colspan="4">Loading</th> </tr> </thead> <tbody> <tr> <td>TP-R4</td> <td>Non-residential activities and non-residential or mixed use buildings if compliant with TP-S2</td> <td>PER</td> <td><i>Commercial and Mixed Use</i></td> </tr> </tbody> </table>	Loading				TP-R4	Non-residential activities and non-residential or mixed use buildings if compliant with TP-S2	PER	<i>Commercial and Mixed Use</i>				
Loading															
TP-R4	Non-residential activities and non-residential or mixed use buildings if compliant with TP-S2	PER	<i>Commercial and Mixed Use</i>												
	TP - Transport and Parking	Consequential Amendment	<table border="1"> <thead> <tr> <th colspan="3">Discretionary Activities</th> <th>Zone</th> </tr> </thead> <tbody> <tr> <td colspan="4">Roading, and Traffic and Transport Structures</td> </tr> <tr> <td>TP-R25</td> <td>The construction, alteration or diversion of roads, but excluding any such construction works which are part of a subdivision.</td> <td>DIS</td> <td><i>General Residential General Rural Rural Production Rural Lifestyle Commercial and Mixed Use City Centre General Industrial Development Area 1 (Gateway Precinct only) Development Area 2</i></td> </tr> </tbody> </table>	Discretionary Activities			Zone	Roading, and Traffic and Transport Structures				TP-R25	The construction, alteration or diversion of roads, but excluding any such construction works which are part of a subdivision.	DIS	<i>General Residential General Rural Rural Production Rural Lifestyle Commercial and Mixed Use City Centre General Industrial Development Area 1 (Gateway Precinct only) Development Area 2</i>
Discretionary Activities			Zone												
Roading, and Traffic and Transport Structures															
TP-R25	The construction, alteration or diversion of roads, but excluding any such construction works which are part of a subdivision.	DIS	<i>General Residential General Rural Rural Production Rural Lifestyle Commercial and Mixed Use City Centre General Industrial Development Area 1 (Gateway Precinct only) Development Area 2</i>												
	TP - Transport and Parking	Introduce new standard relating to access for commercial zones	<table border="1"> <thead> <tr> <th colspan="3">Standards</th> <th>Zone</th> </tr> </thead> <tbody> <tr> <td>TP-S1</td> <td>Where site access is required or provided the following standards apply: (1) All accessways and manoeuvring areas shall be formed and surfaced in accordance with the <u>Code of Practice for Civil Engineering Works</u>. <u>Exemption – the requirement for accessways serving sites solely occupied by unstaffed utilities shall be that the accessway shall be surfaced with permanent all weather surfacing for a minimum length of 5m from the edge of the road carriageway seal.</u></td> <td></td> <td><i>Commercial and Mixed Use</i></td> </tr> </tbody> </table>	Standards			Zone	TP-S1	Where site access is required or provided the following standards apply: (1) All accessways and manoeuvring areas shall be formed and surfaced in accordance with the <u>Code of Practice for Civil Engineering Works</u> . <u>Exemption – the requirement for accessways serving sites solely occupied by unstaffed utilities shall be that the accessway shall be surfaced with permanent all weather surfacing for a minimum length of 5m from the edge of the road carriageway seal.</u>		<i>Commercial and Mixed Use</i>				
Standards			Zone												
TP-S1	Where site access is required or provided the following standards apply: (1) All accessways and manoeuvring areas shall be formed and surfaced in accordance with the <u>Code of Practice for Civil Engineering Works</u> . <u>Exemption – the requirement for accessways serving sites solely occupied by unstaffed utilities shall be that the accessway shall be surfaced with permanent all weather surfacing for a minimum length of 5m from the edge of the road carriageway seal.</u>		<i>Commercial and Mixed Use</i>												

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(2) <u>Sites shall have practical vehicle access to car parking and loading spaces (where provided or required), in accordance with the Code of Practice for Civil Engineering Works. This requirement does not apply to sites solely occupied by unstaffed utilities, provided that vehicles associated with utilities shall not obstruct the footpath or create a traffic hazard on the road.</u></p> <p>(3) Adequate vehicular access shall be made available to the rear of every new building in accordance with the Code of Practice for Civil Engineering Works.</p> <p>(3) <u>Vehicular access to a corner allotment shall be located no closer than 8m from the street corner. Where a site is located on an intersection of a primary or secondary arterial traffic route (as identified in the Transport and Parking (TP) Chapter) the siting of the vehicular access shall be located as far as practicable from the corner of the street. The 8 metre setback shall be measured from where the two front boundaries of the site (refer to the definition of a corner allotment) join, or in accordance with the diagram below.</u></p> <div style="text-align: center;"> </div> <p>(4) <u>Where a corner allotment is located at an intersection of a national, primary or secondary arterial traffic route, as identified in TP-SCHED 1 – Roading Hierarchy, no building, fence or other structure is to be erected and no vegetation allowed to grow so as to obstruct a traffic sight line.</u></p>

IPI - PROPOSED AMENDMENTS													
#	Chapter	Change	Track Change										
			<p>(5) <u>At the intersection of a road or rail level crossing, no building, fence or other obstructions which block sight lines for trains shall be erected, placed or grown in the hatched area marked in TP-Diagram 1.</u></p> <p>(6) <u>Land use activities with direct access to a State Highway shall comply with the access and visibility standards set out in TP-Diagrams 2 to 9.</u></p>										
	TP - Transport and Parking	Introduce new standard relating to loading for commercial zones	<p>TP-S2</p> <p><u>Loading provisions for non-residential activities and for non-residential or mixed use buildings</u></p> <p>(1) <u>The number of loading spaces needed for any building in the Commercial Zone non-residential activities and for non-residential or mixed use buildings shall be as follows:</u></p> <table border="1"> <thead> <tr> <th>Floor area</th> <th>Loading spaces required</th> </tr> </thead> <tbody> <tr> <td>Up to and including 500m²</td> <td>Nil</td> </tr> <tr> <td>Between 100501m² and 1000m²</td> <td>1 space</td> </tr> <tr> <td>Between 1001m² and 2000m²</td> <td>2 spaces</td> </tr> <tr> <td>More than 2000m²</td> <td>2 spaces or 4 spaces if the building is used as a retail store for retail activities or buildings</td> </tr> </tbody> </table> <p>(2) <u>Every loading space requires a manoeuvring space for ingress and egress. The extent of the manoeuvring space is to be in accordance with the Code of Practice for Civil Engineering Works.</u></p> <p>(3) <u>All loading spaces are required to be formed and surfaced in accordance with the Code of Practice for Civil Engineering Works.</u></p> <p>Notes:</p> <ul style="list-style-type: none"> <u>Loading areas must be kept clear and must be available at all times for vehicles used in association with the building during which time the building is being used for the activity to which the car parking and loading spaces relate.</u> <u>Direct access to each loading space may be allowed from any vested service lane</u> 	Floor area	Loading spaces required	Up to and including 500m ²	Nil	Between 100 501m ² and 1000m ²	1 space	Between 1001m ² and 2000m ²	2 spaces	More than 2000m ²	2 spaces or 4 spaces if the building is used as a retail store for retail activities or buildings
Floor area	Loading spaces required												
Up to and including 500m ²	Nil												
Between 100 501m ² and 1000m ²	1 space												
Between 1001m ² and 2000m ²	2 spaces												
More than 2000m ²	2 spaces or 4 spaces if the building is used as a retail store for retail activities or buildings												

Commercial and Mixed Use

IPI - PROPOSED AMENDMENTS												
#	Chapter	Change	Track Change									
	TP - Transport and Parking	Consequential Amendment	<p>TP-S8</p> <p><i>Policy</i> <i>NU-P1</i></p> <p>Where any car parking area accommodates more than five vehicle spaces and adjoins a site which is zoned General Residential, High Density Residential, General Rural, Rural Production, Rural Lifestyle, Open Space or Special Activity, then it shall be effectively screened from that site by a close boarded fence, wall or landscaping of no less than 1.6m in height. A car parking area with more than five vehicle spaces that adjoins a road shall also be screened by a landscaped strip within the site of at least 0.6m in width. Note that additional landscape requirements apply in the Special Activities Zone.</p>									
	TP – Transport and Parking	Consequential Amendment	<table border="1"> <thead> <tr> <th colspan="2">Discretionary Activities</th> <th>Zone</th> </tr> </thead> <tbody> <tr> <td colspan="3">Roading, and Traffic and Transport Structures</td> </tr> <tr> <td>TP-R34</td> <td>The construction, alteration or diversion of roads, but excluding any such construction works which are part of a subdivision.</td> <td> DIS <i>General Residential</i> <i>High Density Residential</i> <i>General Rural</i> <i>Rural Production</i> <i>Rural Lifestyle</i> <i>Commercial and Mixed Use</i> <i>City Centre</i> <i>General Industrial Development</i> <i>Area 1 (Gateway Precinct only) Development</i> <i>Area 2</i> </td> </tr> </tbody> </table>	Discretionary Activities		Zone	Roading, and Traffic and Transport Structures			TP-R34	The construction, alteration or diversion of roads , but excluding any such construction works which are part of a subdivision .	DIS <i>General Residential</i> <i>High Density Residential</i> <i>General Rural</i> <i>Rural Production</i> <i>Rural Lifestyle</i> <i>Commercial and Mixed Use</i> <i>City Centre</i> <i>General Industrial Development</i> <i>Area 1 (Gateway Precinct only) Development</i> <i>Area 2</i>
Discretionary Activities		Zone										
Roading, and Traffic and Transport Structures												
TP-R34	The construction, alteration or diversion of roads , but excluding any such construction works which are part of a subdivision .	DIS <i>General Residential</i> <i>High Density Residential</i> <i>General Rural</i> <i>Rural Production</i> <i>Rural Lifestyle</i> <i>Commercial and Mixed Use</i> <i>City Centre</i> <i>General Industrial Development</i> <i>Area 1 (Gateway Precinct only) Development</i> <i>Area 2</i>										
HAZARDS AND RISKS												
NH – Natural Hazards												
	NH – Natural Hazards	Consequential Amendment	<table border="1"> <thead> <tr> <th colspan="2">Restricted Discretionary Activities</th> <th>Zones</th> </tr> </thead> <tbody> <tr> <td colspan="3"> </td> </tr> </tbody> </table>	Restricted Discretionary Activities		Zones						
Restricted Discretionary Activities		Zones										

IPI - PROPOSED AMENDMENTS											
#	Chapter	Change	Track Change								
			<table border="1"> <tr> <td>ECO-R3</td> <td>Accessory buildings, otherwise permitted under the underlying zone, located within an area identified as Southern Hills Overlay Area_ (see definition of “accessory building” for limitations on size and floor area)</td> <td>PER</td> <td><i>All</i></td> </tr> </table>	ECO-R3	Accessory buildings , otherwise permitted under the underlying zone, located within an area identified as Southern Hills Overlay Area_ (see definition of “accessory building” for limitations on size and floor area)	PER	<i>All</i>				
ECO-R3	Accessory buildings , otherwise permitted under the underlying zone, located within an area identified as Southern Hills Overlay Area_ (see definition of “accessory building” for limitations on size and floor area)	PER	<i>All</i>								
	ECO - Ecosystems and Indigenous Biodiversity	Consequential Amendment	<table border="1"> <tr> <th colspan="2">Restricted Discretionary Activities</th> <th colspan="2">Zone</th> </tr> <tr> <td>ECO-R6</td> <td>Any building or structure or new aboveground network utility (excluding accessory buildings and minor above ground lines), otherwise permitted under the underlying zone, located within an area identified as Southern Hills Overlay Area Council will restrict its discretion to, and may impose conditions on: <ul style="list-style-type: none"> (1) Design, appearance, scale and siting of the building, structure, or new aboveground network utility. (2) Effects on visual values. (3) Effects on landscape values. (4) Effects on ecological values. (5) Measures to avoid, remedy or mitigate potential adverse effects. (6) In addition to the above, for the Mount Marua Structure Plan Development Area, compliance with the Mount Marua Structure Plan. </td> <td>RDIS</td> <td><i>All excluding <u>General Residential Zone</u></i></td> </tr> </table>	Restricted Discretionary Activities		Zone		ECO-R6	Any building or structure or new aboveground network utility (excluding accessory buildings and minor above ground lines), otherwise permitted under the underlying zone, located within an area identified as Southern Hills Overlay Area Council will restrict its discretion to, and may impose conditions on: <ul style="list-style-type: none"> (1) Design, appearance, scale and siting of the building, structure, or new aboveground network utility. (2) Effects on visual values. (3) Effects on landscape values. (4) Effects on ecological values. (5) Measures to avoid, remedy or mitigate potential adverse effects. (6) In addition to the above, for the Mount Marua Structure Plan Development Area, compliance with the Mount Marua Structure Plan. 	RDIS	<i>All excluding <u>General Residential Zone</u></i>
Restricted Discretionary Activities		Zone									
ECO-R6	Any building or structure or new aboveground network utility (excluding accessory buildings and minor above ground lines), otherwise permitted under the underlying zone, located within an area identified as Southern Hills Overlay Area Council will restrict its discretion to, and may impose conditions on: <ul style="list-style-type: none"> (1) Design, appearance, scale and siting of the building, structure, or new aboveground network utility. (2) Effects on visual values. (3) Effects on landscape values. (4) Effects on ecological values. (5) Measures to avoid, remedy or mitigate potential adverse effects. (6) In addition to the above, for the Mount Marua Structure Plan Development Area, compliance with the Mount Marua Structure Plan. 	RDIS	<i>All excluding <u>General Residential Zone</u></i>								
	ECO - Ecosystems and Indigenous Biodiversity	Consequential Amendment	<table border="1"> <tr> <th colspan="2">Discretionary Activities</th> <th colspan="2">Zones</th> </tr> <tr> <td>ECO-R9</td> <td>Any building or structure or new aboveground network utility (including accessory buildings), otherwise controlled or restricted discretionary under the underlying zone, located within an area identified as Southern Hills Overlay Area</td> <td>DIS</td> <td><i>All excluding <u>General Residential Zone</u></i></td> </tr> </table>	Discretionary Activities		Zones		ECO-R9	Any building or structure or new aboveground network utility (including accessory buildings), otherwise controlled or restricted discretionary under the underlying zone, located within an area identified as Southern Hills Overlay Area	DIS	<i>All excluding <u>General Residential Zone</u></i>
Discretionary Activities		Zones									
ECO-R9	Any building or structure or new aboveground network utility (including accessory buildings), otherwise controlled or restricted discretionary under the underlying zone, located within an area identified as Southern Hills Overlay Area	DIS	<i>All excluding <u>General Residential Zone</u></i>								
	ECO - Ecosystems and Indigenous Biodiversity	Consequential Amendment	<table border="1"> <tr> <th colspan="2">Non-complying Activities</th> <th colspan="2">Zones</th> </tr> <tr> <td>ECO-R10</td> <td>Any building or structure or new aboveground network utility, otherwise noncomplying under the underlying zone, located within an area identified as Southern Hills Overlay Area</td> <td>NC</td> <td><i>All excluding <u>General Residential Zone</u></i></td> </tr> </table>	Non-complying Activities		Zones		ECO-R10	Any building or structure or new aboveground network utility , otherwise noncomplying under the underlying zone, located within an area identified as Southern Hills Overlay Area	NC	<i>All excluding <u>General Residential Zone</u></i>
Non-complying Activities		Zones									
ECO-R10	Any building or structure or new aboveground network utility , otherwise noncomplying under the underlying zone, located within an area identified as Southern Hills Overlay Area	NC	<i>All excluding <u>General Residential Zone</u></i>								

IPI - PROPOSED AMENDMENTS											
#	Chapter	Change	Track Change								
NFL – Natural Features and Landscapes											
	NFL - Ecosystems and Indigenous Biodiversity	Consequential Amendment	<table border="1"> <thead> <tr> <th colspan="2">Permitted Activities</th> <th colspan="2">Zone</th> </tr> </thead> <tbody> <tr> <td>NFL-R2</td> <td>Accessory buildings, otherwise permitted under the underlying zone, located within an area identified as Southern Hills Overlay Area_ (see definition of “accessory building” for limitations on size and floor area)</td> <td>PER</td> <td><i>All</i></td> </tr> </tbody> </table>	Permitted Activities		Zone		NFL-R2	Accessory buildings , otherwise permitted under the underlying zone, located within an area identified as Southern Hills Overlay Area_ (see definition of “accessory building” for limitations on size and floor area)	PER	<i>All</i>
			Permitted Activities		Zone						
NFL-R2	Accessory buildings , otherwise permitted under the underlying zone, located within an area identified as Southern Hills Overlay Area_ (see definition of “accessory building” for limitations on size and floor area)	PER	<i>All</i>								
SUBDIVISION											
SUB-GEN – General Subdivision Provisions that Apply in All Zones											
	SUB-GEN– General Subdivision	Consequential Amendment	SUB-GEN-12 <i>That subdivision does not adversely affect significant natural landforms, areas of significant indigenous natural vegetation or significant habitats of indigenous fauna or areas of landscape and/or visual value as identified within the Southern Hills Overlay Area, <u>and Precinct 1 - Indigenous Biodiversity Precinct.</u></i>								
	SUB-GEN- Subdivision Provisions that Apply in All Zones	Insert new objective	SUB-GEN-07 <i>There is no increase in the peak demand on stormwater management systems and increase in flooding from <u>subdivision and development.</u></i>								
	SUB-GEN- Subdivision Provisions that Apply in All Zones	Insert new policy	SUB-GEN-P13 <i><u>Subdivision and development will be designed to achieve hydraulic neutrality in the following zones:</u></i> <ul style="list-style-type: none"> (i) <u>General Residential Zone.</u> (ii) <u>High Density Residential Zone.</u> (iii) <u>City Centre Zone.</u> (iv) <u>Town Centre Zone.</u> (v) <u>Neighbourhood Centre Zone.</u> (vi) <u>Local Centre Zone.</u> (vii) <u>Mixed Use Zone.</u> 								
	SUB-GEN- Subdivision Provisions that Apply in All Zones	Insert new controlled activity rule.	<table border="1"> <thead> <tr> <th colspan="2">Controlled Activities</th> <th colspan="2">Zone</th> </tr> </thead> <tbody> <tr> <td>SUB-GEN-R2A</td> <td>Subdivision and development must be designed to achieve hydraulic neutrality ensure that the stormwater runoff from all new impermeable surfaces will be disposed of or stored on site and released at a rate that does not exceed the</td> <td>CON</td> <td><i>General Residential, High Density</i></td> </tr> </tbody> </table>	Controlled Activities		Zone		SUB-GEN-R2A	Subdivision and development must be designed to achieve hydraulic neutrality ensure that the stormwater runoff from all new impermeable surfaces will be disposed of or stored on site and released at a rate that does not exceed the	CON	<i>General Residential, High Density</i>
			Controlled Activities		Zone						
SUB-GEN-R2A	Subdivision and development must be designed to achieve hydraulic neutrality ensure that the stormwater runoff from all new impermeable surfaces will be disposed of or stored on site and released at a rate that does not exceed the	CON	<i>General Residential, High Density</i>								

IPI - PROPOSED AMENDMENTS														
#	Chapter	Change	Track Change											
			<p>peak stormwater runoff when compared to the pre-development situation for the 10% and 1% rainfall Annual Exceedance Probability event.</p> <p>Council will limit its control to and may impose conditions over the following matters:</p> <ol style="list-style-type: none"> Any potential effects on any downstream flooding hazard; The size and scale of the development and the additional stormwater that the proposal will generate compared to the existing situation; The capacity of the local stormwater network; and Whether there are any site-specific constraints or opportunities within the local area that mean that hydraulic neutrality is not required. 											
			<p><i>Residential, City Centre, Town Centre, Neighbourhood Centre, Local Centre, Mixed Use.</i></p>											
	SUB-GEN– Subdivision in Residential Zones	Consequential Amendment	<p>Standards for Controlled Activities</p> <p>SUB-GEN-S1 Subdivision of land adjoining a river or stream listed below</p> <p><i>Policy SUB-GEN-P6</i></p> <p>(1) Esplanade Reserves</p> <p>When any land being subdivided adjoins any of the following rivers or streams, an esplanade reserve shall be set aside according to the provisions of the following table and Part 77 of the Act:</p> <table border="1"> <thead> <tr> <th>River/stream</th> <th>Width of esplanade reserve</th> </tr> </thead> <tbody> <tr> <td>(a) Hutt River</td> <td rowspan="4">20m (both banks)</td> </tr> <tr> <td>(b) Whakatiki River from ...</td> </tr> <tr> <td>(c) Akatarawa River ...</td> </tr> <tr> <td>(d) Pakuratahi River ...</td> </tr> <tr> <td>(e) Mangaroa River ...</td> <td>8m (minimum) (both banks)</td> </tr> <tr> <td>(f) Mawaihakona Stream for that part of the river passing through the St Patrick's Estate Precinct Area where the adjoining land is reserve</td> <td>5-12m (both banks) with the width being determined having regard to the criteria set out in SUB-GEN-R2</td> </tr> </tbody> </table>	River/stream	Width of esplanade reserve	(a) Hutt River	20m (both banks)	(b) Whakatiki River from ...	(c) Akatarawa River ...	(d) Pakuratahi River ...	(e) Mangaroa River ...	8m (minimum) (both banks)	(f) Mawaihakona Stream for that part of the river passing through the St Patrick's Estate Precinct Area where the adjoining land is reserve	5-12m (both banks) with the width being determined having regard to the criteria set out in SUB-GEN-R2
River/stream	Width of esplanade reserve													
(a) Hutt River	20m (both banks)													
(b) Whakatiki River from ...														
(c) Akatarawa River ...														
(d) Pakuratahi River ...														
(e) Mangaroa River ...	8m (minimum) (both banks)													
(f) Mawaihakona Stream for that part of the river passing through the St Patrick's Estate Precinct Area where the adjoining land is reserve	5-12m (both banks) with the width being determined having regard to the criteria set out in SUB-GEN-R2													
			<p>Zone</p> <p><i>All</i></p>											

Commented [MM27]: S58.38 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS												
#	Chapter	Change	Track Change									
				<div style="border: 1px solid black; padding: 2px; display: inline-block;">(g) Collins Creek from ...</div> <div style="border: 1px solid black; padding: 2px; display: inline-block; margin-left: 10px;">Varying width suitable for ...</div> <p>(2) Esplanade Strips When any land being ...</p>								
	SUB-GEN– Subdivision in Residential Zones	Consequential Amendment	<p>Restricted Discretionary Activities</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 25%;"></th> <th style="width: 45%;"></th> <th style="width: 10%;"></th> <th style="width: 20%;">Zones</th> </tr> </thead> <tbody> <tr> <td> SUB-GEN-R3 <i>Policies</i> SUB-GEN-P1 NFL-P2 NFL-P3, ECO-P6, NFL-P4, ECO-P7, TREE-P1, UTG-P1, NU-P9 </td> <td> Subdivision, otherwise controlled under the underlying zone, within an area identified as Southern Hills Overlay Area Council will restrict its discretion to, and may impose conditions on: (1) The standards for permitted and controlled activities in the underlying zone. (2) The design and layout of the subdivision. (3) Effects on visual values. (4) Effects on landscape values. (5) Effects on ecological values. (6) Measures to avoid, remedy or mitigate potential adverse effects. (7) In addition to the above, for the Mount Marua Structure Plan Development Area, compliance with the Mount Marua Structure Plan. </td> <td>RDIS</td> <td><i>All excluding</i> <u>General Residential Zone</u></td> </tr> </tbody> </table>					Zones	SUB-GEN-R3 <i>Policies</i> SUB-GEN-P1 NFL-P2 NFL-P3, ECO-P6, NFL-P4, ECO-P7, TREE-P1, UTG-P1, NU-P9	Subdivision , otherwise controlled under the underlying zone, within an area identified as Southern Hills Overlay Area Council will restrict its discretion to, and may impose conditions on: (1) The standards for permitted and controlled activities in the underlying zone. (2) The design and layout of the subdivision . (3) Effects on visual values. (4) Effects on landscape values. (5) Effects on ecological values. (6) Measures to avoid, remedy or mitigate potential adverse effects . (7) In addition to the above, for the Mount Marua Structure Plan Development Area, compliance with the Mount Marua Structure Plan.	RDIS	<i>All excluding</i> <u>General Residential Zone</u>
			Zones									
SUB-GEN-R3 <i>Policies</i> SUB-GEN-P1 NFL-P2 NFL-P3, ECO-P6, NFL-P4, ECO-P7, TREE-P1, UTG-P1, NU-P9	Subdivision , otherwise controlled under the underlying zone, within an area identified as Southern Hills Overlay Area Council will restrict its discretion to, and may impose conditions on: (1) The standards for permitted and controlled activities in the underlying zone. (2) The design and layout of the subdivision . (3) Effects on visual values. (4) Effects on landscape values. (5) Effects on ecological values. (6) Measures to avoid, remedy or mitigate potential adverse effects . (7) In addition to the above, for the Mount Marua Structure Plan Development Area, compliance with the Mount Marua Structure Plan.	RDIS	<i>All excluding</i> <u>General Residential Zone</u>									
	SUB-GEN– Subdivision in Residential Zones	Consequential Amendment	<p>Discretionary Activities</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 25%;"></th> <th style="width: 45%;"></th> <th style="width: 10%;"></th> <th style="width: 20%;">Zones</th> </tr> </thead> <tbody> <tr> <td> SUB-GEN-R3 <i>Policies</i> NFL-P2, NFL-P3, ECO-P6, NFL-P4. </td> <td> Subdivision, otherwise restricted discretionary or discretionary under the underlying zone, within an area identified as Southern Hills Overlay Area. </td> <td>DIS</td> <td><i>All excluding</i> <u>General Residential Zone</u></td> </tr> </tbody> </table>					Zones	SUB-GEN-R3 <i>Policies</i> NFL-P2, NFL-P3, ECO-P6, NFL-P4.	Subdivision , otherwise restricted discretionary or discretionary under the underlying zone, within an area identified as Southern Hills Overlay Area.	DIS	<i>All excluding</i> <u>General Residential Zone</u>
			Zones									
SUB-GEN-R3 <i>Policies</i> NFL-P2, NFL-P3, ECO-P6, NFL-P4.	Subdivision , otherwise restricted discretionary or discretionary under the underlying zone, within an area identified as Southern Hills Overlay Area.	DIS	<i>All excluding</i> <u>General Residential Zone</u>									

IPI - PROPOSED AMENDMENTS											
#	Chapter	Change	Track Change								
			<table border="1"> <tr> <td>TREE-P1, UTG-P1, NU-P9</td> <td></td> <td></td> <td></td> </tr> </table>	TREE-P1, UTG-P1, NU-P9							
TREE-P1, UTG-P1, NU-P9											
	SUB-GEN– Subdivision in Residential Zones	Consequential Amendment	<table border="1"> <thead> <tr> <th colspan="2">Non-complying Activities</th> <th colspan="2">Zones</th> </tr> </thead> <tbody> <tr> <td> SUB-GEN-R3 <i>Policies</i> NFL-P2, NFL-P3, ECO-P6, NFL-P4, TREE-P1, UTG-P1, NU-P9 </td> <td> Subdivision, otherwise non-complying under the underlying zone within the Southern Hills Overlay Area </td> <td> DIS </td> <td> <i>All excluding</i> <u>General Residential Zone</u> </td> </tr> </tbody> </table>	Non-complying Activities		Zones		SUB-GEN-R3 <i>Policies</i> NFL-P2, NFL-P3, ECO-P6, NFL-P4, TREE-P1, UTG-P1, NU-P9	Subdivision , otherwise non-complying under the underlying zone within the Southern Hills Overlay Area	DIS	<i>All excluding</i> <u>General Residential Zone</u>
Non-complying Activities		Zones									
SUB-GEN-R3 <i>Policies</i> NFL-P2, NFL-P3, ECO-P6, NFL-P4, TREE-P1, UTG-P1, NU-P9	Subdivision , otherwise non-complying under the underlying zone within the Southern Hills Overlay Area	DIS	<i>All excluding</i> <u>General Residential Zone</u>								
SUB-RES – Subdivision in Residential Zones											
	SUB-RES – Subdivision in the General Residential Zone	Amend Chapter heading	SUB-RES – Subdivision in <u>the General Residential Zones</u>								
	SUB-RES – Subdivision in the General Residential Zone	Delete Issues	Issues SUB-RES I1 — <i>The effects on amenity values of new subdivisions within and adjoining established residential areas.</i> The amount of land suitable for urban use is influenced by servicing, topographical, ecological and other constraints. The General Residential Zone covers the existing residential areas as well as undeveloped land suitable for residential use in the future. Expansion of existing urban areas will be encouraged in appropriate environments with the existing urban areas being the preferred location for higher density development. Council will promote the maintenance of the general character and amenity values of particular neighbourhoods.								
	SUB-RES – Subdivision in the	Amend Objective	SUB-RES-01 The management of the adverse effects of subdivision within residential areas <u>the General Residential Zone.</u>								

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	General Residential Zone		This objective seeks to provide for subdivision which promotes residential amenity values , creates safe and well-designed housing development and promotes the efficient use of natural and physical resources .
	SUB-RES – Subdivision in the General Residential Zone	Add Objective	SUB-RES-O2 <i>A well-functioning Urban Environment that enables all people and communities to provide for their social, economic, and cultural wellbeing, and for their health and safety, now and into the future.</i> [s80H(1)(a)(ii) note: this provision incorporates the objectives in clause 6 of Schedule 3A.]
	SUB-RES – Subdivision in the General Residential Zone	Add Objective	SUB-RES-O3 <i>To encourage the maintenance of indigenous biological diversity values within the Indigenous Biodiversity Precinct.</i>
	SUB-RES – Subdivision in the General Residential Zone	Amend Policy	SUB-RES-P1 <i>To ensure that the scale, appearance design and siting of buildings, structures and activities are compatible with the planned urban built form character and desired amenity values of the area. On the land identified in SUB-RES Figure 2, particular care needs to be taken with the design of any residential subdivision to ensure that it appropriately addresses the interface with Maidstone Park and the adjoining General Industrial Zone.</i>
	SUB-RES – Subdivision in the General Residential Zone	Amend Policy	SUB-RES-P2 <i>To encourage avoiding, remedying and mitigating the actual and potential adverse effects of the subdivision of sites within the Indigenous Biodiversity Precinct to assist in maintaining indigenous biological diversity on land identified in SUB-RES Figure 2 ('Maidstone Terrace Residential') which does not comply with site specific standards controlling the number of allotments and residential units, access from Railway Avenue, boundary setbacks and fencing. On the land identified in SUB-RES Figure 2, particular care needs to be taken with the design of any residential development to ensure that it appropriately addresses the interface with the adjoining General Industrial Mixed Use Zone. In particular, site specific standards apply to the site and compliance with these standards is critical to ensuring that subdivision is appropriate.</i>
	SUB-RES – Subdivision in the General Residential Zone	Amend Policy	SUB-RES-P3 <i>To encourage the protection of trees and vegetation which contribute to the amenity values, landscape values, character, ecological, historical and cultural values within of the Conservation and Hill Precincts Indigenous Biodiversity Precinct. Trees add to the character of residential areas and also have ecological, historical, and cultural values.</i>

Commented [MM28]: S58.42 - Kianga Ora: Homes and Communities.

Commented [MM29]: S58.42 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>The Conservation and Hill Indigenous Biodiversity Precincts have special qualities which merit the protection of trees. They also merit different requirements for encourages the consideration of subdivision to assist in protecting and maintaining their amenity values indigenous biodiversity values as part of the subdivision process. All MDRS subdivision and density standards apply in the Precinct. The Council intends to revisit these issues as part of a future district plan change that will give effect to section 6(c) of the Resource Management Act – <i>the protection of areas of significant indigenous vegetation and significant habitats of indigenous fauna.</i></p>
	SUB-RES – Subdivision in the General Residential Zone	Amend Policy	<p>SUB-RES-P4 <i>To provide for new residential development within the City in a sustainable manner.</i></p> <p>The edge of the urban area is defined primarily by a rural interface. Council generally intends to contain new residential development within the existing zoned urban area. Continuous expansion at the City's edge, while large parts of the urban areas remain undeveloped, does not constitute sustainable management.</p> <p>Greenfield subdivision, for urban residential development outside Residential Zones should be considered by way of a District Plan change to extend the urban area. This enables the full effects of the potential development to be assessed.</p>
	SUB-RES – Subdivision in the General Residential Zone	Amend Policy	<p>SUB-RES-P5 <i>To promote provide for subdivision with a high level of amenity that is compatible with the planned built character urban form of the General Residential Zone, and ensure that it has adequate access to infrastructure and requirements.</i></p> <p>The Plan provides for the intensification of land use within the urban area to accommodate residential development where adverse effects can be avoided, remedied or mitigated.</p> <p>Subdivision requires resource consent because Council may need to impose conditions that relate to provision or co-ordination of services and other matters relating to the sustainable management of resources.</p>
	SUB-RES – Subdivision in the General Residential Zone	Amend Policy	<p>SUB-RES-P6 <i>To encourage provide for higher medium density housing and subdivision within the General Residential Zone, while encouraging the consideration of the protection and retention of indigenous biodiversity values within through the provision of reduced net site area standards and in the form of Comprehensive Residential Developments in identified areas of the City the Indigenous Biodiversity Precinct.</i></p> <p>The Plan identifies areas considered suitable for higher density residential development. These areas are located surrounding the City Centre Zone, around the Trentham neighbourhood centre located at Camp Street, near the Wallaceville railway station from Ward Street to Lane Street and within the Urban Precinct and Grants Bush Precinct of the Wallaceville Structure Plan Development Area.</p>

Commented [MM30]: S58.46 - Kianga Ora: Homes and Communities.

Commented [MM31]: S58.46 - Kianga Ora: Homes and Communities.

Commented [MM32]: S58.47 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>These areas are in close proximity to retail and service facilities as well as the availability of major transport points, including rail and bus services, and a major bus terminal in the CBD.</p> <p>The reduction of net site area standards in the Residential Centres Precinct recognises a minimum site area Council is prepared to allow for housing development. Any reduction below this minimum net site area is provided for as a discretionary activity and will be assessed against the Design Guide for Comprehensive Residential Development so as to ensure that any subdivision or development below this net site area can still achieve a high quality.</p>
	SUB-RES – Subdivision in the General Residential Zone	Add Policy	<p>SUB-RES-P7 <i>Encourage development to achieve attractive and safe streets and public open spaces, including by providing for passive surveillance.</i></p> <p>[s80H(1)(a)(ii) note: this provision incorporates the policies in clause 6 of Schedule 3A of the Act]</p>
	SUB-RES – Subdivision in the General Residential Zone	Add Policy	<p>SUB-RES-P8 <i>Enable housing to be designed to meet the day-to-day needs of residents.</i></p> <p>[s80H(1)(a)(ii) note: this provision incorporates the policies in clause 6 of Schedule 3A of the Act]</p>
	SUB-RES – Subdivision in the General Residential Zone	Add Policy	<p>SUB-RES-P9 <i>New residential subdivision and buildings will avoid, remedy, or mitigate potential reverse sensitivity effects on existing lawfully-established non-residential activities. Potential methods include but are not limited to:</i></p> <ul style="list-style-type: none"> a. <i>Requiring noise mitigation, vibration, insulation, and ventilation for residential units;</i> b. <i>Specifying the location of private and communal outdoor living spaces;</i> c. <i>Specifying the location and function of windows;</i> d. <i>Requiring the provision of buffer areas, setbacks, and no-build areas;</i> e. <i>Specifying fencing and landscaping requirements.</i> <p>SUB-RES-P9 – Provide for developments not meeting permitted activity status, while encouraging high quality developments.</p> <p>[s80H(1)(a)(ii) note: this provision incorporates the policies in clause 6 of Schedule 3A of the Act]</p>
	New SUB-RES - Subdivision in the General Residential Zone	Add District Wide Matters table	<p>Rules</p> <p>District-wide matters</p>

Commented [MM33]: Clause 99, Schedule 1 RMA.

Commented [MM34]: S58.50 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS																								
#	Chapter	Change	Track Change																					
			<p>Subdivision within the General Residential Zone must comply with all relevant rules and standards for qualifying matter areas, and all relevant rules and standards in the District-wide matters and qualifying matter areas of the Plan as listed below:</p> <table border="1"> <tr> <td>District-wide matters</td> </tr> <tr> <td><u>TEMP - Temporary Activities</u></td> </tr> <tr> <td><u>SIGN - Signs</u></td> </tr> <tr> <td><u>EW - Earthworks</u></td> </tr> <tr> <td><u>NATC – Natural Character</u></td> </tr> <tr> <td><u>DC – Development Contributions</u></td> </tr> <tr> <td><u>HH - Historical Heritage</u></td> </tr> <tr> <td><u>TREE - Notable Trees</u></td> </tr> <tr> <td><u>UTG - Urban Tree Groups</u></td> </tr> <tr> <td><u>ECO - Ecosystems and Indigenous Biodiversity</u></td> </tr> <tr> <td><u>NFL - Natural Features and Landscapes</u></td> </tr> <tr> <td><u>PA – Public Access</u></td> </tr> <tr> <td><u>PK - Papakāinga</u></td> </tr> <tr> <td><u>ASW - Activities on the Surface of Water</u></td> </tr> <tr> <td><u>NU – Network Utilities</u></td> </tr> <tr> <td><u>REG - Renewable Energy Generation</u></td> </tr> <tr> <td><u>TP – Transport and Parking</u></td> </tr> <tr> <td><u>NOISE - Noise</u></td> </tr> <tr> <td><u>NH - Natural Hazards</u></td> </tr> <tr> <td><u>CL – Contaminated Land</u></td> </tr> <tr> <td><u>HS - Hazardous Substances</u></td> </tr> </table>	District-wide matters	<u>TEMP - Temporary Activities</u>	<u>SIGN - Signs</u>	<u>EW - Earthworks</u>	<u>NATC – Natural Character</u>	<u>DC – Development Contributions</u>	<u>HH - Historical Heritage</u>	<u>TREE - Notable Trees</u>	<u>UTG - Urban Tree Groups</u>	<u>ECO - Ecosystems and Indigenous Biodiversity</u>	<u>NFL - Natural Features and Landscapes</u>	<u>PA – Public Access</u>	<u>PK - Papakāinga</u>	<u>ASW - Activities on the Surface of Water</u>	<u>NU – Network Utilities</u>	<u>REG - Renewable Energy Generation</u>	<u>TP – Transport and Parking</u>	<u>NOISE - Noise</u>	<u>NH - Natural Hazards</u>	<u>CL – Contaminated Land</u>	<u>HS - Hazardous Substances</u>
District-wide matters																								
<u>TEMP - Temporary Activities</u>																								
<u>SIGN - Signs</u>																								
<u>EW - Earthworks</u>																								
<u>NATC – Natural Character</u>																								
<u>DC – Development Contributions</u>																								
<u>HH - Historical Heritage</u>																								
<u>TREE - Notable Trees</u>																								
<u>UTG - Urban Tree Groups</u>																								
<u>ECO - Ecosystems and Indigenous Biodiversity</u>																								
<u>NFL - Natural Features and Landscapes</u>																								
<u>PA – Public Access</u>																								
<u>PK - Papakāinga</u>																								
<u>ASW - Activities on the Surface of Water</u>																								
<u>NU – Network Utilities</u>																								
<u>REG - Renewable Energy Generation</u>																								
<u>TP – Transport and Parking</u>																								
<u>NOISE - Noise</u>																								
<u>NH - Natural Hazards</u>																								
<u>CL – Contaminated Land</u>																								
<u>HS - Hazardous Substances</u>																								

Commented [MM35]: S27.17 - Transpower New Zealand Ltd.
This is a consequential amendment to this submission point.

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<table border="1"> <tr><td>WM – Waste Management</td></tr> <tr><td>AIR - Air</td></tr> <tr><td>LIGHT - Light</td></tr> </table>	WM – Waste Management	AIR - Air	LIGHT - Light	
WM – Waste Management							
AIR - Air							
LIGHT - Light							
	SUB-RES – Subdivision in the General Residential Zone	Amend Rule	<table border="1"> <thead> <tr> <th>Controlled Activities</th> <th>Zones</th> </tr> </thead> <tbody> <tr> <td> <p>SUB-RES-R1</p> <p>Polities UDF-P1, UDF-P2 SUB-GEN-P1 SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P4, SUB-RES-P1 SUB-RES-P2, SUB-RES-P3, SUB-RES-P4, SUB-RES-P5, SUB-RES-P6, SUB-RES-P7, SUB-RES-P8, SUB-RES-P9 SUB-GEN-P9, SUB-GEN-P10, NATC-P1, TP-P4, DC-P1 GRZ-P1A, GRZ-P1B, GRZ-P1C, GRZ-P1D, GRZ-P1, GRZ-P2, GRZ-P3, GRZ-P5, GRZ-P6, GRZ-P8, GRZ-P9,</p> </td> <td> <p>CON <i>General Residential</i></p> <p>Subdivision within the General Residential Zone of:</p> <p>1. <u>Any allotment with an existing residential unit, if:</u></p> <p>A. <u>Either the subdivision does not increase the degree of any non-compliance with any of the following rules and standards:</u></p> <p>(a) <u>GRZ-R2;</u></p> <p>(b) <u>GRZ-S3 – Building coverage;</u></p> <p>(c) <u>GRZ-S4 – Setbacks;</u></p> <p>(d) <u>GRZ-S5 – Outdoor living space;</u></p> <p>(e) <u>GRZ-S7 – Building height;</u></p> <p>(f) <u>GRZ – S8 – Height in relation to boundary;</u></p> <p>(g) <u>GRZ – S13 – Number of residential units per site;</u></p> <p>(h) <u>GRZ – S14 – Outlook space;</u></p> <p>(i) <u>GRZ – S15 – Windows to street;</u></p> <p>(j) <u>GRZ – S16 – Landscaped area; or</u></p> <p>i. <u>land use consent has been granted; and</u></p> <p>B. <u>no vacant allotments are created;</u></p> <p>2. <u>Any allotment with no existing residential unit, where a subdivision application is accompanied by a land use application that will be determined concurrently if the applicant for the resource consent can demonstrate that:</u></p> </td> </tr> </tbody> </table>	Controlled Activities	Zones	<p>SUB-RES-R1</p> <p>Polities UDF-P1, UDF-P2 SUB-GEN-P1 SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P4, SUB-RES-P1 SUB-RES-P2, SUB-RES-P3, SUB-RES-P4, SUB-RES-P5, SUB-RES-P6, SUB-RES-P7, SUB-RES-P8, SUB-RES-P9 SUB-GEN-P9, SUB-GEN-P10, NATC-P1, TP-P4, DC-P1 GRZ-P1A, GRZ-P1B, GRZ-P1C, GRZ-P1D, GRZ-P1, GRZ-P2, GRZ-P3, GRZ-P5, GRZ-P6, GRZ-P8, GRZ-P9,</p>	<p>CON <i>General Residential</i></p> <p>Subdivision within the General Residential Zone of:</p> <p>1. <u>Any allotment with an existing residential unit, if:</u></p> <p>A. <u>Either the subdivision does not increase the degree of any non-compliance with any of the following rules and standards:</u></p> <p>(a) <u>GRZ-R2;</u></p> <p>(b) <u>GRZ-S3 – Building coverage;</u></p> <p>(c) <u>GRZ-S4 – Setbacks;</u></p> <p>(d) <u>GRZ-S5 – Outdoor living space;</u></p> <p>(e) <u>GRZ-S7 – Building height;</u></p> <p>(f) <u>GRZ – S8 – Height in relation to boundary;</u></p> <p>(g) <u>GRZ – S13 – Number of residential units per site;</u></p> <p>(h) <u>GRZ – S14 – Outlook space;</u></p> <p>(i) <u>GRZ – S15 – Windows to street;</u></p> <p>(j) <u>GRZ – S16 – Landscaped area; or</u></p> <p>i. <u>land use consent has been granted; and</u></p> <p>B. <u>no vacant allotments are created;</u></p> <p>2. <u>Any allotment with no existing residential unit, where a subdivision application is accompanied by a land use application that will be determined concurrently if the applicant for the resource consent can demonstrate that:</u></p>
Controlled Activities	Zones						
<p>SUB-RES-R1</p> <p>Polities UDF-P1, UDF-P2 SUB-GEN-P1 SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P4, SUB-RES-P1 SUB-RES-P2, SUB-RES-P3, SUB-RES-P4, SUB-RES-P5, SUB-RES-P6, SUB-RES-P7, SUB-RES-P8, SUB-RES-P9 SUB-GEN-P9, SUB-GEN-P10, NATC-P1, TP-P4, DC-P1 GRZ-P1A, GRZ-P1B, GRZ-P1C, GRZ-P1D, GRZ-P1, GRZ-P2, GRZ-P3, GRZ-P5, GRZ-P6, GRZ-P8, GRZ-P9,</p>	<p>CON <i>General Residential</i></p> <p>Subdivision within the General Residential Zone of:</p> <p>1. <u>Any allotment with an existing residential unit, if:</u></p> <p>A. <u>Either the subdivision does not increase the degree of any non-compliance with any of the following rules and standards:</u></p> <p>(a) <u>GRZ-R2;</u></p> <p>(b) <u>GRZ-S3 – Building coverage;</u></p> <p>(c) <u>GRZ-S4 – Setbacks;</u></p> <p>(d) <u>GRZ-S5 – Outdoor living space;</u></p> <p>(e) <u>GRZ-S7 – Building height;</u></p> <p>(f) <u>GRZ – S8 – Height in relation to boundary;</u></p> <p>(g) <u>GRZ – S13 – Number of residential units per site;</u></p> <p>(h) <u>GRZ – S14 – Outlook space;</u></p> <p>(i) <u>GRZ – S15 – Windows to street;</u></p> <p>(j) <u>GRZ – S16 – Landscaped area; or</u></p> <p>i. <u>land use consent has been granted; and</u></p> <p>B. <u>no vacant allotments are created;</u></p> <p>2. <u>Any allotment with no existing residential unit, where a subdivision application is accompanied by a land use application that will be determined concurrently if the applicant for the resource consent can demonstrate that:</u></p>						

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>GRZ-R10</p> <p>A. <u>It is practicable to construct on every allotment within the proposed subdivision, as a permitted activity, a residential unit; and</u></p> <p>B. <u>Each residential unit complies with the following rules and standards:</u></p> <ul style="list-style-type: none"> (a) <u>GRZ-R2;</u> (b) <u>GRZ-S3 – Building coverage;</u> (c) <u>GRZ-S4 – Setbacks;</u> (d) <u>GRZ-S5 – Outdoor living space;</u> (e) <u>GRZ-S7 – Building height;</u> (f) <u>GRZ – S8 – Height in relation to boundary;</u> (g) <u>GRZ – S13 – Number of residential units per site;</u> (h) <u>GRZ – S14 – Outlook space;</u> (i) <u>GRZ – S15 – Windows to street;</u> (j) <u>GRZ – S16 – Landscaped area; and</u> <p>C. <u>No vacant allotments are created.</u></p> <p>Notification</p> <p><u>Public and limited notification of an application for resource consent under this rule is precluded.</u></p> <p>Subdivision which complies with the standards in SUB-RES-S1, SUB-RES-S3.</p> <p>Council may impose conditions over the following matters:</p> <ul style="list-style-type: none"> (1) Design, appearance and layout of the subdivision (excluding any minimum size or shape-related subdivision requirements). (2) Landscaping. (3) Provision of and effects on network utilities and/or services.

Commented [MM36]: S58.51 - Kianga Ora: Homes and Communities.

Commented [MM37]: S58.52 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(43) Standard, construction and layout of vehicular access.</p> <p>(54) Earthworks.</p> <p>(65) Provision of esplanade reserves and strips.</p> <p>(76) Protection of any special amenity feature.</p> <p>(87) Financial contributions.</p> <p>(98) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-RES-R7 covers subdivision within the Electricity Transmission Corridor.</p> <p>(109) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site.</p> <p>(10) <u>The matters contained within the Council's Code of Practice for Civil Engineering Works.</u></p> <p>In relation to the land identified in SUB-RES Figure 1 Council may impose conditions over the following matters:</p> <p>(11) Landscape character and visual amenity.</p>
	SUB-RES – Subdivision in the General Residential Zone	Amend Rule	<p>SUB-RES-R2</p> <p><i>Policies</i> <i>UDF-P1,</i> <i>UDF-P2,</i> <i>SUB-GEN-P1,</i> <i>SUB-GEN-P2,</i> <i>SUB-GEN-P3,</i> <i>SUB-GEN-P4,</i> <i>SUB-RES-P1,</i> <i>SUB-RES-P2,</i> <i>SUB-RES-P3,</i> <i>SUB-RES-P4.</i></p> <p>Subdivision that proposes to create one or more vacant allotments.</p> <p>around any existing lawfully established residential unit which does not result in the creation of any new undeveloped site that contains no residential unit.</p> <p>Note: this form of subdivision does not need to comply with the minimum net site area requirements of rule 19.5 SUB-RES S1, but does need to meet the access standards of rule SUB-RES S3</p> <p>Council may impose conditions over the following matters:</p> <p>(1) Design, appearance and layout of the subdivision.</p>

Commented [MM38]: S56.10 - Fire and Emergency New Zealand.

Commented [MM40]: S58.53 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>SUB-RES-P5, SUB-RES-P6, SUB-RES-P7, SUB-RES-P8, SUB-GEN-P9, SUB-GEN-P10, NATC-P1, TP-P4, DC-P1 GRZ-P1A, GRZ-P1B, GRZ-P1C, GRZ-P1D, GRZ-P1, GRZ-P2, GRZ-P3, GRZ-P5, GRZ-P6, GRZ-P8, GRZ-P9, GRZ-P10,</p> <p>(2) Landscaping.</p> <p>(32) Provision of and effects on network utilities and/or services.</p> <p>(43) Standard, construction and layout of vehicular access.</p> <p>(54) Earthworks.</p> <p>(65) Provision of esplanade reserves and strips.</p> <p>(76) Protection of any special amenity feature.</p> <p>(87) Financial contributions.</p> <p>(98) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-RES-R7 covers subdivision within the Electricity Transmission Corridor.</p> <p>(109) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site.</p> <p>(10) The matters contained within the Council's Code of Practice for Civil Engineering Works</p>
	SUB-RES – Subdivision in the General Residential Zone	Delete Rule	<p>SUB-RES-R4</p> <p><i>Policies</i> SUB-GEN-P1, SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P4, SUB-RES-P1, SUB-RES-P2, SUB-RES-P5, SUB-RES-P6, SUB-GEN-P9, SUB-GEN-P10, NATC-P1, TP-P4, DC-P1</p> <p>Subdivision which is a unit title subdivision or an alteration to a company lease, unit title or cross lease title to include a building extension or alteration or accessory building on the site (excluding an additional residential unit) that has been lawfully established in terms of the Building Act 2004</p> <p>Council may impose conditions over the following matters:</p> <p>(1) Design, appearance and layout of the subdivision.</p> <p>(2) Landscaping.</p> <p>(3) Provision of and effects on network utilities and/or services.</p> <p>(4) Standard, construction and layout of vehicular access.</p> <p>(5) Earthworks.</p>

Commented [MM41]: S58.53 - Kianga Ora: Homes and Communities.

Commented [MM39]: S58.51 - Kianga Ora: Homes and Communities.

Commented [MM42]: S56.10 - Fire and Emergency New Zealand.

IPI - PROPOSED AMENDMENTS																				
#	Chapter	Change	Track Change																	
			<p>(6) Provision of esplanade reserves and strips.</p> <p>(7) Protection of any special amenity feature.</p> <p>(8) Financial contributions.</p> <p>(9) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-RES-R7 covers subdivision within the Electricity Transmission Corridor.</p> <p>(10) The outcome of consultation with the owner or operator of consented or existing renewable energy generation activities located on or in proximity to the site.</p> <p>(11) Allocation of accessory units to principal units and covenant areas to leased areas to ensure compliance with car park provisions and to ensure practical physical access to units.</p> <p>(12) Allocation of areas.</p> <p>Controlled activities – restrictions on notification Subject to sections 95A(2)(b), 95A(2)(c), 95A(4) and 95C of the Act, a resource consent application for a controlled activity is precluded from public notification under section 95A and, subject to section 95B(3), is precluded from limited notification under section 95B(2) of the Act.</p>																	
	SUB-RES – Subdivision in the General Residential Zone	Amend Standard	<table border="1"> <thead> <tr> <th colspan="5">Standards for Controlled Activities</th> <th>Zone</th> </tr> </thead> <tbody> <tr> <td rowspan="2"> SUB-RES-S1 <i>Policies</i> SUB-RES-P2 SUB-RES-P3, SUB-RES-P6 NAAC-P1, GRZ-P1A, GRZ-P1B, GRZ-P1C, GRZ-P1D, GRZ-P1 UDF-P1 </td> <td colspan="4">Minimum requirements for subdivision creating one or more vacant allotments:</td> <td rowspan="2">General Residential</td> </tr> <tr> <td>General Residential Zone subdivision under SUB-RES-R2.</td> <td>Front allotments</td> <td>Rear allotments</td> <td>Corner allotments</td> <td>Land Identified in SUB-RES-Figure 1</td> </tr> </tbody> </table>	Standards for Controlled Activities					Zone	SUB-RES-S1 <i>Policies</i> SUB-RES-P2 SUB-RES-P3, SUB-RES-P6 NAAC-P1, GRZ-P1A, GRZ-P1B, GRZ-P1C, GRZ-P1D, GRZ-P1 UDF-P1	Minimum requirements for subdivision creating one or more vacant allotments :				General Residential	General Residential Zone subdivision under SUB-RES-R2.	Front allotments	Rear allotments	Corner allotments	Land Identified in SUB-RES-Figure 1
Standards for Controlled Activities					Zone															
SUB-RES-S1 <i>Policies</i> SUB-RES-P2 SUB-RES-P3, SUB-RES-P6 NAAC-P1, GRZ-P1A, GRZ-P1B, GRZ-P1C, GRZ-P1D, GRZ-P1 UDF-P1	Minimum requirements for subdivision creating one or more vacant allotments :				General Residential															
	General Residential Zone subdivision under SUB-RES-R2.	Front allotments	Rear allotments	Corner allotments		Land Identified in SUB-RES-Figure 1														

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change																																																																						
			<p>UDF-P2, UDF-P3, UDF-P4, SUB-RES-P5, SUB-RES-P6, SUB-RES-P7, SUB-RES-P8, SUB-RES-P9.</p> <table border="1"> <tr> <td>Minimum net site area</td> <td>400m²</td> <td>400m²</td> <td>450m²</td> <td>600m² (900m² average)</td> </tr> <tr> <td>Minimum frontage</td> <td>6m</td> <td>N/A</td> <td>6m</td> <td>N/A</td> </tr> <tr> <td>Shape factor</td> <td>12m</td> <td>12m</td> <td>12m</td> <td>12m</td> </tr> <tr> <td colspan="5">Precinct 1 – Residential Centres Precinct</td> </tr> <tr> <td>Minimum net site area</td> <td>300m²</td> <td>300m²</td> <td>350m²</td> <td>N/A</td> </tr> <tr> <td>Minimum net site area for Comprehensive Residential Developments</td> <td>No minimum</td> <td>No minimum</td> <td>No minimum</td> <td>N/A</td> </tr> <tr> <td>Minimum frontage</td> <td>6m</td> <td>N/A</td> <td>6m</td> <td>N/A</td> </tr> <tr> <td>Shape factor</td> <td>10m</td> <td>10m</td> <td>10m</td> <td>N/A</td> </tr> <tr> <td colspan="5">2 – Residential Hill and Residential Conservation Precinct</td> </tr> <tr> <td>Minimum net site area</td> <td>750m²</td> <td>900m²</td> <td>750m²</td> <td>900m² (1500m² average)</td> </tr> <tr> <td>Minimum frontage</td> <td>6m</td> <td>N/A</td> <td>6m</td> <td>N/A</td> </tr> <tr> <td>Shape factor</td> <td>17m</td> <td>17m</td> <td>17m</td> <td>17m</td> </tr> <tr> <td colspan="5">Exemptions</td> </tr> <tr> <td colspan="5">These standards shall not apply to any allotment for utility, reserve or conservation purposes.</td> </tr> </table>	Minimum net site area	400m ²	400m ²	450m ²	600m ² (900m ² average)	Minimum frontage	6m	N/A	6m	N/A	Shape factor	12m	12m	12m	12m	Precinct 1 – Residential Centres Precinct					Minimum net site area	300m ²	300m ²	350m ²	N/A	Minimum net site area for Comprehensive Residential Developments	No minimum	No minimum	No minimum	N/A	Minimum frontage	6m	N/A	6m	N/A	Shape factor	10m	10m	10m	N/A	2 – Residential Hill and Residential Conservation Precinct					Minimum net site area	750m ²	900m ²	750m ²	900m ² (1500m ² average)	Minimum frontage	6m	N/A	6m	N/A	Shape factor	17m	17m	17m	17m	Exemptions					These standards shall not apply to any allotment for utility, reserve or conservation purposes.				
Minimum net site area	400m ²	400m ²	450m ²	600m ² (900m ² average)																																																																					
Minimum frontage	6m	N/A	6m	N/A																																																																					
Shape factor	12m	12m	12m	12m																																																																					
Precinct 1 – Residential Centres Precinct																																																																									
Minimum net site area	300m ²	300m ²	350m ²	N/A																																																																					
Minimum net site area for Comprehensive Residential Developments	No minimum	No minimum	No minimum	N/A																																																																					
Minimum frontage	6m	N/A	6m	N/A																																																																					
Shape factor	10m	10m	10m	N/A																																																																					
2 – Residential Hill and Residential Conservation Precinct																																																																									
Minimum net site area	750m ²	900m ²	750m ²	900m ² (1500m ² average)																																																																					
Minimum frontage	6m	N/A	6m	N/A																																																																					
Shape factor	17m	17m	17m	17m																																																																					
Exemptions																																																																									
These standards shall not apply to any allotment for utility, reserve or conservation purposes.																																																																									

Commented [MM43]: S58.51 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
	SUB-RES – Subdivision in the General Residential Zone	Delete Standard	<p>SUB-RES-S2</p> <p><i>Policies</i></p> <p>SUB-RES-P1,</p> <p>SUB-RES-P2</p>	<p>Maximum number of allotments and residential units along Maidstone Terrace</p> <p>In relation to the land identified as Area B in SUB-RES Figure 2,</p> <p>(1) There shall be no more than 12 residential units. To avoid any doubt:</p> <p style="padding-left: 20px;">a. The maximum is not the maximum number of residential units on any particular site.</p> <p>(2) There shall be no more than 12 allotments</p>	<p>General Residential – SUB-Figure2</p>
	SUB-RES – Subdivision in the General Residential Zone	Amend Standard	<p>SUB-RES-S3</p> <p><i>Policies</i></p> <p>SUB-GEN-P1,</p> <p>SUB-RES-P1,</p> <p>SUB-RES-P2,</p> <p>SUB-RES-P6,</p> <p>TP-P4</p>	<p>Access standards for subdivision</p> <p>(1) Where vehicle access ...</p> <p>(2) All accessways and ...</p> <p>(3) Sites shall have ...</p> <p>(4) Vehicular access to a ...</p> <div style="text-align: center;"> <p>The diagram illustrates a building footprint with a driveway leading to a road reserve. A vertical dimension line on the right side of the driveway indicates a minimum distance of 8m from the building to the road reserve.</p> </div> <p>(5) Where a corner allotment is ...</p> <p>(6) At the intersection of ...</p>	<p>General Residential</p>

Commented [MM44]: S58.51 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS											
#	Chapter	Change	Track Change								
			<p>(7) Subdivision with direct ...</p> <p>(8) In relation to the land identified in SUB Figure 2:</p> <p>(a) There will be no access off Maidstone Terrace. Access to the land shall be off Railway Avenue.</p> <p>(b) Neither a right of way, private way or legal boundary of any road or accessway serving the land shall at any point encroach within Area B of SUB Figure 2.</p>								
	SUB-RES – Subdivision in the General Residential Zone	Amend Rule	<table border="1"> <thead> <tr> <th colspan="2">Restricted Discretionary Activities</th> <th colspan="2">Zones</th> </tr> </thead> <tbody> <tr> <td>SUB-RES-R6</td> <td> <p>Subdivision that is not a controlled activity under rule SUB-RES-R1; and subdivision that does not comply with one or more of the standards under SUB-RES-S1 (1).</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <p><u>(1) Design, appearance and layout of the subdivision.</u></p> <p>(2) Landscaping.</p> <p><u>(3) Provision of and effects on network utilities and/or services.</u></p> <p><u>(4) Standard, construction and layout of vehicular access.</u></p> <p><u>(5) Earthworks.</u></p> <p><u>(6) Provision of esplanade reserves and esplanade strips.</u></p> <p><u>(7) Protection of any special amenity feature.</u></p> <p><u>(8) Financial contributions.</u></p> <p><u>(9) The outcome of consultation with the owner of operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-RES-R7 covers subdivision within the Electricity Transmission Corridor.</u></p> </td> <td>RDIS</td> <td><i>General Residential</i></td> </tr> </tbody> </table> <p><i>Policies</i> SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P4, SUB-RES-P1, SUB-RES-P4, SUB-RES-P5, SUB-RES-P7, SUB-RES-P8, SUB-RES-P9, SUB-GEN-P9, SUB-GEN-P10, SUB-GEN-P12, NATC-P1</p>	Restricted Discretionary Activities		Zones		SUB-RES-R6	<p>Subdivision that is not a controlled activity under rule SUB-RES-R1; and subdivision that does not comply with one or more of the standards under SUB-RES-S1 (1).</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <p><u>(1) Design, appearance and layout of the subdivision.</u></p> <p>(2) Landscaping.</p> <p><u>(3) Provision of and effects on network utilities and/or services.</u></p> <p><u>(4) Standard, construction and layout of vehicular access.</u></p> <p><u>(5) Earthworks.</u></p> <p><u>(6) Provision of esplanade reserves and esplanade strips.</u></p> <p><u>(7) Protection of any special amenity feature.</u></p> <p><u>(8) Financial contributions.</u></p> <p><u>(9) The outcome of consultation with the owner of operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-RES-R7 covers subdivision within the Electricity Transmission Corridor.</u></p>	RDIS	<i>General Residential</i>
Restricted Discretionary Activities		Zones									
SUB-RES-R6	<p>Subdivision that is not a controlled activity under rule SUB-RES-R1; and subdivision that does not comply with one or more of the standards under SUB-RES-S1 (1).</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <p><u>(1) Design, appearance and layout of the subdivision.</u></p> <p>(2) Landscaping.</p> <p><u>(3) Provision of and effects on network utilities and/or services.</u></p> <p><u>(4) Standard, construction and layout of vehicular access.</u></p> <p><u>(5) Earthworks.</u></p> <p><u>(6) Provision of esplanade reserves and esplanade strips.</u></p> <p><u>(7) Protection of any special amenity feature.</u></p> <p><u>(8) Financial contributions.</u></p> <p><u>(9) The outcome of consultation with the owner of operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-RES-R7 covers subdivision within the Electricity Transmission Corridor.</u></p>	RDIS	<i>General Residential</i>								

Commented [MM46]: 58.56 - Kianga Ora: Homes and Communities.

Commented [MM47]: 58.56 - Kianga Ora: Homes and Communities.

Commented [MM45]: 58.51 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(409) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site.</p> <p>(10) The matters contained within the Council's Code of Practice for Civil Engineering Works.</p> <p>(11) Reverse sensitivity effects.</p> <p>around any existing lawfully established residential unit that does not result in the creation of any new undeveloped site that contains no residential unit, that does not comply with the access standards of SUB-RES-S3.</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <p>(1) The extent to which the activity will adversely affect traffic and pedestrian safety.</p> <p>(2) The extent to which the activity will adversely affect the efficient functioning of the roading network.</p> <p>Council's restriction is also restricted to the matters listed in SUB-RES-R1.</p>
	SUB-RES – Subdivision in the General Residential Zone	Amend Rule	<p>SUB-RES-R8</p> <p><i>Policies</i> SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P4, SUB-RES-P5, SUB-GEN-P9, SUB-GEN-P10, NATC-P1</p> <p>Subdivision within the Ponding Area of the Pinehaven Flood Hazard Extent, which creates any undeveloped allotments that do not contain a residential unit, and complies with the requirements of SUB-RES-S1 and SUB-RES-S4.</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <p>(1) The matters listed in SUB-RES-R1. Design, appearance and layout of the subdivision.</p> <p>(2) Landscaping.</p> <p>(3) Provision of and effects on network utilities and/or services.</p> <p>(4) Standard, construction and layout of vehicular access.</p> <p>(5) Earthworks.</p> <p>(6) Provision of esplanade reserves and esplanade strips.</p> <p>RDIS <i>General Residential</i></p>

Commented [MM48]: S56.10 - Fire and Emergency New Zealand.

Commented [MM50]: S58.58 - Kianga Ora: Homes and Communities.

Commented [MM51]: S58.58 - Kianga Ora: Homes and Communities.

Commented [MM49]: S58.51 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(76) Protection of any special amenity feature.</p> <p>(87) Financial contributions.</p> <p>(98) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-RES-R7 covers subdivision within the Electricity Transmission Corridor.</p> <p>(109) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site.</p> <p>(110) The appropriateness of the proposed building platform in terms of area and location in relation to the flood hazard.</p> <p>(121) Ability for a future residential unit to be constructed above the 1 in 100-year flood level.</p> <p>(132) The effect of the future development of the building platform on the Pinehaven flood hazard extent.</p> <p>(143) Consent notice restricting the future development to the identified platform.</p> <p>(154) Matters addressing the standards for access under SUB-RES-S3 where any standards are not met.</p> <p>(15) <u>The matters contained within the Council's Code of Practice for Civil Engineering Works</u></p>
	SUB-RES – Subdivision in the General Residential Zone	Amend Rule	<p>SUB-RES-R9</p> <p><i>Policies</i> SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P4, SUB-RES-P5, SUB-GEN-P9, SUB-GEN-P10, NATC-P1</p> <p>Subdivision of a site within the Pinehaven Catchment Overlay that complies with the requirements of SUB-RES-S5</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <p>(1) The matters listed in SUB-RES-R1 Design, appearance and layout of the subdivision.</p> <p>(2) Landscaping.</p> <p>(32) Provision of and effects on network utilities and/or services.</p>

Commented [MM52]: S56.10 - Fire and Emergency New Zealand.

Commented [MM54]: S58 - Kianga Ora: Homes and Communities.

Commented [MM55]: S58.58 - Homes and Communities.

Commented [MM53]: S58.51 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(43) Standard, construction and layout of vehicular access.</p> <p>(54) Earthworks.</p> <p>(65) Provision of esplanade reserves and esplanade strips.</p> <p>(76) Protection of any special amenity feature.</p> <p>(87) Financial contributions.</p> <p>(98) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-RES-R7 covers subdivision within the Electricity Transmission Corridor.</p> <p>(109) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site.</p> <p>(140) Ability for the subdivision and proposed design to ensure peak flow of stormwater discharge will be no greater than pre subdivision levels and thus achieve hydraulic neutrality.</p> <p>(121) The effect of the subdivision on the Pinehaven Flood Hazard Extent.</p> <p>(132) Recommendations and mitigation measures of the hydraulic report.</p> <p>(143) Consent notice restricting the future development of the allotment to the design and recommendations of the hydraulic neutrality report.</p> <p>(154) Matters addressing the standards for access under SUB-RES-S3 where any standards are not met.</p> <p>(15) The matters contained within the Council's Code of Practice for Civil Engineering Works</p>
	SUB-RES – Subdivision in the General Residential Zone	Amend Rule	<p>SUB-RES-R10</p> <p><i>Policies</i> <i>SUB-GEN-P2,</i> <i>SUB-GEN-P3,</i> <i>SUB-GEN-P4,</i> <i>SUB-RES-P5,</i> <i>SUB-GEN-P9,</i></p> <p>Subdivision within the Ponding Area or Erosion Hazard Area of the Mangaroa Flood Hazard Extent, which results in any undeveloped allotment that contain no residential unit or non-residential building, and complies with the requirements of SUB-RES-S1 and SUB-RES-S6.</p> <p>Council will restrict its discretion to, and may impose conditions on:</p>
			<p>RDIS <i>General Residential</i></p>

Commented [MM56]: S56.10 - Fire and Emergency New Zealand.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>SUB-GEN-R10, NATC (R1)</p> <p>(1) The matters listed in SUB-RES-R1: <u>Design, appearance</u> and layout of the <u>subdivision</u>.</p> <p>(2) Landscaping.</p> <p>(32) Provision of and effects on network utilities and/or services.</p> <p>(43) Standard, construction and layout of vehicular access.</p> <p>(54) Earthworks.</p> <p>(65) Provision of esplanade reserves and esplanade strips.</p> <p>(76) Protection of any special amenity feature.</p> <p>(87) Financial contributions.</p> <p>(98) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-RES-R7 covers subdivision within the Electricity Transmission Corridor.</p> <p>(109) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site.</p> <p>(140) The appropriateness of the proposed building platform in terms of area and location and erosion risk in relation to the flood hazard.</p> <p>(121) Ability for a future residential unit to be constructed above the 1 in 100 year flood level.</p> <p>(132) The effect of the future development of the building platform on the function of the floodplain.</p> <p>(143) Consent notice restricting the future development to the identified platform.</p> <p>(154) Matters addressing the standards for access under SUB-RES-S3 where any standards are not met.</p>

Commented [MM58]: S58.58 - Kianga Ora: Homes and Communities.

Commented [MM57]: S58.51 - Kianga Ora: Homes and Communities.

Commented [MM59]: S58.58 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			(15) The matters contained within the Council's Code of Practice for Civil Engineering Works
	SUB-RES – Subdivision in the General Residential Zone	Delete Rule	<p>SUB-RES-R11</p> <p><i>Policies</i> SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P4, SUB-RES-P1, SUB-RES-P5, SUB-RES-P6, SUB-GEN-P9, SUB-GEN-P10, NATC-P1, GRZ-P1, GRZ-P4</p> <p>Subdivision of a Comprehensive Residential Development applied for concurrently with a Comprehensive Residential Development under Rule GRZ-PREC1-R3 that also complies with the requirements of SUB-RES-S7.</p> <p>Note: Comprehensive Residential Development within the Residential Centres Precinct is not subject to the minimum net site area requirements of GRZ-S2</p> <p>For subdivision of a Comprehensive Residential Development under this Rule, Council's discretion is also limited to the matters specified in this rule, but not the standards and terms.</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <ol style="list-style-type: none"> (1) Site layout, design and external appearance. (2) Provision of and effects on network utilities and/or services. (3) Landscaping. (4) Standard, construction and layout of vehicular access. (5) Protection of any special amenity feature. (6) Financial contributions. (7) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-RES-R7 covers subdivision within the Electricity Transmission Corridor. <p>In relation to the land identified in SUB-RES Figure 2, Council will restrict its discretion to and may impose conditions over the following matters:</p> <ol style="list-style-type: none"> (8) The measures necessary to address the interface of any residential development with both Maidstone Park and the General Industrial Zone. These may include, but are not limited to:
			RDIS <i>General Residential – Residential Centres Precinct</i>

Commented [MM60]: S56.10 - Fire and Emergency New Zealand.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(a) the orientation of residential units and the location of habitable rooms relative to Maidstone Park and adjacent General Industrial zoned properties;</p> <p>(b) the orientation of buildings, fences, or landscaping to buffer outdoor living spaces from adjacent General Industrial zoned properties.</p> <p>In considering a resource consent application, Council's discretion is also restricted to an assessment against the Design Guide for the Residential Centres Precinct (refer to Appendix 1) and, where relevant, the Wallaceville Structure Plan (refer to DEV1—Wallaceville Structure Plan Development Area).</p> <p>Restriction on notification</p> <p>In respect of this rule, and subject to sections 95A(2)(b), 95A(4) and 95C of the Act, an application which meets the relevant standards and terms will be decided without the need for public notification under section 95A, but limited notification of an application will still be determined in accordance with section 95B. The restriction in respect of public notification does not apply if the application requires land use consent under any other provision of the Plan.</p> <p>For Comprehensive Residential Development in the Wallaceville Structure Plan Development Area, in respect of this rule, and subject to sections 95A(2)(b), 95A(4) and 95C of the Act, an application which meets the relevant standards and terms will be decided without the need for public notification under section 95A and any application that is consistent with the Wallaceville Structure Plan will be decided without the need for limited notification under section 95B.</p> <p>Notes:</p> <ul style="list-style-type: none"> • A Comprehensive Residential Development that does not comply with the relevant standards and terms for this rule, will be assessed against the relevant Matters for Consideration below. • Notwithstanding this rule any Comprehensive Residential Development on land identified in SUB RES Figure 2 that does not comply with SUB RES S1, SUB RES S2, and SUB RES S3, GRZ PREC1 S5 and/or GRZ PREC1 S9 is a non-complying activity.

IPI - PROPOSED AMENDMENTS						
#	Chapter	Change	Track Change			
	SUB-RES – Subdivision in the General Residential Zone	Delete Rule	<p>SUB-RES-R12</p> <p><i>Policies</i> SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P4, SUB-RES-P1, SUB-RES-P5, SUB-RES-P6, SUB-GEN-P9, SUB-GEN-P10, NATC-P1, GRZ-P1, GRZ-P4</p>	<p>Subdivision in relation to land identified in SUB-RES Figure 2 ('Maidstone Terrace Residential') which complies with standards in SUB-RES-S1, SUB-RES-S2 and SUB-RES-S3.</p> <p>Council will restrict its discretion to:</p> <p>(1) — Design, appearance and layout of the subdivision.</p> <p>(2) — Landscaping.</p> <p>(3) — Provision of and effects on network utilities and/or services.</p> <p>(4) — Standard, construction and layout of vehicular access.</p> <p>(5) — Earthworks.</p> <p>(6) — Provision of esplanade reserves and strips.</p> <p>(7) — Protection of any special amenity feature.</p> <p>(8) — Financial contributions.</p> <p>(9) — The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-RES-R7 covers subdivision within the Electricity Transmission Corridor.</p> <p>(10) — The outcome of consultation with the owner or operator of consented or existing renewable energy generation activities located on or in proximity to the site.</p> <p>(11) — The measures necessary to address the interface of any residential development with both Maidstone Park and the General Industrial Zone. These may include, but are not limited to:</p> <p>(a) — the future orientation of residential units and the location of habitable rooms, relative to the Maidstone Park and</p> <p>(b) — adjacent General Industrial zoned properties;</p>	RDIS	General Residential – SUB-RES-Figure 2

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			<p>(c) the future orientation of buildings, fences or landscaping to buffer outdoor living spaces from adjacent General Industrial-zoned properties;</p> <p>(d) whether the subdivision could result in more than 12 residential units being constructed within Area B in SUB-RES Figure 2; and</p> <p>(e) the imposition of the consent notices to give effect to these matters.</p>						
	SUB-RES – Subdivision in the General Residential Zone	Delete Standard	<table border="1"> <thead> <tr> <th colspan="2">Standards for Restricted Discretionary Activities</th> <th>Zones</th> </tr> </thead> <tbody> <tr> <td> SUB-RES S7 <i>Policies</i> SUB-RES P1, SUB-RES P6, SUB-GEN P9, GRZ P1, GRZ P4, </td> <td> Standards and terms for Comprehensive Residential Development <p>(1) Compliance with the access standards of SUB-RES S2.</p> <p>(2) Compliance with the building coverage standard of GRZ-PREC1 S4.</p> <p>(3) Compliance with the yard setback standards of GRZ-PREC1 S5 and GRZ-PREC1 S7 for external boundaries only.</p> <p>(4) Compliance with the outdoor living space standard of GRZ-PREC1 S6.</p> <p>(5) Compliance with the maximum building height standard of GRZ S7.</p> <p>(6) Compliance with the sunlight access planes of GRZ S8 for external boundaries only.</p> <p>(7) Compliance with the on site soakage standard of GRZ-PREC1 S8.</p> <p>Additional standards and terms for Comprehensive Residential Development within the Wallaceville Structure Plan Development Area</p> <p>(8) Compliance with noise insulation and ventilation standards of DEV1 S6 and DEV1 S7</p> <p>(9) Compliance with the fencing standards of DEV1 S8</p> </td> <td> General Residential— Residential Centres Precinct </td> </tr> </tbody> </table>	Standards for Restricted Discretionary Activities		Zones	SUB-RES S7 <i>Policies</i> SUB-RES P1, SUB-RES P6, SUB-GEN P9, GRZ P1, GRZ P4,	Standards and terms for Comprehensive Residential Development <p>(1) Compliance with the access standards of SUB-RES S2.</p> <p>(2) Compliance with the building coverage standard of GRZ-PREC1 S4.</p> <p>(3) Compliance with the yard setback standards of GRZ-PREC1 S5 and GRZ-PREC1 S7 for external boundaries only.</p> <p>(4) Compliance with the outdoor living space standard of GRZ-PREC1 S6.</p> <p>(5) Compliance with the maximum building height standard of GRZ S7.</p> <p>(6) Compliance with the sunlight access planes of GRZ S8 for external boundaries only.</p> <p>(7) Compliance with the on site soakage standard of GRZ-PREC1 S8.</p> <p>Additional standards and terms for Comprehensive Residential Development within the Wallaceville Structure Plan Development Area</p> <p>(8) Compliance with noise insulation and ventilation standards of DEV1 S6 and DEV1 S7</p> <p>(9) Compliance with the fencing standards of DEV1 S8</p>	General Residential— Residential Centres Precinct
Standards for Restricted Discretionary Activities		Zones							
SUB-RES S7 <i>Policies</i> SUB-RES P1, SUB-RES P6, SUB-GEN P9, GRZ P1, GRZ P4,	Standards and terms for Comprehensive Residential Development <p>(1) Compliance with the access standards of SUB-RES S2.</p> <p>(2) Compliance with the building coverage standard of GRZ-PREC1 S4.</p> <p>(3) Compliance with the yard setback standards of GRZ-PREC1 S5 and GRZ-PREC1 S7 for external boundaries only.</p> <p>(4) Compliance with the outdoor living space standard of GRZ-PREC1 S6.</p> <p>(5) Compliance with the maximum building height standard of GRZ S7.</p> <p>(6) Compliance with the sunlight access planes of GRZ S8 for external boundaries only.</p> <p>(7) Compliance with the on site soakage standard of GRZ-PREC1 S8.</p> <p>Additional standards and terms for Comprehensive Residential Development within the Wallaceville Structure Plan Development Area</p> <p>(8) Compliance with noise insulation and ventilation standards of DEV1 S6 and DEV1 S7</p> <p>(9) Compliance with the fencing standards of DEV1 S8</p>	General Residential— Residential Centres Precinct							
	SUB-RES – Subdivision in the General Residential Zone	Delete Rule	<table border="1"> <thead> <tr> <th colspan="2">Discretionary Activities</th> <th>Zone</th> </tr> </thead> <tbody> <tr> <td>SUB-RES R13</td> <td>Subdivision which does not comply with the standards specified in SUB-RES S1.</td> <td>DIS <i>General Residential</i></td> </tr> </tbody> </table>	Discretionary Activities		Zone	SUB-RES R13	Subdivision which does not comply with the standards specified in SUB-RES S1.	DIS <i>General Residential</i>
Discretionary Activities		Zone							
SUB-RES R13	Subdivision which does not comply with the standards specified in SUB-RES S1.	DIS <i>General Residential</i>							

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<i>Policies</i> SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P4, SUB-RES-P5, SUB-GEN-P9, SUB-GEN-P10, NATC-P1				
	SUB-RES – Subdivision in the General Residential Zone	Delete Rule	SUB-RES-R14 <i>Policies</i> SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P4, SUB-RES-P5, SUB-GEN-P9, SUB-GEN-P10, NATC-P1	Subdivision within the Residential Centres Precinct which does not comply with the standards specified in SUB-RES-S1	DIS	General Residential – Residential Centres Precinct	
	SUB-RES – Subdivision in the General Residential Zone	Delete Rule	SUB-RES-R21 <i>Policies</i> SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P4, SUB-RES-P5, SUB-GEN-P9, SUB-GEN-P10, NATC-P1	Subdivision In relation to land identified in SUB-RES-Figure 2 ('Maidstone Terrace Residential') which does not comply with standards in SUB-RES-S1, SUB-RES-S2 and/or SUB-RES-S3	NC	General Residential Precinct 1 – SUB-RES-Figure 2	
	SUB-RES – Subdivision in the General Residential Zone	Amend Matters for Consideration	Matters for Consideration Matters that may be relevant in the consideration of any resource consent may include the following: SUB-RES-MC1 Subdivision (1) For subdivisions with a net site area less than 400m ² located in a the Residential Centres Precinct , the extent to which the proposal meets the requirements for			Zone General Residential	

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>'small site design and development' of the Design Guide for the Residential Centres Precinct;</p> <p>(2) For subdivisions of a Comprehensive Residential Development, the extent to which the proposal meets the requirements of the Design Guide for the Residential Centres Precinct.</p> <p><u>(1)</u> (3) The design and layout of the subdivision where any allotment may affect the safe and effective operation and maintenance of, and access to, regionally significant network utilities (excluding the National Grid), located on or in proximity to the site.</p> <p><u>(2)</u> (4) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-RES-R7 covers subdivision within the Electricity Transmission Corridor.</p> <p><u>(3)</u> (5) The design and layout of the subdivision where any allotment may affect the safe and effective operation and maintenance of, and access to, consented or existing renewable electricity generation activities located on or in proximity to the site.</p> <p><u>(4)</u> (6) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site.</p> <p><u>(5)</u> (7) Account must be taken of the future development potential of adjoining or adjacent land.</p> <p><u>(6)</u> (8) Account must be taken of any potential reverse sensitivity effects on regionally significant network utilities (excluding the National Grid).</p> <p><u>(7)</u> (9) Where located within an identified flood hazard extent, any relevant restricted discretionary activity matters for subdivision.</p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	SUB-RES – Subdivision in the General Residential Zone	Delete Figure	<p>SUB-RES Figure 2 Maidstone Terrace Residential</p> 
SUB-HRZ – Subdivision in the High Density Residential Zone			
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add new Heading and Background	<p>SUB-HRZ – Subdivision within the High Density Residential Zone (including Precinct 2 – St Patrick’s Estate Precinct)</p> <p>Background</p> <p><u>The High Density Residential Zone is to be used predominantly for residential activities with high concentration and bulk of buildings, such as apartments, and other compatible activities.</u></p> <p><u>The High Density Residential Zone is located adjacent to and within a walkable catchment of the following train stations and centre zones:</u></p>

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<p>(i) <u>Silverstream Station</u></p> <p>(ii) <u>Heretaunga Station</u></p> <p>(iii) <u>Trentham Station</u></p> <p>(iv) <u>Wallaceville Station</u></p> <p>(v) <u>Upper Hutt Station</u></p> <p>(vi) <u>City Centre Zone</u></p> <p>(vii) <u>Town Centre Zone</u></p> <p>(viii) <u>Local Centre Zone</u></p> <p>The High Density Residential Zone provides for heights and densities of residential units and buildings greater than those provided for by the Medium Density Residential Standards that apply in the General Residential Zone. The High Density Residential Zone gives effect to policy 3(c) and (d) of the National Policy Statement on Urban Development (2020). The High Density Residential Zone subdivision rules cross-reference to relevant rules and standards in the General Residential Zone where applicable.</p> <p><u>Within the High Density Residential Zone, the St Patrick's Estate Precinct sits at the southern entrance to the City and adjoins the Hutt River and Mawaihakona Stream. Opportunities to enhance the Southern gateway to the City via landscaping the frontage to Fergusson Drive, and providing linkages to the Hutt River walkway and Silverstream Railway Station are required.</u></p>		
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Objective	<p>Objectives</p> <table border="1"> <tr> <td>SUB-HRZ-O1</td> <td> <p><u>Well-functioning Urban Environments</u></p> <p><i>A well-functioning urban environment that enables all people and communities to provide for their social, economic, and cultural wellbeing, and for their health and safety, now and into the future.</i></p> <p>[s80H(1)(a)(ii) note: this provision incorporates the objectives in clause 6 of Schedule 3A.]</p> </td> </tr> </table>	SUB-HRZ-O1	<p><u>Well-functioning Urban Environments</u></p> <p><i>A well-functioning urban environment that enables all people and communities to provide for their social, economic, and cultural wellbeing, and for their health and safety, now and into the future.</i></p> <p>[s80H(1)(a)(ii) note: this provision incorporates the objectives in clause 6 of Schedule 3A.]</p>
SUB-HRZ-O1	<p><u>Well-functioning Urban Environments</u></p> <p><i>A well-functioning urban environment that enables all people and communities to provide for their social, economic, and cultural wellbeing, and for their health and safety, now and into the future.</i></p> <p>[s80H(1)(a)(ii) note: this provision incorporates the objectives in clause 6 of Schedule 3A.]</p>				
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Objective	<table border="1"> <tr> <td>SUB-HRZ-O2</td> <td> <p><i>High quality urban infrastructure is constructed to facilitate the demands of urban intensification and highly walkable <u>accessible</u> urban environments.</i></p> </td> </tr> </table>	SUB-HRZ-O2	<p><i>High quality urban infrastructure is constructed to facilitate the demands of urban intensification and highly walkable <u>accessible</u> urban environments.</i></p>
SUB-HRZ-O2	<p><i>High quality urban infrastructure is constructed to facilitate the demands of urban intensification and highly walkable <u>accessible</u> urban environments.</i></p>				

Commented [MM61]: S5.4 - Bob Anker.

Commented [MM62]: S5.4 - Bob Anker.

Commented [MM63]: S50.13 - Waka Kotahi - New Zealand Transport Agency.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Objective	SUB-HRZ-O3 <i>High quality intensive residential development is provided in close proximity to rapid transport stops, community facilities and commercial activities in multi-storey flats and apartments.</i>
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Objective	SUB-HRZ-O4 <i>The management of the adverse effects of subdivision within the High Density Residential Zone.</i>
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Objective	SUB-HRZ-O5 <i>To encourage the maintenance of indigenous biological diversity values within the Indigenous Biodiversity Precinct.</i>
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Policy	<p>Policies</p> <p>SUB-HRZ-P1 <i>Encourage development to achieve attractive and safe streets and public open spaces, including by providing for passive surveillance.</i></p> <p>[s80H(1)(a)(ii) note: this provision incorporates the policies in clause 6 of Schedule 3A.]</p>
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Policy	SUB-HRZ-P2 <i>Recognise the benefits of wider adoption of public transport through the increase of density along public transport corridors and within walkable distances catchments of centres, while minimising potential reverse sensitivity effects.</i>
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Policy	SUB-HRZ-P3 <i>Recognise and maintain identified urban tree groups, notable trees, and significant natural areas throughout development in residential zones.</i>
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Policy	SUB-HRZ-P4 <i>Maintain and enhance pedestrian active transport facilities established in urban areas within a walkable distance to urban railway stations and the centre zones to increase walking transport accessibility and safety.</i>

High quality **Commented [MM64]:** To create a stand-alone HRZ. **walkable accessible urban environments.**

Commented [MM65]: To create a stand-alone HRZ.

Commented [MM66]: S5.4 - Bob Anker.

Commented [MM67]: S43.9 - Kiwirail Holdings Ltd.

Commented [MM68]: S50.14 - Waka Kotahi - New Zealand Transport Agency.

Commented [MM69]: S5.16 - Bob Anker.

Commented [MM70]: S50.14 - Waka Kotahi - New Zealand Transport Agency.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Policy	SUB-HRZ-P5 <i>Provide for the efficient function of multimodal transport options within the road corridor within a walkable distance to urban railway stations and the centre zones.</i>
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Policy	SUB-HRZ-P6 <i>Enable and encourage high density residential subdivision and development that:</i> a. <i>is compatible with the planned built character of the High Density Residential Zone within a minimum of 800m walkable distance from urban railway stations and the City Centre Zone; and</i> b. <i>makes efficient use of land for high density residential subdivision, use and development.</i>
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Policy	SUB-HRZ-P7 <i>Enable housing to be designed to meet the day-to-day needs of residents.</i> [s80H(1)(a)(ii) note: this provision incorporates the policies in clause 6 of Schedule 3A.]
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Policy	SUB-HRZ-P8 <i>Provide for developments not meeting permitted activity status, while encouraging high-quality developments.</i> [s80H(1)(a)(ii) note: this provision incorporates the policies in clause 6 of Schedule 3A.]
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add policy	SUB-HRZ-P9 <i>Medium and high density residential subdivision, use and development within the St Patrick's Estate Precinct must:</i> (i) <i>provide pedestrian linkages to the Hutt River walkway and Silverstream Railway Station.</i> (ii) <i>Enhance the southern entrance to the City via landscaping along the frontage of the site with Fergusson Drive.</i>
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add policy	SUB-HRZ-P9 <i>New residential subdivision and buildings will avoid, remedy, or mitigate potential reverse sensitivity effects on existing lawfully-established non-residential activities. Potential methods include but are not limited to:</i> a. <i>Requiring noise mitigation, vibration, insulation, and ventilation for residential units;</i> b. <i>Specifying the location of private and communal outdoor living spaces;</i> c. <i>Specifying the location and function of windows;</i> d. <i>Requiring the provision of buffer areas, setbacks, and no-build areas;</i> e. <i>Specifying fencing and landscaping requirements.</i>

Commented [MM71]: All amendments below in blue are to consequential on creating a stand-alone HRZ subdivision chapter.

Commented [MM72]: Clause 99, Schedule 1 RMA. To address reverse sensitivity effects.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add policy	SUB-HRZ-P10 To ensure that the scale, appearance design and siting of buildings, structures and activities are compatible with the planned urban built form character and desired amenity values of the area.
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add policy	SUB-HRZ-P11 To encourage avoiding, remedying and mitigating the actual and potential adverse effects of the subdivision of sites within the Indigenous Biodiversity Precinct to assist in maintaining indigenous biological diversity.
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add policy	SUB-HRZ-P12 To encourage the protection of trees and vegetation which contribute to ecological values within the Indigenous Biodiversity Precinct.
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add policy	SUB-HRZ-P13 To provide for new residential development within the City in a sustainable manner.
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add policy	SUB-HRZ-P14 To provide for subdivision that is compatible with the planned built character urban form of the high Density Residential Zone, and ensure that it has adequate access to infrastructure real requirements.
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add policy	SUB-HRZ-P15 To provide for medium and high density housing and subdivision within the High Density Residential Zone, while encouraging the consideration of the protection and retention of indigenous biodiversity values within the Indigenous Biodiversity Precinct.
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add District Wide Matters table	<p>Rules</p> <p>District-wide matters</p> <p>Subdivision within the High Density Residential Zone must comply with all relevant rules and standards for qualifying matter areas, and all relevant rules and standards in the District-wide matters of the Plan as listed below:</p> <p>District-wide matters</p>

Commented [MM73]: S58.42 - Kianga Ora: Homes and Communities.

Commented [MM74]: S58.42 - Kianga Ora: Homes and Communities.

Commented [MM75]: To create stand-alone HRZ chapter.

Commented [MM76]: To create stand-alone HRZ chapterH

Commented [MM77]: S58.46 - Kianga Ora: Homes and Communities.

Commented [MM78]: S58.46 - Kianga Ora: Homes and Communities.

Commented [MM79]: S58.47 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change																							
			<table border="1"> <tr><td><u>TEMP - Temporary Activities</u></td></tr> <tr><td><u>SIGN - Signs</u></td></tr> <tr><td><u>EW - Earthworks</u></td></tr> <tr><td><u>NATC – Natural Character</u></td></tr> <tr><td><u>DC – Development Contributions</u></td></tr> <tr><td><u>HH - Historical Heritage</u></td></tr> <tr><td><u>TREE - Notable Trees</u></td></tr> <tr><td><u>UTG - Urban Tree Groups</u></td></tr> <tr><td><u>ECO - Ecosystems and Indigenous Biodiversity</u></td></tr> <tr><td><u>NFL - Natural Features and Landscapes</u></td></tr> <tr><td><u>PA – Public Access</u></td></tr> <tr><td><u>ASW - Activities on the Surface of Water</u></td></tr> <tr><td><u>NU – Network Utilities</u></td></tr> <tr><td><u>REG - Renewable Energy Generation</u></td></tr> <tr><td><u>TP – Transport and Parking</u></td></tr> <tr><td><u>NOISE - Noise</u></td></tr> <tr><td><u>NH - Natural Hazards</u></td></tr> <tr><td><u>CL – Contaminated Land</u></td></tr> <tr><td><u>HS - Hazardous Substances</u></td></tr> <tr><td><u>WM – Waste Management</u></td></tr> <tr><td><u>SUB - Subdivision</u></td></tr> <tr><td><u>AIR - Air</u></td></tr> <tr><td><u>LIGHT - Light</u></td></tr> </table>	<u>TEMP - Temporary Activities</u>	<u>SIGN - Signs</u>	<u>EW - Earthworks</u>	<u>NATC – Natural Character</u>	<u>DC – Development Contributions</u>	<u>HH - Historical Heritage</u>	<u>TREE - Notable Trees</u>	<u>UTG - Urban Tree Groups</u>	<u>ECO - Ecosystems and Indigenous Biodiversity</u>	<u>NFL - Natural Features and Landscapes</u>	<u>PA – Public Access</u>	<u>ASW - Activities on the Surface of Water</u>	<u>NU – Network Utilities</u>	<u>REG - Renewable Energy Generation</u>	<u>TP – Transport and Parking</u>	<u>NOISE - Noise</u>	<u>NH - Natural Hazards</u>	<u>CL – Contaminated Land</u>	<u>HS - Hazardous Substances</u>	<u>WM – Waste Management</u>	<u>SUB - Subdivision</u>	<u>AIR - Air</u>	<u>LIGHT - Light</u>
<u>TEMP - Temporary Activities</u>																										
<u>SIGN - Signs</u>																										
<u>EW - Earthworks</u>																										
<u>NATC – Natural Character</u>																										
<u>DC – Development Contributions</u>																										
<u>HH - Historical Heritage</u>																										
<u>TREE - Notable Trees</u>																										
<u>UTG - Urban Tree Groups</u>																										
<u>ECO - Ecosystems and Indigenous Biodiversity</u>																										
<u>NFL - Natural Features and Landscapes</u>																										
<u>PA – Public Access</u>																										
<u>ASW - Activities on the Surface of Water</u>																										
<u>NU – Network Utilities</u>																										
<u>REG - Renewable Energy Generation</u>																										
<u>TP – Transport and Parking</u>																										
<u>NOISE - Noise</u>																										
<u>NH - Natural Hazards</u>																										
<u>CL – Contaminated Land</u>																										
<u>HS - Hazardous Substances</u>																										
<u>WM – Waste Management</u>																										
<u>SUB - Subdivision</u>																										
<u>AIR - Air</u>																										
<u>LIGHT - Light</u>																										

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			PK – Papakāinga
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Rule	<p>SUB-HRZ-R1 Subdivision within the High Density Residential Zone</p> <p>1. <u>Activity status: Controlled</u></p> <p>Where:</p> <p>Subdivision within the High Density Residential Zone of:</p> <p>a. <u>Any allotment with an existing residential unit, if:</u></p> <p> i. <u>Either the subdivision does not increase the degree of any non-compliance with any of the following rules and standards:</u></p> <p> A. HRZ-R2;</p> <p> B. HRZ-S13 – Setbacks Building coverage;</p> <p> C. HRZ-S24 – Building height Setbacks;</p> <p> D. HRZ-S35 – Height in relation to boundary Outdoor living space;</p> <p> E. HRZ-S47 – Building coverage height;</p> <p> F. HRZ – S58 – Number of residential units per site Height in relation to boundary;</p> <p> G. HRZ – S613 – Outdoor living space (per residential unit) Number of residential units per site;</p> <p> H. HRZ – S814 – Outlook space (per residential unit);</p> <p> I. HRZ – S915 – Windows to street;</p> <p> J. HRZ – S106 – Landscaped area; or</p> <p> <u>land use consent has been granted; and</u></p> <p> ii. <u>no vacant allotments are created:</u></p> <p>b. <u>Any allotment with no existing residential unit, where a subdivision application is accompanied by a land use application that will be determined concurrently if the applicant for the resource consent can demonstrate that:</u></p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>i. <u>It is practicable to construct on every allotment within the proposed subdivision, as a permitted activity, a residential unit; and</u></p> <p>ii. <u>Each residential unit complies with the following rules and standards:</u></p> <p>A. GHRZ-R2;</p> <p>B. GHRZ-S13 – Setbacks <u>Building coverage</u>;</p> <p>C. GHRZ-S24 – Building height <u>Setbacks</u>;</p> <p>D. GHRZ-S35 – Height in relation to boundary <u>Outdoor living space</u>;</p> <p>E. GHRZ-S47 – Building coverage <u>height</u>;</p> <p>F. GHRZ – S58 – Number of residential units per site <u>Height in relation to boundary</u>;</p> <p>G. GHRZ – S613 – Outdoor living space (per residential unit) <u>Number of residential units per site</u>;</p> <p>H. GHRZ – S814 – Outlook space per residential unit;</p> <p>I. GHRZ – S915 – Windows to street;</p> <p>J. GHRZ – S106 – Landscaped area; and</p> <p>iii. <u>No vacant allotments are created.</u></p> <p>Notification <u>Public and limited notification of an application for resource consent under this rule is precluded.</u></p> <p>Council may impose conditions over the following matters:</p> <p>(1) <u>Design, appearance and layout of the subdivision (excluding any minimum size or shape-related subdivision requirements).</u></p> <p>(2) Landscaping.</p> <p>(3) <u>Provision of and effects on network utilities and/or services.</u></p> <p>(4-3) <u>Standard, construction and layout of vehicular access.</u></p>

Commented [MM80]: S58.52 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(54) <u>Earthworks.</u></p> <p>(65) <u>Provision of esplanade reserves and strips.</u></p> <p>(76) <u>Protection of any special amenity feature.</u></p> <p>(87) <u>Financial contributions.</u></p> <p>(98) <u>The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-RES-R7 covers subdivision within the Electricity Transmission Corridor.</u></p> <p>(199) <u>The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site.</u></p> <p>(10) <u>The matters contained within the Council's Code of Practice for Civil Engineering Works.</u></p> <p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with one or more of the standards specified under HRZ-SUB-HRZ-R1.</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <p>i. the matters of discretion specified by the relevant standard(s) under SUB-HRZ-R1.</p> <p>(i) <u>Design, appearance and layout of the subdivision (excluding any minimum size or shape-related subdivision requirements).</u></p> <p>(ii) Landscaping.</p> <p>(iii) <u>Provision of and effects on network utilities and/or services.</u></p> <p>(iv) <u>Standard, construction and layout of vehicular access.</u></p> <p>(v) <u>Earthworks.</u></p> <p>(vi) <u>Provision of esplanade reserves and strips.</u></p> <p>(vii) <u>Protection of any special amenity feature.</u></p>

Commented [MM81]: S56.10 - Fire and Emergency New Zealand.

Commented [MM82]: S56.14 - Fire and Emergency New Zealand

Commented [MM83]: Clause 16(2), Schedule 1 RMA - to ensure the rule includes appropriate matters of discretion.

Commented [MM84]: S58.52 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(viii) Financial contributions.</p> <p>(ix) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-RES-R7 covers subdivision within the Electricity Transmission Corridor.</p> <p>(x) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site.+</p> <p>(xi) The matters contained within the Council's Code of Practice for Civil Engineering Works.</p> <p>(xii) Reverse sensitivity effects.</p> <p>Restriction on notification: Public notification of an application for resource consent under this rule is precluded.</p>
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Rule	<p>SUB-HRZ-R2 Subdivision that proposes to create one or more vacant allotments with a net site area of 300m² or less.</p> <p>1. Activity status: Controlled</p> <p>Council may impose conditions over the following matters:</p> <p>(i) Design, appearance and layout of the subdivision (excluding any minimum size or shape-related subdivision requirements).</p> <p>(ii) Landscaping.</p> <p>(ii) Provision of and effects on network utilities and/or services.</p> <p>(iii) Standard, construction and layout of vehicular access.</p> <p>(iv) Earthworks.</p> <p>(v) Provision of esplanade reserves and strips.</p> <p>(vi) Protection of any special amenity feature.</p> <p>(vii) Financial contributions.</p>

Commented [MM85]: S56.10 - Fire and Emergency New Zealand.

Commented [MM86]: S58.52 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<p>(viii) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-RES-R7 covers subdivision within the Electricity Transmission Corridor.</p> <p>(ix) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site.</p> <p>(x) The matters contained within the Council's Code of Practice for Civil Engineering Works.</p>		
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Rule	<table border="1"> <tr> <td>SUB-HRZ-R3</td> <td>Subdivision of land for utilities, reserves or conservation purposes.</td> </tr> </table> <p>1. Activity status: Controlled</p> <p>Council may impose conditions over the following matters:</p> <p>(i) Design, appearance and layout of the subdivision (excluding any minimum size or shape-related subdivision requirements).</p> <p>(ii) Landscaping.</p> <p>(ii) Provision of and effects on network utilities and/or services.</p> <p>(iii) Standard, construction and layout of vehicular access.</p> <p>(iv) Earthworks.</p> <p>(v) Provision of esplanade reserves and strips.</p> <p>(vi) Protection of any special amenity feature.</p> <p>(vii) Financial contributions.</p> <p>(viii) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-RES-R7 covers subdivision within the Electricity Transmission Corridor.</p> <p>(ix) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site.</p>	SUB-HRZ-R3	Subdivision of land for utilities, reserves or conservation purposes.
SUB-HRZ-R3	Subdivision of land for utilities, reserves or conservation purposes.				

Commented [MM87]: S56.10 - Fire and Emergency New Zealand.

Commented [MM88]: S58.52 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			The matters contained within the Council's Code of Practice for Civil Engineering Works.
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Rule	<p>SUB-HRZ-R4 Subdivision that complies with all the standards under SUB-HRZ-S1 but does not comply with one or more of the standards under SUB-HRZ-S2.</p> <p>1. Activity status: Restricted Discretionary</p> <p>Council will restrict its discretion to, and may impose conditions on the matters of discretion specified under SUB-HRZ-S2.</p>
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Rule	<p>SUB-HRZ-R5 Subdivision that proposes to create one or more vacant allotments where one or more allotments has a net site area greater than 300m² but no greater than 800m².</p> <p>1. Activity status: Restricted Discretionary</p>
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Rule	<p>SUB-HRZ-R6 Subdivision which creates building platforms within 20m of high voltage (110kV or greater) electricity transmission lines as shown on the Planning Maps *(refer to the definition of transmission line)</p> <p>1. Activity Status: Restricted Discretionary</p> <p>In addition to the matters listed in SUB-HRZ-R1, Council will restrict its discretion to, and may impose conditions on:</p> <ol style="list-style-type: none"> The extent to which the subdivision design manages potential conflicts with existing lines by locating roads and reserves under the route of the line. The extent to which maintenance and inspections of transmission lines are affected including access. The extent to which potential adverse effects including risk or injury, property damage and visual impact are mitigated through the location of building platforms and landscaping. The outcome of any consultation with the affected utility operator. Separation distances between trees and conductors and the location and mature size of trees planted near the transmission lines. Compliance with the New Zealand Electrical Code of Practice for Electrical Safe Distances 2001 (NZECP 34:2001).

Commented [MM89]: S56.10 - Fire and Emergency New Zealand.

Commented [MM90]: Clause 99(2) or Clause 16(2), Schedule 1, RMA amendments to include relevant matters of discretion.

Commented [MM91]: Consequential amendment to submission S5.16 – Bob Anker.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>g. <u>Measures necessary to avoid, remedy or mitigate the potential adverse effects of earthworks, dust generation and construction activities, including provision of appropriate separation distances, managing the risks to structural integrity, and safety risks associated with the use of mobile machinery.</u></p> <p>h. <u>The matters contained within the Council's Code of Practice for Civil Engineering Works.</u></p> <p>Restriction on notification</p> <p><u>A resource consent application under this rule will be precluded from public notification, and limited notification will be served on Transpower New Zealand Limited as the only affected party.</u></p>
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Rule	<p>SUB-HRZ-R7 <u>Subdivision of a site identified in Schedules HH-SCHED1 or TREE-SCHED1.</u></p> <p>1. <u>Activity Status: Discretionary</u></p>
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Rule	<p>SUB-HRZ-R8 <u>Subdivision that is not listed as a permitted, controlled, restricted discretionary or non-complying activity.</u></p> <p>1. <u>Activity Status: Discretionary</u></p>
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Rule	<p>SUB-HRZ-R9 <u>Subdivision creating one or more vacant allotments with a net site area greater than 800m².</u></p> <p><u>The following are excluded from this rule:</u></p> <p><u>(i) The creation of vacant allotments with a net site area greater than 800m² that are to vest in Council or the Wellington Regional Council.</u></p> <p><u>(ii) Subdivision for network utilities.</u></p> <p><u>(iii) Balance allotments created as part of a staged subdivision.</u></p> <p>1. <u>Activity Status: Non-Complying</u></p>
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Standard	<p>Standards</p> <p>Matters of Discretion for all restricted discretionary activity subdivision)</p>

Commented [MM92]: S56.16 - Fire and Emergency New Zealand

Commented [MM93]: S5.16 – Bob Anker

			<p>SUB-HRZ-S1 The standards for permitted activities within the General High Density Residential Zone referred to in SUB-HRZ-R1.</p>	<ul style="list-style-type: none"> (1) <u>Design, appearance and layout of the subdivision.</u> (2) <u>Landscaping.</u> (3) <u>Provision of and effects on network utilities and/or services.</u> (4) <u>Standard, construction and layout of vehicular access.</u> (5) <u>Earthworks.</u> (6) <u>Provision of esplanade reserves and esplanade strips.</u> (7) <u>Protection of any special amenity feature.</u> (8) <u>Methods to avoid, remedy or mitigate adverse effects on historic heritage.</u> (9) <u>The future development potential of adjoining or adjacent land.</u> (10) <u>Financial contributions.</u> (11) <u>The outcome of consultation with the owner of operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-RES-R7 covers subdivision within the Electricity Transmission Corridor.</u> (12) <u>The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site.</u> (13) <u>Ensuring the safe operation, maintenance and access to any Regionally Significant Infrastructure on or adjacent to the site, taking into account the outcome of consultation with the Regionally Significant Infrastructure owner.</u> (14) <u>Reverse sensitivity effects.</u> (15) <u>Methods to avoid, remedy or mitigate adverse effects on historic heritage.</u>
--	--	--	--	--


IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(16) <u>Any natural hazard risk to people's lives and properties and the measures to reduce this risk;</u></p> <p>(17) <u>The provision of esplanade reserves where land adjoins rivers whose bed has an average width of 3m or more.</u></p> <p>(18) <u>Pedestrian access to open space, commercial centres, and public transport.</u></p> <p>(19) <u>Ensuring roads and any vehicle access to sites allow for safe and efficient traffic movements and can safely accommodate the intended number of users.</u></p> <p>(20) <u>Ensuring infrastructure meets Council standards and has the capacity to accommodate the development or anticipated future development in accordance with the purpose of the zone, and is in place at the time of allotment creation.</u></p> <p>(21) <u>Ensuring telecommunications and power supply is provided to all allotments.</u></p> <p>(22) <u>Achieving the outcomes sought by the Medium and High Density Design Guide in Appendix 1.</u></p> <p>(23) <u>The matters contained within the Council's Code of Practice for Civil Engineering Works.</u></p>
	New SUB-HRZ - Subdivision in the High Density Residential Zone	Add Rule	<p>SUB-HRZ-S2 <u>Access standards for subdivision</u></p> <p>(1) <u>Where vehicle access points are shared by three or more residential units, for all rear allotments and for all sites fronting arterial, or distributor/collector streets (identified in the Transport and Parking (TP) Chapter there must be provision for turning a vehicle on site in order that vehicles do not reverse into the street.</u></p> <p>(1) <u>The extent to which the activity will adversely affect traffic and pedestrian safety.</u></p> <p>(2) <u>The extent to which the activity will adversely affect the efficient functioning of the roading network.</u></p> <p>(3) <u>Design, appearance and layout of the subdivision.</u></p> <p>(4) <u>Provision of and effects on network utilities and/or services.</u></p>

Commented [MM94]: S56.16 - Fire and Emergency New Zealand

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(2) <u>All accessways and manoeuvring areas shall be formed and surfaced in accordance with the Code of Practice for Civil Engineering Works. The required surfacing must be completed prior to certification of the survey plan. Exemption – the requirement for accessways serving sites solely occupied by unstaffed utilities shall be that the accessway shall be surfaced with permanent all weather surfacing for a minimum length of 5m from the edge of the road carriageway seal.</u></p> <p>(3) <u>Sites shall have practical vehicle access to car parking and loading spaces, in accordance with the Code of Practice for Civil Engineering Works. This requirement does not apply to sites solely occupied by unstaffed utilities, provided that vehicles associated with utilities shall not obstruct the footpath or create a traffic hazard on the road.</u></p> <p>(4) <u>Vehicular access to a corner allotment shall be located no closer than 8m from the street corner. Where a site is located on an intersection of a primary or secondary arterial traffic route (identified in the Transport and Parking (TP) Chapter the siting of the vehicular access shall be located as far as practicable from the corner of the street. The 8 metre setback shall be measured from where the two front boundaries of the site (refer to the</u></p> <p>(5) <u>Standard, construction and layout of vehicular access.</u></p> <p>(6) <u>The outcome of consultation with the owner of operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-RES-R7 covers subdivision within the Electricity Transmission Corridor.</u></p> <p>(7) <u>The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site.</u></p> <p>(8) <u>Ensuring the safe operation, maintenance and access to any Regionally Significant Infrastructure on or adjacent to the site, taking into account the outcome of consultation with the Regionally Significant Infrastructure owner.</u></p> <p>(9) <u>Ensuring roads and any vehicle access to sites allow for safe and efficient traffic movements and can safely accommodate the intended number of users.</u></p> <p>(10) <u>Ensuring infrastructure meets Council standards and has the capacity to accommodate the development or anticipated future development in accordance with the purpose of the zone, and is in place at the time of allotment creation.</u></p> <p>(11) <u>The matters contained within the Council's Code of Practice for Civil Engineering Works.</u></p>

Commented [MM95]: S56.16 - Fire and Emergency New Zealand

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
			<p><u>definition of a corner allotment join, or in accordance with the diagram below.</u></p>  <p>The diagram illustrates a corner allotment at the intersection of two roads. A building is situated on a lot that extends into the corner. A driveway provides access from the building to the road. The road reserve is shown on both sides of the road. A dimension line indicates a minimum clearance of 8m from the building to the road reserve.</p> <p>(5) <u>Where a corner allotment is located at an intersection of a national, primary or secondary arterial traffic route, as identified in the Transport and Parking (TP) Chapter, no building, fence or other structure is to be erected and no <u>vegetation allowed to grow so as to obstruct a traffic sight line.</u></u></p> <p>(6) <u>At the intersection of a road or rail level crossing, no building, fence or other obstructions which block sight lines for trains shall be erected, placed or grown in the hatched area marked in Diagram 1A in the Transport and Parking (TP) Chapter.</u></p> <p>(7) <u>Subdivision with direct access to a State Highway shall comply with the access and visibility standards set out in Diagrams 2</u></p>

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			to 9 in the Transport and Parking (TP) Chapter.						
SUB-CMU – Subdivision in Commercial and Mixed Use Zones									
New SUB-CMU – Subdivision in Commercial and Mixed Use Zones	Introduce new Policy SUB-CMU-P1		<p>Policies</p> <p>SUB-CMU-P1 Subdivision in the Commercial and Mixed Use Zones</p> <p>Provide for subdivision in the Commercial and Mixed Use zones where it:</p> <ul style="list-style-type: none"> (i) is consistent with the anticipated purpose, character and role of the zone; and (ii) is consistent with the anticipated level of development and density in the zone. 						
New SUB-CMU - Subdivision in Commercial and Mixed Use Zones	Add policy		<p>SUB-CMU-P2 Subdivision within the St Patrick’s Estate Precinct must:</p> <ul style="list-style-type: none"> (i) Provide pedestrian linkages to the Hutt River walkway and Silverstream Railway Station. (ii) Enhance the southern entrance to the City via landscaping along the frontage of the site with Fergusson Drive and County Lane. 						
New SUB-RES - Subdivision in the Commercial and Mixed Use Zones	Add District Wide Matters table		<p>Rules</p> <p>District-wide matters</p> <p>Subdivision within the Commercial and Mixed Use Zones must comply with all relevant rules and standards in the District-wide matters and qualifying matter areas of the Plan as listed below:</p> <table border="1"> <tr> <td>District-wide matters</td> </tr> <tr> <td>TEMP - Temporary Activities</td> </tr> <tr> <td>SIGN - Signs</td> </tr> <tr> <td>EW - Earthworks</td> </tr> <tr> <td>NATC – Natural Character</td> </tr> <tr> <td>DC – Development Contributions</td> </tr> </table>	District-wide matters	TEMP - Temporary Activities	SIGN - Signs	EW - Earthworks	NATC – Natural Character	DC – Development Contributions
District-wide matters									
TEMP - Temporary Activities									
SIGN - Signs									
EW - Earthworks									
NATC – Natural Character									
DC – Development Contributions									

IPI - PROPOSED AMENDMENTS																						
#	Chapter	Change	Track Change																			
			<table border="1"> <tr><td><u>HH - Historical Heritage</u></td></tr> <tr><td><u>TREE - Notable Trees</u></td></tr> <tr><td><u>UTG - Urban Tree Groups</u></td></tr> <tr><td><u>ECO - Ecosystems and Indigenous Biodiversity</u></td></tr> <tr><td><u>NFL - Natural Features and Landscapes</u></td></tr> <tr><td><u>PA – Public Access</u></td></tr> <tr><td><u>PK - Papakāinga</u></td></tr> <tr><td><u>ASW - Activities on the Surface of Water</u></td></tr> <tr><td><u>NU – Network Utilities</u></td></tr> <tr><td><u>REG - Renewable Energy Generation</u></td></tr> <tr><td><u>TP – Transport and Parking</u></td></tr> <tr><td><u>NOISE - Noise</u></td></tr> <tr><td><u>NH - Natural Hazards</u></td></tr> <tr><td><u>CL – Contaminated Land</u></td></tr> <tr><td><u>HS - Hazardous Substances</u></td></tr> <tr><td><u>WM – Waste Management</u></td></tr> <tr><td><u>SUB - Subdivision</u></td></tr> <tr><td><u>AIR - Air</u></td></tr> <tr><td><u>LIGHT - Light</u></td></tr> </table>	<u>HH - Historical Heritage</u>	<u>TREE - Notable Trees</u>	<u>UTG - Urban Tree Groups</u>	<u>ECO - Ecosystems and Indigenous Biodiversity</u>	<u>NFL - Natural Features and Landscapes</u>	<u>PA – Public Access</u>	<u>PK - Papakāinga</u>	<u>ASW - Activities on the Surface of Water</u>	<u>NU – Network Utilities</u>	<u>REG - Renewable Energy Generation</u>	<u>TP – Transport and Parking</u>	<u>NOISE - Noise</u>	<u>NH - Natural Hazards</u>	<u>CL – Contaminated Land</u>	<u>HS - Hazardous Substances</u>	<u>WM – Waste Management</u>	<u>SUB - Subdivision</u>	<u>AIR - Air</u>	<u>LIGHT - Light</u>
<u>HH - Historical Heritage</u>																						
<u>TREE - Notable Trees</u>																						
<u>UTG - Urban Tree Groups</u>																						
<u>ECO - Ecosystems and Indigenous Biodiversity</u>																						
<u>NFL - Natural Features and Landscapes</u>																						
<u>PA – Public Access</u>																						
<u>PK - Papakāinga</u>																						
<u>ASW - Activities on the Surface of Water</u>																						
<u>NU – Network Utilities</u>																						
<u>REG - Renewable Energy Generation</u>																						
<u>TP – Transport and Parking</u>																						
<u>NOISE - Noise</u>																						
<u>NH - Natural Hazards</u>																						
<u>CL – Contaminated Land</u>																						
<u>HS - Hazardous Substances</u>																						
<u>WM – Waste Management</u>																						
<u>SUB - Subdivision</u>																						
<u>AIR - Air</u>																						
<u>LIGHT - Light</u>																						
	New SUB-CMU – Subdivision in Commercial and Mixed Use Zones	Introduce new Rule SUB-CMU-R1	<table border="1"> <tr> <td colspan="2">Rules</td> </tr> <tr> <td><u>SUB-CMU-R1</u></td> <td><u>Subdivision around any existing lawfully established building which does not result in the creation of any new undeveloped allotment</u></td> </tr> </table>	Rules		<u>SUB-CMU-R1</u>	<u>Subdivision around any existing lawfully established building which does not result in the creation of any new undeveloped allotment</u>															
Rules																						
<u>SUB-CMU-R1</u>	<u>Subdivision around any existing lawfully established building which does not result in the creation of any new undeveloped allotment</u>																					

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>1. Activity status: Controlled</p> <p><u>Where:</u></p> <p>a. Compliance is achieved with</p> <p>i. SUB-CMU-S2; and</p> <p>ii. SUB-CMU-S3; and</p> <p>iii. SUB-CMU-S1.</p> <p><u>Matters of control are limited to:</u></p> <p>(1) Design, appearance and layout of the subdivision.</p> <p>(2) Landscaping.</p> <p>(3) Provision of and effects on network utilities and/or services.</p> <p>(4) Standard, construction and layout of vehicular access.</p> <p>(5) Earthworks.</p> <p>(6) Provision of esplanade reserves and esplanade strips.</p> <p>(7) Protection of any special amenity feature.</p> <p>(8) Financial contributions.</p> <p>(9) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site.</p> <p>(10) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-CMU-R7 covers subdivision within the Electricity Transmission Corridor.</p> <hr/> <p>2. Activity status: Restricted Discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with SUB-CMU-S1, SUB-CMU-S2 or SUB-CMU-S3.</p> <p><u>Matters of discretion are restricted to:</u></p>

Commented [MM96]: S56.17 - Fire and Emergency New Zealand

Commented [MM97]: S58.64 - Kāinga Ora: Homes and Communities

Commented [MM98]: S56.17 - Fire and Emergency New Zealand

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<ul style="list-style-type: none"> (1) <u>The extent to which the activity will adversely affect traffic and pedestrian safety.</u> (2) <u>The extent to which the activity will adversely affect the efficient functioning of the roading network.</u> (3) <u>The matters of control listed in SUB-CMU-R1.1</u> 				
	New SUB-CMU – Subdivision in Commercial and Mixed Use Zones	Introduce new Rule SUB-CMU-R2	<table border="1"> <thead> <tr> <th>SUB-CMU-R2</th> <th>Subdivision that creates one or more vacant allotments</th> </tr> </thead> <tbody> <tr> <td colspan="2"> <p><u>1. Activity status: Controlled</u></p> <p><u>Where:</u></p> <p><u>a. Compliance is achieved with</u></p> <ul style="list-style-type: none"> <u>i. SUB-CMU-S1;</u> <u>ii. SUB-CMU-S2; and</u> <u>iii. SUB-CMU-S3.</u> <p><u>Matters of control are limited to:</u></p> <ul style="list-style-type: none"> <u>(1) Design, appearance and layout of the subdivision.</u> (2) Landscaping. (3) Provision of and effects on network utilities and/or services. (4) Standard, construction and layout of vehicular access. (5) Earthworks. (6) Provision of esplanade reserves and esplanade strips. (7) Protection of any special amenity feature. (8) Financial contributions. (9) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site. (10) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-CMU-R7 covers subdivision within the </td> </tr> </tbody> </table>	SUB-CMU-R2	Subdivision that creates one or more vacant allotments	<p><u>1. Activity status: Controlled</u></p> <p><u>Where:</u></p> <p><u>a. Compliance is achieved with</u></p> <ul style="list-style-type: none"> <u>i. SUB-CMU-S1;</u> <u>ii. SUB-CMU-S2; and</u> <u>iii. SUB-CMU-S3.</u> <p><u>Matters of control are limited to:</u></p> <ul style="list-style-type: none"> <u>(1) Design, appearance and layout of the subdivision.</u> (2) Landscaping. (3) Provision of and effects on network utilities and/or services. (4) Standard, construction and layout of vehicular access. (5) Earthworks. (6) Provision of esplanade reserves and esplanade strips. (7) Protection of any special amenity feature. (8) Financial contributions. (9) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site. (10) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-CMU-R7 covers subdivision within the 	
SUB-CMU-R2	Subdivision that creates one or more vacant allotments						
<p><u>1. Activity status: Controlled</u></p> <p><u>Where:</u></p> <p><u>a. Compliance is achieved with</u></p> <ul style="list-style-type: none"> <u>i. SUB-CMU-S1;</u> <u>ii. SUB-CMU-S2; and</u> <u>iii. SUB-CMU-S3.</u> <p><u>Matters of control are limited to:</u></p> <ul style="list-style-type: none"> <u>(1) Design, appearance and layout of the subdivision.</u> (2) Landscaping. (3) Provision of and effects on network utilities and/or services. (4) Standard, construction and layout of vehicular access. (5) Earthworks. (6) Provision of esplanade reserves and esplanade strips. (7) Protection of any special amenity feature. (8) Financial contributions. (9) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site. (10) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-CMU-R7 covers subdivision within the 							

Commented [MM99]: S58.64 - Kāinga Ora: Homes and Communities

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p><u>Electricity Transmission Corridor.</u></p> <p>2. Activity status: Restricted Discretionary</p> <p>Where:</p> <p>a. <u>Compliance is not achieved with SUB-CMU-S2 or SUB-CMU-S3</u></p> <p><u>Matters of discretion are restricted to:</u></p> <p>(1) <u>The extent to which the activity will adversely affect traffic and pedestrian safety.</u></p> <p>(2) <u>The extent to which the activity will adversely affect the efficient functioning of the roading network.</u></p> <p>(3) <u>The matters of control listed in SUB-CMU-R2.1</u></p> <p>3. Activity status: Discretionary</p> <p>Where:</p> <p>a. <u>Compliance is not achieved with SUB-CMU-S1</u></p>
	New SUB-CMU – Subdivision in Commercial and Mixed Use Zones	Introduce new Rule SUB-CMU-R3	<p>SUB-CMU-R3 <u>Subdivision of Land for Utilities, Reserves or Conservation Purposes.</u></p> <p>1. Activity status: Controlled</p> <p><u>Matters of control are limited to:</u></p> <p>(1) <u>Design, appearance and layout of the subdivision.</u></p> <p>(2) <u>Landscaping.</u></p> <p>(3) <u>Provision of and effects on network utilities and/or services.</u></p> <p>(4) <u>Standard, construction and layout of vehicular access.</u></p> <p>(5) <u>Earthworks.</u></p> <p>(6) <u>Provision of esplanade reserves and esplanade strips.</u></p> <p>(7) <u>Protection of any special amenity feature.</u></p> <p>(8) <u>Financial contributions.</u></p>

Commented [MM100]: S58.64 - Kāinga Ora: Homes and Communities

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(98) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site.</p> <p>(109) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site.</p>
	New SUB-CMU – Subdivision in Commercial and Mixed Use Zones	Introduce new Rule SUB-CMU-R4	<p>SUB-CMU-R4 Subdivision within the Ponding Area of the Pinehaven Flood Hazard Extent and the Erosion Hazard Area of the Mangaroa Flood Hazard Extent that creates one or more vacant allotments.</p> <p>1. Activity status: Restricted Discretionary</p> <p>Where:</p> <p>a. Compliance is achieved with</p> <p>i. SUB-CMU-S1;</p> <p>ii. SUB-CMU-S2;</p> <p>iii. SUB-CMU-S3; and</p> <p>iv. SUB-CMU-S4.</p> <p>Matters of discretion are restricted to:</p> <p>(1) Design, appearance and layout of the subdivision.</p> <p>(2) Landscaping.</p> <p>(23) Provision of and effects on network utilities and/or services.</p> <p>(34) Standard, construction and layout of vehicular access.</p> <p>(45) Earthworks.</p> <p>(56) Provision of esplanade reserves and esplanade strips.</p> <p>(67) Protection of any special amenity feature.</p> <p>(78) Financial contributions.</p> <p>(89) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site.</p>


Commented [MM101]: S58.64 - Kāinga Ora: Homes and Communities

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(94) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-CMU-R7 covers subdivision within the Electricity Transmission Corridor.</p> <p>(104) The appropriateness of the proposed building platform in terms of area and location in relation to the flood hazard.</p> <p>(112) Ability for a future building to be constructed above the 1 in 25- year flood level.</p> <p>(123) The effect of the future development of the building platform on the function of the floodplain.</p> <p>(134) Consent notice restricting the future development to the identified platform.</p> <p>(145) The extent to which the activity will adversely affect traffic and pedestrian safety.</p> <p>(156) The extent to which the activity will adversely affect the efficient functioning of the roading network.</p> <p>3. Activity status: Discretionary Where: a. Compliance is not achieved with SUB-CMU-S2 or SUB-CMU-S3</p> <p>3. Activity status: Non-complying Where: a. Compliance is not achieved with SUB-CMU-S1 or SUB-CMU-S4</p>
	New SUB-CMU – Subdivision in Commercial and Mixed Use Zones	Introduce new Rule SUB-CMU-R5	<p>SUB-CMU-R5 Subdivision which creates building platforms within 20m of high voltage (110kV or greater) electricity transmission lines as shown on the Planning Maps.</p> <p>1. Activity status: Restricted Discretionary Where: a. Compliance is achieved with i. SUB-CMU-S1; ii. SUB-CMU-S2; and</p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>iii. SUB-CMU-S3.</p> <p>Matters of discretion are restricted to:</p> <p>(1) Design, appearance and layout of the subdivision.</p> <p>(2) Landscaping.</p> <p>(32) Provision of and effects on network utilities and/or services.</p> <p>(43) Standard, construction and layout of vehicular access.</p> <p>(54) Earthworks.</p> <p>(65) Provision of esplanade reserves and esplanade strips.</p> <p>(76) Protection of any special amenity feature.</p> <p>(87) Financial contributions.</p> <p>(98) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site.</p> <p>(409) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-CMU-R7 covers subdivision within the Electricity Transmission Corridor.</p> <p>(104) The extent to which the subdivision design manages potential conflicts with existing lines by locating roads and reserves under the route of the line.</p> <p>(112) The extent to which maintenance and inspections of transmission lines are affected including access.</p> <p>(123) The extent to which potential adverse effects including risk or injury, property damage and visual impact are mitigated through the location of building platforms and landscaping.</p> <p>(134) The outcome of any consultation with the affected utility operator.</p> <p>(145) Separation distances between trees and conductors and the location and mature size of trees planted near the transmission lines.</p> <p>(156) Compliance with the New Zealand Electrical Code of Practice for Electrical Safe Distances 2001 (NZECP 34:2001).</p> <p>(167) Measures necessary to avoid, remedy or mitigate the potential adverse effects of earthworks, dust generation and construction activities, including provision of appropriate separation distances, managing the risks to</p>

Commented [MM102]: S58.64 - Kāinga Ora: Homes and Communities

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p><u>structural integrity, and safety risks associated with the use of mobile machinery.</u></p> <p>Restriction on notification</p> <p>A resource consent application under this rule will be precluded from public notification under section 95A, and limited notification will be served on Transpower New Zealand Limited as the only affected party under section 95B.</p> <p>3. Activity status: Discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with SUB-CMU-S1, SUB-CMU-S2 or SUB-CMU-S3</p>
	New SUB-CMU – Subdivision in Commercial and Mixed Use Zones	Introduce new Rule SUB-CMU-R6	<p>SUB-CMU-R6 Subdivision of sites that contain Historic Heritage or Notable Trees and are identified in HH-SCHED1 or TREE-SCHED1.</p> <p>1. Activity status: Discretionary</p>
	New SUB-CMU – Subdivision in Commercial and Mixed Use Zones	Introduce new Standard SUB-CMU-S1	<p>Standards</p> <p>SUB-CMU-S1 Access</p> <p>Where site access is required or provided the following standards apply</p> <p>(1) All accessways and manoeuvring areas shall be formed and surfaced in accordance with the Code of Practice for Civil Engineering Works.</p> <p>Exemption – the requirement for accessways serving sites solely occupied by unstaffed utilities shall be that the accessway shall be surfaced with permanent all weather surfacing for a minimum length of 5m from the edge of the road carriageway seal.</p> <p>(2) Sites shall have practical vehicle access to car parking and loading spaces (where provided or required), in accordance with the Code of Practice for Civil Engineering Works. This requirement does not apply to sites solely occupied by unstaffed utilities, provided that vehicles associated with utilities shall not obstruct the footpath or create a traffic hazard on the road.</p> <p>(3) Adequate vehicular access shall be made available to the rear of every new building in accordance with the Code of Practice for Civil Engineering Works.</p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(3) Vehicular access to a corner allotment lot shall be located no closer than 8m from the street corner. Where a site is located on an intersection of a primary or secondary arterial traffic route (identified in the Transport and Parking (TP) Chapter the siting of the vehicular access shall be located as far as practicable from the corner of the street. The 8 metre setback shall be measured from where the two front boundaries of the site (refer to the definition of a corner allotment lot) join, or in accordance with the diagram below.</p>  <p>(4) Where a corner allotment lot is located at an intersection of a national, primary or secondary arterial traffic route, as identified in the Transport and Parking (TP) Chapter, no building, fence or other structure is to be erected and no vegetation allowed to grow so as to obstruct a traffic sight line.</p> <p>(5) At the intersection of a road or rail level crossing, no building, fence or other obstructions which block sight lines for trains shall be erected, placed or grown in the hatched area marked in Diagram 1A in the Transport and Parking (TP) Chapter.</p> <p>(6) Subdivision with direct access to a State Highway shall comply with the access and visibility standards set out in Diagrams 2 to 9 in the Transport and Parking (TP) Chapter.</p>
	New SUB-CMU – Subdivision in Commercial and Mixed Use Zones	Introduce new Standard SUB-CMU-S2	<p>SUB-CMU-S2 Water supply, stormwater and wastewater</p> <p>All subdivisions shall comply with the water supply, stormwater and wastewater standards in the Code of Practice for Civil Engineering Works.</p>
	New SUB-CMU – Subdivision in	Introduce new Standard SUB-CMU-S3	<p>SUB-CMU-S3 Subdivision in the Erosion Hazard Area of the Mangaroa Flood Hazard Extent</p> <p>All subdivision within the Erosion Hazard Area of the Mangaroa Flood Hazard Extent shall comply with the following:</p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	Commercial and Mixed Use Zones		<ol style="list-style-type: none"> 1. <u>A suitable future building platform area must be identified and must not be located within the River Corridor.</u> 2. <u>Where the proposed building platform is located within the Erosion Hazard Area, provision of a report by a suitability qualified and experienced person to determine the erosion risk to the proposed building platform is required in accordance with Section 2.4.10 of Part 1 of this Plan.</u>

SUB-COM – Subdivision in Industrial Zones


SUB-COM – Subdivision in Commercial Zones	Delete reference to Commercial and City Centre and retain Industrial only	SUB-INDCOM – Subdivision in <u>Industrial</u> Commercial Zones								
		<p>Rules</p> <p>Activities Tables</p> <table border="1"> <thead> <tr> <th colspan="2">Controlled Activities</th> <th colspan="2">Zones</th> </tr> </thead> <tbody> <tr> <td>SUB-GIZCOM-R1</td> <td> <p>Subdivision which complies with the standards in SUB-INDCOM-S1 and SUB-INDCOM-S2 unless specified below</p> <p>Council may impose conditions over the following matters:</p> <ol style="list-style-type: none"> (1) Design, appearance and layout of the subdivision. (2) Landscaping. (3) Provision of and effects on network utilities and/or services. (4) Standard, construction and layout of vehicular access. (5) Earthworks. (6) Provision of esplanade reserves and strips. (7) Protection of any special amenity feature. (8) Financial contributions. (9) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site. </td> <td>CON</td> <td> Commercial City Centre General Industrial </td> </tr> </tbody> </table>			Controlled Activities		Zones		SUB-GIZCOM-R1	<p>Subdivision which complies with the standards in SUB-INDCOM-S1 and SUB-INDCOM-S2 unless specified below</p> <p>Council may impose conditions over the following matters:</p> <ol style="list-style-type: none"> (1) Design, appearance and layout of the subdivision. (2) Landscaping. (3) Provision of and effects on network utilities and/or services. (4) Standard, construction and layout of vehicular access. (5) Earthworks. (6) Provision of esplanade reserves and strips. (7) Protection of any special amenity feature. (8) Financial contributions. (9) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site.
Controlled Activities		Zones								
SUB-GIZCOM-R1	<p>Subdivision which complies with the standards in SUB-INDCOM-S1 and SUB-INDCOM-S2 unless specified below</p> <p>Council may impose conditions over the following matters:</p> <ol style="list-style-type: none"> (1) Design, appearance and layout of the subdivision. (2) Landscaping. (3) Provision of and effects on network utilities and/or services. (4) Standard, construction and layout of vehicular access. (5) Earthworks. (6) Provision of esplanade reserves and strips. (7) Protection of any special amenity feature. (8) Financial contributions. (9) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site. 	CON	Commercial City Centre General Industrial							
Consequential Amendment										

IPI - PROPOSED AMENDMENTS						
#	Chapter	Change	Track Change			
				(10) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site . Note: Rule SUB- INDCOM -R7 covers subdivision within the Electricity Transmission Corridor.		
	SUB-COM – Subdivision in Commercial Zones	Consequential Amendment	<p>SUB-INDCOM-R2</p> <p><i>Policies</i> SUB-GEN-P1, SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P9, SUB-GEN-P10, CCZ-P1, GIZ-P1, CCZ-P3, COMZ-P2, CCZ-P4, GIZ-P3, DEV1-P7</p>	<p>Subdivision around any existing lawfully established residential unit or commercial activity or industrial activity building which does not result in the creation of any new undeveloped site that contains no Residential Unit or commercial activity or industrial activity building.</p> <p>Note: this form of subdivision does not need to comply with the minimum net site area requirements of SUB-INDCOM-S1, but does need to meet the access standards of SUB-INDCOM-S2</p> <p>Council may impose conditions over the following matters:</p> <p>(1) Design, appearance and layout of the subdivision.</p> <p>(2) Landscaping.</p> <p>(3) Provision of and effects on network utilities and/or services.</p> <p>(4) Standard, construction and layout of vehicular access.</p> <p>(5) Earthworks.</p> <p>(6) Provision of esplanade reserves and strips.</p> <p>(7) Protection of any special amenity feature.</p> <p>(8) Financial contributions.</p> <p>(9) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site.</p> <p>(10) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-INDCOM-R7 covers subdivision within the Electricity Transmission Corridor.</p>	CON	Commercial City Centre General Industrial

IPI - PROPOSED AMENDMENTS						
#	Chapter	Change	Track Change			
	SUB-COM – Subdivision in Commercial Zones	Consequential Amendment	<p>SUB-INDCOM-R3</p> <p><i>Policies</i> SUB-GEN-P1, SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P9, SUB-GEN-P10, CCZ-P1, GIZ-P1, CCZ-P3, COMZ-P2, CCZ-P4, GIZ-P3, DEV1-P7</p>	<p>Subdivision of land for utilities, reserves or conservation purposes. Council may impose conditions over the following matters:</p> <ol style="list-style-type: none"> (1) Design, appearance and layout of the subdivision. (2) Landscaping. (3) Provision of and effects on network utilities and/or services. (4) Standard, construction and layout of vehicular access. (5) Earthworks. (6) Provision of esplanade reserves and strips. (7) Protection of any special amenity feature. (8) Financial contributions. (9) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site. (10) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. <p>Note: Rule SUB-INDCOM-R7 covers subdivision within the Electricity Transmission Corridor.</p>	CON	Commercial City Centre General Industrial
	SUB-COM – Subdivision in Commercial Zones	Consequential Amendment	<p>SUB-INDCOM-R4</p> <p><i>Policies</i> SUB-GEN-P1, SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P9, SUB-GEN-P10,</p>	<p>Subdivision which is a unit title subdivision or an alteration to a company lease, unit title or cross lease title to include a building extension or alteration or accessory building on the site (excluding an additional residential unit) that has been lawfully established in terms of the Building Act 2004.</p> <p>Council may impose conditions over the following matters:</p> <ol style="list-style-type: none"> (1) Design, appearance and layout of the subdivision. (2) Landscaping. 	CON	Commercial City Centre General Industrial

IPI - PROPOSED AMENDMENTS																					
#	Chapter	Change	Track Change																		
			<p>CCZ-P1, GIZ-P1, CCZ-P3, COMZ-P2, CCZ-P4, GIZ-P3, DEV1-P7</p> <p>(3) Provision of and effects on network utilities and/or services.</p> <p>(4) Standard, construction and layout of vehicular access.</p> <p>(5) Earthworks.</p> <p>(6) Provision of esplanade reserves and strips.</p> <p>(7) Protection of any special amenity feature.</p> <p>(8) Financial contributions.</p> <p>(9) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site.</p> <p>(10) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-INDCOM-R7 covers subdivision within the Electricity Transmission Corridor.</p> <p>(11) Allocation of accessory units to principal units and covenant areas to leased areas to ensure compliance with car park provisions and to ensure practical physical access to units.</p> <p>(12) Allocation of areas.</p> <p>Controlled activities – restrictions on notification Subject to sections 95A(2)(b), 95A(2)(c), 95A(4) and 95C of the Act, a resource consent application for a controlled activity is precluded from public notification under section 95A and, subject to section 95B(3), is precluded from limited notification under section 95B(2) of the Act.</p>																		
	SUB-COM – Subdivision in Commercial Zones	Consequential Amendment	<table border="1"> <thead> <tr> <th colspan="3">Standards for Controlled Activities</th> <th>Zone</th> </tr> </thead> <tbody> <tr> <td rowspan="4">SUB-INDCOM-S1 Policy CCZ-P1, GIZ-P1</td> <td colspan="3">Minimum requirements for subdivision</td> <td rowspan="4">Commercial City Centre General Industrial</td> </tr> <tr> <td>Commercial and Industrial Zones</td> <td>Minimum net site area</td> <td>Shape factor</td> </tr> <tr> <td>Commercial</td> <td>300m²</td> <td>7.5m</td> </tr> <tr> <td>City Centre</td> <td>300m²</td> <td>7.5m</td> </tr> </tbody> </table>	Standards for Controlled Activities			Zone	SUB- INDCOM -S1 Policy CCZ-P1, GIZ-P1	Minimum requirements for subdivision			Commercial City Centre General Industrial	Commercial and Industrial Zones	Minimum net site area	Shape factor	Commercial	300m ²	7.5m	City Centre	300m ²	7.5m
Standards for Controlled Activities			Zone																		
SUB- INDCOM -S1 Policy CCZ-P1, GIZ-P1	Minimum requirements for subdivision			Commercial City Centre General Industrial																	
	Commercial and Industrial Zones	Minimum net site area	Shape factor																		
	Commercial	300m ²	7.5m																		
	City Centre	300m ²	7.5m																		

IPI - PROPOSED AMENDMENTS						
#	Chapter	Change	Track Change			
				General Industrial	500m ²	20m
			Exemptions			
			These standards shall not apply to any allotments for utility, reserve or conservation purposes.			
	SUB-COM – Subdivision in Commercial Zones	Consequential Amendment	<p>SUB-INDCOM-S2</p> <p><i>Policies SUB-GEN-P1, TP-P4, CCZ-P1, GIZ-P1, CCZ-P2</i></p>	<p>Access standards for subdivision</p> <p>(1) All accessways and manoeuvring areas shall be formed and surfaced in accordance with the Code of Practice for Civil Engineering Works. Exemption – the requirement for accessways serving sites solely occupied by unstaffed utilities shall be that the accessway shall be surfaced with permanent all weather surfacing for a minimum length of 5m from the edge of the road carriageway seal.</p> <p>(2) All sites shall have practical vehicle access to car parking and loading spaces, in accordance with the Code of Practice for Civil Engineering Works. This requirement does not apply to sites solely occupied by unstaffed utilities, provided that vehicles associated with utilities shall not obstruct the footpath or create a traffic hazard on the road.</p> <p>(3) Adequate vehicular access shall be made available to the rear of every new building in accordance with the Code of Practice for Civil Engineering Works.</p> <p>(4) Vehicular access to a corner allotment lot shall be located no closer than 8m from the street corner. Where a site is located on an intersection of a primary or secondary arterial traffic route (identified in the Transport and Parking (TP) Chapter the siting of the vehicular access shall be located as far as practicable from the corner of the street. The 8 metre setback shall be measured from where the two front boundaries of the site (refer to the definition of a corner allotment lot) join, or in accordance with the diagram below.</p>		<p>Commercial City Centre General Industrial Development Area1</p>

IPI - PROPOSED AMENDMENTS						
#	Chapter	Change	Track Change			
				<p>(5) Where a corner allotment lot is located at an intersection of a national, primary or secondary arterial traffic route, as identified in the Transport and Parking (TP) Chapter, no building, fence or other structure is to be erected and no vegetation allowed to grow so as to obstruct a traffic sight line.</p> <p>(6) At the intersection of a road or rail level crossing, no building, fence or other obstructions which block sight lines for trains shall be erected, placed or grown in the hatched area marked in Diagram 1A in the Transport and Parking (TP) Chapter.</p> <p>(7) Subdivision with direct access to a State Highway shall comply with the access and visibility standards set out in Diagrams 2 to 9 in the Transport and Parking (TP) Chapter.</p>		
	SUB-COM – Subdivision in Commercial Zones	Consequential Amendment	<p>SUB-INDCOM-S3</p> <p><i>Policies</i> SUB-GEN-P1, NATC-P1</p>	<p>Water supply, stormwater and wastewater</p> <p>(1) All activities shall comply with the water supply, stormwater and wastewater standards in the Code of Practice for Civil Engineering Works.</p>	<p>Commercial, City Centre General Industrial</p>	

IPI - PROPOSED AMENDMENTS						
#	Chapter	Change	Track Change			
	SUB-COM – Subdivision in Commercial Zones	Consequential Amendment	<p>Restricted Discretionary Activities</p> <p>SUB-INDCOM-R5</p> <p><i>Policies</i> SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P10, SUB-GEN-P12, CCZ-P1, GIZ-P1</p>	<p>Subdivision which complies with the standards of SUB-INDCOM-S1 but not SUB-INDCOM-S2</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <ol style="list-style-type: none"> (1) The extent to which the activity will adversely affect traffic and pedestrian safety. (2) The extent to which the activity will adversely affect the efficient functioning of the roading network. <p>Council’s discretion is also restricted to the matters listed in rule SUB-INDCOM-R1.</p>	<p>RDIS</p>	<p>Zones</p> <p>Commercial City Centre General Industrial</p>
	SUB-COM – Subdivision in Commercial Zones	Consequential Amendment	<p>SUB-INDCOM-R6</p> <p><i>Policies</i> SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P10, SUB-GEN-P12, CCZ-P1, GIZ-P1</p>	<p>Subdivision around any existing lawfully established residential unit or commercial activity or industrial activity building which does not result in the creation of any new undeveloped site that contains no residential unit or commercial or industrial activity, that does not comply with the access standards of SUB-INDCOM-S2</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <ol style="list-style-type: none"> (1) The extent to which the activity will adversely affect traffic and pedestrian safety. (2) The extent to which the activity will adversely affect the efficient functioning of the roading network. <p>Council’s discretion is also restricted to the matters listed in rule SUB-INDCOM-R1.</p>	<p>RDIS</p>	<p>Zones</p> <p>Commercial City Centre General Industrial</p>
	SUB-COM – Subdivision in Commercial Zones	Consequential Amendment	<p>SUB-INDCOM-R7</p> <p><i>Policies</i> SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P10, CCZ-P1,</p>	<p>Subdivision which creates building platforms within 20m of high voltage (110kV or greater) electricity transmission lines as shown on the Planning Maps *(refer to the definition of transmission line)</p> <p>In addition to the matters listed in SUB-INDCOM-R1, Council will restrict its discretion to, and may impose conditions on:</p> <ol style="list-style-type: none"> (1) The extent to which the subdivision design manages potential conflicts with existing lines by locating roads and reserves under the route of the line. 	<p>RDIS</p>	<p>Zones</p> <p>Commercial City Centre General Industrial</p>

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<p><i>GIZ-P1, NU-P1</i></p>	<p>(2) The extent to which maintenance and inspections of transmission lines are affected including access.</p> <p>(3) The extent to which potential adverse effects including risk or injury, property damage and visual impact are mitigated through the location of building platforms and landscaping.</p> <p>(4) The outcome of any consultation with the affected utility operator.</p> <p>(5) Separation distances between trees and conductors and the location and mature size of trees planted near the transmission lines.</p> <p>(6) Compliance with the New Zealand Electrical Code of Practice for Electrical Safe Distances 2001 (NZECP 34:2001).</p> <p>(7) Measures necessary to avoid, remedy or mitigate the potential adverse effects of earthworks, dust generation and construction activities, including provision of appropriate separation distances, managing the risks to structural integrity, and safety risks associated with the use of mobile machinery.</p> <p>Restriction on notification</p> <p>Subject to sections 95A(2)(b), 95A(2)(c), 95A(4) and 95C of the Act, a resource consent application under this rule will be precluded from public notification under section 95A, and limited notification will be served on Transpower New Zealand Limited as the only affected party under section 95B.</p>			
	SUB-COM – Subdivision in Commercial Zones	Consequential Amendment	<p>SUB-INDCOM-R8</p> <p><i>Policies</i> <i>SUB-GEN-P2,</i> <i>SUB-GEN-P3,</i> <i>SUB-GEN-P10,</i> <i>CCZ-P1,</i> <i>GIZ-P1</i></p>	<p>Subdivision within the Ponding Area of the Pinehaven Flood Hazard Extent, which results in any undeveloped site that contains no building, and complies with the requirements of SUB-INDCOM-S1</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <p>(1) The matters contained in Rule SUB-INDCOM-R1.</p> <p>(2) The appropriateness of the proposed building platform in terms of area and location in relation to the flood hazard.</p>	RDIS	<p><i>Commercial</i> <i>City Centre</i> <i>General</i> <i>Industrial</i></p>	

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
				<p>(3) Ability for a future building to be constructed above the 1 in 25- year flood level.</p> <p>(4) The effect of the future development of the building platform on the function of the floodplain.</p> <p>(5) Consent notice restricting the future development to the identified platform.</p> <p>(6) Matters addressing the standards for access under SUB-INDCOM-S2 where any standards are not met.</p>			
	SUB-COM – Subdivision in Commercial Zones	Consequential Amendment	<p>SUB-INDCOM-R9</p> <p><i>Policies</i> SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P10, CCZ-P1, GIZ-P1</p>	<p>Subdivision within the Erosion Hazard Area of the Mangaroa Flood Hazard Extent, which results in any undeveloped allotments that contain no building, and complies with the requirements of SUB-INDCOM-S1 and SUB-INDCOM-S4.</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <p>(1) The matters contained in SUB-INDCOM-R1.</p> <p>(2) The appropriateness of the proposed building platform in terms of area and location in relation to the flood hazard.</p> <p>(3) Ability for a future building to be constructed above the 1 in 100- year flood level.</p> <p>(4) The effect of the future development of the building platform on the function of the floodplain.</p> <p>(5) Consent notice restricting the future development to the identified platform.</p> <p>(6) The suitability of the proposed access to the future building platform to facilitate access during a 1 in 100-year flood event and does not obstruct or divert floodwater flows within the Flood Hazard Extent.</p>	RDIS	Commercial City Centre General Industrial	
	SUB-COM – Subdivision in Commercial Zones	Consequential Amendment	Standards for Restricted Discretionary Activities			Zones	

IPI - PROPOSED AMENDMENTS						
#	Chapter	Change	Track Change			
			<p>SUB-INDCOM-S4</p> <p><i>Policies</i> SUB-GEN-P2 SUB-GEN-P3</p>	<p>Standards for Subdivision within the Erosion Hazard Area of the Mangaroa Flood Hazard Extent</p> <p>(1) Suitable future building platform area must be identified and must not be located within the River Corridor.</p> <p>(2) Where the proposed building platform is located within the Erosion Hazard Area, provision of a report by a suitability qualified and experienced person to determine the erosion risk to the proposed building platform is required in accordance with Section 2.4.10 of Part 1 of this Plan.</p>		<p>Commercial City Centre General Industrial</p>
	SUB-COM – Subdivision in Commercial Zones	Consequential Amendment	<p>Discretionary Activities</p>			<p>Zone</p>
			<p>SUB-INDCOM-R10</p> <p><i>Policies</i> SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P4, SUB-GEN-P9, SUB-GEN-P10, NATC-P1, NH-P6, CCZ-P1, GIZ-P1</p>	<p>Subdivision of a site identified in Schedules HH-SCHED1 or TREE-SCHED1</p>	<p>DIS</p>	<p>Commercial City Centre General Industrial Development Area1</p>
	SUB-COM – Subdivision in Commercial Zones	Consequential Amendment	<p>SUB-INDCOM-R11</p> <p><i>Policies</i> SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P10, CCZ-P1, GIZ-P1</p>	<p>Subdivision which does not comply with the standards specified in rule SUB-INDCOM-S1</p>	<p>DIS</p>	<p>Commercial City Centre General Industrial</p>

IPI - PROPOSED AMENDMENTS						
#	Chapter	Change	Track Change			
	SUB-COM – Subdivision in Commercial Zones	Consequential Amendment	<p>SUB-INDCOM- R12</p> <p><i>Policies</i> SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P4, SUB-GEN-P9, SUB-GEN-P10, NATC-P1, CCZ-P1, GIZ-P1</p>	<p>Subdivision that is not listed as a permitted, controlled, restricted discretionary or non-complying activity.</p>	<p>DIS</p>	<p>Commercial City Centre General Industrial Development Area1</p>
	SUB-COM – Subdivision in Commercial Zones	Consequential Amendment	<p>Non-Complying Activities</p>			<p>Zone</p>
			<p>SUB-INDCOM- 13</p> <p><i>Policies</i> SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P4, SUB-GEN-P9, SUB-GEN-P10, NATC-P1, NH-P6, CCZ-P1, GIZ-P1</p>	<p>Creation of an allotment that does not have formed legal access to a formed legal road, unless the proposal is for a paper road or other access to be formed as a condition of subdivision approval in accordance with the Code of Practice for Civil Engineering Works</p>	<p>NC</p>	<p>Commercial City Centre General Industrial Development Area1</p>
	SUB-COM – Subdivision in Commercial Zones	Consequential Amendment	<p>SUB-INDCOM- R14</p> <p><i>Policies</i> SUB-GEN-P2, SUB-GEN-P3,</p>	<p>Subdivision within the Pinehaven Flood Hazard Extent which results in any undeveloped allotments that contain no building, and does not comply with the requirements of SUB-INDCOM-S1</p>	<p>NC</p>	<p>Commercial City Centre General Industrial</p>

IPI - PROPOSED AMENDMENTS						
#	Chapter	Change	Track Change			
			<i>SUB-GEN-P10, CCZ-P1, GIZ-P1</i>			
	SUB-COM – Subdivision in Commercial Zones	Consequential Amendment	SUB-INDCOM- R15 <i>Policies SUB-GEN-P2, SUB-GEN-P3, SUB-GEN-P10, CCZ-P1, GIZ-P1</i>	Subdivision within the Mangaroa Flood Hazard Extent which results in any undeveloped allotments that contain no building , where one or more of the following occurs: Does not comply with the requirements of SUB- INDCOM-S1 ; The proposed building platform is located within a River Corridor .	NC	Commercial City Centre General Industrial
	SUB-COM – Subdivision in Commercial Zones	Consequential Amendment	Matters for Consideration			Zone
			Matters that may be relevant in the consideration of any resource consent may include the following:			
			SUB-INDCOM- MC1	Subdivision (1) The design and layout of the subdivision where any allotments may affect the safe and effective operation and maintenance of, and access to, regionally significant network utilities (excluding the National Grid), located on or in proximity to the site . (2) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site . Note: Rule SUB- INDCOM-R7 covers subdivision within the Electricity Transmission Corridor. (3) The design and layout of the subdivision where any allotment may affect the safe and effective operation and maintenance of, and access to, consented or existing renewable electricity generation activities located on or in proximity to the site . (4) The outcome of consultation with the owner or operator of consented or existing renewable electricity generation activities located on or in proximity to the site .		Commercial City Centre General Industrial

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
				<ul style="list-style-type: none"> (5) Account must be taken of the future development potential of adjoining or adjacent land. (6) Account must be taken of any potential reverse sensitivity effects on regionally significant network utilities (excluding the National Grid). (7) Where located within an identified flood hazard extent, any relevant matters of discretion identified under SUB-INDCOM-R8 or SUB-INDCOM-R9. 	
	SUB-COM – Subdivision in Commercial Zones	Consequential Amendment	SUB-INDCOM-MC2	Access <ul style="list-style-type: none"> (8) Accessibility for public transport, cyclists and pedestrians. (9) Compliance with the Code of Practice for Civil Engineering Works. (10) Whether the topography, size or shape of the site or the location of any natural or built feature(s) on the site or other requirements such as easements, rights-of-way or restrictive covenants impose constraints that make compliance impracticable. (11) Whether the activities proposed will not generate a demand for servicing facilities. (12) Whether suitable alternative provision for servicing can be made. (13) Whether the nature of adjacent roads is such that the entry, exit and manoeuvring of vehicles can be conducted safely. (14) The extent to which any subdivision and/or development within the Mount Marua Structure Plan Development Area is consistent with the Mount Marua Structure Plan. 	Commercial, City Centre General Industrial
SUB-SAZ - Subdivision in the Special Activity Zone					
	SUB-SAZ - Subdivision in the Special Activity Zone	Consequential Amendment	Matters for Consideration		Zone
			Matters that may be relevant in the consideration of any resource consent may include the following:		
			SUB-SAZ-MC3	Site layout	<i>Special Activity</i>

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
				<ul style="list-style-type: none"> (1) The arrangement of buildings, car parks and vehicle movements on site. (2) The extent of landscaping and screening particularly where sites adjoin General Residential, <u>High Density Residential</u>, or Open Space Zones. (3) Whether the topography of the site has been taken into account. (4) Whether a better standard of development can be achieved by varying the design. 	
	SUB-SAZ - Subdivision in the Special Activity Zone	Consequential Amendment	SUB-SAZ-MC6	Additional matters for the St Patrick's <u>Estate College Area</u> <ul style="list-style-type: none"> (1) Whether flooding effects have been adequately addressed. (2) Whether the proposal maintains a landscaped gateway to the City, a low density, open development and contains screening from residential areas and Fergusson Drive. (3) Whether the landscaping will maintain and enhance the amenity of the area. (4) Whether pedestrian linkages to the Hutt River walkway and Silverstream Railway Station are provided. 	<i>Special Activity</i>
	SUB-SAZ - Subdivision in the Special Activity Zone	Consequential Amendment	SUB-SAZ-MC7	Access <ul style="list-style-type: none"> (22) Accessibility for public transport, cyclists and pedestrians. (23) Compliance with the Code of Practice for Civil Engineering Works. (24) Whether the topography, size or shape of the site or the location of any natural or built feature(s) on the site or other requirements such as easements, rights-of-way or restrictive covenants impose constraints that make compliance impracticable. (25) Whether the activities proposed will not generate a demand for servicing facilities. (26) Whether suitable alternative provision for servicing can be made. (27) Whether the nature of adjacent roads is such that the entry, exit and manoeuvring of vehicles can be conducted safely. 	<i>General Rural Rural Production Rural Lifestyle Commercial and Mixed Use <u>City Centre</u> General Industrial Open Space Special Activity Development Area 2</i>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			(28) The extent to which any subdivision within the Mount Marua Structure Plan Development Area is consistent with the Mount Marua Structure Plan.
SUB-DEV1 - Subdivision in Development Area 1			
	SUB-DEV1 - Subdivision in Development Area 1	Consequential Amendment	This chapter contains the subdivision provisions which relate to the Wallaceville Structure Plan Development Area . These rules apply in addition to the underlying subdivision rules of the General Residential Zone (SUB-RES) , High Density Residential Zone (SUB-HRZ) and the Commercial and Mixed Use Zones (SUB-COMCMU) . Where there is any conflict between the provisions the Wallaceville Structure Plan Development Area provisions shall prevail.
DFC – Development Financial Contributions			
	Background	Amend Financial contributions to include urban development infrastructure and transport in IPI zones.	<p>Section 77E(1) of the Act authorises rules requiring a empowered Council to impose financial contributions for any class of activity other than a prohibited activity.</p> <p>Section 108 (9) defines the types of possible financial contributions are described in the Act as</p> <p>(a) money, or</p> <p>(b) land, including an esplanade reserve or esplanade strip (other than in relation to a subdivision consent), but excluding Māori land within the meaning of the Te Ture Whenua Maori Act 1993 unless that Act provides otherwise;</p> <p>or</p> <p>(c) a combination of money and land.</p> <p>This part of the Plan chapter sets out the objective, policy, methods and rules relating to the imposition of financial contributions for reserves and leisure facilities contains the requirements for financial contributions which can be imposed for subdivision and development of land. Financial Contributions referred to in this Chapter are different from, and have a different purpose than Development Contributions imposed under the Local Government Act 2002. Under section 200 of that Act, the Council cannot collect financial contributions for the same development and for the same purpose as a development contribution (and vice versa). Financial contributions are assessed, calculated, and directly related to the effects of subdivision and development of land.</p> <p>Purpose of Financial Contributions</p> <p>Financial contributions received for reserves and <u>local</u> leisure facilities may be used anywhere in the City. The allocation of such contributions is made through the Annual Plan process.</p>

Commented [MM103]: S58.69 - Kāinga Ora: Homes and Communities

Commented [MM104]: S58.69 - Kāinga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>The purposes for which reserves and <u>local</u> leisure facilities contributions may be used are as follows:</p> <ul style="list-style-type: none"> • The provision for community facilities, reserves, amenities and open space. <u>Contributions toward large city-wide community infrastructure will be obtained via development contributions under the Local Government Act 2002.</u> • The protection and conservation of amenity values, and the life supporting capacity of ecosystems and waterbodies. • The provision of access to identified rivers, streams or lakes. • The protection of historical, scientific, cultural or aesthetic values of landscape features, landforms, places or buildings. <p>Financial contributions received for water, wastewater, stormwater, or transport infrastructure will be used to address the specific effects generated by a land use or subdivision for the following purposes:</p> <ul style="list-style-type: none"> • <u>Upgrades to the water, wastewater, or stormwater networks.</u> • <u>Footpaths, streetlighting or pedestrian shelter</u> • <u>Road upgrades;</u> • <u>Shared paths;</u> • <u>cycle parking; or</u> • <u>Offsetting any adverse effect(s) to ensure positive effects on the environment.</u> <p>Development Impact Fees Calculation of Financial Contributions This chapter contains <u>provisions</u> relating to <u>how development impact fees</u> <u>financial contributions</u> are assessed and calculated, including <u>provisions related to:</u></p> <ul style="list-style-type: none"> • the effects of specific activities, • defining areas affected, • methods of calculation, and, • methods of application;
	Background	Consequential amendment	<p>... The development contributions policy is included in the Long Term Council Community Plan (LTCCP) under Section 102(4)(d) of the Local Government Act 2002. Provisions relating to esplanade reserves and esplanade strips and financial contributions in lieu of car parks are found in the Transport and Parking Chapter (TP) and the Public Access Chapter (PA) respectively.</p>
	Policies	Amend Policy Dc-P1 and add 6 additional policies	<p>DC-P1 To require those developing or subdividing land subdividers or developers to contribute to the provision of utilities, community facilities, services, reading <u>transportation</u> and amenities.</p>

Commented [MM105]: S58.69 - Kāinga Ora: Homes and Communities.

Commented [MM106]: S58.69 - Kāinga Ora: Homes and Communities.

Commented [MM107]: S58.69 - Kāinga Ora: Homes and Communities

Commented [MM108]: S58.71 - Kāinga Ora: Homes and Communities

Commented [MM109]: S50.15 - Waka Kotahi.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>The most effective means of ensuring that these financial contributions are made is to require them at the time land is either subdivided or developed.</p> <p>DFC-P2 <u>Require those developing or subdividing land Subdividers and developers should to be responsible for the fair and reasonable bear the cost of providing all utility services within the land being subdivided or developed where the benefits accrue to the land being subdivided or developed, where such costs are not otherwise addressed by development contributions collected under the Local Government Act.</u></p> <p>DFC-P3 <u>In circumstances where the existing services outside the land being subdivided or developed are adequate but, the proposed subdivision or development will require upgrading or provision of new services and facilities, the subdivider or developer shall pay the full and actual cost of such upgrading or new utility services and facilities where such costs are not otherwise addressed by development contributions collected under the Local Government Act.</u></p> <p>DFC-P4 <u>Where Council has provided the necessary utility services in advance of land being subdivided or developed, it is necessary for owners of such land to make a fair and reasonable contribution when the land is subdivided or developed.</u></p> <p>DFC-P5 <u>Subdivision or development of land can lead to an increase in demand or need for reserves and open space and have adverse effects on the environment. It is important that subdividers or developers make a fair and reasonable contribution, either in cash or land, so that demand or need can be met and adverse effects can be avoided, remedied or mitigated. Require those developing or subdividing land to make a fair and reasonable contribution, in money or land, to open space and/or reserve contribution, where such costs are not otherwise addressed by the Council's Development Contributions collected under the Local Government Act.</u></p> <p>DFC-P6 <u>To ensure that developers make a fair and reasonable financial contribution to manage or mitigate adverse transportation or infrastructure effects arising from residential intensification activities where such costs are not otherwise addressed by development contributions collected under the Local Government Act 2002.</u></p> <p>DFC-P7 <u>A financial contribution may be required for any land use or subdivision application to ensure positive effects on the environment are achieved to offset any adverse effects that cannot otherwise be avoided, remedied or mitigated.</u></p>
	Rules	Amend rule DC-R1	Financial Contributions

Commented [MM110]: S58.69 - Kāinga Ora: Homes and Communities

Commented [MM111]: S58.72 - Kāinga Ora: Homes and Communities

Commented [MM112]: S58.72 - Kāinga Ora: Homes and Communities.

Commented [MM113]: S58.69 - Kāinga Ora: Homes and Communities

Commented [MM114]: S58.73 - Kāinga Ora: Homes and Communities

Commented [MM115]: S58.69 - Kāinga Ora: Homes and Communities

Commented [MM116]: S58.69 - Kāinga Ora: Homes and Communities

Commented [MM117]: S58.75 - Kāinga Ora: Homes and Communities

Commented [MM118]: S58.69 - Kāinga Ora: Homes and Communities

Commented [MM119]: S58.69 - Kāinga Ora: Homes and Communities

IPI - PROPOSED AMENDMENTS											
#	Chapter	Change	Track Change								
			<p>Reserve and Local Leisure Facilities Contribution</p> <p>DFC-R1 <i>Policy DC-P1</i></p> <p>A Reserve and Local Leisure Facilities Contribution is required where:</p> <ol style="list-style-type: none"> (1) Any additional site is created as part of a subdivision; (2) Two or more residential units are erected on a vacant site; (3) One or more additional residential units are erected on a site. <p>A Reserves and Local Leisure Facilities Contribution will be required in the form of money, land or a combination of money and land in accordance with the following table:</p> <table border="1"> <thead> <tr> <th colspan="2">Reserves and Local Leisure Facilities Contribution (All Zones)</th> </tr> <tr> <th colspan="2">Money</th> </tr> </thead> <tbody> <tr> <td>4%</td> <td>of the market ...</td> </tr> <tr> <td>...</td> <td></td> </tr> </tbody> </table>	Reserves and Local Leisure Facilities Contribution (All Zones)		Money		4%	of the market	
Reserves and Local Leisure Facilities Contribution (All Zones)											
Money											
4%	of the market ...										
...											
	Rules	Add new rule R2A to R2E	<p><u>Financial contribution for infrastructure and transport for residential intensification activities in Residential zones and Commercial and Mixed Use Zones</u></p> <p>DFC-R2A</p> <p><u>In all Residential or Commercial and Mixed Use Zones all residential intensification activities where two or more residential units or allotments are proposed, a financial contribution shall be a maximum contribution in cash or land to an equivalent value equal to 4% of the value of each new residential unit or allotment up to a maximum of \$10,000 per residential unit or allotment.</u></p> <p>(a) <u>Council recognises that the financial contribution is not appropriate in all cases and in determining whether the base maximum should be adjusted the following matters will be taken into account:</u></p> <ol style="list-style-type: none"> (i) <u>Whether there will be an increase in the intensity of use of land from that which existed before the development.</u> (ii) <u>Whether there is a change in nature and character of the use of land.</u> (iii) <u>The subsidies that council may receive from New Zealand Transport Agency or other central government agencies.</u> (iv) <u>Whether a development contribution for the same purpose applies under the Council's</u> 								

Commented [MM120]: S58.69 - Kāinga Ora: Homes and Communities

Commented [MM121]: S58.69 - Kāinga Ora: Homes and Communities

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p style="text-align: center;"><u>Development Contributions Policy</u></p>
			<p>Financial Contributions relating to transport including roads, private ways, service lanes, accessways, footpaths, cycleways, and walkways</p>
		DFC-R2B	<p>In all zones, except rural zones, the following financial contribution will be required:</p> <p>(a) <u>The full and actual costs of providing all new roads, private ways, service lanes, accessways, facilities to access public transport, cycleways, footpaths and walkways within the land being developed or subdivided. The developer must meet the full and actual cost of providing the necessary road lighting within the land being developed.</u></p> <p>(b) <u>Where existing roads, service lanes, accessways, footpaths and walkways outside the subdivision or development are adequate to serve the existing development but the proposed development will result in such roading facilities being inadequate the developer must pay the full and actual cost for all upgrading and any new facilities.</u> <u>For all Council provided services the council may elect to reduce the financial contribution from full and actual costs where the works address an existing and meaningful level of service deficit or provide significant benefits to other parties, such as other development sites.</u></p> <p>(c) <u>Where Council has upgraded facilities to take into account both vehicular and pedestrian traffic increases from land yet to be developed, developers of such undeveloped land shall be required to pay the full and actual costs of the upgrading and the new facilities based on trips generated by the development and taking into account the time value of money.</u></p>
			<p>Financial Contributions relating to site formation and development works, electricity, gas and telephone supply in all zones</p>
		DFC-R2C	<p>(a) <u>Within the land being subdivided or developed the subdivider or developer must pay for the full and actual cost of providing the necessary site formation and development works, electricity, gas and telephone services for the site.</u></p>

Commented [MM122]: S58.78 - Kāinga Ora: Homes and Communities

Commented [MM123]: Consequential on S50.15 - Waka Kotahi.

Commented [MM124]: S58.69 - Kāinga Ora: Homes and Communities

Commented [MM125]: S50.15 - Waka Kotahi.

Commented [MM126]: S58.69 - Kāinga Ora: Homes and Communities

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(b) <u>The subdivider or developer must pay for the full and actual cost of all site formation and development works within the land being subdivided or developed.</u></p> <p>(c) <u>Where site formation and development works within the land being subdivided or developed require remedial or stabilising work to be carried out on land adjoining or adjacent to the land being subdivided or developed the subdivider or developer must pay the full and actual cost of such work.</u></p>
			<p>Financial Contributions relating to water supply, disposal of waste water and stormwater for subdivision or development of land</p>
		DFC-R2D	<p>In all zones, except rural zones, the following a financial contribution will be required:</p> <p>(a) <u>Within the land being subdivided or developed the subdivider or developer must pay the full and actual cost of providing the necessary water supply, wastewater and stormwater disposal facilities for the proposed allotments or dwellings.</u></p> <p>(b) <u>Where the existing water supply, wastewater and/or stormwater capacity and pressure is adequate to serve existing development but the proposed subdivision will result in the capacity and/or pressure being inadequate the subdivider or developer must pay the full and actual costs for all such upgrading and new facilities.</u></p> <p>(c) <u>Where the Council provides the necessary water, sewage or stormwater disposal system for vacant land in advance of such land being subdivided or developed either by carrying out the necessary work the Council shall require a contribution from the subdivider or developer when such land is subdivided or developed based on the actual and full cost of providing the service to that land after taking into account the time value of money.</u></p> <p>(d) <u>The above provisions shall also apply to all staged subdivisions.</u></p>
			<p>Offsetting of adverse environmental effects</p>
		DFC-R2E	<p>In all Residential or Commercial and Mixed Use Zones all residential intensification activities where two or more residential units or allotments are proposed, a financial contribution may be</p>

Commented [MM127]: S58.69 - Kāinga Ora: Homes and Communities

Commented [MM128]: S58.69 - Kāinga Ora: Homes and Communities


IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<p><u>required for the amount of money or land or both needed to offset any adverse environmental effects that cannot otherwise be avoided, remedied or mitigated.</u></p>				
	DC-R2- Requirements for financial contributions	Consequential Amendment	<table border="1"> <thead> <tr> <th colspan="2">Financial Contributions</th> </tr> </thead> <tbody> <tr> <td style="vertical-align: top;"> <p>DC-R2</p> <p><i>Policy DC-P1</i></p> </td> <td> <p>Requirements for financial contributions</p> <ol style="list-style-type: none"> (1) All financial contributions on subdivisions are payable prior to the release of the completion certificate for the subdivision. (2) All financial contributions for any additional residential unit or multiple residential unit/unit development, where a subdivision has not taken place, are payable prior to the issuing of the <u>Code Compliance Certificate for Building Consent(s)</u> for the second or more residential unit /unit. (3) The valuation shall apply to the land only. For the purposes of the valuation, where the size of the site is larger than 1000m² the valuation will be based on a hypothetical 1000m² building site. (4) Where staged and further development takes place within 10 years, then a credit will apply against the reserves and leisure facilities contribution for the earlier payment, but no refunds will be given. (5) Contributions in accordance with the above are exclusive of GST. <p>Exemptions: The following forms of subdivision will not be required to provide financial contributions:</p> <ol style="list-style-type: none"> (6) Subdivision around any existing principal buildings lawfully established prior to 4 August 2006 that do not create any vacant sites. (7) <u>Subdivision around existing a residential unit(s) where a financial contribution has been paid previously for the residential unit(s).</u> (8) (7) Allotments set aside as reserves or for conservation purposes. (9) (8) Access lots. (10) (9) Rural allotments where there is a legal instrument preventing use of the allotment for residential purposes (e.g. – a forestry allotment). (11) (10) Allotments created for unstaffed utility services up to 200m² in area. (12) (11) Boundary adjustments or amalgamation of allotments with no resulting increase in titles. </td> </tr> </tbody> </table>	Financial Contributions		<p>DC-R2</p> <p><i>Policy DC-P1</i></p>	<p>Requirements for financial contributions</p> <ol style="list-style-type: none"> (1) All financial contributions on subdivisions are payable prior to the release of the completion certificate for the subdivision. (2) All financial contributions for any additional residential unit or multiple residential unit/unit development, where a subdivision has not taken place, are payable prior to the issuing of the <u>Code Compliance Certificate for Building Consent(s)</u> for the second or more residential unit /unit. (3) The valuation shall apply to the land only. For the purposes of the valuation, where the size of the site is larger than 1000m² the valuation will be based on a hypothetical 1000m² building site. (4) Where staged and further development takes place within 10 years, then a credit will apply against the reserves and leisure facilities contribution for the earlier payment, but no refunds will be given. (5) Contributions in accordance with the above are exclusive of GST. <p>Exemptions: The following forms of subdivision will not be required to provide financial contributions:</p> <ol style="list-style-type: none"> (6) Subdivision around any existing principal buildings lawfully established prior to 4 August 2006 that do not create any vacant sites. (7) <u>Subdivision around existing a residential unit(s) where a financial contribution has been paid previously for the residential unit(s).</u> (8) (7) Allotments set aside as reserves or for conservation purposes. (9) (8) Access lots. (10) (9) Rural allotments where there is a legal instrument preventing use of the allotment for residential purposes (e.g. – a forestry allotment). (11) (10) Allotments created for unstaffed utility services up to 200m² in area. (12) (11) Boundary adjustments or amalgamation of allotments with no resulting increase in titles.
Financial Contributions							
<p>DC-R2</p> <p><i>Policy DC-P1</i></p>	<p>Requirements for financial contributions</p> <ol style="list-style-type: none"> (1) All financial contributions on subdivisions are payable prior to the release of the completion certificate for the subdivision. (2) All financial contributions for any additional residential unit or multiple residential unit/unit development, where a subdivision has not taken place, are payable prior to the issuing of the <u>Code Compliance Certificate for Building Consent(s)</u> for the second or more residential unit /unit. (3) The valuation shall apply to the land only. For the purposes of the valuation, where the size of the site is larger than 1000m² the valuation will be based on a hypothetical 1000m² building site. (4) Where staged and further development takes place within 10 years, then a credit will apply against the reserves and leisure facilities contribution for the earlier payment, but no refunds will be given. (5) Contributions in accordance with the above are exclusive of GST. <p>Exemptions: The following forms of subdivision will not be required to provide financial contributions:</p> <ol style="list-style-type: none"> (6) Subdivision around any existing principal buildings lawfully established prior to 4 August 2006 that do not create any vacant sites. (7) <u>Subdivision around existing a residential unit(s) where a financial contribution has been paid previously for the residential unit(s).</u> (8) (7) Allotments set aside as reserves or for conservation purposes. (9) (8) Access lots. (10) (9) Rural allotments where there is a legal instrument preventing use of the allotment for residential purposes (e.g. – a forestry allotment). (11) (10) Allotments created for unstaffed utility services up to 200m² in area. (12) (11) Boundary adjustments or amalgamation of allotments with no resulting increase in titles. 						

Commented [MM129]: S58.69 - Kāinga Ora: Homes and Communities

IPI - PROPOSED AMENDMENTS												
#	Chapter	Change	Track Change									
GENERAL DISTRICT WIDE MATTERS												
AIR - Air												
	AIR - Air	Consequential Amendment	<table border="1"> <thead> <tr> <th colspan="2">Permitted Activities</th> <th colspan="2">Zones</th> </tr> </thead> <tbody> <tr> <td>AIR-R1</td> <td>All activities that comply with AIR-S1</td> <td>PER</td> <td> <i>General Residential</i> <i>High Density Residential</i> <i>Commercial and Mixed Use</i> <i>City-Centre</i> <i>General Industrial</i> <i>Open Space</i> <i>Special Activity</i> <i>Development Area 1</i> </td> </tr> </tbody> </table>		Permitted Activities		Zones		AIR-R1	All activities that comply with AIR-S1	PER	<i>General Residential</i> <i>High Density Residential</i> <i>Commercial and Mixed Use</i> <i>City-Centre</i> <i>General Industrial</i> <i>Open Space</i> <i>Special Activity</i> <i>Development Area 1</i>
Permitted Activities		Zones										
AIR-R1	All activities that comply with AIR-S1	PER	<i>General Residential</i> <i>High Density Residential</i> <i>Commercial and Mixed Use</i> <i>City-Centre</i> <i>General Industrial</i> <i>Open Space</i> <i>Special Activity</i> <i>Development Area 1</i>									
	AIR - Air	Consequential Amendment	<table border="1"> <thead> <tr> <th>AIR-S1</th> <th>Dust</th> <th>Zones</th> </tr> </thead> <tbody> <tr> <td> <i>Policies</i> <i>AIR-P1,</i> <i>AIR-P2,</i> <i>GRZ-P3,</i> <i>COMZ-P1,</i> <i>CCZ-P3,</i> <i>GIZ-P2,</i> <i>OSZ-P27,</i> <i>SAZ-P2</i> </td> <td> (1) Activities shall not create a dust nuisance. A dust nuisance may occur if: (a) There is visible evidence of suspended solids in the air beyond the site boundary. (b) There is visible evidence of suspended solids, traceable from a dust source, settling on the ground, building or structure on a neighbouring property or on water. </td> <td> <i>General Residential</i> <i>High Density Residential</i> <i>Commercial and Mixed Use</i> <i>City-Centre</i> <i>General Industrial</i> <i>Open Space</i> <i>Special Activity</i> <i>Development Area 1</i> </td> </tr> </tbody> </table>	AIR-S1	Dust	Zones	<i>Policies</i> <i>AIR-P1,</i> <i>AIR-P2,</i> <i>GRZ-P3,</i> <i>COMZ-P1,</i> <i>CCZ-P3,</i> <i>GIZ-P2,</i> <i>OSZ-P27,</i> <i>SAZ-P2</i>	(1) Activities shall not create a dust nuisance. A dust nuisance may occur if: (a) There is visible evidence of suspended solids in the air beyond the site boundary . (b) There is visible evidence of suspended solids, traceable from a dust source, settling on the ground, building or structure on a neighbouring property or on water .	<i>General Residential</i> <i>High Density Residential</i> <i>Commercial and Mixed Use</i> <i>City-Centre</i> <i>General Industrial</i> <i>Open Space</i> <i>Special Activity</i> <i>Development Area 1</i>			
AIR-S1	Dust	Zones										
<i>Policies</i> <i>AIR-P1,</i> <i>AIR-P2,</i> <i>GRZ-P3,</i> <i>COMZ-P1,</i> <i>CCZ-P3,</i> <i>GIZ-P2,</i> <i>OSZ-P27,</i> <i>SAZ-P2</i>	(1) Activities shall not create a dust nuisance. A dust nuisance may occur if: (a) There is visible evidence of suspended solids in the air beyond the site boundary . (b) There is visible evidence of suspended solids, traceable from a dust source, settling on the ground, building or structure on a neighbouring property or on water .	<i>General Residential</i> <i>High Density Residential</i> <i>Commercial and Mixed Use</i> <i>City-Centre</i> <i>General Industrial</i> <i>Open Space</i> <i>Special Activity</i> <i>Development Area 1</i>										
	AIR - Air	Consequential Amendment	<table border="1"> <thead> <tr> <th colspan="2">Discretionary Activities</th> <th>Zones</th> </tr> </thead> <tbody> <tr> <td colspan="2"></td> <td></td> </tr> </tbody> </table>		Discretionary Activities		Zones					
Discretionary Activities		Zones										

IPI - PROPOSED AMENDMENTS						
#	Chapter	Change	Track Change			
			AIR-R3	Activities which do not comply with AIR-S1	DIS <i>General Residential High Density Residential Commercial and Mixed Use City Centre General Industrial Open Space (Speedway Area only) Special Activity (excluding St. Patrick's Estate Area) Development Area 1</i>	
	AIR - Air	Consequential Amendment	Non-complying Activities			Zones
			AIR-R4	Activities which do not comply with AIR-S1	NC <i>Special Activity - St. Patrick's Estate Area only</i>	
	AIR - Air	Consequential Amendment	Matters for Consideration			Zone
			Matters that may be relevant in the consideration of any resource consent may include the following:			
			AIR-MC1	Nuisance (1) The potential impacts of noise, dust , glare, vibration, fumes, smoke, other discharges or pollutants or the excavation or deposition of earth.	<i>General Residential High Density Residential Commercial and Mixed Use City Centre</i>	

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
					<i>General Industrial Open Space Special Activity Development Area 1</i>
	AIR - Air	Consequential Amendment	AIR-MC2	Cumulative effects (1) Whether cumulative effects such as pollution, risk to public safety and nuisances have been assessed.	<i>General Residential High Density Residential Commercial and Mixed Use City Centre General Industrial Open Space Special Activity Development Area 1</i>
EW - Earthworks					
	EW - Earthworks	Consequential Amendment	Standards for Permitted Activities		
			EW-S1 <i>Policies EW-P1, EW-P2</i>	(1) Existing ground level shall not be altered by cutting by a vertical height of more than 1.5m, or filling by a vertical height of more than 0.5m. Exemption (2) The above shall not apply where the area of earthworks for a specific building extends no more than 2 metres beyond the exterior foundations of the proposed building but no closer than 1 metre to a boundary and complies with an earthworks plane (as defined in Section 3.1) measured from a height of 1.5 metres at the ground level boundary and an angle of 45° into the site .	<i>General Residential High Density Residential Commercial and Mixed Use City Centre General Industrial Special Activity</i>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			 <p style="text-align: right;"><i>Development Area 1</i></p>
	EW - Earthworks	Consequential Amendment	<p>EW-S3</p> <p><i>Policies EW-P1, EW-P2</i></p> <p>(1) The physical extent of earthworks shall not exceed 150m² in surface area on any one site within any continuous 12 month period.</p> <p>Exemption</p> <p>(2) In the General Residential, <u>High Density Residential</u>, Commercial and Mixed Use, City Centre, General Industrial, Special Activity, General Rural, Rural Production and Rural Lifestyle Zones, earthworks exceeding the foundations of a specific building by more than 2 metres are exempt from the 150m² surface area limit provided that the earthworks beyond the 2 metre foundation line of a building:</p> <ul style="list-style-type: none"> (a) do not exceed a vertical cut height of 1.5m or a vertical fill height of 0.5m; and (b) do not go closer than 1 metre to any boundary; and (c) comply with an earthworks plane (as defined in Section 3.1) measured from a height of 1.5 metres at the ground level boundary and an angle of 45° into the site.

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
LIGHT - Light					
	LIGHT - Light	Consequential Amendment	Permitted Activities		Zones
			LIGHT-R1	All activities complying with LIGHT-S1	PER
	LIGHT - Light	Consequential Amendment	Standards for Permitted Activities		Zones
			LIGHT-S1 <i>Policies LIGHT P1, GRZ-P3</i>	Artificial light (1) Light emissions from a site shall not exceed a measurement of 8 lux (lumens per m2) measured in both the horizontal and vertical planes, 1.5m above the ground at the site boundary .	

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			GRUZ-P1, RPROZ-P1, RLZ-P1 COMZ-P1, CCZ-P3, GIZ-P2 OSZ-P4 SAZ-P2	(2) Light emissions will be measured by an instrument that meets NZSS CP22 (1962) requirements and amendments. (3) Light emissions from a site shall not spill directly onto roads .		<i>Rural Production Rural Lifestyle Commercial <u>and</u> <u>Mixed Use</u> City Centre General Industrial, Open Space (excluding Speedway Area) Special Activity (including St. Patrick's Estate Area) Development Area 1 Development Area 2</i>	
	LIGHT - Light	Consequential Amendment	Discretionary Activities LIGHT-R4 All activities that do not complying with permitted activity standards in Light-S1			DIS	Zones <i>General Residential <u>High Density Residential</u> General Rural Rural Production Rural Lifestyle Commercial <u>and</u> <u>Mixed Use</u> City Centre General Industrial</i>

IPI - PROPOSED AMENDMENTS						
#	Chapter	Change	Track Change			
					Special Activity (excluding St. Patrick's Estate Area) Development Area 1 Development Area 2	
	LIGHT - Light	Consequential Amendment	Non-complying Activities			Zones
			LIGHT R6	All activities that do not complying with permitted activity standards in Light S1	NC	
					Special Activity - St. Patrick's Estate Area only	
PK – Papakāinga						
	PK-Papakāinga	Insert new papakāinga chapter	<p><u>PK – Papakāinga</u></p> <p><u>Background</u></p> <p>The purpose of the Papakāinga Chapter is to assist tangata whenua in the development and use of papakāinga on their ancestral land. Ancestral land is land that belonged to tipuna/tupuna. It was a base upon which the hapū was nurtured and was handed down in succession through generations by continuous occupation. This is known as ahi kā or ahi kā roa. In the context of the District Plan, ancestral Māori land includes land held under the Te Ture Whenua Māori Act 1993, Māori customary land, Māori freehold land, and general title land owned by Māori.</p> <p>It is recognised that tangata whenua face barriers to developing and using their land in the way that fits into the principle of Tino Rangatiranga, and that this is different to land held in European title. The emergence of these barriers can be linked to the process of land alienation. This process occurred alongside the introduction by the Crown of a system of land tenure that individualised title to land in a manner that did not provide for the communal approach that underpinned Māori institutions, including Māori decision-making around the traditional use and development of land. Over time, this has contributed to the fragmentation and loss of land owned by tangata whenua, and created barriers to the development of the land that does remain in the ownership of tangata whenua.</p>			

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>The status of Māori land held under Te Ture Whenua Māori Act 1993 creates unique ownership issues, demonstrating the need for Māori land to be treated differently to land under European title. The costs associated with obtaining approval for papakāinga development from Council and other organisations are an issue for tangata whenua. The provisions in this Chapter seek to reduce the barriers that tangata whenua face in the development of papakāinga on their ancestral land.</p> <p>Papakāinga developments are developments led by Māori landowners on their ancestral land. These developments reconnect Māori to their land. Papakāinga development provides a pathway to sustain the social, economic and cultural well-being of tangata whenua. Papakāinga developments include housing and associated activities such as social, cultural, educational, recreational and commercial activities.</p> <p>This Chapter contains the provisions that provide for the development and use of papakāinga by tangata whenua on land where there is a whakapapa or ancestral connection. In addition to providing for papakāinga through these provisions, the Council is committed to working actively with tangata whenua on the development of papakāinga through the range of other strategies and plans that it prepares and implements (including the Long Term Plan and Infrastructure Strategy).</p> <p>The Objectives and Policies, rules and standards contained within this Chapter apply to papakāinga throughout the City. Papakāinga is specifically provided for within the following zones:</p> <ul style="list-style-type: none"> (i) <u>The General Residential Zone;</u> (ii) <u>The High Density Residential Zone</u> (iii) <u>The General Rural Zone;</u> (iv) <u>The Rural Production Zone;</u> (v) <u>The Rural Lifestyle Zone;</u> (vi) <u>The City Centre Zone;</u> (vii) <u>Town Centre Zone</u> (viii) <u>Local Centre Zone;</u> (ix) <u>Neighbourhood Centre Zone; and</u> (x) <u>Mixed Use Zone.</u>

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
			<p><u>Objectives</u></p>
			<p><u>PK-01</u> <u>Papakāinga – Papakāinga are a Taonga</u> <i>To provide for traditional papakāinga, which are a taonga that:</i></p> <ul style="list-style-type: none"> (i) <i>empower and enable tanqata whenua to live on their ancestral land;</i> (ii) <i>provide for tanqata whenua to maintain and enhance their traditional and cultural relationship with their ancestral land; and</i> (iii) <i>are developed and used in accordance with tikanqa Māori, while recognising that papakāinga may develop their own tikanqa.</i>
			<p><u>PK-02</u> <u>Papakāinga – Kia ora te mauri o te Whānau (Māori living as Māori)</u> <i>Oranga is central to a thriving whānau/hapū/iwi. Tanqata whenua are supported to ensure they can thrive as a Māori community living on and around their papakāinga.</i></p> <p><i>To provide for papakāinga development that achieves:</i></p> <ul style="list-style-type: none"> (i) <i>a place where kaupapa and Tikanqa Māori are in the ascendant;</i> (ii) <i>affordable, warm, dry and safe housing for tanqata whenua;</i> (iii) <i>security of tenure, connection and participation for tanqata whenua in their community; and</i> (iv) <i>access to the services needed by tanqata whenua to sustain their housing.</i>
			<p><u>PK-03</u> <u>Papakāinga – Provide for the sustained occupation of ancestral land</u> <i>To provide for the sustained occupation of ancestral land by tanqata whenua, through papakāinga development that provides for the land to be held and managed for the benefit of current and future generations.</i></p>
			<p><u>PK-04</u> <u>Papakāinga – Provide for the development of land owned by Tanqata Whenua</u> <i>To provide for the connection between tanqata whenua and their ancestral land through providing for the development of papakāinga on land owned by tanqata whenua.</i></p>
			<p><u>PK-05</u> <u>Papakāinga – Working in partnership with Tanqata Whenua to exercise their Tino Ranqatiratanga</u></p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>To work in partnership with tangata whenua to exercise their tino rangatiratanga through the development of papakāinga, by providing maximum flexibility for tangata whenua to develop and live on their ancestral land, within the limitations of the site.</p>
			<p>PK-06 <u>Papakāinga – Increasing the visibility of Tangata Whenua through the design of papakāinga</u> <i>To increase the visibility of tangata whenua through papakāinga design that is led by tangata whenua and guided by tikanga Māori.</i></p>
			<p>PK-07 <u>Papakāinga – Implementing Te Ao Māori and demonstrating Kaitiakitanga in papakāinga development</u> <i>To protect and enhance ecological, cultural and environmental and indigenous values through the design, development and use of papakāinga.</i></p>
<u>Policies</u>			
			<p>PK-P1 <u>Providing for papakāinga on Māori owned land</u> Papakāinga will be: (i) <i>provided for on land held under Te Ture Whenua Māori Act 1993; and</i> (ii) <i>allowed on general title land where it can be demonstrated that there is a whakapapa or ancestral connection to the land, and the land will remain in Māori ownership.</i></p>
			<p>PK-P2 <u>Papakāinga development to be led by Tangata Whenua</u> <i>The design and development of papakāinga will be led by tangata whenua.</i></p>
			<p>PK-P3 <u>Location, extent and design of papakāinga</u> <i>The location, extent and design of papakāinga, including extensions to existing papakāinga, will be guided by kaupapa Māori in accordance with tikanga Māori.</i></p>
			<p>PK-P4 <u>Maximum scale of papakāinga development</u> <i>The maximum intensity and scale of papakāinga development will be determined by the limitations of the site, including:</i> (i) <i>adequate provision of access, on-site or off-site infrastructure to serve the papakāinga; and</i> (ii) <i>adverse effects on adjoining properties and the environment are avoided, remedied or mitigated;</i></p>

Commented [MM130]: S50.16 - Waka Kotahi - New Zealand Transport Agency.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p><i>while recognising that papakāinga may contain activities of a character, scale, intensity or range that are not provided for in the surrounding area.</i></p>
			<p>PK-P5</p> <p><u>Non-residential aspects of papakāinga</u> <i>Social, cultural, educational, recreation and commercial activities will be provided for as part of a papakāinga, where they:</i></p> <ul style="list-style-type: none"> (i) <i>are consistent with tanqata whenua aspirations for the papakāinga; and</i> (ii) <i>are of a scale, character and intensity that are consistent with kaupapa, kawa and tikanga Māori.</i> <p>Note: refer to the commercial and mixed use chapters for objectives and policies on commercial activities outside of commercial and mixed use zones.</p>
			<p>PK-P6</p> <p><u>Papakāinga Design Guides and Development Plans</u> <i>The Council will actively partner with tanqata whenua to prepare papakāinga design guides that are clearly underpinned by kaupapa Māori. The guidelines should draw on traditional land use and other environmental features distinctive to the takiwā. As an ecosystem it should give expression to the whānau/hapū/iwi traditional papakāinga.</i></p> <p><i>Tanqata whenua will be encouraged to prepare development plans for papakāinga that are consistent with these design guides.</i></p> <p>Notes:</p> <ol style="list-style-type: none"> 1. <u>Where these Objectives and Policies are relevant to the consideration of a resource consent application, the Council will seek advice from the relevant iwi authority and will rely on this advice. The matters that Council will seek advice from iwi authorities on include:</u> <ul style="list-style-type: none"> ▪ <u>where the papakāinga is on general title land, whether the applicant has demonstrated a whakapapa or ancestral connection to the land;</u> ▪ <u>any other matter related to tikanga Māori.</u> 2. <u>Subject to the requirements of section 33 of the Resource Management Act 1991, the Council is able to transfer its powers to the relevant iwi authority for the rohe in which the land is located.</u> 3. <u>Provisions in other chapters of the Plan may also be relevant.</u>

IPI - PROPOSED AMENDMENTS																					
#	Chapter	Change	Track Change																		
			<p><u>Rules</u></p> <p><u>Zone Rules and District-wide matters</u></p> <p><u>Papakāinga shall comply with the rules within the relevant zone chapter for buildings and structures within proximity to high voltage (110kV or greater) electricity transmission lines, and shall comply with all relevant permitted activity standards in the District-wide matters of the Plan as listed below.:</u></p> <table border="1"> <tr><td><u>District-wide matters</u></td></tr> <tr><td><u>TEMP - Temporary Activities</u></td></tr> <tr><td><u>SIGN - Signs</u></td></tr> <tr><td><u>EW - Earthworks</u></td></tr> <tr><td><u>NATC – Natural Character</u></td></tr> <tr><td><u>DC – Development Contributions</u></td></tr> <tr><td><u>HH - Historical Heritage</u></td></tr> <tr><td><u>TREE - Notable Trees</u></td></tr> <tr><td><u>UTG - Urban Tree Groups</u></td></tr> <tr><td><u>ECO - Ecosystems and Indigenous Biodiversity</u></td></tr> <tr><td><u>NFL - Natural Features and Landscapes</u></td></tr> <tr><td><u>PA – Public Access</u></td></tr> <tr><td><u>ASW - Activities on the Surface of Water</u></td></tr> <tr><td><u>NU – Network Utilities</u></td></tr> <tr><td><u>REG - Renewable Energy Generation</u></td></tr> <tr><td><u>TP – Transport and Parking</u></td></tr> <tr><td><u>NOISE - Noise</u></td></tr> <tr><td><u>NH - Natural Hazards</u></td></tr> </table>	<u>District-wide matters</u>	<u>TEMP - Temporary Activities</u>	<u>SIGN - Signs</u>	<u>EW - Earthworks</u>	<u>NATC – Natural Character</u>	<u>DC – Development Contributions</u>	<u>HH - Historical Heritage</u>	<u>TREE - Notable Trees</u>	<u>UTG - Urban Tree Groups</u>	<u>ECO - Ecosystems and Indigenous Biodiversity</u>	<u>NFL - Natural Features and Landscapes</u>	<u>PA – Public Access</u>	<u>ASW - Activities on the Surface of Water</u>	<u>NU – Network Utilities</u>	<u>REG - Renewable Energy Generation</u>	<u>TP – Transport and Parking</u>	<u>NOISE - Noise</u>	<u>NH - Natural Hazards</u>
<u>District-wide matters</u>																					
<u>TEMP - Temporary Activities</u>																					
<u>SIGN - Signs</u>																					
<u>EW - Earthworks</u>																					
<u>NATC – Natural Character</u>																					
<u>DC – Development Contributions</u>																					
<u>HH - Historical Heritage</u>																					
<u>TREE - Notable Trees</u>																					
<u>UTG - Urban Tree Groups</u>																					
<u>ECO - Ecosystems and Indigenous Biodiversity</u>																					
<u>NFL - Natural Features and Landscapes</u>																					
<u>PA – Public Access</u>																					
<u>ASW - Activities on the Surface of Water</u>																					
<u>NU – Network Utilities</u>																					
<u>REG - Renewable Energy Generation</u>																					
<u>TP – Transport and Parking</u>																					
<u>NOISE - Noise</u>																					
<u>NH - Natural Hazards</u>																					

Commented [MM131]: S27.21 - Transpower New Zealand Limited.

Commented [MM132]: S27.21 - Transpower New Zealand Limited.

IPI - PROPOSED AMENDMENTS											
#	Chapter	Change	Track Change								
			<table border="1"> <tr><td><u>CL – Contaminated Land</u></td></tr> <tr><td><u>HS - Hazardous Substances</u></td></tr> <tr><td><u>WM – Waste Management</u></td></tr> <tr><td><u>SUB - Subdivision</u></td></tr> <tr><td><u>AIR - Air</u></td></tr> <tr><td><u>LIGHT – Light</u></td></tr> </table> <p>Activities Tables</p> <table border="1"> <tr> <td>PK-R1</td> <td> <p>Papakāinga on land held under Te Ture Whenua Māori Act 1993 within the following zones:</p> <ul style="list-style-type: none"> (i) <u>The General Residential Zone</u> (ii) <u>The High Density Residential Zone</u> (iii) <u>The General Rural Zone</u> (iv) <u>The Rural Production Zone</u> (v) <u>The Rural Lifestyle Zone</u> (vi) <u>The City Centre Zone</u> (vii) <u>The Town Centre Zone</u> (viii) <u>The Local Centre Zone</u> (ix) <u>The Neighbourhood Centre Zone</u> (x) <u>The Mixed Use Zone.</u> </td> </tr> </table> <p>1. Activity Status: Permitted</p> <p>Where:</p> <ul style="list-style-type: none"> a. <u>Any building must comply with the relevant zone standards for building height, height in relation to boundary, yard setbacks and building coverage where specified in the relevant zone chapter.</u> 	<u>CL – Contaminated Land</u>	<u>HS - Hazardous Substances</u>	<u>WM – Waste Management</u>	<u>SUB - Subdivision</u>	<u>AIR - Air</u>	<u>LIGHT – Light</u>	PK-R1	<p>Papakāinga on land held under Te Ture Whenua Māori Act 1993 within the following zones:</p> <ul style="list-style-type: none"> (i) <u>The General Residential Zone</u> (ii) <u>The High Density Residential Zone</u> (iii) <u>The General Rural Zone</u> (iv) <u>The Rural Production Zone</u> (v) <u>The Rural Lifestyle Zone</u> (vi) <u>The City Centre Zone</u> (vii) <u>The Town Centre Zone</u> (viii) <u>The Local Centre Zone</u> (ix) <u>The Neighbourhood Centre Zone</u> (x) <u>The Mixed Use Zone.</u>
<u>CL – Contaminated Land</u>											
<u>HS - Hazardous Substances</u>											
<u>WM – Waste Management</u>											
<u>SUB - Subdivision</u>											
<u>AIR - Air</u>											
<u>LIGHT – Light</u>											
PK-R1	<p>Papakāinga on land held under Te Ture Whenua Māori Act 1993 within the following zones:</p> <ul style="list-style-type: none"> (i) <u>The General Residential Zone</u> (ii) <u>The High Density Residential Zone</u> (iii) <u>The General Rural Zone</u> (iv) <u>The Rural Production Zone</u> (v) <u>The Rural Lifestyle Zone</u> (vi) <u>The City Centre Zone</u> (vii) <u>The Town Centre Zone</u> (viii) <u>The Local Centre Zone</u> (ix) <u>The Neighbourhood Centre Zone</u> (x) <u>The Mixed Use Zone.</u> 										

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>b. <u>The gross floor area of all commercial activities must not exceed the lesser of 20% of the area of the subject site, or 500m².</u></p>
			<p>2. Activity Status: Discretionary</p> <p>Where:</p> <p>a. <u>Compliance is not achieved with one or more of the standards under rule PK-R1.</u></p> <p>Restriction on Notification: <u>Except where compliance with rule PK-R1 standard (b) is not met, public notification of an application for resource consent under this rule is precluded.</u></p>
			<p>PK-R2 <u>Papakāinga on general title land.</u></p>
			<p>Activity Status: Restricted Discretionary</p> <p>Where:</p> <p>a. <u>The applicant is a member of Ngāti Toa Rangatira, Port Nicholson Block Settlement Trust, Wellington Tenth Trust, or Palmerston North Māori Reserve Trust.</u></p> <p>Matters of Discretion:</p> <p>a. <u>Whether the applicant has demonstrated their whakapapa or ancestral connection to the land;</u> b. <u>Evidence of appropriate legal mechanism(s) to ensure that land is maintained in Māori ownership.</u> c. <u>The matters contained in the Code Civil Engineering Works.</u> d. <u>The matters contained in the Medium and High Density Design Guide in Appendix 1.</u></p> <p>Restriction on notification: <u>Public notification of an application for resource consent under this Rule is precluded.</u></p> <p>Notes:</p>

IPI - PROPOSED AMENDMENTS								
#	Chapter	Change	Track Change					
			<p><u>1.</u> For resource consent applications under this rule, the Council will seek advice from the relevant iwi authority and will rely on this advice. The matters that Council will seek advice from iwi authorities on include:</p> <p>(i) where the papakāinga is on general title land, whether the applicant has demonstrated a whakapapa or ancestral connection to the land; and</p> <p>(ii) any other matter related to tikanga Māori.</p>					
			<p>PK-R3 Papakāinga on land on general title land</p>					
			<p>Activity Status: Discretionary</p> <p>Where:</p> <p>a. <u>Compliance is not achieved with one or more of the permitted activity standards set out under Rule PK-R1.</u></p> <p>Restriction on Notification <u>Except where compliance with rule PK-R1 standard (b) is not met, public notification of an application for resource consent under this Rule is precluded.</u></p> <p>Notes:</p> <p><u>2.</u> For resource consent applications under this rule, the Council will seek advice from the relevant iwi authority and will rely on this advice. The matters that Council will seek advice from iwi authorities on include:</p> <p>(iii) where the papakāinga is on general title land, whether the applicant has demonstrated a whakapapa or ancestral connection to the land; and</p> <p>(iv) any other matter related to tikanga Māori.</p>					
PK – Papakāinga amendments – multi-zone								
	Amendments to the District-wide matters table at the top of the rules tables within the following zone chapters:	Insert references to PK-Papakāinga chapter.	<table border="1"> <tr> <td>District-wide matters</td> </tr> <tr> <td>TEMP - Temporary Activities</td> </tr> <tr> <td>SIGN - Signs</td> </tr> <tr> <td>EW - Earthworks</td> </tr> <tr> <td>NATC – Natural Character</td> </tr> </table>	District-wide matters	TEMP - Temporary Activities	SIGN - Signs	EW - Earthworks	NATC – Natural Character
District-wide matters								
TEMP - Temporary Activities								
SIGN - Signs								
EW - Earthworks								
NATC – Natural Character								

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
	(i) General Residential Zone		DC – Development Contributions
			HH - Historical Heritage
	(ii) High Density Residential Zone		TREE - Notable Trees
			UTG - Urban Tree Groups
	(iii) City Centre Zone		ECO - Ecosystems and Indigenous Biodiversity
	(iv) Town Centre Zone		NFL - Natural Features and Landscapes
	(v) Local Centre Zone		PA – Public Access
	(vi) Neighbourhood Centre Zone		<u>PK - Papakāinga</u>
	(vii) Mixed Use Zone		ASW - Activities on the Surface of Water
	(viii) General Rural Zone		NU – Network Utilities
			REG - Renewable Energy Generation
	(ix) Rural Production Zone		TP – Transport and Parking
			NOISE - Noise
	(x) Rural Lifestyle Zone		NH - Natural Hazards
			CL – Contaminated Land
			HS - Hazardous Substances
			WM – Waste Management
			SUB - Subdivision
			AIR - Air
			LIGHT - Light
NOISE - Noise			
			Policies

IPI - PROPOSED AMENDMENTS																						
#	Chapter	Change	Track Change																			
			<p>NOISE-P2 <i>To mitigate the adverse effects of noise within the General Residential <u>and High Density Residential Zones</u> to a level consistent with a predominantly residential environment.</i></p> <p>Noise is a particularly important amenity consideration in residential areas as people are living in close proximity to each other. This policy aims to ensure that noise levels experienced are reasonable for a General Residential <u>and High Density Residential Zones</u>. In the Wallaceville Structure Plan Development Area, fencing, noise insulation and/or ventilation standards seek to mitigate the reasonable adverse effects of noise arising from adjoining activities. The standards ensure a reasonable level of acoustic amenity within buildings that have their windows closed. Ventilation standards have been developed to avoid the need to open windows.</p>																			
	NOISE - Noise	Consequential Amendment	<p>Standards for Permitted Activities</p> <p>NOISE-S3 Noise from all other activities</p> <p><i>Policies</i> NOISE-P1 NOISE-P2</p> <p>(1) The following noise rules shall not apply to:</p> <p>(a) Normal agricultural and forestry practices undertaken for a limited duration.</p> <p>(b) Normal residential activities such as lawn mowing.</p> <p>(c) Noise generated by sirens and alarms used by emergency services.</p> <p>(2) All activities, other than those specified above, shall not exceed the following noise standards:</p> <table border="1"> <thead> <tr> <th rowspan="2">dBA</th> <th colspan="2">Mon to Sat 7:00am – 7:00pm</th> <th colspan="2">All other times, Sundays & public holidays</th> </tr> <tr> <th>L10</th> <th>Lmax</th> <th>L10</th> <th>Lmax</th> </tr> </thead> <tbody> <tr> <td>Maximum noise levels measured at or within the boundary of any site (other than the source site) in the General Residential, <u>High Density Residential</u>, General Rural, Rural Production, Rural Lifestyle and Open Space Zones.</td> <td>50</td> <td>-</td> <td>40</td> <td>70</td> </tr> <tr> <td>Maximum noise levels measured at or within the boundary of any site (other than the source site) in the Commercial <u>and Mixed Use</u>, <u>Industrial</u> and Special Activity Zones.</td> <td>65</td> <td>-</td> <td>45</td> <td>75</td> </tr> </tbody> </table>	dBA	Mon to Sat 7:00am – 7:00pm		All other times, Sundays & public holidays		L10	Lmax	L10	Lmax	Maximum noise levels measured at or within the boundary of any site (other than the source site) in the General Residential, <u>High Density Residential</u> , General Rural, Rural Production, Rural Lifestyle and Open Space Zones.	50	-	40	70	Maximum noise levels measured at or within the boundary of any site (other than the source site) in the Commercial <u>and Mixed Use</u> , <u>Industrial</u> and Special Activity Zones.	65	-	45	75
dBA	Mon to Sat 7:00am – 7:00pm		All other times, Sundays & public holidays																			
	L10	Lmax	L10	Lmax																		
Maximum noise levels measured at or within the boundary of any site (other than the source site) in the General Residential, <u>High Density Residential</u> , General Rural, Rural Production, Rural Lifestyle and Open Space Zones.	50	-	40	70																		
Maximum noise levels measured at or within the boundary of any site (other than the source site) in the Commercial <u>and Mixed Use</u> , <u>Industrial</u> and Special Activity Zones.	65	-	45	75																		

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change																			
			<p>(3) The following standards apply to the Business Industrial Land on Eastern Hutt Road</p> <table border="1"> <thead> <tr> <th rowspan="2">dBA</th> <th colspan="2">Day-time 7:00am – 9:00pm</th> <th colspan="2">Night-time 9:00pm – 7:00am</th> </tr> <tr> <th>L10</th> <th>Lmax</th> <th>L10</th> <th>Lmax</th> </tr> </thead> <tbody> <tr> <td>Maximum noise levels from activities in the General Industrial Zone located on Eastern Hutt Road measured at or within the boundary of any site: (1) In the General Residential Zone; (2) In the Residential Conservation Precinct and in the General Rural Zone, but assessed no closer than 100m from the zone boundary of the General Industrial zone; (3) In the Special Activity Zone that is St Patricks Estate College area. (4) In the High Density Residential Zone.</td> <td>50</td> <td>-</td> <td>40</td> <td>70</td> </tr> <tr> <td>Maximum noise levels from activities in the General Industrial zone on Eastern Hutt Road* measured at or within the boundary of any site (other than the source site) in the General Industrial zone on Eastern Hutt Road and at or within the boundary of any site within a Commercial and Mixed Use zone.</td> <td>65</td> <td>-</td> <td>65</td> <td>-</td> </tr> </tbody> </table> <p>Exemption * Except that primary warehousing operations including: (1) Truck movements on sites and on access roads; and (2) Loading and unloading activities – shall be exempt from the noise rules only as they apply to receiving sites within the General Industrial zone on Eastern Hutt Road.</p> <p>Notes</p>	dBA	Day-time 7:00am – 9:00pm		Night-time 9:00pm – 7:00am		L10	Lmax	L10	Lmax	Maximum noise levels from activities in the General Industrial Zone located on Eastern Hutt Road measured at or within the boundary of any site : (1) In the General Residential Zone ; (2) In the Residential Conservation Precinct and in the General Rural Zone, but assessed no closer than 100m from the zone boundary of the General Industrial zone; (3) In the Special Activity Zone that is St Patricks Estate College area. (4) In the High Density Residential Zone .	50	-	40	70	Maximum noise levels from activities in the General Industrial zone on Eastern Hutt Road* measured at or within the boundary of any site (other than the source site) in the General Industrial zone on Eastern Hutt Road and at or within the boundary of any site within a Commercial and Mixed Use zone .	65	-	65	-
dBA	Day-time 7:00am – 9:00pm		Night-time 9:00pm – 7:00am																			
	L10	Lmax	L10	Lmax																		
Maximum noise levels from activities in the General Industrial Zone located on Eastern Hutt Road measured at or within the boundary of any site : (1) In the General Residential Zone ; (2) In the Residential Conservation Precinct and in the General Rural Zone, but assessed no closer than 100m from the zone boundary of the General Industrial zone; (3) In the Special Activity Zone that is St Patricks Estate College area. (4) In the High Density Residential Zone .	50	-	40	70																		
Maximum noise levels from activities in the General Industrial zone on Eastern Hutt Road* measured at or within the boundary of any site (other than the source site) in the General Industrial zone on Eastern Hutt Road and at or within the boundary of any site within a Commercial and Mixed Use zone .	65	-	65	-																		

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<ul style="list-style-type: none"> • Noise levels shall be measured in accordance with the requirements of NZS 6801:1991 Measurement of Sound, and assessed in accordance with the requirements of NZS 6802:1991 Assessment of Environmental Sound. • Noise levels shall be measured with a sound level meter complying with International Standard IEC 60651 (1979): Sound Level Meters, Type 2. • Adjustments for special audible characteristics, if present, as provided for in clauses 4.3 and 4.4 of NZS 6802:1991, shall apply and will have the effect of imposing a maximum permitted noise level 5dBA more stringent than the L10 levels stated above. This condition shall not apply to impulse noise emissions arising from firing and detonation activities at the Trentham Ranges. • The definitions of dBA, dBC, L10 and Lmax are those found in NZS 6802:1991.

SIGN - Signs

	SIGN - Signs	Consequential Amendment	Standards for Permitted Activities		Zones
			SIGN-S2		
			<p>SIGN-S2</p> <p>Signs in General Residential Zones, High Density Residential Zones, General Rural Zones, Rural Production Zones, Rural Lifestyle Zones and Open Space Zones and in Development Area 1 (except for the Gateway Precinct) and Development Area 2</p> <p>(1) In Residential Zones and Rural Zones, a maximum of one sign per site, visible in any one direction.</p> <p>(2) In Open Space Zones there shall be no more than one freestanding sign per 100m of road frontage.</p> <p>(3) The maximum area of any sign visible in any one direction shall not exceed:</p> <p>(a) 1.5m² in Residential Zones;</p> <p>(b) 3.0 m² in Rural Zones;</p> <p>(c) In Open Space Zones:</p> <p>(i) 4.5m² for free-standing signs,</p> <p>(ii) 3m² for any sign attached to a building;</p>		<p><i>General Residential</i></p> <p><i>High Density Residential</i></p> <p><i>General Rural Rural</i></p> <p><i>Production Rural Lifestyle</i></p> <p><i>Open Space Development Area 1 (excluding Gateway Precinct)</i></p> <p><i>Development Area 2</i></p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(iii) 0.5m² for signs used for marking tracks; and</p> <p>(iv) 2m² for signs providing interpretation or identification.</p> <p>(4) The maximum height above ground level of any part of a free-standing sign above ground level shall not exceed 3 metres.</p> <p>(5) No sign shall extend beyond the elevation of the building to which it is attached, or extend above the roofline of the building.</p> <p>(6) The maximum width of any free-standing sign shall not exceed 2 metres.</p> <p>(7) In Residential Zones, signs on buildings must not cover any windows.</p> <p>(8) In Open Space Zones, signs not directly visible from any public road or the boundary of any residential zone are not limited in size and number.</p> <p>(9) No illumination (internal or external) of signs in the Residential and Rural zones.</p> <p>(10) No illumination (internal or external) of signs in the Open Space zone.</p>
	SIGN - Signs	Consequential Amendment	<p>SIGN-S3 Free-Standing Signs in Commercial and Mixed Use Zones, City Centre, General Industrial Zones and Special Activity Zones and in the Gateway Precinct of Development Area 1</p> <p>(1) The number of free-standing signs on a site visible in any one direction shall not exceed:</p> <p>(a) One sign per site on sites with road frontages less than 50m; or</p> <p>(b) Two signs per site where the road frontage exceeds 50m.</p> <p>(2) The maximum height above ground level of any part of a free-standing sign above ground level shall not exceed:</p> <p>(a) 8m in Commercial <u>and Mixed Use</u> and City Centre Zones.</p> <p>(b) 9m in General Industrial and Special Activity Zones.</p> <p>(3) The maximum width of any free-standing sign shall not exceed 2m.</p> <p>(4) The maximum area of any free-standing sign, visible in any one direction shall not exceed 7.5m²</p>

Commercial and Mixed Use City Centre General Industrial Special Activity Development Area 1 (Gateway Precinct only)

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(5) In General Industrial Zones, free-standing signs greater than 4 metres in height on any site must be located a minimum distance of 15m from any other free-standing sign that is greater than 4m in height on an adjoining site; and</p> <p>(6) Signs on land identified in the Commercial-Neighbourhood Centre Zone in COMZNCZ-Figure1 one free-standing sign per site visible in any one direction with a maximum area of 7.5m².</p> <p>(7) No illumination (internal or external) of signs in the Business Commercial <u>and Mixed Use, City Centre</u> and General Industrial zones within 10m of a General residential or <u>High Density Residential zone</u> boundary.</p>
	SIGN - Signs	Consequential Amendment	<p>SIGN-S4</p> <p>Signs on buildings and other structures in Commercial and Mixed Use, City Centre and General Industrial and Special Activity Zones and in the Gateway Precinct of Development Area 1</p> <p>(1) No sign shall extend beyond the elevation of the building or beyond the height of the structure to which it is to be attached to, or extend above the roofline of the building, except where;</p> <p>(a) The sign is positioned at 90 degrees to the front elevation of the building; and</p> <p>(b) must not extend from the wall by more than 1m.</p> <p>(2) The maximum area of any single sign is:</p> <p>(a) 5m² for Commercial and Mixed Use Zones, City Centre and Special Activity Zones;</p> <p>(b) 10m² for General Industrial Zone.</p> <p>(3) the total area of all combined signs on any elevation does not exceed 30% of the total area of the building elevation or structure.</p> <p>(4) For signs located above a building's ground floor level there shall be a minimum horizontal separation distance of 5 metres between signs on the same floor level.</p> <p>(5) Any sign located on the parapet of a building shall not exceed an area of 5m², or an area of 30% of the total area of the parapet, whichever is the lesser.</p>

*Commercial and Mixed Use
City Centre
General Industrial
Special Activity
Development Area 1
(Gateway Precinct only)*

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
			<p>(6) The maximum height above ground level of any sign located on the fascia of a veranda must not exceed a height of:</p> <ul style="list-style-type: none"> (a) 0.6 metres; or (b) where the height of the fascia is 0.6m or greater, an additional 25% of the fascia height. <p>(7) Signs below verandas which overhang pedestrian pathways, must have a minimum clearance of 2.5m above ground level.</p> <p>(8) Signs must;</p> <ul style="list-style-type: none"> (a) not have changing content; (b) not be in a digital format; (c) be situated on the site to which the sign relates; and, (d) have no illumination (internally or externally) of signs in the Commercial <u>and Mixed Use</u> and General Industrial zones within 10m of a General Residential <u>or High Density Residential zone</u> boundary. <p>(9) In the General Industrial zone on Eastern Hutt Road identified in GIZ-Figure2:</p> <ul style="list-style-type: none"> (a) no sign shall be located within 6m of Eastern Hutt Road. (b) no sign shall be located on the elevation of any building facing Eastern Hutt Road. (c) there shall be a maximum of one free-standing sign which may be located at the road entrance to the General Industrial Zone and it shall not exceed a face area of 20m² visible from any one direction; or be more than 9m above ground level. <p>(10) On land identified in the Commercial <u>Neighbourhood Centre</u> Zone at Riverstone Terrace in COMZNCZ-Figure1, the area of any signs attached to buildings shall not exceed a total area of 7.5m².</p>

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
	SIGN - Signs	Consequential Amendment	SIGN-S5	<p>Signs for direction of traffic on a site in Commercial and Mixed Use, City Centre, General Industrial and Special Activity Zones and in the Gateway Precinct of Development Area 1</p> <p>(1) The maximum vertical dimension of the sign shall not exceed 1.2m</p> <p>(2) The maximum area of the sign, visible in any one direction, shall not exceed 1m².</p> <p>(3) The content of the sign must be limited to directional purposes.</p>	<p><i>Commercial and Mixed Use City Centre General Industrial Special Activity Development Area 1 (Gateway Precinct only)</i></p>

TEMP – Temporary Activities					
	TEMP – Temporary Activities	Consequential Amendment	Standards for Permitted Activities		Zones
			TEMP-S3	<p>Outdoor Amplified Noise</p> <p>(1) Any outdoor amplified sound from a temporary event ...</p> <p>(a) Be emitted for ...</p> <p>...</p> <p>(b) Be emitted for a consecutive ...</p> <p>(c) Be emitted for no ...</p> <p>When measured:</p> <p>(d) At any point within the boundary of any site (other than the source site/s) within a General-Residential <u>or High Density Residential zone</u>; and</p> <p>(e) At any point within the notional boundary of any residential unit on a site (other than the source site/s) within a General Rural, Rural Production or Rural Lifestyle zone; and</p> <p>(f) At any point ...</p> <p>Exemptions:</p>	All

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
				(2) ... (3) ...	
	TEMP – Temporary Activities	Consequential Amendment	TEMP-S4	<p>Non-amplified Noise</p> <p>(1) Any noise resulting from a temporary event ...</p> <p>(a) ...</p> <p>(b) ...</p> <p>When measured:</p> <p>(c) At any point within the boundary of any site (other than the source site/s) within a General Residential <u>or High Density Residential</u> zone; and</p> <p>(d) At any point within the notional boundary of any residential unit on a site (other than the source site/s) within a General Rural, Rural Production or Rural Lifestyle zone; and</p> <p>(e) At any point within the boundary of any site (other than the source site/s) occupied by a hotel, motel, motor camp, early childhood centre, school or education facility, health care facility or aged care facility within any zone.</p> <p>(2) Any such noise shall also be pursuant to the general hours of operation in TEMP-S1.</p> <p>(a) Any noise ...</p> <p>Exemptions:</p> <p>(3) ...</p> <p>(4) ...</p>	<i>All</i>
	TEMP – Temporary Activities	Consequential Amendment	Standards for Restricted Discretionary Activities		
			TEMP-S10	<p>Noise</p> <p>(1) Any noise from any temporary event which exceeds 80 dB LAeq (5 mins) or 85dB LAm_{ax}.</p>	
				Zones	
				<i>All</i>	

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>When measured:</p> <ul style="list-style-type: none"> (a) At any point within the boundary of any site (other than the source site/s) within a General Residential or High Density Residential zone; and (b) At any point within the notional boundary of any residential unit on a site (other than the source site/s) within a General Rural, Rural Production or Rural Lifestyle zone; and (c) At any point within the boundary of any site (other than the source site/s) occupied by a hotel, motel, motor camp, early childhood centre, school or education facility, health care facility or aged care facility within any zone. <p>Exemptions:</p> <ul style="list-style-type: none"> (2) Noise produced by crowds; (3) All activities occurring at the Speedway Area (including temporary events) shall be subject to specific rules pertaining to the Speedway Area in the Open Space Zone (OSZ) and the Noise (NOISE) Chapters; and (4) Organised fireworks displays undertaken at Trentham Memorial Park shall be subject to the specific provisions in NOISE-R3 and NOISE-S6.
PART 3 – AREA SPECIFIC MATTERS			
RESIDENTIAL ZONES			
GRZ – General Residential Zone			
	GRZ – General Residential Zone	Amend Background	<p>Background</p> <p>The residential areas within the City are characterised by mainly low rise residential units sited on individual allotments. Past architectural styles, settlement patterns and geographical factors have resulted in diverse residential characteristics and form, resulting in a range of individual neighbourhoods. <u>These residential areas make an important contribution towards a well-functioning urban environment; however it is important to recognise that the past character, densities and styles of residential development currently enjoyed by the community will develop and change over time in response to the diverse and changing needs</u></p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>of the community and future generations. It is also important to note that there are areas within the Zone where permitted development may be modified or limited by qualifying matter areas.</p> <p>Demand for higher density residential development is increasing in the City and the manner in which the District Plan provides for higher density residential development is important to the character and amenity of existing established neighbourhoods. Higher density residential development is becoming more desirable to certain sectors of the community and it is also desirable in establishing a variety of housing types and styles, thereby providing a greater variety to the housing stock of the City.</p> <p>A mix of housing densities are provided for, with medium density housing enabled across the General Residential Zone by the incorporation of the Medium Density Residential Standards. Higher density residential development is best located in close proximity to retail, service and public transport centres specifically near the City Centre Zone (central business district), neighbourhood centres and major transport nodes. Higher density residential development is provided for in these areas in the form of Comprehensive Residential Development and by way of an increased density for residential development. The development of papakāinga is also provided for within the Zone.</p> <p>Within the General Residential Zone the Residential Conservation and Residential Hill Indigenous Biodiversity Precincts reflects the particular environmental and topographical significant indigenous vegetation and habitats that have been identified in the characteristics of those areas. The Precinct encourage the protection and retention of indigenous biodiversity values.</p> <p>It is anticipated that the character, form and amenity of residential areas within the General Residential Zone will change over time. These changes may be significant and may detract from amenity values appreciated by the community but may improve the amenity values appreciated by other people and future generations, including by providing for increased and varied housing densities and types. To help manage this change, the Medium and High Density Design Guide in Appendix 1 promotes a high standard of urban design are included in the District Plan. It is anticipated this will encourage new development to make a positive contribution toward the evolving character of the General Residential Zone.</p> <p>The City's residential areas are also characterised by the presence of non-residential activities and community facilities. These activities tend to provide essential community services, including shops, churches, schools, doctors' surgeries, day care centres and halls. In some areas motels and hotels have been established. Many non-residential activities and community facilities are generally accepted within residential areas provided they do not give rise to significant adverse effects.</p>
	GRZ – General Residential Zone	Delete Issues	<p><i>Resource Management Issues</i></p> <p>GRZ 11 – The loss of environmental quality within residential areas caused by adverse effects of activities.</p> <p>Amenity values are those inherent qualities or characteristics which contribute to people's appreciation or enjoyment of the local environment. Components of amenity include privacy, sunlight admission, open space, visual streetscape, noise and public health and safety.</p>

Commented [MM133]: S27.22 - Transpower New Zealand Limited.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>Factors which could adversely affect the amenity values of the local residential environment include:</p> <p>(1) — Noise and illumination.</p> <p>(2) — The presence of non residential activities and facilities.</p> <p>(3) — Signs.</p> <p>(4) — The design, appearance and siting of buildings.</p> <p>(5) — Toxic, noxious, offensive, dangerous or hazardous elements.</p> <p>Residential units and other buildings can block out sunlight, and reduce privacy and amenity in residential areas. Council seeks to minimise these adverse effects while maintaining a choice of residential unit styles and development opportunities.</p> <p>Operating non residential activities in residential areas may also have adverse effects including noise, increased traffic flows and the appearance of utilitarian buildings. Council seeks to maintain a high standard of residential amenity in residential environments.</p> <p>GRZ-12 — The effects on amenity values of infill development, redevelopment within and adjoining established residential areas.</p> <p>The amount of land suitable for urban use is influenced by servicing, topographical, ecological and other constraints. The General Residential Zone covers the existing residential areas as well as undeveloped land suitable for residential use in the future. Expansion of existing urban areas will be encouraged in appropriate environments with the existing urban areas being the preferred location for higher density development. Council will promote the maintenance of the general character and amenity values of particular neighbourhoods.</p>
	GRZ – General Residential Zone	Amend Objective	<p>GRZ-O1 <i>The promotion of a high quality residential environment which maintains and enhances acknowledges the physical character that is consistent with the planned urban built form of the residential areas, and provides a choice of living styles and types while recognising that character and amenity values develop and change over time and a high level of residential amenity.</i></p> <p>The essential components of residential amenity values include adequate daylight and open space, satisfactory design standards, a reasonable degree of privacy and low noise levels.</p> <p>The primary role of the General Residential Zone is to provide opportunities for residential activity. Residents want a range of living styles to reflect their various needs, while maintaining high levels of amenity and residential character. In the General Residential Zone, the provisions of the Plan seek to ensure that new development will be</p>

Commented [MM134]: S58.97 - Kianga Ora: Homes and Communities.

Commented [MM135]: S58.97 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>provided for in a manner that will respect existing forms. Appropriate activities are provided for as permitted and others will be assessed by way of resource consent applications.</p> <p>Certain non-residential activities are most appropriately located within the General Residential Zone provided that the effects of these activities, such as noise and traffic, are appropriately managed.</p>
	GRZ – General Residential Zone	Add mandatory MDRS Objective	<p>GRZ-O2 <u>Well-functioning Urban Environments</u></p> <p><u>A well-functioning urban environment that enables all people and communities to provide for their social, economic, and cultural wellbeing, and for their health and safety, now and into the future.</u></p> <p>[s80H(1)(a)(ii) note: this provision incorporates the objectives in clause 6 of Schedule 3A.]</p>
	GRZ – General Residential Zone	Add mandatory MDRS Objective	<p>GRZ-O3 <u>Housing Variety</u></p> <p><u>A relevant residential zone provides for a variety of housing types and sizes that respond to—</u></p> <p style="padding-left: 40px;">a. <u>housing needs and demand; and</u></p> <p style="padding-left: 40px;">b. <u>the neighbourhood’s planned urban built character, including 3-storey buildings.</u></p> <p>[s80H(1)(a)(ii) note: this provision incorporates the objectives in clause 6 of Schedule 3A.]</p>
	GRZ – General Residential Zone	Insert new objective	<p>GRZ-O4 <u>There is no increase in the peak demand on stormwater management systems and increase in flooding from new buildings and development.</u></p>
	GRZ – General Residential Zone	Add mandatory MDRS Policies	<p>GRZ-P1A <u>Enable a variety of housing types with a mix of densities within the General Residential Zone, including 3-storey attached and detached dwellings, and low-rise apartments.</u></p> <p>[s80H(1)(a)(ii) note: this provision incorporates the policies in clause 6 of Schedule 3A.]</p>
	GRZ – General Residential Zone	Add mandatory MDRS Policies	<p>GRZ-P1B <u>Apply the MDRS across all relevant residential zones in the district plan except in circumstances where a qualifying matter is relevant (including matters of significance such as significant natural areas, historic heritage and the relationship of Māori and their culture and traditions with their ancestral lands, water, sites, wāhi tapu, and other taonga).</u></p> <p>[s80H(1)(a)(ii) note: this provision incorporates the policies in clause 6 of Schedule 3A.]</p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	GRZ – General Residential Zone	Add mandatory MDRS Policies	GRZ-P1C <u>Encourage development to achieve attractive and safe streets and public open spaces, including by providing for passive surveillance.</u> [s80H(1)(a)(ii) note: this provision incorporates the policies in clause 6 of Schedule 3A.]
	GRZ – General Residential Zone	Add mandatory MDRS Policies	GRZ-P1D <u>Enable housing to be designed to meet the day-to-day needs of residents.</u> [s80H(1)(a)(ii) note: this provision incorporates the policies in clause 6 of Schedule 3A.]
	GRZ – General Residential Zone	Add mandatory MDRS Policies	GRZ-P1E <u>Provide for developments not meeting permitted activity status, while encouraging high-quality developments.</u> [s80H(1)(a)(ii) note: this provision incorporates the policies in clause 6 of Schedule 3A.]
	GRZ – General Residential Zone	Amend Policy	GRZ-P1 <u>To provide for a range of building densities within the residential areas that are compatible in form and scale with the neighbourhood's planned urban built form and character (amenity) which takes into account the existing character of the area, topography and the capacity of the infrastructure.</u> A number of housing density standards are provided for within the General Residential Zone to provide choice, and to take into account existing characteristics, topography and infrastructure. These differences were recognised under zoning policies relating to the General Residential Zone and Residential Conservation Precinct in the previous District Plan. In addition the Plan makes specific provision for higher density housing through reduced minimum net site area standards and Comprehensive Residential Developments in identified areas of the City within which this form of development is considered to be most appropriate. These locations are called the Residential Centres Precinct . Density refers to the amount of built development in a given area, together with the relationship between buildings and open spaces on sites . Density affects the potential number of people living in an area, the area occupied by buildings and the amount of hard surfacing, as well as the available space for gardens. The controls on allowable levels of development provide a degree of certainty to residents on such matters. Increasing the amount of buildings and hard surfaces on a site also has an impact on infrastructure, in particular on the amount of stormwater runoff. Over time, incremental change can have a significant effect on infrastructure operations. The Plan includes a requirement for new Comprehensive Residential Developments to include a specified amount of on site stormwater soakage, in order to reduce this impact.
	GRZ – General Residential Zone	Amend Policy	GRZ-P2 <u>To ensure that the scale, appearance and siting of buildings, structures and activities are compatible with the in form and scale with the neighbourhood's planned urban built form and character (amenity) and desired amenity values of the area.</u>

Commented [MM136]: S58.106 - Kianga Ora: Homes and Communities.

Commented [MM137]: S58.107 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>Buildings, structures and activities need to be of a scale or type that reflects the character of the neighbourhood. The overall aim of this policy is to promote residential character, and to ensure the compatibility of activities with the surrounding environment. Assessment of new developments may include the degree of integration a proposal achieves with not only the adjoining sites, but with the streetscape and, in some cases, the wider townscape.</p> <p>The Plan includes visual amenity standards, including controls over the location of residential buildings, and the screening of non-residential buildings. The relocation of residential buildings requires resource consent as it can cause adverse visual effects.</p>
	GRZ – General Residential Zone	Amend Policy	<p>GRZ-P4 <i>To ensure that the location and design of buildings and earthworks do not significantly detract from the residential amenity of the area, while recognising that amenity values may change over time to reflect the neighbourhood's planned urban built form.</i></p> <p>There are a number of matters that influence residential amenity. These include:</p> <ol style="list-style-type: none"> (1) The density and topography of sites. (2) The closeness of residential units to boundaries and other buildings. (3) The height and orientation of buildings. (4) The height or existence of fences, trees or other vegetation. (5) The size, location and appearance of earthworks, retaining walls and fill batters. <p>Private open space is an important factor in the use and enjoyment of a residential site. Open space provides an area for outdoor leisure activities. This policy seeks to provide a reasonably open and private outlook protecting residential sites from being 'closed in' by neighbouring buildings.</p> <p>Access to sunlight and daylight also contribute to the use and enjoyment of a residential site. To avoid excessive shading effects and allow the admission of daylight to a site, the Plan provides daylight controls on all side and rear boundaries. Similarly, to control the size and height of earthworks and associated retaining, the Plan provides for earthworks plane controls along all boundaries in order to avoid or mitigate adverse effects.</p>
	GRZ – General Residential Zone	Amend Policy	<p>GRZ-P5 <i>To ensure that <u>encourage sites fronting streets to present a pleasant and coherent residential appearance.</u></i></p> <p>The setback of buildings from the front boundary assists with privacy and provides for landscaping. The front setback provides an open style streetscape which is part of the established residential character of Upper Hutt.</p>

Commented [MM138]: Consequential amendment resulting from S58.107 - Kianga Ora: Homes and Communities.

Commented [MM139]: S58.109 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	GRZ – General Residential Zone	Amend Policy	<p>GRZ-P9 <i>To promote residential development <u>that is consistent with the planned urban built form, appearance, and with a high level of amenity of the zone</u>, and ensure that it has adequate access to infrastructural requirements, while recognising that amenity values develop and change over time.</i></p> <p>The Plan provides for the intensification of land use within the urban area to accommodate residential development where adverse effects can be avoided, remedied or mitigated.</p>
	GRZ – General Residential Zone	Delete Policy	<p>GRZ-P10 <i>To identify and maintain amenity values that the community wishes to protect while recognising that character and amenity values resulting from the built environment develop and change over time.</i></p> <p>Amenity values are those features or aspects about an area which enhance it or make it pleasant to be in. They can include access to sunlight, landscaping and visual qualities. They may also include important public features, such as parks and reserves. Activities which can adversely affect the amenities of an area must be managed, while also recognising the rights of individuals to use their own properties and the need for utilities to operate effectively and safely.</p> <p>A particular concern of the Upper Hutt community relates to the effects of the establishment and use of what are commonly referred to as gang fortifications. These are sometimes accompanied by an increase in antisocial behaviour.</p> <p>It is Council's view that the adverse effects of these fortifications on the environment, in particular in respect of the social, economic, aesthetic and cultural conditions of the Upper Hutt people and community, and the amenity values of the Upper Hutt environment, are such that these activities should not be permitted. The activity is therefore prohibited anywhere in Upper Hutt City.</p>
	GRZ – General Residential Zone	Add new policy	GRZ-P11 <i>New buildings and development will be designed to achieve hydraulic neutrality.</i>
	GRZ – General Residential Zone	Add new policy	<p>GRZ-P12 <i><u>New residential subdivision and buildings will avoid, remedy, or mitigate potential reverse sensitivity effects on existing lawfully-established non-residential activities. Potential methods include but are not limited to:</u></i></p> <ol style="list-style-type: none"> a. <i><u>Requiring noise mitigation, vibration, insulation, and ventilation for residential units;</u></i> b. <i><u>Specifying the location of private and communal outdoor living spaces;</u></i> c. <i><u>Specifying the location and function of windows;</u></i> d. <i><u>Requiring the provision of buffer areas, setbacks, and no-build areas;</u></i> e. <i><u>Specifying fencing and landscaping requirements.</u></i>
	GRZ – General Residential Zone	Amend the existing District-	Rules

Commented [MM140]: S58.110 - Kianga Ora: Homes and Communities.

Commented [MM141]: S58.110 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS															
#	Chapter	Change	Track Change												
		wide matters rule table within the GRZ	<p>District-wide matters</p> <p>Each activity in the General Residential Zone must comply with the relevant qualifying matter area rules and standards, and permitted activity the relevant rules and standards in the District-wide matters section of the Plan, and qualifying matter areas as listed below:</p> <table border="1"> <tr> <td>District-wide matters</td> </tr> <tr> <td>...</td> </tr> </table>	District-wide matters	...										
District-wide matters															
...															
	GRZ – General Residential Zone	Amend Rule	<table border="1"> <tr> <td colspan="3">Permitted Activities</td> </tr> <tr> <td colspan="3">Residential Activities</td> </tr> <tr> <td>GRZ-R2</td> <td>One Three residential units per site. [s80H(1)(a)(i) note: this rule incorporates the density standards in Part 2 of Schedule 3A] [This rule has immediate legal effect subject to sections 77M and 86BA of the RMA]</td> <td>PER</td> </tr> </table>	Permitted Activities			Residential Activities			GRZ-R2	One Three residential units per site. [s80H(1)(a)(i) note: this rule incorporates the density standards in Part 2 of Schedule 3A] [This rule has immediate legal effect subject to sections 77M and 86BA of the RMA]	PER			
Permitted Activities															
Residential Activities															
GRZ-R2	One Three residential units per site. [s80H(1)(a)(i) note: this rule incorporates the density standards in Part 2 of Schedule 3A] [This rule has immediate legal effect subject to sections 77M and 86BA of the RMA]	PER													
	GRZ – General Residential Zone	Amend Rule	<table border="1"> <tr> <td>GRZ-R3</td> <td>One family flat in conjunction with a residential unit on any site Buildings.</td> <td>PER</td> </tr> </table>	GRZ-R3	One family flat in conjunction with a residential unit on any site Buildings .	PER									
GRZ-R3	One family flat in conjunction with a residential unit on any site Buildings .	PER													
	GRZ – General Residential Zone	Add Rule	<table border="1"> <tr> <td>GRZ-R5A</td> <td>Residential activities</td> <td>PER</td> </tr> </table>	GRZ-R5A	Residential activities	PER									
GRZ-R5A	Residential activities	PER													
	GRZ – General Residential Zone	Delete Rule	<table border="1"> <tr> <td colspan="3">Controlled Activities</td> </tr> <tr> <td colspan="3">Residential Activities</td> </tr> <tr> <td>GRZ-R8</td> <td>Two or more residential units on a site complying with the net site area standard of GRZ-S2 Council may impose conditions over the following matters: <ul style="list-style-type: none"> (1) Design, appearance and layout of the development. (2) Landscaping. (3) Provision of and effects on utilities and/or services. (4) Standard, construction and layout of vehicular access. </td> <td>CON</td> </tr> <tr> <td colspan="3"> <i>Policies</i> GRZ-P1, GRZ-P2, GRZ-PREC1-P2, GRZ-P4, GRZ-PREC1-P3, DC-P1 </td> </tr> </table>	Controlled Activities			Residential Activities			GRZ-R8	Two or more residential units on a site complying with the net site area standard of GRZ-S2 Council may impose conditions over the following matters: <ul style="list-style-type: none"> (1) Design, appearance and layout of the development. (2) Landscaping. (3) Provision of and effects on utilities and/or services. (4) Standard, construction and layout of vehicular access. 	CON	<i>Policies</i> GRZ-P1, GRZ-P2, GRZ-PREC1-P2, GRZ-P4, GRZ-PREC1-P3, DC-P1		
Controlled Activities															
Residential Activities															
GRZ-R8	Two or more residential units on a site complying with the net site area standard of GRZ-S2 Council may impose conditions over the following matters: <ul style="list-style-type: none"> (1) Design, appearance and layout of the development. (2) Landscaping. (3) Provision of and effects on utilities and/or services. (4) Standard, construction and layout of vehicular access. 	CON													
<i>Policies</i> GRZ-P1, GRZ-P2, GRZ-PREC1-P2, GRZ-P4, GRZ-PREC1-P3, DC-P1															

- Commented [MM142]:** S27.27 - Transpower New Zealand Limited. Consequential amendment.
- Commented [MM143]:** S27.27 - Transpower New Zealand Limited.
- Commented [MM144]:** S27.27 - Transpower New Zealand Limited.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(5) Earthworks.</p> <p>(6) Provision of esplanade reserves and strips.</p> <p>(7) Protection of any special amenity feature.</p> <p>(8) Financial contributions.</p>
	GRZ – General Residential Zone		<p>GRZ-R9</p> <p><i>Policy</i> GRZ-P2</p> <p>Establishment of a relocated building from another site</p> <p>Council may impose conditions on:</p> <p>(1) Reinstatement works to the condition and appearance of the building relating to:</p> <p>(a) Works to the exterior fabric of the building to repair, replace or renovate damaged, defective or substandard elements;</p> <p>(b) Painting and/or cleaning of the exterior fabric of the building if necessary; Cladding or other means of enclosing open subfloor areas below the building;</p> <p>(c) Alterations required to ensure that the reinstated exterior of any relocated building is not likely to detract from the amenity values of the surrounding area.</p> <p>(2) The timeframe for the work to be completed;</p> <p>(3) Landscaping, screening and boundary treatment;</p> <p>(4) Execution of a performance bond to provide security for exterior reinstatement works required as a condition of resource consent;</p> <p>(5) Provision of and effects on utilities and/or services;</p> <p>(6) Standard, construction and layout of vehicular access.</p> <p>Notes in respect of (4):</p> <ul style="list-style-type: none"> A bond is not mandatory. It will only be required when Council considers it necessary in view of the scale and/or nature of exterior reinstatement works required. The requirement for a bond and its value will be determined in the context of the building assessment report submitted at resource consent stage. <p>CON</p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<ul style="list-style-type: none"> The bond shall be executed at the time application is made for a building consent, and security shall be in the form of either money or a guarantee by an institution approved by Council as guarantor. The bond shall be cancelled upon completion of exterior reinstatement works required in the conditions of the resource consent. The verification method for completion of these works shall be the issuing of a full or interim Code Compliance Certificate as defined in the Building Act. In the event that conditions relating to exterior reinstatement works are not complied with, the bond may be used in whole or in part to complete the works.
	GRZ – General Residential Zone	Delete Standard	<p>Standards for Permitted and Controlled Activities</p> <p>GRZ-S2</p> <p>Minimum net site area for residential units</p> <p>The minimum net site area required for any residential unit to be erected on a site is the same as the minimum required for subdivision.</p> <p>Policies GRZ-P1, GRZ-P2</p>
	GRZ – General Residential Zone	Amend Standard	<p>GRZ-S3</p> <p>Building coverage</p> <p>(1) The maximum building coverage by buildings on the net area of a site shall not exceed 50% of the net site area.</p> <p>(a) 35% in the General Residential Zone</p> <p>[s80H(1)(a)(i) note: this standard incorporates the density standards in Part 2 of Schedule 3A]</p> <p>[This rule has immediate legal effect subject to sections 77M and 86BA of the RMA]</p> <p>Exemption:</p> <p>(2) Non enclosed and uncovered decks.</p> <p>Policies GRZ-P1A, GRZ-P1B, GRZ-P1C, GRZ-P1D, GRZ-P1E, GRZ-P1, GRZ-P2, DEV1 PS</p>
	GRZ – General Residential Zone	Amend Standard	<p>GRZ-S4</p> <p>Setbacks from boundaries</p> <p>(1) Buildings must be set back from the relevant boundary by the minimum depth listed in the yards table below:</p> <p>Policies GRZ-P1A,</p>


Commented [MM145]: Clause 99, part 6, schedule 1 RMA recommendation as a consequence of S58.51 - Kāinga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS																					
#	Chapter	Change	Track Change																		
		<p>GRZ-P1B, GRZ-P1C, GRZ-P1D, GRZ-P1E, GRZ-P2, GRZ-PREC1-P2, GRZ-P4.</p>	<table border="1"> <thead> <tr> <th>Yard</th> <th>Minimum depth</th> </tr> </thead> <tbody> <tr> <td>Front</td> <td>1.5 metres</td> </tr> <tr> <td>Side</td> <td>1 metre</td> </tr> <tr> <td>Rear</td> <td>1 metre (excluding corner sites)</td> </tr> </tbody> </table> <p>(2) This standard does not apply to site boundaries where there is an existing common wall between 2 buildings on adjacent sites or where a common wall is proposed.</p> <p>[s80H(1)(a)(i) note: this standard incorporates the density standards in Part 2 of Schedule 3A]</p> <p>[This rule has immediate legal effect subject to sections 77M and 86BA of the RMA]</p> <p>(1) The setback distance for residential and non-residential buildings (excluding accessory buildings) shall not be less than:</p> <table border="1"> <thead> <tr> <th>Boundary</th> <th>Minimum setback</th> </tr> </thead> <tbody> <tr> <td>(a) Front boundary along all roads specifically named in the Transport and Parking Chapter (TP) and all roads abutting the Residential Conservation and Residential Hill Precincts.</td> <td>6m</td> </tr> <tr> <td>(b) Front boundary along all other roads.</td> <td>4m</td> </tr> <tr> <td>(c) Rear boundaries.</td> <td>3m</td> </tr> <tr> <td>(d) Side boundaries</td> <td>One of 1.5m & one of 3m</td> </tr> </tbody> </table> <p>Exemptions:</p> <p>(2) Eaves, bay windows or similar features may encroach into boundary setbacks by up to 0.7m.</p> <p>(3) Non-enclosed and uncovered decks of 1.0m or less in height above ground level.</p> <p>Notes:</p> <ul style="list-style-type: none"> On a rear allotment, as defined in Section 3.1, rear boundary setbacks apply to all boundaries. <p>[s80H(1)(b)(i) note: this standard is replaced by the density standards in Part 2 of Schedule 3A]</p>	Yard	Minimum depth	Front	1.5 metres	Side	1 metre	Rear	1 metre (excluding corner sites)	Boundary	Minimum setback	(a) Front boundary along all roads specifically named in the Transport and Parking Chapter (TP) and all roads abutting the Residential Conservation and Residential Hill Precincts.	6m	(b) Front boundary along all other roads.	4m	(c) Rear boundaries.	3m	(d) Side boundaries	One of 1.5m & one of 3m
Yard	Minimum depth																				
Front	1.5 metres																				
Side	1 metre																				
Rear	1 metre (excluding corner sites)																				
Boundary	Minimum setback																				
(a) Front boundary along all roads specifically named in the Transport and Parking Chapter (TP) and all roads abutting the Residential Conservation and Residential Hill Precincts.	6m																				
(b) Front boundary along all other roads.	4m																				
(c) Rear boundaries.	3m																				
(d) Side boundaries	One of 1.5m & one of 3m																				

Commented [MM146]: Clause 99, part 6, schedule 1 RMA recommendation as a consequence of S58.51 - Kāinga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	GRZ – General Residential Zone	Amend Standard	<p>GRZ-S5</p> <p><i>Policies</i> GRZ-P1A; GRZ-P1B; GRZ-P1C; GRZ-P1D; GRZ-P1E; GRZ-P2; DEV1-PS</p> <p>Outdoor living space (per residential unit)</p> <p>(1) A residential unit at ground floor level must have an outdoor living space that is at least 20 square metres and that comprises ground floor, balcony, patio, or roof terrace space that,—</p> <p>(a) <u>where located at ground level, has no dimension less than 3 metres; and</u></p> <p>(b) <u>where provided in the form of a balcony, patio, or roof terrace, is at least 8 square metres and has a minimum dimension of 1.8 metres; and</u></p> <p>(c) <u>is accessible from the residential unit; and</u></p> <p>(d) <u>may be—</u></p> <p>i. <u>grouped cumulatively by area in 1 communally accessible location; or</u></p> <p>ii. <u>located directly adjacent to the unit; and</u></p> <p>(e) <u>is free of buildings, parking spaces, and servicing and manoeuvring areas.</u></p> <p>(2) A residential unit located above ground floor level must have an outdoor living space in the form of a balcony, patio, or roof terrace that—</p> <p>(a) <u>is at least 8 square metres and has a minimum dimension of 1.8 metres; and</u></p> <p>(b) <u>is accessible from the residential unit; and</u></p> <p>(c) <u>may be—</u></p> <p>i. <u>grouped cumulatively by area in 1 communally accessible location, in which case it may be located at ground level; or</u></p> <p>ii. <u>located directly adjacent to the unit.</u></p> <p>[s80H(1)(a)(i) note: this standard incorporates the density standards in Part 2 of Schedule 3A] [This rule has immediate legal effect subject to sections 77M and 86BA of the RMA]</p> <p>(1) One outdoor living space capable of containing a 6m diameter circle shall be provided for each residential unit and be located at its northern aspect, or directly accessible from a living area.</p> <p>Exemptions:</p>


Commented [MM147]: Clause 99, part 6, schedule 1 RMA recommendation as a consequence of S58.51 - Kāinga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(2) Non enclosed verandahs, decks, porches, swimming pools, and a glassed conservatory with a maximum area of 13m² may encroach over or into 25% of the outdoor living space.</p> <p>[s80H(1)(b)(i) note: this standard is replaced by the density standards in Part 2 of Schedule 3A]</p>
	GRZ – General Residential Zone	Delete Standard	<p>GRZ-S6</p> <p>Policies GRZ-P2, GRZ-P4</p> <p>Building form</p> <p>Where three or more residential units are attached, a step in plan of at least 3m shall be provided between every second unit, as shown in the following diagram:</p> 
	GRZ – General Residential Zone	Amend Standard	<p>GRZ-S7</p> <p>Policies GRZ-P1A, GRZ-P1B, GRZ-P1C, GRZ-P1D, GRZ-P1E, GRZ-P2, GRZ-P4</p> <p>Building height</p> <p><u>Buildings must not exceed 11 metres in height, except that 50% of a building's roof in elevation, measured vertically from the junction between wall and roof, may exceed this height by 1 metre, where the entire roof slopes 15° or more, as shown on the following diagram:</u></p>


Commented [MM148]: Clause 99, part 6, schedule 1 RMA recommendation as a consequence of S58.51 - Kāinga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<div data-bbox="967 379 1429 727" data-label="Diagram"> </div> <p>[s80H(1)(a)(i) note: this standard incorporates the density standards in Part 2 of Schedule 3A] [This rule has immediate legal effect subject to sections 77M and 86BA of the RMA]</p> <p>(1) — The maximum height above ground level of any building shall not exceed 8m.</p> <p>Exemption:</p> <p>(2) — Chimneys, flues and minor decorative features may exceed the maximum height above ground level by up to 1m.</p> <p>[s80H(1)(b)(i) note: this provision is replaced by the density standards in Part 2 of Schedule 3A]</p>
	GRZ – General Residential Zone	Amend Standard	<p>GRZ-S8</p> <p><i>Policies</i> <i>GRZ-P1A;</i> <i>GRZ-P1B;</i> <i>GRZ-P1C;</i> <i>GRZ-P1D;</i> <i>GRZ-P1E;</i></p> <p>Sunlight access Height in relation to boundary</p> <p>(1) Buildings must not project beyond a 60° recession plane measured from a point 4 metres vertically above ground level along all boundaries, as shown on the following diagram. Where the boundary forms part of a legal right of way, entrance strip, access site, or pedestrian access way, the height in relation to boundary applies from the farthest boundary of that legal right of way, entrance strip, access site, or pedestrian access way.</p>

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
			<p>GRZ-P2, GRZ-P4</p>  <p>(2) <u>This standard does not apply to—</u></p> <ul style="list-style-type: none"> (a) <u>a boundary with a road;</u> (b) <u>existing or proposed internal boundaries within a site;</u> (c) <u>site boundaries where there is an existing common wall between 2 buildings on adjacent sites or where a common wall is proposed.</u> <p><u>[s80H(1)(a)(i) note: this provision incorporates the density standards in Part 2 of Schedule 3A]</u></p> <p><u>[This rule has immediate legal effect subject to sections 77M and 86BA of the RMA]</u></p> <p>(1) Height control planes apply to all buildings:</p> <ul style="list-style-type: none"> (a) In, or adjacent to, a General Residential Zone. (b) On sites smaller than 1500m² in a General Rural, Rural Production or Rural Lifestyle Zone. <p>(2) Buildings shall be designed so that they fit within the height control planes defined below:</p>

Commented [MM149]: Clause 99, part 6, schedule 1 RMA recommendation as a consequence of S58.51 - Kāinga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			 <p>Exemptions:</p> <p>(3) Chimneys, flues, and minor decorative features may extend beyond the height control plane by up to 1m.</p> <p>(4) The top of a dormer or gable, but not the eaves, may extend beyond the height control plane by up to 0.5m provided that the aggregate length of all projections through the plane does not exceed 25% of the total building length.</p> <p>(5) Where the boundary involved in the measurement of the height control plane adjoins an access strip or right of way to a rear allotment, the outside boundary of such an access strip or right of way may be substituted for the nearest site boundary.</p> <p>[s80H(1)(b)(i) note: this provision is replaced by the density standards in Part 2 of Schedule 3A]</p>
	GRZ – General Residential Zone	Delete and replace Standard	<p>GRZ-S9</p> <p><i>Policies</i> GRZ-P2, GRZ-P4, GRZ-P5</p> <p>Hydraulic neutrality</p> <p><u>New buildings and development must be designed to ensure that the stormwater runoff from all new impermeable surfaces will be disposed of or stored on-site and released at a rate that does not exceed the peak stormwater runoff when compared to the pre-development situation for the 10% and 1% rainfall Annual Exceedance Probability event.</u></p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>Accessory buildings</p> <p>(1) Accessory buildings shall not be erected within the front boundary setback.</p> <p>(2) Any wall closer than 1m from a boundary shall be no longer than 8m.</p> <p>(3) The distance between an accessory building and any point of the main window of a habitable room on an adjoining site, measured at right angles to the plane of the window, shall be not less than 3m.</p> <p>For garages and other accessory buildings which form a part of a residential unit, the standards for accessory buildings shall apply to that residential unit, but only to the area of the residential unit which is an accessory building.</p>
	GRZ – General Residential Zone	Add Standard	<p><u>GRZ-S13</u></p> <p>Number of residential units per site</p> <p>There must be no more than 3 residential units per site.</p> <p>[s80H(1)(a)(i) note: this provision incorporates the density standards in Part 2 of Schedule 3A]</p> <p>[This rule has immediate legal effect subject to sections 77M and 86BA of the RMA]</p>
	GRZ – General Residential Zone	Add Standard	<p><u>GRZ-S14</u></p> <p>Outlook space (per residential unit)</p> <p>(1) An outlook space must be provided for each residential unit as specified in this clause.</p> <p>(2) An outlook space must be provided from habitable room windows as shown in the diagram below:</p>

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
			<div data-bbox="920 384 1435 770" data-label="Diagram"> <p>The diagram illustrates a building footprint with an outlook space. The outlook space is a square with a depth of 4m and a width of 4m. It is located to the left of the building. The building has a habitable room on top and a principal living room on the bottom. The distance from the center point of the largest window to the outlook space is 1m. The diagram also shows a 1m x 1m square area above the habitable room, with a 1m distance from its center point to the outlook space.</p> </div> <p>(3) <u>The minimum dimensions for a required outlook space are as follows:</u></p> <ul style="list-style-type: none"> i. <u>a principal living room must have an outlook space with a minimum dimension of 4 metres in depth and 4 metres in width; and</u> ii. <u>all other habitable rooms must have an outlook space with a minimum dimension of 1 metre in depth and 1 metre in width.</u> <p>(4) <u>The width of the outlook space is measured from the centre point of the largest window on the building face to which it applies.</u></p> <p>(5) <u>Outlook spaces may be over driveways and footpaths within the site or over a public street or other public open space.</u></p> <p>(6) <u>Outlook spaces may overlap where they are on the same wall plane in the case of a multi-storey building.</u></p> <p>(7) <u>Outlook spaces may be under or over a balcony.</u></p> <p>(8) <u>Outlook spaces required from different rooms within the same building may overlap.</u></p> <p>(9) <u>Outlook spaces must—</u></p>

IPI - PROPOSED AMENDMENTS											
#	Chapter	Change	Track Change								
			<p>i. <u>be clear and unobstructed by buildings; and</u></p> <p>ii. <u>not extend over an outlook space or outdoor living space required by another dwelling.</u></p> <p>[s80H(1)(a)(i) note: this provision incorporates the density standards in Part 2 of Schedule 3A]</p> <p>[This rule has immediate legal effect subject to sections 77M and 86BA of the RMA]</p>								
	GRZ – General Residential Zone	Add Standard	<p><u>GRZ-S15</u></p> <p><u>Windows to street</u></p> <p>Any residential unit facing the street must have a minimum of 20% of the street-facing façade in glazing. This can be in the form of windows or doors.</p> <p>[s80H(1)(a)(i) note: this provision incorporates the density standards in Part 2 of Schedule 3A]</p> <p>[This rule has immediate legal effect subject to sections 77M and 86BA of the RMA]</p>								
	GRZ – General Residential Zone	Add Standard	<p><u>GRZ-S16</u></p> <p><u>Landscaped area</u></p> <p>(1) <u>A residential unit at ground floor level must have a landscaped area of a minimum of 20% of a developed site with grass or plants, and can include the canopy of trees regardless of the ground treatment below them.</u></p> <p>(2) <u>The landscaped area may be located on any part of the development site, and does not need to be associated with each residential unit.</u></p> <p>[s80H(1)(a)(i) note: this provision incorporates the density standards in Part 2 of Schedule 3A]</p> <p>[This rule has immediate legal effect subject to sections 77M and 86BA of the RMA].</p>								
	GRZ – General Residential Zone	Amend rule	<table border="1"> <thead> <tr> <th colspan="2">Restricted Discretionary Activities</th> </tr> <tr> <th colspan="2">Residential Activities</th> </tr> </thead> <tbody> <tr> <td> <p><u>GRZ-R11</u></p> <p><i><u>Policies</u></i> <i><u>UDF-P1,</u></i> <i><u>UDF-P2,</u></i></p> </td> <td> <p>Buildings accessory to a permitted or controlled activity which do not comply with permitted and controlled activity standards</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> </td> </tr> <tr> <td></td> <td>RDIS</td> </tr> </tbody> </table>	Restricted Discretionary Activities		Residential Activities		<p><u>GRZ-R11</u></p> <p><i><u>Policies</u></i> <i><u>UDF-P1,</u></i> <i><u>UDF-P2,</u></i></p>	<p>Buildings accessory to a permitted or controlled activity which do not comply with permitted and controlled activity standards</p> <p>Council will restrict its discretion to, and may impose conditions on:</p>		RDIS
Restricted Discretionary Activities											
Residential Activities											
<p><u>GRZ-R11</u></p> <p><i><u>Policies</u></i> <i><u>UDF-P1,</u></i> <i><u>UDF-P2,</u></i></p>	<p>Buildings accessory to a permitted or controlled activity which do not comply with permitted and controlled activity standards</p> <p>Council will restrict its discretion to, and may impose conditions on:</p>										
	RDIS										

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>GRZ-P1A; GRZ-P1B; GRZ-P1C; GRZ-P1D; GRZ-P1E; GRZ-P1; GRZ-P2; GRZ-P3; GRZ-P4; GRZ-P5; GRZ-P8; GRZ-P9; GRZ-P10;</p> <p>(1) Height and sunlight access. (2) Setbacks and coverage. (3) Landscaping and screening. (4) Provision of and effects on utilities and/or services. (5) Standard, construction and layout of vehicular access, manoeuvring and traffic safety. (6) Streetscape effects. (7) Effects on neighbourhood character and amenity. (8) Financial contributions. (9) <u>The matters contained in the Medium and High Density Design Guide in Appendix 1.</u> (10) <u>Measures to avoid, remedy or mitigate adverse effects.</u> (11) <u>Cumulative effects.</u> (12) <u>Reverse sensitivity effects.</u> (13) <u>The effects of the standard(s) not met.</u></p> <p>This rule does not apply to residential units.</p>
	GRZ – General Residential Zone	Delete rule	<p>GRZ-R12</p> <p><i>Policies</i> GRZ-P2; GRZ-P4</p> <p>A family flat in conjunction with a residential unit where the family flat does not comply with permitted activity standards</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <p>(1) Land tenure. (2) Location. (3) Provision of and effects on utilities and/or services. (4) Landscaping. (5) Setbacks and coverage.</p>

Commented [MM150]: Clause 99, part 6, schedule 1 RMA recommendation as a consequence of S58.51 - Kāinga Ora: Homes and Communities.

Commented [MM151]: S33.9 - Fuel Companies.

Commented [MM152]: S56.25 - Fire and Emergency New Zealand.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(6) Height and sunlight access.</p> <p>(7) Standard, construction and layout of vehicular access.</p> <p>(8) Effects on character and amenity.</p> <p>(9) Financial contributions.</p>
	GRZ – General Residential Zone	Add rule	<p><u>GRZ-R12</u></p> <p>The construction and use of 1, 2 or 3 residential units that do not comply with one or more of the following permitted standards:</p> <ul style="list-style-type: none"> (i) <u>GRZ-S3 – Building coverage.</u> (ii) <u>GRZ-S4 – Setbacks.</u> (iii) <u>GRZ-S5 Outdoor living space.</u> (iv) <u>GRZ-S7 – Building height.</u> (v) <u>GRZ-S8 – Height in relation to boundary.</u> (vi) <u>GRZ-S9 – Hydraulic neutrality.</u> (vii) <u>GRZ-S14 – Outlook space (per unit).</u> (viii) <u>GRZ-S15 – Windows to street.</u> (ix) <u>GRZ-S16 – Landscaped area.</u> <p><u>Council will restrict its discretion to, and may impose conditions on:</u></p> <ul style="list-style-type: none"> (1) <u>The matters contained in the Medium and High Density Design Guide in Appendix 1.</u> (2) <u>Site layout and design.</u> (3) <u>Consideration of the effects of the standard not met.</u> (4) <u>Cumulative effects.</u> (5) <u>The matters contained in the Code of Practice for Civil Engineering Works.</u> (6) <u>The imposition of financial contributions.</u> (7) Reverse sensitivity effects.

Commented [MM153]: S33.10 & S33.11 - Fuel Companies.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>Restriction on notification:</p> <p>Public notification of an application is precluded under this rule.</p> <p>[s80H(1)(a)(i) note: this provision incorporates the density standards in Part 2 of Schedule 3A]</p> <p>[This rule has immediate legal effect subject to sections 77M and 86BA of the RMA]</p>
	GRZ – General Residential Zone	Add rule	<p>GRZ-R12A</p> <p><u>The construction and use of 4 or more residential units that comply with the following permitted standards:</u></p> <ul style="list-style-type: none"> (i) <u>GRZ-S3 – Building coverage.</u> (ii) <u>GRZ-S4 – Setbacks.</u> (iii) <u>GRZ-S5 Outdoor living space.</u> (iv) <u>GRZ-S7 – Building height.</u> (v) <u>GRS-S8 – Height in relation to boundary.</u> (vi) <u>GRZ-S9 – Hydraulic neutrality.</u> (vii) <u>GRZ-S14 – Outlook space (per unit).</u> (viii) <u>GRZ-S15 – Windows to street.</u> (ix) <u>GRZ-S16 – Landscaped area.</u> <p><u>Council will restrict its discretion to, and may impose conditions on:</u></p> <ul style="list-style-type: none"> (1) <u>The matters contained in the Medium and High Density Design Guide in Appendix 1.</u> (2) <u>Site layout.</u> (3) <u>The matters contained in the Code of Practice for Civil Engineering Works.</u> (4) <u>Transport effects.</u> (5) <u>Cumulative effects.</u> (6) <u>Reverse Sensitivity effects.</u> <p>RDIS</p> <p>Restriction on notification:</p>

Commented [MM154]: Formatting corrections pursuant to Cl.16(2), Schedule 1 RMA.

Commented [MM155]: S33.10 & S33.11 - Fuel Companies.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p><u>Public and limited notification of an application under this rule is precluded.</u></p> <p><u>[s80H(1)(a)(i) note: this provision incorporates the density standards in Part 2 of Schedule 3A]</u></p> <p><u>[This rule has immediate legal effect subject to sections 77M and 86BA of the RMA]</u></p>
	GRZ – General Residential Zone	Add rule	<p><u>GRZ-R12B</u></p> <p>The construction and use of a residential unit(s) that is not a permitted activity, and do not fall under rules GRZ-R12 or GRZ-R12A.</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <ol style="list-style-type: none"> (1) <u>The matters contained in the Medium and High Density Design Guide in Appendix 1.</u> (2) <u>Site layout and design.</u> (3) <u>The matters contained in the Code of Practice for Civil Engineering Works.</u> (4) <u>Consideration of the effects of the standard not met.</u> (5) <u>Transport effects.</u> (6) <u>Methods to avoid, remedy, or mitigate adverse effects.</u> (7) <u>Cumulative effects.</u> (8) Reverse sensitivity effects. <p>Restriction on notification:</p> <p><u>Public notification of an application under this rule is precluded.</u></p> <p><u>[s80H(1)(a)(i) note: this provision incorporates the density standards in Part 2 of Schedule 3A]</u></p> <p><u>[This rule has immediate legal effect subject to sections 77M and 86BA of the RMA]</u></p>
	GRZ – General Residential Zone	Delete rule	<p><u>GRZ-R14</u></p> <p>Buildings accessory to a permitted or controlled activity which do not comply with permitted or controlled activity standards</p> <p>Policies GRZ-P2, GRZ-P4, GRZ-P5</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <ol style="list-style-type: none"> (1) Height and sunlight access.

Commented [MM156]: S33.11 - Fuel Companies.

IPI - PROPOSED AMENDMENTS												
#	Chapter	Change	Track Change									
			<p>(2) Setbacks and coverage.</p> <p>(3) Landscaping and screening.</p> <p>(4) Provision of and effects on utilities and/or services.</p> <p>(5) Standard, construction and layout of vehicular access, manoeuvring and traffic safety.</p> <p>(6) Streetscape effects.</p> <p>(7) Effects on neighbourhood character and amenity.</p> <p>(8) Financial contributions.</p> <p>[s80H(1)(b)(i) note: this provision is replaced by the density standards in Part 2 of Schedule 3A]</p>									
	GRZ – General Residential Zone	Amend Rule	<table border="1"> <tr> <td colspan="3">Discretionary Activities</td> </tr> <tr> <td colspan="3">Non-Residential Activities</td> </tr> <tr> <td>GRZ-R22</td> <td>Activities listed as permitted or controlled which do not comply with the relevant standards in this chapter, except as specified below unless specifically provided for under other rules.</td> <td>DIS</td> </tr> </table>	Discretionary Activities			Non-Residential Activities			GRZ-R22	Activities listed as permitted or controlled which do not comply with the relevant standards in this chapter, except as specified below unless specifically provided for under other rules.	DIS
Discretionary Activities												
Non-Residential Activities												
GRZ-R22	Activities listed as permitted or controlled which do not comply with the relevant standards in this chapter, except as specified below unless specifically provided for under other rules.	DIS										
	GRZ – General Residential Zone	Amend Matters for Consideration	<table border="1"> <tr> <td colspan="3">Matters for Consideration</td> </tr> <tr> <td colspan="3">Matters that may be relevant in the consideration of any resource consent, other than for a restricted discretionary activity, may include the following:</td> </tr> <tr> <td>GRZ-MC1</td> <td> Site layout, area and Building coverage <ol style="list-style-type: none"> The arrangement of buildings, car parking and vehicle movements on site. The extent of landscaping and screening. Whether the topography of the site has been taken into account. Whether a better standard of development can be achieved by varying the design standards. The ability to provide adequate outdoor living areas. </td> <td></td> </tr> </table>	Matters for Consideration			Matters that may be relevant in the consideration of any resource consent, other than for a restricted discretionary activity, may include the following:			GRZ-MC1	Site layout, area and Building coverage <ol style="list-style-type: none"> The arrangement of buildings, car parking and vehicle movements on site. The extent of landscaping and screening. Whether the topography of the site has been taken into account. Whether a better standard of development can be achieved by varying the design standards. The ability to provide adequate outdoor living areas. 	
Matters for Consideration												
Matters that may be relevant in the consideration of any resource consent, other than for a restricted discretionary activity, may include the following:												
GRZ-MC1	Site layout, area and Building coverage <ol style="list-style-type: none"> The arrangement of buildings, car parking and vehicle movements on site. The extent of landscaping and screening. Whether the topography of the site has been taken into account. Whether a better standard of development can be achieved by varying the design standards. The ability to provide adequate outdoor living areas. 											

IPI - PROPOSED AMENDMENTS						
#	Chapter	Change	Track Change			
			(6) The extent to which decreases in site size or increased building coverage would have an adverse effect on the amenity of the area is compatible in form and scale with the neighbourhood's planned urban built character form.			
	GRZ – General Residential Zone		<p>GRZ-MC2 Bulk and location of buildings</p> <p>(1) Whether the buildings will cause a loss of privacy, interfere with sunlight access or create shadows on surrounding allotments.</p> <p>(2) Whether the building location, design, appearance and scale will detrimentally affect the character of the surrounding area is compatible in form and scale with the neighbourhood's planned urban built character form.</p>			
	GRZ – General Residential Zone	Delete Rule	<p>Prohibited Activities</p> <p>Non Residential Activities</p> <table border="1"> <tr> <td>GRZ-R24</td> <td>Gang fortifications</td> <td>PR</td> </tr> </table>	GRZ-R24	Gang fortifications	PR
GRZ-R24	Gang fortifications	PR				
	GRZ – General Residential Zone	Delete Methods	<p>Methods</p> <p>GRZ M1 District Plan provisions consisting of a General Residential Zone identifying the residential environments within the City, including the Conservation and Hill Areas Precincts, the Residential Centres Precinct and the Wallaceville Structure Plan Development Area. Rules and standards apply to activities so that adverse effects are avoided, remedied or mitigated. Consent application procedures provide for the consideration of effects on a case by case basis and the imposition of appropriate conditions when necessary. Design guidelines provides for assessment of Comprehensive and subdivision design in the Residential Centres Precinct.</p> <p>GRZ M2 Code of Practice for Civil Engineering Works.</p> <p>GRZ M3 Abatement notices and enforcement orders may be issued where it is necessary to enforce the Plan rules and mitigate any adverse effects of activities.</p> <p>GRZ M4 Reserve Management Plans.</p> <p>GRZ M5 District Plan rules requiring reserve contributions and development impact fees.</p> <p>GRZ M6 District Plan rules setting standards to protect adjacent properties from adverse shading effects.</p>			

Commented [MM157]: S58.135 - Kianga Ora: Homes and Communities.

Commented [MM158]: S58.136 - Kianga Ora: Homes and Communities.1

IPI - PROPOSED AMENDMENTS																		
#	Chapter	Change	Track Change															
			GRZ M7 District Plan rules prohibiting gang fortifications because of their adverse effects on the environment.															
	GRZ – General Residential Zone	Delete Anticipated Environmental Results	<p>Anticipated Environmental Results</p> <p>The following results are expected to be achieved by the objectives, policies and methods of this chapter. The means of monitoring whether this Plan achieves the anticipated environmental results are also set out below.</p> <table border="1"> <thead> <tr> <th>Anticipated environmental results</th> <th>Monitoring indicators</th> <th>Data source</th> </tr> </thead> <tbody> <tr> <td>GRZ AER1</td> <td>Maintenance of residential amenity and special landscape characteristics, including on-site amenity, streetscape design and appearance</td> <td> Number of resource consents by type Community Survey Complaints and enforcement proceedings </td> <td> Council records Council Survey Complaints register proceedings </td> </tr> <tr> <td>GRZ AER2</td> <td>Development of the General Residential Zone which reflects the amenity values of the area</td> <td> Compliance with performance standards within the General Residential Zone Number of resource consents by type </td> <td>Council records</td> </tr> <tr> <td>GRZ AER3</td> <td>A built environment which supports the health and safety of the City's residents</td> <td> Resource consents and type and effect on health and safety issues Consultation and community initiatives </td> <td>Council records</td> </tr> </tbody> </table>	Anticipated environmental results	Monitoring indicators	Data source	GRZ AER1	Maintenance of residential amenity and special landscape characteristics, including on-site amenity, streetscape design and appearance	Number of resource consents by type Community Survey Complaints and enforcement proceedings	Council records Council Survey Complaints register proceedings	GRZ AER2	Development of the General Residential Zone which reflects the amenity values of the area	Compliance with performance standards within the General Residential Zone Number of resource consents by type	Council records	GRZ AER3	A built environment which supports the health and safety of the City's residents	Resource consents and type and effect on health and safety issues Consultation and community initiatives	Council records
Anticipated environmental results	Monitoring indicators	Data source																
GRZ AER1	Maintenance of residential amenity and special landscape characteristics, including on-site amenity, streetscape design and appearance	Number of resource consents by type Community Survey Complaints and enforcement proceedings	Council records Council Survey Complaints register proceedings															
GRZ AER2	Development of the General Residential Zone which reflects the amenity values of the area	Compliance with performance standards within the General Residential Zone Number of resource consents by type	Council records															
GRZ AER3	A built environment which supports the health and safety of the City's residents	Resource consents and type and effect on health and safety issues Consultation and community initiatives	Council records															
GRZ – Precinct 1 - Indigenous Biodiversity Precinct																		
	GRZ – General Residential Zone – Precinct 1	Amend Precinct description	<p><u>Precinct 1 – Residential Centres-Indigenous Biodiversity Precinct</u></p> <p>The Indigenous Biodiversity Precinct identifies areas where the Council is applying additional policy direction and guidance regarding significant natural areas that have been identified for the purpose of giving effect to section 6(c) of the RMA and Policies 23 and 24 of the RPS, but have not yet been incorporated into the district plan via a comprehensive plan change. The policy direction and guidance that applies to the Precinct does not reduce the applicability of any of the Medium Density Residential Standards, nor does it impose the need for any additional resource consents, but it does introduce additional policy consideration to accommodate a matter of national importance under section 6 (c) of the RMA that is not addressed by the MDRS. The Council is required to recognise and provide for the following matter of national importance:</p>															

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<p>(c) - the protection of areas of significant indigenous vegetation and significant habitats of indigenous fauna.</p> <p>The following objectives, and policies and rules apply within the Residential Centres Indigenous Biodiversity Precinct (as identified on the planning maps) in addition to the provisions of the underlying General Residential Zone. Where there is any conflict between the provisions the Precinct provisions shall prevail. Precinct specific subdivision provisions are located in the Subdivision Chapter (SUB).</p>				
	GRZ – General Residential Zone – Precinct 1	Amend Objective	<table border="1"> <thead> <tr> <th colspan="2">Objective</th> </tr> </thead> <tbody> <tr> <td>GRZ-PREC1-01</td> <td> <p><u>The maintenance of indigenous biological diversity values within the Indigenous Biodiversity Precinct is encouraged.</u></p> <p>To provide for higher density residential development by way of Comprehensive Residential Developments and specific net site area standards around the central business district, neighbourhood centres and major transport nodes.</p> <p>Providing a choice of living options involves the provision of more intensive types of residential development as well as traditional forms of development in Upper Hutt, which generally comprise standalone residential units on individual allotments. Higher density housing may suit the needs of certain groups of the community.</p> <p>It is important to locate higher density housing in appropriate areas. The Plan identifies areas where higher density housing is specifically encouraged due to the proximity of these areas to retail and service centres and transport nodes. The Plan provides for this type of development through reduced minimum net site area standards compared to the remainder of the Residential Zone, and through provisions for Comprehensive Residential Development.</p> <p>To ensure that new higher density residential development, including Comprehensive Residential Development, is well designed and achieves a high degree of amenity, assessment against the Design Guide for Residential Developments will be required.</p> </td> </tr> </tbody> </table>	Objective		GRZ-PREC1-01	<p><u>The maintenance of indigenous biological diversity values within the Indigenous Biodiversity Precinct is encouraged.</u></p> <p>To provide for higher density residential development by way of Comprehensive Residential Developments and specific net site area standards around the central business district, neighbourhood centres and major transport nodes.</p> <p>Providing a choice of living options involves the provision of more intensive types of residential development as well as traditional forms of development in Upper Hutt, which generally comprise standalone residential units on individual allotments. Higher density housing may suit the needs of certain groups of the community.</p> <p>It is important to locate higher density housing in appropriate areas. The Plan identifies areas where higher density housing is specifically encouraged due to the proximity of these areas to retail and service centres and transport nodes. The Plan provides for this type of development through reduced minimum net site area standards compared to the remainder of the Residential Zone, and through provisions for Comprehensive Residential Development.</p> <p>To ensure that new higher density residential development, including Comprehensive Residential Development, is well designed and achieves a high degree of amenity, assessment against the Design Guide for Residential Developments will be required.</p>
Objective							
GRZ-PREC1-01	<p><u>The maintenance of indigenous biological diversity values within the Indigenous Biodiversity Precinct is encouraged.</u></p> <p>To provide for higher density residential development by way of Comprehensive Residential Developments and specific net site area standards around the central business district, neighbourhood centres and major transport nodes.</p> <p>Providing a choice of living options involves the provision of more intensive types of residential development as well as traditional forms of development in Upper Hutt, which generally comprise standalone residential units on individual allotments. Higher density housing may suit the needs of certain groups of the community.</p> <p>It is important to locate higher density housing in appropriate areas. The Plan identifies areas where higher density housing is specifically encouraged due to the proximity of these areas to retail and service centres and transport nodes. The Plan provides for this type of development through reduced minimum net site area standards compared to the remainder of the Residential Zone, and through provisions for Comprehensive Residential Development.</p> <p>To ensure that new higher density residential development, including Comprehensive Residential Development, is well designed and achieves a high degree of amenity, assessment against the Design Guide for Residential Developments will be required.</p>						
	GRZ – General Residential Zone – Precinct 1	Amend Policy	<table border="1"> <thead> <tr> <th>Policies</th> </tr> </thead> <tbody> <tr> <td> </td> </tr> </tbody> </table>	Policies			
Policies							

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>GRZ-PREC1-P1</p> <p><i>To encourage the recognition and provision for the protection and maintenance of areas of significant indigenous vegetation and significant habitats of indigenous fauna from the potential adverse effects of medium density residential development within the Indigenous Biodiversity Precinct.</i></p> <p><i>To ensure that the scale, appearance and siting of buildings, structures and activities are compatible with the character and desired amenity values of the area.</i></p> <p>Higher density housing has the potential to affect both existing residential character and amenity. Accordingly the Plan includes standards and design guidelines for higher density housing against which this type of development is assessed in order to ensure that residential character is appropriately managed and that existing amenity values are not adversely affected. The retention of existing trees and vegetation where practical is important in this respect.</p> <p>Comprehensive Residential Developments may include an existing residential unit on a site, but there may be instances where an existing residential unit requires additional changes to ensure it is compatible with a proposed development. This will be assessed through the resource consent and Design Guide assessment process.</p> <p>On the land identified in GRZ Figure 1, particular care needs to be taken with the design of any residential development to ensure that it appropriately addresses the interface with Maidstone Park and the adjoining General Industrial Zone.</p>
	GRZ – General Residential Zone – Precinct 1	Amend Policy	<p>GRZ-PREC1-P2</p> <p><i>To encourage the avoidance, remedying and mitigation of the actual and potential adverse effects of the use and development of sites within the Indigenous Biodiversity Precinct to assist in maintaining indigenous biological diversity through:</i></p> <p><i>(1) The consideration of methods to avoid, remedy or mitigate adverse effects on areas of significant indigenous vegetation and significant habitats of indigenous fauna; and</i></p> <p><i>(2) The consideration of methods to ensure positive indigenous ecological effects.</i></p> <p>To avoid development on land identified in GRZ Figure 1 ('Maidstone Terrace Residential') which does not comply with site specific standards controlling the number of allotments and residential units, access from Railway Avenue, boundary setbacks and fencing.</p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>On the land identified in GRZ Figure 1, particular care needs to be taken with the design of any residential development to ensure that it appropriately addresses the interface with the adjoining General Industrial Zone. In particular, site specific standards apply to the site and compliance with these standards is critical to ensuring that development is appropriate.</p>
	GRZ – General Residential Zone – Precinct 1	Delete policy	<p>GRZ-PREC1-P3</p> <p><i>To encourage higher density housing through the provision of reduced net site area standards and in the form of Comprehensive Residential Developments in identified areas of the City.</i></p> <p>The Plan identifies areas considered suitable for higher density residential development. These areas are located surrounding the central business district, around the Trentham neighbourhood centre located at Camp Street, near the Wallaceville railway station from Ward Street to Lane Street and within the Urban Precinct and Grants Bush Precinct of the Wallaceville Structure Plan Development Area.</p> <p>These areas are in close proximity to retail and service facilities as well as the availability of major transport points, including rail and bus services, and a major bus terminal in the CBD.</p> <p>The reduction of net site area standards in the Residential Centres Precinct recognises a minimum site area Council is prepared to allow for housing development. Any reduction below this minimum net site area is provided for as a discretionary activity and will be assessed against the Design Guide for Comprehensive Residential Development so as to ensure that any subdivision or development below this net site area can still achieve a high quality.</p>
	GRZ – General Residential Zone – Precinct 1	Add Permitted Activity Rule	<p>Rules</p> <p>GRZ-PREC1-R1 All permitted activity rules, standards, matters and information requirements of the underlying zone apply unless specifically stated below.</p>
	GRZ – General Residential Zone – Precinct 1	Delete Controlled Activity Rule	<p>Controlled Activities</p> <p>GRZ-PREC1-R2 Two or more residential units on a site within the Residential Centres Precinct except on land identified as Pt Section 618 Hutt District complying with the net site area standard of SUB-RES-S1</p> <p><i>Policies GRZ-P3,</i></p> <p>CON</p>

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<p><i>GRZ-PREC1-P1, GRZ-PREC1-P2, GRZ-P4, GRZ-PREC1-P3, DC-P1</i></p> <p>Council may impose conditions over the following matters: Design, appearance and layout of the development. Landscaping: Provision of and effects on utilities and/or services. Standard, construction and layout of vehicular access. Earthworks: Provision of esplanade reserves and strips. Protection of any special amenity feature. Financial contributions.</p> <p>In relation to the land identified in GRZ Figure 1, Council may impose conditions over the following matters: The measures necessary to address the interface of any residential development with both Maidstone Park and the General Industrial Zone. These may include, but are not limited to: the orientation of residential units and the location of habitable rooms relative to Maidstone Park and adjacent General Industrial zoned properties; the orientation of buildings, fences or landscaping to buffer outdoor living spaces from adjacent General Industrial zoned properties.</p> <p>Controlled activities – restrictions on notification Subject to sections 95A(2)(b), 95A(2)(c), 95A(4) and 95C of the Act, a resource consent application for a controlled activity is precluded from public notification under section 95A and, subject to section 95B(3), is precluded from limited notification under section 95B(2) of the Act.</p>				
	GRZ – General Residential Zone – Precinct 1	Add Controlled Activity Rule	<table border="1"> <tr> <td>GRZ-PREC1-R3</td> <td>All controlled activity rules, standards, matters, and information requirements of the underlying zone apply unless specifically stated in this table.</td> </tr> </table>	GRZ-PREC1-R3	All controlled activity rules, standards, matters, and information requirements of the underlying zone apply unless specifically stated in this table.		
GRZ-PREC1-R3	All controlled activity rules, standards, matters, and information requirements of the underlying zone apply unless specifically stated in this table.						
	GRZ – General Residential Zone – Precinct 1	Delete Standards for Permitted and Controlled Activities	<p>Standards for Permitted and Controlled Activities</p> <table border="1"> <tr> <td>GRZ-PREC1-S1</td> <td>Maximum number of residential units along Maidstone Terrace</td> </tr> <tr> <td><i>Policies GRZ-PREC1-P1, GRZ-PREC1-P2</i></td> <td> <ol style="list-style-type: none"> 1. In relation to the land identified as Area B in GRZ Figure 1, <ol style="list-style-type: none"> a. There shall be no more than 12 residential units. To avoid any doubt: </td> </tr> </table>	GRZ-PREC1-S1	Maximum number of residential units along Maidstone Terrace	<i>Policies GRZ-PREC1-P1, GRZ-PREC1-P2</i>	<ol style="list-style-type: none"> 1. In relation to the land identified as Area B in GRZ Figure 1, <ol style="list-style-type: none"> a. There shall be no more than 12 residential units. To avoid any doubt:
GRZ-PREC1-S1	Maximum number of residential units along Maidstone Terrace						
<i>Policies GRZ-PREC1-P1, GRZ-PREC1-P2</i>	<ol style="list-style-type: none"> 1. In relation to the land identified as Area B in GRZ Figure 1, <ol style="list-style-type: none"> a. There shall be no more than 12 residential units. To avoid any doubt: 						

				<p>i. The maximum is not the maximum number of residential units on any particular site.</p>						
			<p>GRZ-PREC1-S2</p> <p><i>Policies</i> GRZ-PREC1-P1, GRZ-PREC1-P2, GRZ-P7, GRZ-PREC1-P3</p>	<p>Access standards for land use activities</p> <p>The following standards apply in addition to the requirements of GRZ-S1:</p> <p>1. In relation to the land identified in GRZ-Figure 1:</p> <p>a. There will be no access off Maidstone Terrace. Access to the land shall be off Railway Avenue.</p> <p>Neither a right of way, private way or legal boundary of any road or accessway serving the land shall at any point encroach within Area B of GRZ-Figure 1.</p>						
			<p>GRZ-PREC1-S3</p> <p><i>Policies</i> GRZ-P1, GRZ-PREC1-P1</p>	<p>Minimum net site area for residential units</p> <p>Within the Residential Centres Precinct there is no minimum net site area requirement for a residential unit forming a part of a Comprehensive Residential Development.</p>						
			<p>GRZ-PREC1-S4</p> <p><i>Policies</i> GRZ-P1, GRZ-PREC1-P1, DEV1-P5</p>	<p>Building coverage</p> <p>The maximum coverage by buildings on the net area of a site shall not exceed 45% for Comprehensive Residential Development in the Residential Centres Precinct.</p>						
			<p>GRZ-PREC1-S5</p> <p><i>Policies</i> GRZ-PREC1-P1, GRZ-PREC1-P2, GRZ-P4</p>	<p>Setbacks from boundaries</p> <p>The setback distance for residential and non-residential buildings (excluding accessory buildings) shall not be less than:</p> <table border="1"> <thead> <tr> <th>Boundary</th> <th>Minimum setback</th> </tr> </thead> <tbody> <tr> <td>(a) In relation to the land identified in Area B of GRZ-Figure 1, measured from the legal edge of Maidstone Terrace.</td> <td>8m</td> </tr> <tr> <td>(b) Front boundary along all roads specifically named in the Transport and Parking Chapter (TP) where the site is located within the Residential Centres Precinct.</td> <td>4m</td> </tr> </tbody> </table>	Boundary	Minimum setback	(a) In relation to the land identified in Area B of GRZ-Figure 1, measured from the legal edge of Maidstone Terrace.	8m	(b) Front boundary along all roads specifically named in the Transport and Parking Chapter (TP) where the site is located within the Residential Centres Precinct.	4m
Boundary	Minimum setback									
(a) In relation to the land identified in Area B of GRZ-Figure 1, measured from the legal edge of Maidstone Terrace.	8m									
(b) Front boundary along all roads specifically named in the Transport and Parking Chapter (TP) where the site is located within the Residential Centres Precinct.	4m									
			<p>GRZ-PREC1-S6</p>	<p>Outdoor living space</p>						

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p><i>Policies</i> GRZ-PREC1-P1 DEV1-P5</p> <p>For Comprehensive Residential Developments in the Residential Centres Precinct, an area of outdoor living space(s) shall be provided for each residential unit on the net site area for that residential unit that meets the following criteria: (a) Able to accommodate a ‘principal area’ of 4 metres by 4 metres; and (b) Is not required for vehicle access, parking or manoeuvring.</p>
			<p>GRZ-PREC1-S7</p> <p><i>Policies</i> GRZ-PREC1-P1, GRZ-P4, GRZ-P5</p> <p>Accessory buildings</p> <p>In the Residential Centres Precinct on a site with a net site area of less than 400m², any wall closer than 1m from a boundary shall be no longer than 6m.</p>
			<p>GRZ-PREC1-S8</p> <p><i>Policies</i> GRZ-P1</p> <p>On-site soakage</p> <p>Within a Comprehensive Residential Development an outdoor area of 25m² of water permeable surface per residential unit shall be provided.</p>
			<p>GRZ-PREC1-S9</p> <p><i>Policies</i> GRZ-PREC1-P1, GRZ-PREC1-P2, GRZ-P3, GRZ-P5, GRZ-P10</p> <p>Screening</p> <p>Outdoor storage areas shall be screened by a close-boarded fence, a solid wall or dense planting of vegetation. The screening shall: (a) In relation to the land identified in Area B of GRZ-Figure 1, sites which have a south boundary adjacent to Maidstone Terrace shall be screened along that boundary by a close-boarded fence or a solid wall no less than 1.8m in height.</p>
	GRZ – General Residential Zone – Precinct 1	Add Rule	<p>GRZ-PREC1-R4 <u>All restricted discretionary activity rules, standards, matters, and information requirements of the underlying zone apply unless specifically stated in this table.</u></p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	GRZ – General Residential Zone – Precinct 1	Delete Restricted Discretionary Rules Table	<p>Restricted Discretionary Activities</p> <p>GRZ-PREC1-R3</p> <p><i>Policies</i> GRZ-P4, GRZ-PREC1-P1, GRZ-PREC1-P2, DEV1-P5, NU-P3</p> <p>Comprehensive Residential Development on a site within a the Residential Centres Precinct complying with the standards and terms of GRZ-PREC1-S10</p> <p>Note: Comprehensive Residential Development within the Residential Centres Precinct is not subject to the minimum net site area requirements of GRZ-PREC1-S3</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <p>(0) Site layout, design and external appearance.</p> <p>(1) Provision of and effects on network utilities and/or services.</p> <p>(2) Landscaping.</p> <p>(2) Standard, construction and layout of vehicular access.</p> <p>(4) Protection of any special amenity feature.</p> <p>(5) Financial contributions.</p> <p>(6) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site.</p> <p>In relation to the land identified in GRZ-Figure 1, Council will restrict its discretion to and may impose conditions over the following matters:</p> <p>(7) The measures necessary to address the interface of any residential development with both Maidstone Park and the General Industrial Zone. These may include, but are not limited to:</p> <p>the orientation of residential units and the location of habitable rooms relative to Maidstone Park and adjacent General Industrial zoned properties;</p> <p>the orientation of buildings, fences, or landscaping to buffer outdoor living spaces from adjacent General Industrial zoned properties.</p> <p>In considering a resource consent application, Council's discretion is also restricted to an assessment against the Design Guide for the Residential Centres Precinct (refer to Appendix 1).</p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>Restriction on notification In respect of this rule, and subject to sections 95A(2)(b), 95A(4) and 95C of the Act, an application which meets the relevant standards and terms will be decided without the need for public notification under section 95A, but limited notification of an application will still be determined in accordance with section 95B. The restriction in respect of public notification does not apply if the application requires land use consent under any other provision of the Plan.</p> <p>Note: A Comprehensive Residential Development that does not comply with the relevant standards and terms for of this rule, will be assessed against the relevant matters set out in GRZ MC1 to GRZ MC10 and GRZ-PREC1 MC1 to GRZ-PREC1 MC2. Notwithstanding this rule any Comprehensive Residential Development on land identified in GRZ Figure 1 that does not comply with SUB-RES S1, GRZ-PREC1 S1, and GRZ-PREC1 S2, GRZ-PREC1 S5 and/or GRZ-PREC1 S9 is a non-complying activity.</p>
	GRZ – General Residential Zone – Precinct 1	Delete Restricted Discretionary Standards	<p>Restricted Discretionary Activity Standards</p> <p>GRZ-PREC1-S10</p> <p><i>Policies</i> GRZ-PREC1-P1, GRZ-P1, GRZ-P4, GRZ-PREC1-P3, DEV1-P5, NU-P3</p> <p>Comprehensive Residential Development</p> <p>Standards and terms for Comprehensive Residential Development:</p> <ul style="list-style-type: none"> (0) — Compliance with the access standards of GRZ-PREC1 S2. (1) — Compliance with the building coverage standard of GRZ-PREC1 S4. (2) — Compliance with the yard setback standards of GRZ-PREC1 S5 and GRZ-PREC1 S7 for external boundaries only. (3) — Compliance with the outdoor living space standard of GRZ-PREC1 S6 (4) — Compliance with the maximum building height standard of GRZ S7 (5) — Compliance with the sunlight access planes of GRZ S8 for external boundaries only. (7) — Compliance with the on-site soakage standard of GRZ-PREC1 S8.

IPI - PROPOSED AMENDMENTS															
#	Chapter	Change	Track Change												
	GRZ – General Residential Zone – Precinct 1	Add Rule	GRZ-PREC1-R5 All discretionary activity rules in the underlying zone apply unless specifically stated in this table.												
	GRZ – General Residential Zone – Precinct 1	Delete Discretionary Activities Rule Table	<table border="1"> <thead> <tr> <th colspan="3">Discretionary Activities</th> </tr> </thead> <tbody> <tr> <td>GRZ-PREC1-R4</td> <td>Two or more residential units on a site within the Residential Centres Precinct that does not comply with the net site area standard of SUB-RES-S1</td> <td>DIS</td> </tr> <tr> <td>GRZ-PREC1-R5</td> <td>Comprehensive Residential Development on a site within the Residential Centres Precinct not complying with the standards and terms of GRZ-PREC1-S10</td> <td>DIS</td> </tr> </tbody> </table>	Discretionary Activities			GRZ-PREC1-R4	Two or more residential units on a site within the Residential Centres Precinct that does not comply with the net site area standard of SUB-RES-S1	DIS	GRZ-PREC1-R5	Comprehensive Residential Development on a site within the Residential Centres Precinct not complying with the standards and terms of GRZ-PREC1-S10	DIS			
Discretionary Activities															
GRZ-PREC1-R4	Two or more residential units on a site within the Residential Centres Precinct that does not comply with the net site area standard of SUB-RES-S1	DIS													
GRZ-PREC1-R5	Comprehensive Residential Development on a site within the Residential Centres Precinct not complying with the standards and terms of GRZ-PREC1-S10	DIS													
	GRZ – General Residential Zone – Precinct 1	Add Rule	GRZ-PREC1-R6 All non-complying rules in the underlying zone apply unless specifically stated in this table.												
	GRZ – General Residential Zone – Precinct 1	Delete Non-Complying Activities Table	<table border="1"> <thead> <tr> <th colspan="3">Non-Complying Activities</th> </tr> <tr> <th colspan="3">Residential Activities</th> </tr> </thead> <tbody> <tr> <td>GRZ-PREC1-R6</td> <td>In relation to the land identified in GRZ Figure 1 ('Maidstone Terrace Residential') Activities which do not comply with standards SUB-RES-S1, GRZ-PREC1-S1, GRZ-PREC1-S2, GRZ-PREC1-S5 and/or GRZ-PREC1-S9</td> <td>NC</td> </tr> <tr> <td>GRZ-PREC1-R7</td> <td>In relation to the land identified in GRZ Figure 1 ('Maidstone Terrace Residential') Rest homes and community care housing</td> <td>NC</td> </tr> </tbody> </table>	Non-Complying Activities			Residential Activities			GRZ-PREC1-R6	In relation to the land identified in GRZ Figure 1 ('Maidstone Terrace Residential') Activities which do not comply with standards SUB-RES-S1, GRZ-PREC1-S1, GRZ-PREC1-S2, GRZ-PREC1-S5 and/or GRZ-PREC1-S9	NC	GRZ-PREC1-R7	In relation to the land identified in GRZ Figure 1 ('Maidstone Terrace Residential') Rest homes and community care housing	NC
Non-Complying Activities															
Residential Activities															
GRZ-PREC1-R6	In relation to the land identified in GRZ Figure 1 ('Maidstone Terrace Residential') Activities which do not comply with standards SUB-RES-S1, GRZ-PREC1-S1, GRZ-PREC1-S2, GRZ-PREC1-S5 and/or GRZ-PREC1-S9	NC													
GRZ-PREC1-R7	In relation to the land identified in GRZ Figure 1 ('Maidstone Terrace Residential') Rest homes and community care housing	NC													
	GRZ – General Residential Zone – Precinct 1	Add Rule	GRZ-PREC1-R7 All prohibited activity rules in the underlying zone apply unless specifically stated in this table.												
	GRZ – General Residential Zone – Precinct 1	Delete Matters for Consideration	<table border="1"> <thead> <tr> <th colspan="2">Matters for Consideration</th> </tr> </thead> <tbody> <tr> <td colspan="2">Matters that may be relevant in the consideration of any resource consent, other than for a restricted discretionary activity, may include the following:</td> </tr> <tr> <td>GRZ-PREC1-MC1</td> <td> <p>Comprehensive Residential Development</p> <p>(1) The extent to which the proposal meets the guidance for Comprehensive Residential Developments included in the Design Guide for the Residential Centres Precinct.</p> <p>(2) Matters listed under 'Site layout, area and building coverage' in this rule.</p> <p>(3) Matters listed under 'Bulk and location of buildings' in this rule.</p> <p>(4) Matters listed under 'Sunlight access' in this rule.</p> </td> </tr> </tbody> </table>	Matters for Consideration		Matters that may be relevant in the consideration of any resource consent, other than for a restricted discretionary activity, may include the following:		GRZ-PREC1-MC1	<p>Comprehensive Residential Development</p> <p>(1) The extent to which the proposal meets the guidance for Comprehensive Residential Developments included in the Design Guide for the Residential Centres Precinct.</p> <p>(2) Matters listed under 'Site layout, area and building coverage' in this rule.</p> <p>(3) Matters listed under 'Bulk and location of buildings' in this rule.</p> <p>(4) Matters listed under 'Sunlight access' in this rule.</p>						
Matters for Consideration															
Matters that may be relevant in the consideration of any resource consent, other than for a restricted discretionary activity, may include the following:															
GRZ-PREC1-MC1	<p>Comprehensive Residential Development</p> <p>(1) The extent to which the proposal meets the guidance for Comprehensive Residential Developments included in the Design Guide for the Residential Centres Precinct.</p> <p>(2) Matters listed under 'Site layout, area and building coverage' in this rule.</p> <p>(3) Matters listed under 'Bulk and location of buildings' in this rule.</p> <p>(4) Matters listed under 'Sunlight access' in this rule.</p>														

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(5) Matters listed under 'Traffic generation and access' in this rule.</p> <p>GRZ-PREC1-MC2 Development of two or more residential units with a net site area less than 400m² in the Residential Centres Precinct that is not otherwise a Comprehensive Residential Development</p> <p>(1) The extent to which the proposal meets the guidance on small site design and development contained in the Design Guide for the Residential Centres Precinct.</p>
	GRZ – General Residential Zone – Precinct 2	Delete Precinct 2	<p>Precinct 2 – Residential and Hill Residential Conservation Precinct</p> <p>The following objectives, policies, and rules apply within the Residential Hill Residential Conservation Precinct (as identified on the planning maps) in addition to the provisions of the underlying General Residential Zone. Where there is any conflict between the provisions the Precinct provisions shall prevail. Precinct specific subdivision provisions are located in the Subdivision Chapter (SUB).</p> <p>Objective</p> <p>GRZ-PREC2-O1 <i>The maintenance and enhancement of the special landscape and natural values of the Conservation and Hill Areas.</i></p> <p>Within the General Residential Zone of the City are environments with special character. The Residential Conservation Precinct includes the areas adjoining Trentham Memorial Park, Palfrey Street, Chatsworth Road and parts of Pinehaven. These areas have a mature landscape and townscape, contain native flora and fauna, natural watercourses, as well as larger sections. They also include residential development on the hills surrounding the urban area. These areas require a lower density of development in order to maintain their important landscape and ecological values.</p> <p>In contrast, the Residential Hill Precinct is characterised by more recent development which recognises the topographical constraints by having a lower density of development. This Precinct also contains areas undergoing development as well as some earmarked for future development.</p> <p>Within the Conservation and Hill Areas there are a number of standards and controls which maintain and enhance the special values of those parts of the General Residential Zone. These controls are in addition to the provisions relating to the General Residential Zone.</p> <p>Policies</p> <p>GRZ-PREC2-P1 <i>To promote a relatively low intensity of development within the Conservation and Hill Areas.</i></p>

IPI - PROPOSED AMENDMENTS															
#	Chapter	Change	Track Change												
			<p>These areas have a lower level of building density with a corresponding sense of spaciousness compared with other residential areas. They have developed a certain character as a result of past patterns of development. Higher density forms of development such as Comprehensive Residential Development may erode the character and amenity of these areas, and higher density housing is therefore not encouraged. This policy seeks to recognise and protect the existing and potential future levels of amenity.</p> <p>GRZ-PREC2-P2 To protect trees and vegetation which contribute to the amenity values, landscape values, character, ecological, historical and cultural values of the Conservation and Hill Areas.</p> <p>Trees add to the character of residential areas and also have ecological, historical, and cultural values.</p> <p>The Conservation and Hill Areas have special qualities which merit the protection of trees. They also merit different requirements for development to assist in protecting their amenity values and land stability.</p> <p>Rules</p> <table border="1"> <thead> <tr> <th colspan="2">Standards for Permitted and Controlled Activities</th> </tr> </thead> <tbody> <tr> <td> <p>GRZ-PREC2-S1</p> <p><i>Policies</i> GRZ-P1, GRZ-P2, DEV1-P5</p> </td> <td> <p>Building coverage</p> <p>The maximum coverage by buildings on the net area of a site shall not exceed 30% in the Residential Conservation and Residential Hill Precincts;</p> </td> </tr> <tr> <td> <p>GRZ-PREC2-S2</p> <p><i>Policies</i> GRZ-P2, GRZ-PREC1-P2, GRZ-P4</p> </td> <td> <p>Setbacks from boundaries</p> <p>The setback distance for residential and non-residential buildings (excluding accessory buildings) shall not be less than:</p> <table border="1"> <thead> <tr> <th>Boundary</th> <th>Minimum setback</th> </tr> </thead> <tbody> <tr> <td>Front boundary along all roads specifically named in Transport and Parking Chapter (TP) and all roads abutting the Residential Conservation and Residential Hill Precincts.</td> <td>6m</td> </tr> <tr> <td>Side boundaries within the Residential Conservation and Residential Hill Precincts.</td> <td>3m (both sides)</td> </tr> </tbody> </table> </td> </tr> </tbody> </table>	Standards for Permitted and Controlled Activities		<p>GRZ-PREC2-S1</p> <p><i>Policies</i> GRZ-P1, GRZ-P2, DEV1-P5</p>	<p>Building coverage</p> <p>The maximum coverage by buildings on the net area of a site shall not exceed 30% in the Residential Conservation and Residential Hill Precincts;</p>	<p>GRZ-PREC2-S2</p> <p><i>Policies</i> GRZ-P2, GRZ-PREC1-P2, GRZ-P4</p>	<p>Setbacks from boundaries</p> <p>The setback distance for residential and non-residential buildings (excluding accessory buildings) shall not be less than:</p> <table border="1"> <thead> <tr> <th>Boundary</th> <th>Minimum setback</th> </tr> </thead> <tbody> <tr> <td>Front boundary along all roads specifically named in Transport and Parking Chapter (TP) and all roads abutting the Residential Conservation and Residential Hill Precincts.</td> <td>6m</td> </tr> <tr> <td>Side boundaries within the Residential Conservation and Residential Hill Precincts.</td> <td>3m (both sides)</td> </tr> </tbody> </table>	Boundary	Minimum setback	Front boundary along all roads specifically named in Transport and Parking Chapter (TP) and all roads abutting the Residential Conservation and Residential Hill Precincts.	6m	Side boundaries within the Residential Conservation and Residential Hill Precincts.	3m (both sides)
Standards for Permitted and Controlled Activities															
<p>GRZ-PREC2-S1</p> <p><i>Policies</i> GRZ-P1, GRZ-P2, DEV1-P5</p>	<p>Building coverage</p> <p>The maximum coverage by buildings on the net area of a site shall not exceed 30% in the Residential Conservation and Residential Hill Precincts;</p>														
<p>GRZ-PREC2-S2</p> <p><i>Policies</i> GRZ-P2, GRZ-PREC1-P2, GRZ-P4</p>	<p>Setbacks from boundaries</p> <p>The setback distance for residential and non-residential buildings (excluding accessory buildings) shall not be less than:</p> <table border="1"> <thead> <tr> <th>Boundary</th> <th>Minimum setback</th> </tr> </thead> <tbody> <tr> <td>Front boundary along all roads specifically named in Transport and Parking Chapter (TP) and all roads abutting the Residential Conservation and Residential Hill Precincts.</td> <td>6m</td> </tr> <tr> <td>Side boundaries within the Residential Conservation and Residential Hill Precincts.</td> <td>3m (both sides)</td> </tr> </tbody> </table>	Boundary	Minimum setback	Front boundary along all roads specifically named in Transport and Parking Chapter (TP) and all roads abutting the Residential Conservation and Residential Hill Precincts.	6m	Side boundaries within the Residential Conservation and Residential Hill Precincts.	3m (both sides)								
Boundary	Minimum setback														
Front boundary along all roads specifically named in Transport and Parking Chapter (TP) and all roads abutting the Residential Conservation and Residential Hill Precincts.	6m														
Side boundaries within the Residential Conservation and Residential Hill Precincts.	3m (both sides)														

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<p>Matters for Consideration</p> <p>Matters that may be relevant in the consideration of any resource consent, other than for a restricted discretionary activity, may include the following:</p> <table border="1"> <tr> <td>GRZ-PREC2-MC1</td> <td> <p>Work on trees in the Residential Conservation and Residential Hill Precinct</p> <p>(1) The contribution the tree makes to the amenity of the area.</p> <p>(2) The health of the tree.</p> <p>(3) The function the tree may have in an ecosystem or habitat.</p> <p>(4) Whether the tree is causing or is likely to cause significant damage to buildings, structures or utilities.</p> <p>(5) Significant adverse environmental effects caused by the tree and the nature of works proposed to avoid, remedy or mitigate them.</p> </td> </tr> </table> <p>Figures</p>	GRZ-PREC2-MC1	<p>Work on trees in the Residential Conservation and Residential Hill Precinct</p> <p>(1) The contribution the tree makes to the amenity of the area.</p> <p>(2) The health of the tree.</p> <p>(3) The function the tree may have in an ecosystem or habitat.</p> <p>(4) Whether the tree is causing or is likely to cause significant damage to buildings, structures or utilities.</p> <p>(5) Significant adverse environmental effects caused by the tree and the nature of works proposed to avoid, remedy or mitigate them.</p>
GRZ-PREC2-MC1	<p>Work on trees in the Residential Conservation and Residential Hill Precinct</p> <p>(1) The contribution the tree makes to the amenity of the area.</p> <p>(2) The health of the tree.</p> <p>(3) The function the tree may have in an ecosystem or habitat.</p> <p>(4) Whether the tree is causing or is likely to cause significant damage to buildings, structures or utilities.</p> <p>(5) Significant adverse environmental effects caused by the tree and the nature of works proposed to avoid, remedy or mitigate them.</p>				

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>GRZ Figure 1</p> <p>Maidstone Terrace Residential</p> 
HRZ – High Density Residential Zone			
	HRZ – High Density Residential Zone	New Background	<p><u>HRZ – High Density Residential Zone</u></p> <p><u>Background</u></p> <p><u>The High Density Residential Zone is to be used predominantly for residential activities with high concentration and bulk of buildings, such as apartments, and other compatible activities.</u></p> <p><u>The High Density Residential Zone is located adjacent to and within a walkable catchment of the following train stations and centre zones:</u></p> <ul style="list-style-type: none"> (i) <u>Silverstream Station</u> (ii) <u>Heretaunga Station</u> (iii) <u>Trentham Station</u>

IPI - PROPOSED AMENDMENTS													
#	Chapter	Change	Track Change										
			<p>(iv) <u>Wallaceville Station</u></p> <p>(v) <u>Upper Hutt Station</u></p> <p>(vi) <u>City Centre Zone</u></p> <p>(vii) <u>Town Centre Zone</u></p> <p>(viii) <u>Local Centre Zone</u></p> <p>The High Density Residential Zone provides for heights and densities of residential units and buildings greater than those provided for by the Medium Density Residential Standards that apply in the General Residential Zone. The High Density Residential Zone gives effect to policy 3(c) and (d) of the National Policy Statement on Urban Development (2020).</p> <p>Within the High Density Residential Zone, development within the St Patrick's Estate Precinct will maintain and enhance linkages to the Hutt River walkway and Silverstream Railway Station.</p> <p>Should there be any conflict between the High Density Residential Zone and the General Residential Zone provisions, the provisions of the High Density Residential Zone prevail.</p>										
	HRZ – High Density Residential Zone	New Objective	<table border="1"> <thead> <tr> <th colspan="2">Objectives</th> </tr> </thead> <tbody> <tr> <td>HRZ-O1</td> <td>Well-functioning Urban Environments</td> </tr> <tr> <td colspan="2">A well-functioning urban environment that enables all people and communities to provide for their social, economic, and cultural wellbeing, and for their health and safety, now and into the future.</td> </tr> <tr> <td colspan="2">[s80H(1)(a)(ii) note: this provision incorporates the objectives in clause 6 of Schedule 3A.]</td> </tr> </tbody> </table>	Objectives		HRZ-O1	Well-functioning Urban Environments	A well-functioning urban environment that enables all people and communities to provide for their social, economic, and cultural wellbeing, and for their health and safety, now and into the future.		[s80H(1)(a)(ii) note: this provision incorporates the objectives in clause 6 of Schedule 3A.]			
Objectives													
HRZ-O1	Well-functioning Urban Environments												
A well-functioning urban environment that enables all people and communities to provide for their social, economic, and cultural wellbeing, and for their health and safety, now and into the future.													
[s80H(1)(a)(ii) note: this provision incorporates the objectives in clause 6 of Schedule 3A.]													
	HRZ – High Density Residential Zone	New Objective	<table border="1"> <thead> <tr> <td>HRZ-O2</td> <td>Housing Variety</td> </tr> </thead> <tbody> <tr> <td colspan="2">A relevant residential zone provides for a variety of housing types and sizes that respond to—</td> </tr> <tr> <td colspan="2">a. <u>housing needs and demand</u>; and</td> </tr> <tr> <td colspan="2">b. <u>the neighbourhood's planned urban built character, including 3-storey buildings</u>.</td> </tr> <tr> <td colspan="2">[s80H(1)(a)(ii) note: this provision incorporates the objectives in clause 6 of Schedule 3A.]</td> </tr> </tbody> </table>	HRZ-O2	Housing Variety	A relevant residential zone provides for a variety of housing types and sizes that respond to—		a. <u>housing needs and demand</u> ; and		b. <u>the neighbourhood's planned urban built character, including 3-storey buildings</u> .		[s80H(1)(a)(ii) note: this provision incorporates the objectives in clause 6 of Schedule 3A.]	
HRZ-O2	Housing Variety												
A relevant residential zone provides for a variety of housing types and sizes that respond to—													
a. <u>housing needs and demand</u> ; and													
b. <u>the neighbourhood's planned urban built character, including 3-storey buildings</u> .													
[s80H(1)(a)(ii) note: this provision incorporates the objectives in clause 6 of Schedule 3A.]													
	HRZ – High Density Residential Zone	New Objective	<table border="1"> <thead> <tr> <td>HRZ-O3</td> <td>Hydraulic neutrality</td> </tr> </thead> <tbody> </tbody> </table>	HRZ-O3	Hydraulic neutrality								
HRZ-O3	Hydraulic neutrality												

Commented [MM159]: S5.4 - Bob Anker.

Commented [MM160]: S5.4 - Bob Anker, and S58.140 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			There is no increase in the peak demand on stormwater management systems and increase in flooding from <u>subdivision</u> and development.
	HRZ-High Density Residential Zone	New Objective	<p>HRZ-O4 High Density Residential Zone</p> <p>The planned built urban form of the High Density Residential Zone includes high density residential development of heights and densities of urban form greater than that provided for in the General Residential Zone.</p>
	HRZ-High Density Residential Zone	New Objective	<p>HRZ-O5 Planned urban built form</p> <p><i>The promotion of a high quality residential environment that is consistent with the planned urban built form of the High Density Residential Zone and provides a choice of living styles and types while recognising that character and amenity values develop and change over time.</i></p>
	HRZ – High Density Residential Zone	New Policy	<p>Policies</p> <p>HRZ-P1 Apply the MDRS across all relevant residential zones in the district plan except in circumstances where a qualifying matter is relevant (including matters of significance such as historic heritage and the relationship of Māori and their culture and traditions with their ancestral lands, water, sites, wāhi tapu, and other taonga).</p> <p>[s80H(1)(a)(ii) note: this provision incorporates the policies in clause 6 of Schedule 3A.]</p>
	HRZ – High Density Residential Zone	New Policy	<p>HRZ-P2 Encourage development to achieve attractive and safe streets and public open spaces, including by providing for passive surveillance.</p> <p>[s80H(1)(a)(ii) note: this provision incorporates the policies in clause 6 of Schedule 3A.]</p>
	HRZ – High Density Residential Zone	New Policy	<p>HRZ-P3 Enable housing to be designed to meet the day-to-day needs of residents.</p> <p>[s80H(1)(a)(ii) note: this provision incorporates the policies in clause 6 of Schedule 3A.]</p>
	HRZ – High Density Residential Zone	New Policy	<p>HRZ-P4 Provide for developments not meeting permitted activity status, while encouraging high-quality developments.</p>

Commented [MM161]: To create a stand-alone HRZ chapter.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			[s80H(1)(a)(ii) note: this provision incorporates the policies in clause 6 of Schedule 3A.]
	HRZ – High Density Residential Zone	New Policy	HRZ-P5 To provide for a range of building densities within the residential areas that are compatible in form and scale with the neighbourhood’s planned urban built character form .
	HRZ – High Density Residential Zone	New Policy	HRZ-P6 Provide for and encourage medium and high density residential development that is consistent with the Council’s Medium and High Density Design Guide in Appendix 1.
	HRZ – High Density Residential Zone	New Policy	HRZ-P7 Enable more people to live in the High Density Residential Zone by enabling residential building heights up to 206 metres.
	HRZ – High Density Residential Zone	New Policy	HRZ-P8 New buildings and development will be designed to achieve hydraulic neutrality .
	HRZ – High Density Residential Zone	New Policy	HRZ-P9 <i>To ensure that the scale, appearance and siting of buildings, structures and activities are compatible in form and scale with the neighbourhood’s planned urban built form and amenity.</i>
	HRZ – High Density Residential Zone	New Policy	HRZ-P10 <i>To ensure that the location and design of buildings and earthworks do not significantly detract from the residential amenity of the area, while recognising that amenity values may change over time to reflect the neighbourhood’s planned urban built form.</i> <i>(1) There are a number of matters that influence residential amenity. These include:</i> <i>(2) The density and topography of sites.</i> <i>(3) The closeness of residential units to boundaries and other buildings.</i> <i>(4) The height and orientation of buildings.</i> <i>(5) The height or existence of fences, trees or other vegetation.</i>
	HRZ – High Density Residential Zone	New Policy	HRZ-P11 <i>To encourage sites fronting streets to present a coherent residential appearance.</i>
	HRZ – High Density Residential Zone	New Policy	HRZ-P12 <i>To ensure that non-residential activities within residential areas do not cause significant adverse environmental effects.</i>
	HRZ – High Density Residential Zone	New Policy	HRZ-P13 <i>To mitigate the adverse effects of noise within residential areas to a level consistent with a predominantly residential environment.</i>

Commented [MM162]: S58.149 - Kianga Ora: Homes and Communities.

Commented [MM163]: Consequential amendment arising from S5.26 - Bob Anker.

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
	HRZ – High Density Residential Zone	New Policy	<p>HRZ-P14 <i>To promote a safe and efficient roading network which avoids, remedies or mitigates the adverse effects of road traffic on residential areas.</i></p>						
	HRZ – High Density Residential Zone	New Policy	<p>HRZ-P15 <i>To provide for new residential development within the City in a sustainable manner</i></p>						
	HRZ – High Density Residential Zone	New Policy	<p>HRZ-P16 <i>To promote residential development that is consistent with the planned urban built form, appearance, and amenity of the zone, and ensure that it has adequate access to infrastructural requirements, while recognising that amenity values develop and change over time.</i></p>						
	HRZ – High Density Residential Zone	New Policy	<p>HRZ-P17 <i>New residential subdivision and buildings will avoid, remedy, or mitigate potential reverse sensitivity effects on existing lawfully-established non-residential activities. Potential methods include but are not limited to:</i></p> <ol style="list-style-type: none"> a. <i>Requiring noise mitigation, vibration, insulation, and ventilation for residential units;</i> b. <i>Specifying the location of private and communal outdoor living spaces;</i> c. <i>Specifying the location and function of windows;</i> d. <i>Requiring the provision of buffer areas, setbacks, and no-build areas;</i> e. <i>Specifying fencing and landscaping requirements.</i> 						
	HRZ – High Density Residential Zone	New Rules	<p>Rules</p> <p>District-wide matters</p> <p>Each activity in the High Density Residential Zone must comply with the relevant qualifying matter area rules and standards, and permitted activity the relevant rules and standards in the District-wide matters of the Plan, and qualifying matter areas as listed below:</p> <table border="1"> <tr> <td>District-wide matters</td> </tr> <tr> <td>TEMP - Temporary Activities</td> </tr> <tr> <td>SIGN - Signs</td> </tr> <tr> <td>EW - Earthworks</td> </tr> <tr> <td>NATC – Natural Character</td> </tr> <tr> <td>DC – Development Contributions</td> </tr> </table>	District-wide matters	TEMP - Temporary Activities	SIGN - Signs	EW - Earthworks	NATC – Natural Character	DC – Development Contributions
District-wide matters									
TEMP - Temporary Activities									
SIGN - Signs									
EW - Earthworks									
NATC – Natural Character									
DC – Development Contributions									

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change																			
			<table border="1"> <tr><td><u>HH - Historical Heritage</u></td></tr> <tr><td><u>TREE - Notable Trees</u></td></tr> <tr><td><u>UTG - Urban Tree Groups</u></td></tr> <tr><td><u>ECO - Ecosystems and Indigenous Biodiversity</u></td></tr> <tr><td><u>NFL - Natural Features and Landscapes</u></td></tr> <tr><td><u>PA – Public Access</u></td></tr> <tr><td><u>ASW - Activities on the Surface of Water</u></td></tr> <tr><td><u>NU – Network Utilities</u></td></tr> <tr><td><u>REG - Renewable Energy Generation</u></td></tr> <tr><td><u>TP – Transport and Parking</u></td></tr> <tr><td><u>NOISE - Noise</u></td></tr> <tr><td><u>NH - Natural Hazards</u></td></tr> <tr><td><u>CL – Contaminated Land</u></td></tr> <tr><td><u>HS - Hazardous Substances</u></td></tr> <tr><td><u>WM – Waste Management</u></td></tr> <tr><td><u>SUB - Subdivision</u></td></tr> <tr><td><u>AIR - Air</u></td></tr> <tr><td><u>LIGHT - Light</u></td></tr> <tr><td><u>PK – Papakāinga</u></td></tr> </table>	<u>HH - Historical Heritage</u>	<u>TREE - Notable Trees</u>	<u>UTG - Urban Tree Groups</u>	<u>ECO - Ecosystems and Indigenous Biodiversity</u>	<u>NFL - Natural Features and Landscapes</u>	<u>PA – Public Access</u>	<u>ASW - Activities on the Surface of Water</u>	<u>NU – Network Utilities</u>	<u>REG - Renewable Energy Generation</u>	<u>TP – Transport and Parking</u>	<u>NOISE - Noise</u>	<u>NH - Natural Hazards</u>	<u>CL – Contaminated Land</u>	<u>HS - Hazardous Substances</u>	<u>WM – Waste Management</u>	<u>SUB - Subdivision</u>	<u>AIR - Air</u>	<u>LIGHT - Light</u>	<u>PK – Papakāinga</u>
<u>HH - Historical Heritage</u>																						
<u>TREE - Notable Trees</u>																						
<u>UTG - Urban Tree Groups</u>																						
<u>ECO - Ecosystems and Indigenous Biodiversity</u>																						
<u>NFL - Natural Features and Landscapes</u>																						
<u>PA – Public Access</u>																						
<u>ASW - Activities on the Surface of Water</u>																						
<u>NU – Network Utilities</u>																						
<u>REG - Renewable Energy Generation</u>																						
<u>TP – Transport and Parking</u>																						
<u>NOISE - Noise</u>																						
<u>NH - Natural Hazards</u>																						
<u>CL – Contaminated Land</u>																						
<u>HS - Hazardous Substances</u>																						
<u>WM – Waste Management</u>																						
<u>SUB - Subdivision</u>																						
<u>AIR - Air</u>																						
<u>LIGHT - Light</u>																						
<u>PK – Papakāinga</u>																						

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	HRZ – High Density Residential Zone	New Rule	<p>HRZ-R1</p> <p>All permitted activity rules, standards, matters, and information requirements that apply to the General Residential Zone except as specifically provided for in this table.</p> <p>Should there be any conflict between the High Density Residential Zone and the General Residential Zone provisions, the provisions of the High Density Residential Zone prevail.</p> <p>Residential activities:</p> <ul style="list-style-type: none"> (a) <u>Minor structures</u> (b) <u>Rest homes and community care housing</u> (c) <u>Removal of a building from a site</u> (d) <u>Residential activities</u> <p>Non-residential activities:</p> <ul style="list-style-type: none"> (a) <u>Home business ancillary to residential activities carried out on the site</u> (b) <u>Passive recreation</u> <p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <ul style="list-style-type: none"> a. <u>Compliance is achieved with all permitted activity rules and standards that apply to the General High Density Residential Zone.</u> <p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <ul style="list-style-type: none"> a. <u>Compliance is not achieved with one or more of the permitted activity standards that apply to the General High Density Residential Zone (excluding building height, height in relation to boundary, and building coverage). See the General Residential Zone for relevant rules, standards, matters, and information requirements.</u> <p>Restriction on notification:</p> <p><u>See the General Residential Zone provisions for specific restrictions on notification.</u></p>
	HRZ – High Density Residential Zone	New Rule	<p>HRZ-R2</p> <p><u>Buildings</u></p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. Compliance is achieved with:</p> <ul style="list-style-type: none"> i. HRZ-S1 - Setbacks ii. HRZ-S2 – Building height. iii. HRZ-S3 – Height in relation to boundary. iv. HRZ-S4 – Building coverage. v. HRZ-S5 – Number of Residential units per site. vi. HRZ-S6 – Outdoor living space (per residential unit). vii. HRZ-S8 – Outlook space (per residential unit). viii. HRZ-S9 – Windows to street. ix. HRZ-S10 – Landscaped Area
			<p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with one or more of the standards under HRZ-R2.1.a</p> <p>Council will restrict its discretion to, and may impose conditions on the matters of discretion of any infringed standard.</p> <p>Restriction on notification:</p> <ul style="list-style-type: none"> 1. Public notification of an application is precluded for an application that only fails to comply with standard 1.a.ii – Height in relation to boundary. 2. Public notification of an application is precluded for an application that only fails to comply with standard 1.a.iv. – Number of residential units per site.
	HRZ – High Density Residential Zone	New Rule from GRZ chapter	<p>HRZ-R3</p> <p>Marae</p> <p>All controlled activity rules, standards, matters, and information requirements in the General Residential Zone apply unless specifically stated in this table.</p>

Commented [MM164]: S58.170 - Kianga Ora: Homes and Communities. Consequential amendment.

Commented [MM165]: S58.153 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>1. Activity status: Controlled</p> <p>Council may impose conditions over the following matters:</p> <p>(1) Bulk, location, appearance and design of the buildings.</p> <p>(2) Design and layout of car parking, loading, manoeuvring and access areas.</p> <p>(3) Provision of and effects on utilities and/or services.</p> <p>(4) Landscaping, including the retention of existing trees. (5) Hours of operation.</p> <p>(5) Financial contributions.</p> <p>Controlled activities – restrictions on notification Subject to sections 95A(2)(b), 95A(2)(c), 95A(4) and 95C of the Act, a resource consent application for a controlled activity is precluded from public notification under section 95A and, subject to section 95B(3), is precluded from limited notification under section 95B(2) of the Act.</p>
	HRZ – High Density Residential Zone	New Rule	<p>HRZ-R4 All restricted discretionary activity rules, standards, matters, and information requirements in the General Residential Zone apply unless specifically stated in this table.</p>
	HRZ – High Density Residential Zone	New Rule from GRZ chapter.	<p>HRZ-R5 Home business ancillary to residential activities carried out on the site</p> <p>1. Activity status: Restricted Discretionary</p> <p>Where:</p> <p>a. the home business does not comply with one or more permitted activity standards.</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <p>(1) External storage.</p> <p>(2) The number of non-resident workers employed on the site.</p> <p>(3) The creation of dust, light, noise, vibration or other nuisance.</p> <p>(4) Appearance of buildings.</p> <p>(5) Size, number of location and appearance of signs.</p> <p>(6) Car parking, traffic and pedestrian safety and the efficient functioning of the roading network.</p> <p>(7) Financial contributions</p>

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
	HRZ – High Density Residential Zone New Rule from GRZ chapter	HRZ – High Density Residential Zone New Rule from GRZ chapter	<p>HRZ-R6 Early childhood centre(s)</p> <p>1. Activity status: Restricted Discretionary</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <ol style="list-style-type: none"> (1) Location of the proposed early childhood centre. (2) Bulk, location, appearance and design of the buildings. (3) The extent to which the proposal will adversely affect traffic and pedestrian safety, and the efficient functioning of the roading network. (4) Design and layout of car parking, loading, manoeuvring and access areas. (5) Provision of and utilities and/or services. (6) Landscaping, including the retention of existing trees. (7) Hours of operation. (8) Financial contributions. <p>Restriction on notification</p> <p>Subject to sections 95A(2)(b), 95A(2)(c), 95A(4) and 95C of the Act, a resource consent application for an early childhood centre will be precluded from public notification under section 95A, but limited notification of an application will be determined in accordance with section 95B.</p>
	HRZ – High Density Residential Zone	New Rule from GRZ chapter	<p>HRZ-R7 Buildings or structures within 12-20m of high voltage (110kV or greater) electricity transmission lines as shown on the Planning Maps *(refer to the definition of transmission line)</p> <p>1. Activity status: Restricted Discretionary</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <ol style="list-style-type: none"> (1) Compliance with the New Zealand Electrical Code of Practice for Electrical Safe Distances 2001 (NZECP 34:2001). (2) The location, height, scale, orientation and use of buildings and structures to ensure the following are addressed: <ol style="list-style-type: none"> a. The risk to the structural integrity of the transmission line. b. The effects on the ability of the transmission line owner to operate, maintain and upgrade the transmission network. c. The risk of electrical hazards affecting public or individual safety, and risk of property damage. d. The extent of earthworks required, and use of mobile machinery near the transmission line which may put the line at risk. e. Minimising the visual effects of the transmission line.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>f. The outcome of any consultation with the affected utility operator.</p> <p>Restriction on notification</p> <p>Subject to sections 95A(2)(b), 95A(2)(c), 95A(4) and 95C of the Act, a resource consent application under this rule will be precluded from public notification under section 95A, and limited notification will be served on Transpower New Zealand Limited as the only affected party under section 95B</p>
	HRZ – High Density Residential Zone	New Rule from GRZ chapter	<p>HRZ-R8 Activities listed as permitted or controlled which do not comply with the access standards in HRZ-S11.</p> <p>1. Activity status: Restricted Discretionary</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <p>(1) The extent to which the activity will adversely affect traffic and pedestrian safety.</p> <p>(2) The extent to which the activity will adversely affect the efficient functioning of the roading network.</p>
	HRZ – High Density Residential Zone	New Rule from GRZ chapter	<p>HRZ-R59 All discretionary activity rules in the General Residential Zone apply unless specifically stated in this table.</p> <p>Activities listed as permitted or controlled which do not comply with the relevant standards in this chapter, unless specifically provided for under other rules.</p> <p>Activity status: Discretionary</p>
	HRZ – High Density Residential Zone	New Rule from GRZ chapter	<p>HRZ-R10 Veterinarian, medical and health clinics.</p> <p>Activity status: Discretionary</p>
	HRZ – High Density Residential Zone	New Rule from GRZ chapter	<p>HRZ-R11 Places of assembly (including places of worship, educational facilities).</p> <p>Activity status: Discretionary</p>
	HRZ – High Density Residential Zone	New Rule from GRZ chapter	<p>HRZ-R12 Visitor accommodation including hotels and motels, other than as part of any home business.</p> <p>Activity status: Discretionary</p>

IPI - PROPOSED AMENDMENTS																	
#	Chapter	Change	Track Change														
	HRZ – High Density Residential Zone	New Rule from GRZ chapter	<table border="1"> <tr> <td>HRZ-R13</td> <td>Activities which are not listed in this Table unless otherwise covered in the District-wide matters of the Plan.</td> </tr> <tr> <td></td> <td>Activity status: Discretionary</td> </tr> </table>	HRZ-R13	Activities which are not listed in this Table unless otherwise covered in the District-wide matters of the Plan.		Activity status: Discretionary										
HRZ-R13	Activities which are not listed in this Table unless otherwise covered in the District-wide matters of the Plan.																
	Activity status: Discretionary																
	HRZ – High Density Residential Zone	New Rule from GRZ chapter.	<table border="1"> <tr> <td>HRZ-R614</td> <td>All non-complying rules in the General Residential Zone apply unless specifically stated in this table. Buildings or structures within 12m of high voltage (110kV or greater) electricity transmission lines as shown on the Planning Maps *(refer to the definition of transmission line)</td> </tr> </table>	HRZ-R614	All non-complying rules in the General Residential Zone apply unless specifically stated in this table. Buildings or structures within 12m of high voltage (110kV or greater) electricity transmission lines as shown on the Planning Maps *(refer to the definition of transmission line)												
HRZ-R614	All non-complying rules in the General Residential Zone apply unless specifically stated in this table. Buildings or structures within 12m of high voltage (110kV or greater) electricity transmission lines as shown on the Planning Maps *(refer to the definition of transmission line)																
	HRZ – High Density Residential Zone	New Rule	<table border="1"> <tr> <td>HRZ-R7</td> <td>All prohibited activity rules in the General Residential Zone apply unless specifically stated in this table.</td> </tr> </table>	HRZ-R7	All prohibited activity rules in the General Residential Zone apply unless specifically stated in this table.												
HRZ-R7	All prohibited activity rules in the General Residential Zone apply unless specifically stated in this table.																
	HRZ – High Density Residential Zone	New advice note from GRZ	<p>Advice note For any activity within the Stream/River Corridor, Overflow Path, Ponding Area or Erosion Hazard Area, applicants are advised to consult the Wellington Regional Council to determine if regional consent is also required.</p>														
	HRZ – High Density Residential Zone	New Standard	<table border="1"> <thead> <tr> <th colspan="2">Standards for Permitted Activities</th> <th>Matters of Discretion where Permitted Activity Standard(s) are not met</th> </tr> </thead> <tbody> <tr> <td>HRZ-S1</td> <td> <p>Setbacks The standards for permitted activities within the General Residential Zone apply except as specifically provided for in this table.</p> <p>(1) Buildings must be set back from the relevant boundary by the minimum depth listed in the yards table below:</p> <table border="1"> <thead> <tr> <th>Yard</th> <th>Minimum depth</th> </tr> </thead> <tbody> <tr> <td>Front</td> <td>1.5 metres</td> </tr> <tr> <td>Side</td> <td>1 metre</td> </tr> <tr> <td>Rear</td> <td>1 metre (excluding corner sites)</td> </tr> </tbody> </table> <p>(2) This standard does not apply to site boundaries where there is an existing</p> </td> <td> <p>The matters of discretion are restricted to: within the General Residential Zone apply except as specifically provided for in this table.</p> <ol style="list-style-type: none"> (1) The matters contained in the Medium and High Density Design Guide in Appendix 1. (2) Site layout and design. (3) Consideration of the effects of the standard not met. (4) Cumulative effects. (5) The matters contained in the Code of Practice for Civil Engineering Works. (6) The imposition of financial contributions. (7) Reverse sensitivity effects. </td> </tr> </tbody> </table>	Standards for Permitted Activities		Matters of Discretion where Permitted Activity Standard(s) are not met	HRZ-S1	<p>Setbacks The standards for permitted activities within the General Residential Zone apply except as specifically provided for in this table.</p> <p>(1) Buildings must be set back from the relevant boundary by the minimum depth listed in the yards table below:</p> <table border="1"> <thead> <tr> <th>Yard</th> <th>Minimum depth</th> </tr> </thead> <tbody> <tr> <td>Front</td> <td>1.5 metres</td> </tr> <tr> <td>Side</td> <td>1 metre</td> </tr> <tr> <td>Rear</td> <td>1 metre (excluding corner sites)</td> </tr> </tbody> </table> <p>(2) This standard does not apply to site boundaries where there is an existing</p>	Yard	Minimum depth	Front	1.5 metres	Side	1 metre	Rear	1 metre (excluding corner sites)	<p>The matters of discretion are restricted to: within the General Residential Zone apply except as specifically provided for in this table.</p> <ol style="list-style-type: none"> (1) The matters contained in the Medium and High Density Design Guide in Appendix 1. (2) Site layout and design. (3) Consideration of the effects of the standard not met. (4) Cumulative effects. (5) The matters contained in the Code of Practice for Civil Engineering Works. (6) The imposition of financial contributions. (7) Reverse sensitivity effects.
Standards for Permitted Activities		Matters of Discretion where Permitted Activity Standard(s) are not met															
HRZ-S1	<p>Setbacks The standards for permitted activities within the General Residential Zone apply except as specifically provided for in this table.</p> <p>(1) Buildings must be set back from the relevant boundary by the minimum depth listed in the yards table below:</p> <table border="1"> <thead> <tr> <th>Yard</th> <th>Minimum depth</th> </tr> </thead> <tbody> <tr> <td>Front</td> <td>1.5 metres</td> </tr> <tr> <td>Side</td> <td>1 metre</td> </tr> <tr> <td>Rear</td> <td>1 metre (excluding corner sites)</td> </tr> </tbody> </table> <p>(2) This standard does not apply to site boundaries where there is an existing</p>	Yard	Minimum depth	Front	1.5 metres	Side	1 metre	Rear	1 metre (excluding corner sites)	<p>The matters of discretion are restricted to: within the General Residential Zone apply except as specifically provided for in this table.</p> <ol style="list-style-type: none"> (1) The matters contained in the Medium and High Density Design Guide in Appendix 1. (2) Site layout and design. (3) Consideration of the effects of the standard not met. (4) Cumulative effects. (5) The matters contained in the Code of Practice for Civil Engineering Works. (6) The imposition of financial contributions. (7) Reverse sensitivity effects. 							
Yard	Minimum depth																
Front	1.5 metres																
Side	1 metre																
Rear	1 metre (excluding corner sites)																

IPI - PROPOSED AMENDMENTS				
#	Chapter	Change	Track Change	
				<p>common wall between 2 buildings on adjacent sites or where a common wall is proposed.</p> <p>[s80H(1)(a)(i) note: this standard incorporates the density standards in Part 2 of Schedule 3A]</p>
	HRZ – High Density Residential Zone	New Standard	<p>HRZ-S2</p> <p>Building height</p>	<p>Matters of Discretion where Permitted Activity Standard(s) are not met</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> (1) Height and sunlight access. (2) Effects on public spaces (3) Setbacks and coverage. (4) Landscaping and screening. (5) Privacy effects. (6) <u>The matters contained in the Medium and High Density Design Guide in Appendix 1.</u> (7) <u>Whether the building location, design, appearance, and scale is compatible in form and scale with the neighbourhood’s planned built character.</u> (8) Reverse sensitivity effects.
	HRZ – High Density Residential Zone	New Standard	<p>HRZ-S3</p> <p>Height in relation to boundary</p>	<p>Matters of Discretion where Permitted Activity Standard(s) are not met</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> (1) Height and sunlight access.

Commented [MM166]: S33.14 - Fuel Companies.

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			<p>access way, the height in relation to boundary applies from the farthest boundary of that legal right of way, entrance strip, access site, or pedestrian access way.</p> <p>(2) <u>This standard does not apply to—</u></p> <p>(a) <u>a boundary with a road:</u></p> <p>(b) <u>existing or proposed internal boundaries within a site:</u></p> <p>(c) <u>site boundaries where there is an existing common wall between 2 buildings on adjacent sites or where a common wall is <u>proposed</u>.</u></p> <p>(2) Setbacks.</p> <p>(3) Landscaping and screening.</p> <p>(4) Privacy effects.</p> <p>(5) The matters contained in the Medium and High Density Design Guide in Appendix 1.</p> <p>(6) Whether the building location, design, appearance, and scale is compatible in form and scale with the neighbourhood’s planned built character.</p> <p>(7) <u>Reverse sensitivity effects.</u></p>						
	HRZ – High Density Residential Zone	New Standard	<table border="1"> <thead> <tr> <th>HRZ-S4</th> <th>Building coverage</th> <th>Matters of Discretion where Permitted Activity Standard(s) are not met</th> </tr> </thead> <tbody> <tr> <td>1. The maximum building coverage on an allotment must not exceed 70% of the net site area.</td> <td></td> <td> Matters of discretion are restricted to: <p>(1) Height and sunlight access.</p> <p>(2) Setbacks and coverage.</p> <p>(3) Landscaping and screening.</p> <p>(4) Privacy effects.</p> <p>(5) The matters contained in the Medium and High Density Design Guide in Appendix 1.</p> <p>(6) Whether the building location, design, appearance, and scale is compatible in form and scale with the neighbourhood’s planned built character.</p> <p>(7) <u>Reverse sensitivity effects.</u></p> </td> </tr> </tbody> </table>	HRZ-S4	Building coverage	Matters of Discretion where Permitted Activity Standard(s) are not met	1. The maximum building coverage on an allotment must not exceed 70% of the net site area .		Matters of discretion are restricted to: <p>(1) Height and sunlight access.</p> <p>(2) Setbacks and coverage.</p> <p>(3) Landscaping and screening.</p> <p>(4) Privacy effects.</p> <p>(5) The matters contained in the Medium and High Density Design Guide in Appendix 1.</p> <p>(6) Whether the building location, design, appearance, and scale is compatible in form and scale with the neighbourhood’s planned built character.</p> <p>(7) <u>Reverse sensitivity effects.</u></p>
HRZ-S4	Building coverage	Matters of Discretion where Permitted Activity Standard(s) are not met							
1. The maximum building coverage on an allotment must not exceed 70% of the net site area .		Matters of discretion are restricted to: <p>(1) Height and sunlight access.</p> <p>(2) Setbacks and coverage.</p> <p>(3) Landscaping and screening.</p> <p>(4) Privacy effects.</p> <p>(5) The matters contained in the Medium and High Density Design Guide in Appendix 1.</p> <p>(6) Whether the building location, design, appearance, and scale is compatible in form and scale with the neighbourhood’s planned built character.</p> <p>(7) <u>Reverse sensitivity effects.</u></p>							

Commented [MM167]: S39.1 - Design Network Architecture Ltd.

Commented [MM168]: S33.15 - Fuel Companies.

Commented [MM169]: S33.16 - Fuel Companies.

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
	HRZ- High Density Residential Zone	New Standard	<table border="1"> <thead> <tr> <th>HRZ-S5</th> <th>Number of Residential units per site.</th> <th>Matters of Discretion where Permitted Activity Standard(s) are not met</th> </tr> </thead> <tbody> <tr> <td>1.</td> <td>There must be no more than 6 residential units per site.</td> <td> <p>Matters of discretion are restricted to:</p> <ul style="list-style-type: none"> (1) <u>Height and sunlight access.</u> (2) <u>Setbacks and coverage.</u> (3) <u>Landscaping and screening.</u> (4) <u>Privacy effects.</u> (5) <u>The matters contained in the Medium and High Density Design Guide in Appendix 1.</u> (6) <u>Whether the building location, design, appearance, and scale is compatible in form and scale with the neighbourhood's planned built character.</u> (7) <u>Reverse sensitivity effects.</u> (8) <u>Provision of and effects on utilities and services.</u> </td> </tr> </tbody> </table>	HRZ-S5	Number of Residential units per site.	Matters of Discretion where Permitted Activity Standard(s) are not met	1.	There must be no more than 6 residential units per site.	<p>Matters of discretion are restricted to:</p> <ul style="list-style-type: none"> (1) <u>Height and sunlight access.</u> (2) <u>Setbacks and coverage.</u> (3) <u>Landscaping and screening.</u> (4) <u>Privacy effects.</u> (5) <u>The matters contained in the Medium and High Density Design Guide in Appendix 1.</u> (6) <u>Whether the building location, design, appearance, and scale is compatible in form and scale with the neighbourhood's planned built character.</u> (7) <u>Reverse sensitivity effects.</u> (8) <u>Provision of and effects on utilities and services.</u>
HRZ-S5	Number of Residential units per site.	Matters of Discretion where Permitted Activity Standard(s) are not met							
1.	There must be no more than 6 residential units per site.	<p>Matters of discretion are restricted to:</p> <ul style="list-style-type: none"> (1) <u>Height and sunlight access.</u> (2) <u>Setbacks and coverage.</u> (3) <u>Landscaping and screening.</u> (4) <u>Privacy effects.</u> (5) <u>The matters contained in the Medium and High Density Design Guide in Appendix 1.</u> (6) <u>Whether the building location, design, appearance, and scale is compatible in form and scale with the neighbourhood's planned built character.</u> (7) <u>Reverse sensitivity effects.</u> (8) <u>Provision of and effects on utilities and services.</u> 							
	HRZ- High Density Residential Zone	New Standard from GRZ	<table border="1"> <thead> <tr> <th>HRZ-S6</th> <th>Outdoor living space (per residential unit)</th> <th>Matters of Discretion where Permitted Activity Standard(s) are not met</th> </tr> </thead> <tbody> <tr> <td></td> <td> <p><u>Outdoor living space (per residential unit)</u></p> <ul style="list-style-type: none"> (1) <u>A residential unit at ground floor level must have an outdoor living space that is at least 20 square metres and that comprises ground floor, balcony, patio, or roof terrace space that,—</u> <ul style="list-style-type: none"> (a) <u>where located at ground level, has no dimension less than 3 metres; and</u> </td> <td> <p>Matters of discretion are restricted to:</p> <ul style="list-style-type: none"> (1) <u>The matters contained in the Medium and High Density Design Guide in Appendix 1.</u> (2) <u>Site layout and design.</u> (3) <u>Consideration of the effects of the standard not met.</u> (4) <u>Cumulative effects.</u> </td> </tr> </tbody> </table>	HRZ-S6	Outdoor living space (per residential unit)	Matters of Discretion where Permitted Activity Standard(s) are not met		<p><u>Outdoor living space (per residential unit)</u></p> <ul style="list-style-type: none"> (1) <u>A residential unit at ground floor level must have an outdoor living space that is at least 20 square metres and that comprises ground floor, balcony, patio, or roof terrace space that,—</u> <ul style="list-style-type: none"> (a) <u>where located at ground level, has no dimension less than 3 metres; and</u> 	<p>Matters of discretion are restricted to:</p> <ul style="list-style-type: none"> (1) <u>The matters contained in the Medium and High Density Design Guide in Appendix 1.</u> (2) <u>Site layout and design.</u> (3) <u>Consideration of the effects of the standard not met.</u> (4) <u>Cumulative effects.</u>
HRZ-S6	Outdoor living space (per residential unit)	Matters of Discretion where Permitted Activity Standard(s) are not met							
	<p><u>Outdoor living space (per residential unit)</u></p> <ul style="list-style-type: none"> (1) <u>A residential unit at ground floor level must have an outdoor living space that is at least 20 square metres and that comprises ground floor, balcony, patio, or roof terrace space that,—</u> <ul style="list-style-type: none"> (a) <u>where located at ground level, has no dimension less than 3 metres; and</u> 	<p>Matters of discretion are restricted to:</p> <ul style="list-style-type: none"> (1) <u>The matters contained in the Medium and High Density Design Guide in Appendix 1.</u> (2) <u>Site layout and design.</u> (3) <u>Consideration of the effects of the standard not met.</u> (4) <u>Cumulative effects.</u> 							

Commented [MM170]: S33.17 - Fuel Companies.

Commented [MM171]: S58.168 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS				
#	Chapter	Change	Track Change	
			<p>(b) <u>where provided in the form of a balcony, patio, or roof terrace, is at least 8 square metres and has a minimum dimension of 1.8 metres; and</u></p> <p>(c) <u>is accessible from the residential unit; and</u></p> <p>(d) <u>may be—</u></p> <p style="padding-left: 20px;">i. <u>grouped cumulatively by area in 1 communally accessible location; or</u></p> <p style="padding-left: 20px;">ii. <u>located directly adjacent to the unit; and</u></p> <p>(e) <u>is free of buildings, parking spaces, and servicing and manoeuvring areas.</u></p> <p>(2) <u>A residential unit located above ground floor level must have an outdoor living space in the form of a balcony, patio, or roof terrace that—</u></p> <p style="padding-left: 20px;">(a) <u>is at least 8 square metres and has a minimum dimension of 1.8 metres; and</u></p> <p style="padding-left: 20px;">(b) <u>is accessible from the residential unit; and</u></p> <p style="padding-left: 20px;">(c) <u>may be—</u></p> <p style="padding-left: 40px;">i. <u>grouped cumulatively by area in 1 communally accessible location, in which case it may be located at ground level; or</u></p> <p style="padding-left: 40px;">ii. <u>located directly adjacent to the unit.</u></p> <p><u>[s80H(1)(a)(i) note: this standard incorporates the density standards in Part 2 of Schedule 3A]</u></p>	
	HRZ- High Density Residential Zone	New Standard from GRZ	<u>HRZ-S7</u>	<p><u>Hydraulic neutrality</u></p> <p><u>Matters of Discretion where Permitted Activity Standard(s) are not met</u></p>


IPI - PROPOSED AMENDMENTS								
#	Chapter	Change	Track Change					
			<p>New buildings and development must be designed to achieve hydraulic neutrality.</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> Methods to avoid, remedy or mitigate any adverse effects resulting from any increase in pre-development peak stormwater runoff. Cumulative effects. 					
	HRZ- High Density Residential Zone	New Standard from GRZ	<table border="1"> <thead> <tr> <th>HRZ-S8</th> <th>Outlook space (per residential unit)</th> <th>Matters of Discretion where Permitted Activity Standard(s) are not met</th> </tr> </thead> <tbody> <tr> <td> <p>(1) An outlook space must be provided for each residential unit as specified in this clause.</p> <p>(2) An outlook space must be provided from habitable room windows as shown in the diagram below:</p> <div data-bbox="566 790 1084 1177" data-label="Diagram"> </div> <p>(3) The minimum dimensions for a required outlook space are as follows:</p> </td> <td> <p>Matters of Discretion where Permitted Activity Standard(s) are not met</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The matters contained in the Medium and High Density Design Guide in Appendix 1. Site layout and design. Consideration of the effects of the standard not met. Cumulative effects. The matters contained in the Code of Practice for Civil Engineering Works. The imposition of financial contributions. Reverse sensitivity effects. </td> </tr> </tbody> </table>	HRZ-S8	Outlook space (per residential unit)	Matters of Discretion where Permitted Activity Standard(s) are not met	<p>(1) An outlook space must be provided for each residential unit as specified in this clause.</p> <p>(2) An outlook space must be provided from habitable room windows as shown in the diagram below:</p> <div data-bbox="566 790 1084 1177" data-label="Diagram"> </div> <p>(3) The minimum dimensions for a required outlook space are as follows:</p>	<p>Matters of Discretion where Permitted Activity Standard(s) are not met</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The matters contained in the Medium and High Density Design Guide in Appendix 1. Site layout and design. Consideration of the effects of the standard not met. Cumulative effects. The matters contained in the Code of Practice for Civil Engineering Works. The imposition of financial contributions. Reverse sensitivity effects.
HRZ-S8	Outlook space (per residential unit)	Matters of Discretion where Permitted Activity Standard(s) are not met						
<p>(1) An outlook space must be provided for each residential unit as specified in this clause.</p> <p>(2) An outlook space must be provided from habitable room windows as shown in the diagram below:</p> <div data-bbox="566 790 1084 1177" data-label="Diagram"> </div> <p>(3) The minimum dimensions for a required outlook space are as follows:</p>	<p>Matters of Discretion where Permitted Activity Standard(s) are not met</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The matters contained in the Medium and High Density Design Guide in Appendix 1. Site layout and design. Consideration of the effects of the standard not met. Cumulative effects. The matters contained in the Code of Practice for Civil Engineering Works. The imposition of financial contributions. Reverse sensitivity effects. 							

IPI - PROPOSED AMENDMENTS						
#	Chapter	Change	Track Change			
			<p><u>i. a principal living room must have an outlook space with a minimum dimension of 4 metres in depth and 4 metres in width; and</u></p> <p><u>ii. all other habitable rooms must have an outlook space with a minimum dimension of 1 metre in depth and 1 metre in width.</u></p> <p><u>(4) The width of the outlook space is measured from the centre point of the largest window on the building face to which it applies.</u></p> <p><u>(5) Outlook spaces may be over driveways and footpaths within the site or over a public street or other public open space.</u></p> <p><u>(6) Outlook spaces may overlap where they are on the same wall plane in the case of a multi-storey building.</u></p> <p><u>(7) Outlook spaces may be under or over a balcony.</u></p> <p><u>(8) Outlook spaces required from different rooms within the same building may overlap.</u></p> <p><u>(9) Outlook spaces must—</u></p> <p><u>i. be clear and unobstructed by buildings; and</u></p> <p><u>ii. not extend over an outlook space or outdoor living space required by another dwelling.</u></p> <p><u>[s80H(1)(a)(i) note: this provision incorporates the density standards in Part 2 of Schedule 3A]</u></p>			
	HRZ- High Density Residential Zone	New Standard from GRZ	<table border="1"> <tr> <td><u>HRZ-S9</u></td> <td><u>Windows to street</u></td> <td><u>Matters of Discretion where Permitted Activity Standard(s) are not met</u></td> </tr> </table>	<u>HRZ-S9</u>	<u>Windows to street</u>	<u>Matters of Discretion where Permitted Activity Standard(s) are not met</u>
<u>HRZ-S9</u>	<u>Windows to street</u>	<u>Matters of Discretion where Permitted Activity Standard(s) are not met</u>				

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			<p>Any residential unit facing the street must have a minimum of 20% of the street-facing façade in glazing. This can be in the form of windows or doors.</p> <p>[s80H(1)(a)(i) note: this provision incorporates the density standards in Part 2 of Schedule 3A]</p>						
			<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> (1) The matters contained in the Medium and High Density Design Guide in Appendix 1. (2) Site layout and design. (3) Consideration of the effects of the standard not met. (4) Cumulative effects. (5) The matters contained in the Code of Practice for Civil Engineering Works. (6) The imposition of financial contributions. (7) Reverse sensitivity effects. 						
	HRZ- High Density Residential Zone	New Standard from GRZ	<table border="1"> <thead> <tr> <th>HRZ-S10</th> <th>Landscaped area</th> <th>Matters of Discretion where Permitted Activity Standard(s) are not met</th> </tr> </thead> <tbody> <tr> <td> <ol style="list-style-type: none"> (1) A residential unit at ground floor level must have a landscaped area of a minimum of 20% of a developed site with grass or plants, and can include the canopy of trees regardless of the ground treatment below them. (2) The landscaped area may be located on any part of the development site, and does not need to be associated with each residential unit. <p>[s80H(1)(a)(i) note: this provision incorporates the density standards in Part 2 of Schedule 3A]</p> </td> <td></td> <td> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> (1) The matters contained in the Medium and High Density Design Guide in Appendix 1. (2) Site layout and design. (3) Consideration of the effects of the standard not met. (4) Cumulative effects. (5) The matters contained in the Code of Practice for Civil Engineering Works. (6) The imposition of financial contributions. (7) Reverse sensitivity effects. </td> </tr> </tbody> </table>	HRZ-S10	Landscaped area	Matters of Discretion where Permitted Activity Standard(s) are not met	<ol style="list-style-type: none"> (1) A residential unit at ground floor level must have a landscaped area of a minimum of 20% of a developed site with grass or plants, and can include the canopy of trees regardless of the ground treatment below them. (2) The landscaped area may be located on any part of the development site, and does not need to be associated with each residential unit. <p>[s80H(1)(a)(i) note: this provision incorporates the density standards in Part 2 of Schedule 3A]</p>		<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> (1) The matters contained in the Medium and High Density Design Guide in Appendix 1. (2) Site layout and design. (3) Consideration of the effects of the standard not met. (4) Cumulative effects. (5) The matters contained in the Code of Practice for Civil Engineering Works. (6) The imposition of financial contributions. (7) Reverse sensitivity effects.
HRZ-S10	Landscaped area	Matters of Discretion where Permitted Activity Standard(s) are not met							
<ol style="list-style-type: none"> (1) A residential unit at ground floor level must have a landscaped area of a minimum of 20% of a developed site with grass or plants, and can include the canopy of trees regardless of the ground treatment below them. (2) The landscaped area may be located on any part of the development site, and does not need to be associated with each residential unit. <p>[s80H(1)(a)(i) note: this provision incorporates the density standards in Part 2 of Schedule 3A]</p>		<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> (1) The matters contained in the Medium and High Density Design Guide in Appendix 1. (2) Site layout and design. (3) Consideration of the effects of the standard not met. (4) Cumulative effects. (5) The matters contained in the Code of Practice for Civil Engineering Works. (6) The imposition of financial contributions. (7) Reverse sensitivity effects. 							

IPI - PROPOSED AMENDMENTS				
#	Chapter	Change	Track Change	
	HRZ- High Density Residential Zone	New Standard from GRZ	HRZ-S11	<p>Access standards for land use activities</p> <p>Matters of Discretion where Permitted Activity Standard(s) are not met</p>
			<p>1. Where vehicle access points are shared by three or more residential units, for all rear allotments and for all sites fronting arterial, or distributor/collector streets (identified in the Transport and Parking (TP) Chapter) there must be provision for turning a vehicle on site in order that vehicles do not reverse into the street.</p> <p>2. All accessways and manoeuvring areas shall be formed and surfaced in accordance with the Code of Practice for Civil Engineering Works. The required surfacing must be completed prior to certification of the survey plan. Exemption – the requirement for accessways serving sites solely occupied by unstaffed utilities shall be that the accessway shall be surfaced with permanent all weather surfacing for a minimum length of 5m from the edge of the road carriageway seal.</p> <p>3. Sites shall have practical vehicle access to car parking and loading spaces, in accordance with the Code of Practice for Civil Engineering Works. This requirement does not apply to sites solely occupied by unstaffed utilities, provided that vehicles associated with utilities shall not obstruct the footpath or create a traffic hazard on the road.</p> <p>4. Vehicular access to a corner allotment shall be located no closer than 8m from the street corner. Where a site is located on an intersection of a primary or secondary arterial traffic route (identified in the Transport and Parking (TP) Chapter) the siting of the vehicular access shall be located as far as practicable from the corner of the street. The 8 metre setback shall be measured from where the two front boundaries of the site (refer to the definition of a corner allotment) join, or in accordance with the diagram below.</p>	

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change		
			 <p data-bbox="548 742 1108 1173"> 5. Where a corner allotment is located at an intersection of a national, primary or secondary arterial traffic route, as identified in the Transport and Parking (TP) Chapter, no building, fence or other structure is to be erected and no vegetation allowed to grow so as to obstruct a traffic sight line. 6. At the intersection of a road or rail level crossing, no building, fence or other obstructions which block sight lines for trains shall be erected, placed or grown in the hatched area marked in TP-Diagram 1 in the Transport and Parking (TP) Chapter. 7. Land use activities with direct access to a State Highway shall comply with the access and visibility standards set out in TP-Diagrams 2 to 9 in the Transport and Parking (TP) Chapter </p>		
	HRZ- High Density Residential Zone	New Standard from GRZ	HRZ-S12	Water supply, stormwater and wastewater	Matters of Discretion where Permitted Activity Standard(s) are not met

IPI - PROPOSED AMENDMENTS				
#	Chapter	Change	Track Change	
			(1) <u>All activities shall comply with the water supply, stormwater and wastewater standards in the Code of Practice for Civil Engineering Works.</u> N/A	
	HRZ- High Density Residential Zone	New Standard from GRZ	<u>HRZ-S13</u>	<u>Screening</u>
			<u>Matters of Discretion where Permitted Activity Standard(s) are not met</u>	
			(1) <u>Outdoor storage areas shall be screened by a close-boarded fence, a solid wall or dense planting of vegetation. The screening shall:</u> N/A	
			(a) <u>be no less than 1.8m in height</u>	
	HRZ- High Density Residential Zone	New Standard from GRZ	<u>HRZ-S14</u>	<u>Home business ancillary to residential activities carried out on the site</u>
			<u>Matters of Discretion where Permitted Activity Standard(s) are not met</u>	
			<ol style="list-style-type: none"> <u>1. At least one of the persons engaged in the home business shall live on the site as their principal place of residence.</u> <u>2. No more than three non-resident persons may be engaged in the home business at any one time.</u> <u>3. The repair or maintenance of vehicles or engines, other than those belonging to the residents, is not permitted.</u> <u>4. The site shall not be used as a depot for any heavy vehicle associated with a trade.</u> <u>5. Only goods produced or grown on the site may be sold from the site, provided that no retailing activity shall take place where access is to the State Highway.</u> <u>6. Homestay activities, where accommodation and meals are provided in a family type environment, are permitted provided the total number of persons accommodated on the site at any one time, including persons normally resident on the site, does not exceed twelve.</u> <u>7. Equipment used shall not interfere with radio and television reception.</u> 	

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	HRZ – High Density Residential Zone	Insert New Restricted Discretionary Rule	<p>HRZ-R8 Buildings within the High Density Residential Zone that exceed 20 metres in height.</p> <p>Matters of discretion are restricted to:</p> <p>(1) Height and sunlight access.</p> <p>(2) Effects on public spaces.</p> <p>(3) Setbacks and coverage.</p> <p>(4) Landscaping and screening.</p> <p>(5) Privacy effects.</p> <p>(6) The matters contained in the Medium and High Density Design Guide in Appendix 1.</p> <p>(107) Whether the building location, design, appearance, and scale is compatible in form and scale with the neighbourhood's planned built character.</p>
Precinct 2 – St Patrick's Estate Precinct			
	HRZ – High Density Residential Zone	Insert Precinct description	<p>Precinct 2 – St Patrick's Estate Precinct</p> <p>The St Patrick's Estate Precinct comprises approximately 45 hectares of undeveloped land bordering the Hutt River, and forms part of the flood plain. The St Patrick's Estate Precinct is within the walkable catchment of Silverstream Railway Station, and is located in proximity to State Highway 2. The Precinct provides a significant development opportunity within Upper Hutt, and therefore high density residential development and compatible non-residential activities are anticipated. as such high density residential development is provided for within the Precinct.</p> <p>Development within the Precinct needs to address potential transportation safety effects on the road network including the state highway.</p> <p>The Precinct sits near the Southern gateway to the City and therefore subdivision and development of the Precinct provides an opportunity for to enhance the entrance to the City via landscaping along Fergusson Drive, and to ensure key active transport connections between the Hutt River and Silverstream Town Centre and rail station are provided.</p>

Commented [MM172]: S58.170 - Kianga Ora: Homes and Communities - deletion of HRZ-R8.

Commented [MM173]: S62.4 - Silverstream Land Holdings Limited

Commented [MM174]: S62.4 - Silverstream Land Holdings Limited; or clause 99, part 6 of Schedule 1 RMA.

Commented [MM175]: S62.4 - Silverstream Land Holdings Limited; or clause 99, part 6 of Schedule 1 RMA.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			The following objectives, policies and rules apply within the St Patrick's Estate Precinct in addition to the provisions of the underlying High Density Residential Zone . Where there is any conflict between the provisions the St Patrick's Estate Precinct provisions shall prevail.
	HRZ - High Density Residential Zone	Insert Precinct Objective	<p>Objectives</p> <p>All objectives of the High Density Residential Zone apply.</p> <p>HRZ-PREC2-O1</p> <p>Development of the St Patrick's Estate Precinct will provide a mix of high density residential and compatible non-residential activities which avoids, or remedies reverse sensitivity effects, and adverse effects on services and the transportation network.</p>
	HRZ - High Density Residential Zone	Insert Precinct Policy	<p>Policies</p> <p>In addition to HRZ-PREC2-P1 and P2 below, all policies of the High Density Residential Zone apply.</p> <p>HRZ-PREC2-P1</p> <p>Provide for medium and high density residential subdivision, use and development, and a mix of compatible non-residential activities within the St Patrick's Estate Precinct that:</p> <ul style="list-style-type: none"> (i) avoids significant adverse effects arising from potential inundation from the Hutt River and the Mawaihakona Stream; and (ii) provides pedestrian linkages to the Hutt River walkway and Silverstream Railway Station. (iii) enhances the southern entrance to the City via landscaping along the frontage of the site with Fergusson Drive (iv) Avoids or remedies adverse effects on the transportation network. (iv) Avoids potential reverse sensitivity effects.
	HRZ - High Density Residential Zone	Insert Precinct Rule	<p>Rules</p> <p>HRZ-PREC2-R1</p> <p>All permitted activity rules and standards in the High Density Residential Zone apply unless specifically provided for in this table.</p>
	HRZ - High Density Residential Zone	Insert Precinct Rule	<p>HRZ-PREC2-R2</p> <p>All controlled activity rules, standards, and matters of control in the High Density Residential Zone apply unless specifically provided for in this table.</p>
	HRZ - High Density Residential Zone	Insert Precinct Rule	<p>HRZ-PREC2-R3</p> <p>All restricted activity rules, standards, matters of discretion, and information requirements in the High Density Residential Zone apply unless specifically provided for in this table.</p>

Commented [MM176]: S62.6 - Silverstream Land Holdings Limited; or clause 99, part 6 Schedule 1 RMA.

Commented [MM177]: In part - S62.4 Silverstream Land Holdings Limited; or Clause 99, part 6 Schedule 1 RMA.

Commented [MM178]: Clause 99, part 6 Schedule 1 RMA.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	HRZ – High Density Residential Zone	Insert Precinct Rule	HRZ-PREC2-R5 All discretionary activity rules in the High Density Residential Zone apply unless specifically stated in this table.
	HRZ – High Density Residential Zone	Insert Precinct Rule	HRZ-PREC2-R6 All non-complying rules in the High Density Residential Zone apply unless specifically stated in this table.
	HRZ – High Density Residential Zone	Insert Precinct Rule	HRZ-PREC2-R7 All prohibited activity rules in the High Density Residential Zone apply unless specifically stated in this table.
RURAL ZONES			
GRUZ – General Rural Zone			
	GRUZ – General Rural Zone	Amend Standard	<p>Standards for Permitted and Controlled Activities</p> <p>GRUZ-S4 Sunlight Access</p> <p><i>Policies</i> GRZ-P4, GRUZ-P10, GRUZ-P11</p> <p>(1) Height control planes apply to all buildings:</p> <p>(a) Adjacent to a General Residential or High Density Residential Zone.</p> <p>(b) On sites smaller than 1500m² in a General Rural Zone.</p> <p>(2) Buildings shall be designed so ...</p> <p>...</p>
RLZ – Rural Lifestyle Zone			
	RLZ – General Rural Zone	Amend Standard	<p>Standards for Permitted and Controlled Activities</p> <p>RLZ-S4 Sunlight Access</p> <p><i>Policies</i> GRZ-P4, RLZ-P7, RLZ-P8</p> <p>(1) Height control planes apply to all buildings:</p> <p>(a) Adjacent to a General Residential or High Density Residential Zone.</p> <p>(b) On sites smaller than 1500m² in a Rural Lifestyle Zone.</p> <p>(2) Buildings shall be designed so ...</p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change

COMMERCIAL AND MIXED USE ZONES

COMZ – Commercial Zone

	COMZ— Commercial Zone	Delete existing Commercial Zone Chapter	<p>COMZ—Commercial Zone</p> <p>Background</p> <p>Businesses within the City are located in the Central Business District (CBD), commercial and industrial areas, and suburban areas. Some parts of the business areas include hotels, tourist facilities and other activities.</p> <p>Historically, the location of industry in Upper Hutt has been influenced by two factors, land availability in southern and eastern Upper Hutt and the close proximity of transportation links.</p> <p>Resource Management Issues</p> <p>COMZ-11— Adverse effects on amenity values and environmental quality resulting from commercial activities.</p> <p>Commercial activities in general, while vital to the well-being of the community, may have a range of adverse effects on the surrounding environment, including residential areas. These effects need to be identified and managed to ensure that amenity values are not diminished. The adverse environmental effects which commercial activities may have can include increases in traffic density, noise and odour, a decrease in sunlight, and loss of privacy and visual amenity.</p> <p>COMZ-12— The adverse effects of commercial activities on the existing infrastructure and resources of the commercial areas.</p> <p>Activities in commercial areas can result in effects on the infrastructure and resources which have established there.</p> <p>The efficient use of the existing infrastructure and resources of the commercial areas, including new development, is considered to be an important resource management matter.</p> <p>COMZ-13— Providing for a range of commercial activities which are readily accessible.</p> <p>The variety of activities which exist in the commercial areas contributes to the vitality and convenience of the City. A number of distinct commercial areas are found in the City. Suburban centres provide for a more limited range of shopping and business needs. Local shops and dairies provide day to day convenience shopping.</p> <p>COMZ-14— The continued maintenance of an appropriate level of environmental quality within commercial areas.</p>
--	--------------------------	---	---

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>Commercial activities can generate traffic, smoke, noise, vibration, glare or other nuisances that can adversely affect other nearby activities. They also can have potential adverse effects on the natural environment, such as waterbodies and indigenous bush areas.</p> <p>Some commercial areas within the City are characterised by pedestrian orientated activities and amenities. It is therefore important to recognise the particular elements which affect the amenity values of an area.</p> <p>Objectives</p> <p>COMZ-O1 <i>The sustainable management of physical resources within the existing commercial areas of the City to protect and enhance their amenity values.</i></p> <p>This objective recognises the importance of particular elements and characteristics that define the commercial areas. Commercial activities and development can have both positive and adverse environmental effects on the areas that surround them. Any consideration of effects must take account of the need to provide sufficient areas for commercial development needs, and the maintenance of amenity values and character.</p> <p>The commercial areas within the City are divided into two specific zones to reflect the Plan's policies:</p> <p>(a) The Commercial Zone focuses on retail and service functions which support the local community. Commercial activities are provided for at Silverstream and other suburban areas. These areas provide for a limited range of shopping and business needs. The smaller neighbourhood shops, including dairies, provide for day to day convenience shopping.</p> <p>(b) The City Centre Zone (CBD) accommodates a variety of activities in a compact, convenient layout which is characterised by pedestrian orientated traffic.</p> <p>COMZ-O2 <i>The avoidance, remedying, or mitigation of the adverse effects of commercial activities on the amenity of surrounding neighbourhoods.</i></p> <p>The effects generated by the wide range of activities provided for in the Commercial Zone, such as smoke, noise, vibration, glare or other nuisances, can have adverse effects on areas beyond the Commercial Zone boundaries.</p> <p>Policies</p> <p>COMZ-P1 <i>To ensure that activities in the Commercial Zone do not unduly detract from the character and amenity of neighbouring areas.</i></p> <p>This policy recognises the potential for business activities to impact adversely on adjoining areas and consequently aims to preserve the amenity values of areas adjacent to the Commercial Zone.</p>

IPI - PROPOSED AMENDMENTS										
#	Chapter	Change	Track Change							
			<p>COMZ P2 – To control the size and scale of buildings and the visual appearance of sites within the Commercial Zone.</p> <p>This policy aims to preserve amenity values within the Commercial Zone. Buildings and sites need to be attractive and be of a size or type that is compatible with the neighbourhood.</p> <p>COMZ P3 – To identify and maintain amenity values that the community wishes to protect.</p> <p>Amenity values are those features or aspects about an area which enhance it or make it pleasant to be in. They can include access to sunlight, landscaping and visual qualities. They may also include important public features, such as parks and reserves. Activities which can adversely affect the amenities of an area must be managed, while also recognising the rights of individuals to use their own properties and the need for utilities to operate effectively and safely.</p> <p>A particular concern of the Upper Hutt community relates to the effects of the establishment and use of what are commonly referred to as gang fortifications. These are sometimes accompanied by an increase in antisocial behaviour.</p> <p>It is Council's view that the adverse effects of these fortifications on the environment, in particular in respect of the social, economic, aesthetic and cultural conditions of the Upper Hutt people and community, and the amenity values of the Upper Hutt environment, are such that these activities should not be permitted. The activity is therefore prohibited anywhere in Upper Hutt City.</p> <p>Rules</p> <p>District-wide matters</p> <p>Each activity in the Commercial Zone shall comply with the relevant permitted activity standards in the District-wide matters of the Plan as listed below.</p> <table border="1"> <thead> <tr> <th>District-wide matters</th> </tr> </thead> <tbody> <tr> <td>TEMP – Temporary Activities</td> </tr> <tr> <td>SIGN – Signs</td> </tr> <tr> <td>EW – Earthworks</td> </tr> <tr> <td>NATC – Natural Character</td> </tr> <tr> <td>DC – Development Contributions</td> </tr> <tr> <td>HH – Historical Heritage</td> </tr> </tbody> </table>	District-wide matters	TEMP – Temporary Activities	SIGN – Signs	EW – Earthworks	NATC – Natural Character	DC – Development Contributions	HH – Historical Heritage
District-wide matters										
TEMP – Temporary Activities										
SIGN – Signs										
EW – Earthworks										
NATC – Natural Character										
DC – Development Contributions										
HH – Historical Heritage										


IPI - PROPOSED AMENDMENTS																										
#	Chapter	Change	Track Change																							
			<table border="1"> <tr><td>TREE – Notable Trees</td></tr> <tr><td>UTG – Urban Tree Groups</td></tr> <tr><td>ECO – Ecosystems and Indigenous Biodiversity</td></tr> <tr><td>NFL – Natural Features and Landscapes</td></tr> <tr><td>PA – Public Access</td></tr> <tr><td>ASW – Activities on the Surface of Water</td></tr> <tr><td>NU – Network Utilities</td></tr> <tr><td>REG – Renewable Energy Generation</td></tr> <tr><td>TP – Transport and Parking</td></tr> <tr><td>NOISE – Noise</td></tr> <tr><td>NH – Natural Hazards</td></tr> <tr><td>CL – Contaminated Land</td></tr> <tr><td>HS – Hazardous Substances</td></tr> <tr><td>WM – Waste Management</td></tr> <tr><td>SUB – Subdivision</td></tr> <tr><td>AIR – Air</td></tr> <tr><td>LIGHT – Light</td></tr> </table> <p>Activities Tables</p> <p><i>Policies NU-P4, CCZ-P1, GIZ-P1</i></p> <table border="1"> <thead> <tr> <th colspan="3">Permitted Activities</th> </tr> </thead> <tbody> <tr> <td>COMZ-R1</td> <td>All activities other than those identified below are permitted provided they meet the standards specified in the Plan for permitted activities</td> <td>PER</td> </tr> </tbody> </table>	TREE – Notable Trees	UTG – Urban Tree Groups	ECO – Ecosystems and Indigenous Biodiversity	NFL – Natural Features and Landscapes	PA – Public Access	ASW – Activities on the Surface of Water	NU – Network Utilities	REG – Renewable Energy Generation	TP – Transport and Parking	NOISE – Noise	NH – Natural Hazards	CL – Contaminated Land	HS – Hazardous Substances	WM – Waste Management	SUB – Subdivision	AIR – Air	LIGHT – Light	Permitted Activities			COMZ-R1	All activities other than those identified below are permitted provided they meet the standards specified in the Plan for permitted activities	PER
TREE – Notable Trees																										
UTG – Urban Tree Groups																										
ECO – Ecosystems and Indigenous Biodiversity																										
NFL – Natural Features and Landscapes																										
PA – Public Access																										
ASW – Activities on the Surface of Water																										
NU – Network Utilities																										
REG – Renewable Energy Generation																										
TP – Transport and Parking																										
NOISE – Noise																										
NH – Natural Hazards																										
CL – Contaminated Land																										
HS – Hazardous Substances																										
WM – Waste Management																										
SUB – Subdivision																										
AIR – Air																										
LIGHT – Light																										
Permitted Activities																										
COMZ-R1	All activities other than those identified below are permitted provided they meet the standards specified in the Plan for permitted activities	PER																								

IPI - PROPOSED AMENDMENTS																														
#	Chapter	Change	Track Change																											
			<table border="1"> <tr> <td>COMZ R2</td> <td>Any retail activity unless otherwise provided for below</td> <td>PER</td> </tr> <tr> <td>COMZ R3</td> <td>The following retail activities: (1) The sale and maintenance of heavy machinery; (2) Garden centres; (3) Building improvement centres; (4) Yard-oriented retail activities; (5) The sale of goods manufactured on the site, provided that the retail component is ancillary to the manufacturing activity; (6) The sale of kit set buildings and framing.</td> <td>PER</td> </tr> <tr> <td>COMZ R4</td> <td>Retail activity, restaurants, offices, early childhood centres, and residential accommodation (including at ground level) on land identified in COMZ Figure 1</td> <td>PER</td> </tr> <tr> <td>COMZ R5</td> <td>Visitor accommodation</td> <td>PER</td> </tr> <tr> <td>COMZ R6</td> <td>Residential accommodation for a caretaker, where the caretaker is required to live on the site</td> <td>PER</td> </tr> <tr> <td>COMZ R7</td> <td>Residential accommodation not otherwise provided below</td> <td>PER</td> </tr> <tr> <td>COMZ R8</td> <td>Minor Structures</td> <td>PER</td> </tr> <tr> <td colspan="3">Controlled Activities</td> </tr> <tr> <td>COMZ R9 <i>Policies</i> COMZ P1, COMZ P2</td> <td>Churches Council may impose conditions on: (1) Avoiding, remedying or mitigating adverse effects on the business function of the area. (2) Location and nature of activities within the site. (3) Traffic generation, car parking, access arrangements and on-site vehicle movements. (4) Bulk, location, design and appearance of buildings.</td> <td>CON</td> </tr> </table>	COMZ R2	Any retail activity unless otherwise provided for below	PER	COMZ R3	The following retail activities : (1) The sale and maintenance of heavy machinery; (2) Garden centres; (3) Building improvement centres; (4) Yard-oriented retail activities ; (5) The sale of goods manufactured on the site , provided that the retail component is ancillary to the manufacturing activity ; (6) The sale of kit set buildings and framing.	PER	COMZ R4	Retail activity, restaurants, offices, early childhood centres, and residential accommodation (including at ground level) on land identified in COMZ Figure 1	PER	COMZ R5	Visitor accommodation	PER	COMZ R6	Residential accommodation for a caretaker, where the caretaker is required to live on the site	PER	COMZ R7	Residential accommodation not otherwise provided below	PER	COMZ R8	Minor Structures	PER	Controlled Activities			COMZ R9 <i>Policies</i> COMZ P1, COMZ P2	Churches Council may impose conditions on: (1) Avoiding, remedying or mitigating adverse effects on the business function of the area. (2) Location and nature of activities within the site . (3) Traffic generation, car parking, access arrangements and on-site vehicle movements . (4) Bulk, location, design and appearance of buildings .	CON
COMZ R2	Any retail activity unless otherwise provided for below	PER																												
COMZ R3	The following retail activities : (1) The sale and maintenance of heavy machinery; (2) Garden centres; (3) Building improvement centres; (4) Yard-oriented retail activities ; (5) The sale of goods manufactured on the site , provided that the retail component is ancillary to the manufacturing activity ; (6) The sale of kit set buildings and framing.	PER																												
COMZ R4	Retail activity, restaurants, offices, early childhood centres, and residential accommodation (including at ground level) on land identified in COMZ Figure 1	PER																												
COMZ R5	Visitor accommodation	PER																												
COMZ R6	Residential accommodation for a caretaker, where the caretaker is required to live on the site	PER																												
COMZ R7	Residential accommodation not otherwise provided below	PER																												
COMZ R8	Minor Structures	PER																												
Controlled Activities																														
COMZ R9 <i>Policies</i> COMZ P1, COMZ P2	Churches Council may impose conditions on: (1) Avoiding, remedying or mitigating adverse effects on the business function of the area. (2) Location and nature of activities within the site . (3) Traffic generation, car parking, access arrangements and on-site vehicle movements . (4) Bulk, location, design and appearance of buildings .	CON																												

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(5) Hours of operation.</p> <p>(6) Landscaping and screening.</p> <p>(7) Noise.</p> <p>(8) Lighting.</p> <p>(9) Signage.</p> <p>(10) Provision of and effects on utilities and/or services.</p> <p>(11) Financial contributions.</p>
		<p>COMZ R10 <i>Policies</i> COMZ P2</p>	<p>Establishment of a relocated building from another site</p> <p>Council may impose conditions on:</p> <p>(1) Reinstatement works to the condition and appearance of the building relating to:</p> <p>(a) Works to the exterior fabric of the building to repair, replace or renovate damaged, defective or substandard elements;</p> <p>(b) Painting and/or cleaning of the exterior fabric of the building if necessary;</p> <p>(c) Cladding or other means of enclosing open subfloor areas below the building;</p> <p>(d) *Alterations required to ensure that the reinstated exterior of any relocated building is not likely to detract from the amenity values of the surrounding area.</p> <p>(2) The timeframe for the work to be completed;</p> <p>(3) Landscaping, screening and boundary treatment;</p> <p>(4) Execution of a performance bond to provide security for exterior reinstatement works required as a condition of resource consent.</p> <p>(5) Provision of and effects on utilities and/or services.</p> <p>(6) Standard, construction and layout of vehicular access.</p> <p>Notes in respect of (4):</p>

CON

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<ul style="list-style-type: none"> • A bond is not mandatory. It will only be required when Council considers it necessary in view of the scale and/or nature of exterior reinstatement works required. The requirement for a bond and its value will be determined in the context of the building assessment report submitted at resource consent stage. • The bond shall be executed at the time application is made for a building consent, and security shall be in the form of either money or a guarantee by an institution approved by Council as guarantor. • The bond shall be cancelled upon completion of exterior reinstatement works required in the conditions of the resource consent. The verification method for completion of these works shall be the issuing of a full or interim Code Compliance Certificate as defined in the Building Act. In the event that conditions relating to exterior reinstatement works are not complied with, the bond may be used in whole or in part to complete the works. 		
			<p>Controlled activities – restrictions on notification</p> <p>Subject to sections 95A(2)(b), 95A(2)(c), 95A(4) and 95C of the Act, a resource consent application for a controlled activity is precluded from public notification under section 95A and, subject to section 95B(3), is precluded from limited notification under section 95B(2) of the Act.</p>		
			<p>Standards for Permitted and Controlled Activities</p> <p>Note:</p> <p>The following standards for Permitted and Controlled Activities apply to all properties in the Commercial Zone unless otherwise specified in the text of the standard in question.</p>		
			<table border="1"> <tr> <td style="vertical-align: top;"> <p>COMZ-S1 <i>Policies</i> <i>CCZ-P1,</i> <i>GIZ-P1,</i> <i>IP-P5</i></p> </td> <td style="vertical-align: top;"> <p>Access standards for land use activities</p> <p>(1) All accessways and manoeuvring areas shall be formed and surfaced in accordance with the Code of Practice for Civil Engineering Works. Exemption – the requirement for accessways serving sites solely occupied by unstaffed utilities shall be that the accessway shall be surfaced with permanent all weather surfacing for a minimum length of 5m from the edge of the road carriageway seal.</p> <p>(2) All sites shall have practical vehicle access to car parking and loading spaces, in accordance with the Code of Practice for Civil Engineering Works. This requirement does not apply to sites solely</p> </td> </tr> </table>	<p>COMZ-S1 <i>Policies</i> <i>CCZ-P1,</i> <i>GIZ-P1,</i> <i>IP-P5</i></p>	<p>Access standards for land use activities</p> <p>(1) All accessways and manoeuvring areas shall be formed and surfaced in accordance with the Code of Practice for Civil Engineering Works. Exemption – the requirement for accessways serving sites solely occupied by unstaffed utilities shall be that the accessway shall be surfaced with permanent all weather surfacing for a minimum length of 5m from the edge of the road carriageway seal.</p> <p>(2) All sites shall have practical vehicle access to car parking and loading spaces, in accordance with the Code of Practice for Civil Engineering Works. This requirement does not apply to sites solely</p>
<p>COMZ-S1 <i>Policies</i> <i>CCZ-P1,</i> <i>GIZ-P1,</i> <i>IP-P5</i></p>	<p>Access standards for land use activities</p> <p>(1) All accessways and manoeuvring areas shall be formed and surfaced in accordance with the Code of Practice for Civil Engineering Works. Exemption – the requirement for accessways serving sites solely occupied by unstaffed utilities shall be that the accessway shall be surfaced with permanent all weather surfacing for a minimum length of 5m from the edge of the road carriageway seal.</p> <p>(2) All sites shall have practical vehicle access to car parking and loading spaces, in accordance with the Code of Practice for Civil Engineering Works. This requirement does not apply to sites solely</p>				

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>occupied by unstaffed utilities, provided that vehicles associated with utilities shall not obstruct the footpath or create a traffic hazard on the road.</p> <p>(3) Adequate vehicular access shall be made available to the rear of every new building in accordance with the Code of Practice for Civil Engineering Works.</p> <p>(4) Vehicular access to a corner allotment shall be located no closer than 8m from the street corner. Where a site is located on an intersection of a primary or secondary arterial traffic route (as identified in the Transport and Parking (TP) Chapter) the siting of the vehicular access shall be located as far as practicable from the corner of the street. The 8 metre setback shall be measured from where the two front boundaries of the site (refer to the definition of a corner allotment) join, or in accordance with the diagram below.</p>  <p>(5) Where a corner allotment is located at an intersection of a national, primary or secondary arterial traffic route, as identified in the Transport and Parking (TP) Chapter, no building, fence or other structure is to be erected and no vegetation allowed to grow so as to obstruct a traffic sight line.</p> <p>(6) At the intersection of a road or rail level crossing, no building, fence or other obstructions which block sight lines for trains shall be erected, placed or grown in the hatched area marked in TP-Diagram 1 in the Transport and Parking (TP) Chapter.</p>

IPI - PROPOSED AMENDMENTS																								
#	Chapter	Change	Track Change																					
			<p>(7) Land use activities with direct access to a State Highway shall comply with the access and visibility standards set out in TP Diagrams 2 to 9 in the Transport and Parking (TP) Chapter.</p>																					
		<p>COMZ S2 <i>Policies</i> COMZ P1, COMZ P2</p>	<p>Setbacks from boundaries</p> <p>(1) The setback distance for buildings from boundaries shall be not less than:</p> <table border="1"> <tr> <td>(a)</td> <td>Front boundary</td> <td>8m</td> </tr> <tr> <td>(b)</td> <td>Side and rear boundaries except where adjoining a General Residential or Open Space Zone</td> <td>0m</td> </tr> <tr> <td>(c)</td> <td>Side and rear boundaries adjoining a General Residential or Open Space Zone</td> <td>3m</td> </tr> <tr> <td>(d)</td> <td>Front boundary on land identified in COMZ Figure1</td> <td>4m</td> </tr> <tr> <td>(e)</td> <td>Side boundaries on land identified in COMZ Figure1</td> <td>0m</td> </tr> <tr> <td>(f)</td> <td>Minimum building setback from the power pylon and electricity transmission lines on land identified in COMZ Figure1</td> <td>12m</td> </tr> <tr> <td>(g)</td> <td>Rear boundaries on land identified in COMZ Figure1 except where the rear boundary adjoins a Reserve in which case an exemption from the rear boundary setback applies.</td> <td>3m</td> </tr> </table> <p>Exemptions:</p> <p>(2) Service station canopies are exempt from the front boundary setback requirement.</p> <p>(3) Pole signs are exempt from the front boundary setback requirement.</p>	(a)	Front boundary	8m	(b)	Side and rear boundaries except where adjoining a General Residential or Open Space Zone	0m	(c)	Side and rear boundaries adjoining a General Residential or Open Space Zone	3m	(d)	Front boundary on land identified in COMZ Figure1	4m	(e)	Side boundaries on land identified in COMZ Figure1	0m	(f)	Minimum building setback from the power pylon and electricity transmission lines on land identified in COMZ Figure1	12m	(g)	Rear boundaries on land identified in COMZ Figure1 except where the rear boundary adjoins a Reserve in which case an exemption from the rear boundary setback applies.	3m
(a)	Front boundary	8m																						
(b)	Side and rear boundaries except where adjoining a General Residential or Open Space Zone	0m																						
(c)	Side and rear boundaries adjoining a General Residential or Open Space Zone	3m																						
(d)	Front boundary on land identified in COMZ Figure1	4m																						
(e)	Side boundaries on land identified in COMZ Figure1	0m																						
(f)	Minimum building setback from the power pylon and electricity transmission lines on land identified in COMZ Figure1	12m																						
(g)	Rear boundaries on land identified in COMZ Figure1 except where the rear boundary adjoins a Reserve in which case an exemption from the rear boundary setback applies.	3m																						
		<p>COMZ S3 <i>Policies</i> COMZ P2</p>	<p>Building height</p> <p>(1) The maximum height above ground level of any building in the following areas shall not exceed 8m.</p>																					
		<p>COMZ S4 <i>Policies</i> GRZ P4, COMZ P1, COMZ P2</p>	<p>Sunlight access</p> <p>(1) All buildings on sites adjoining, or separated by a road from a site in the General Residential or Open Space Zone, shall comply with the height control planes defined in GRZ S8 along the adjoining boundary or the boundary or boundaries separated by a road.</p>																					

IPI - PROPOSED AMENDMENTS															
#	Chapter	Change	Track Change												
			<p>COMZ-S5</p> <p>Building coverage on land identified in COMZ-Figure1</p> <p>(1) The maximum coverage by buildings on the net area of a site shall not exceed 20% for land identified in COMZ-Figure1.</p>												
			<p>COMZ-S6 <i>Policies</i> COMZ-P1</p> <p>Loading provisions</p> <p>(1) The number of loading spaces needed for any building in the Commercial-Zone shall be as follows:</p> <table border="1"> <thead> <tr> <th></th> <th>Floor-area</th> <th>Loading spaces required</th> </tr> </thead> <tbody> <tr> <td>(a)</td> <td>Between 100m² and 1000m²</td> <td>1-space</td> </tr> <tr> <td>(b)</td> <td>Between 1001m² and 2000m²</td> <td>2 spaces</td> </tr> <tr> <td>(c)</td> <td>More than 2000m²</td> <td>2 spaces or 4 spaces if the building is used as a retail store</td> </tr> </tbody> </table> <p>Notes</p> <ul style="list-style-type: none"> • Every loading space requires a manoeuvring space for ingress and egress. The extent of the manoeuvring space is to be in accordance with the Code of Practice for Civil Engineering Works. • Loading areas must be kept clear and must be available at all times for vehicles used in association with the building during which time the building is being used for the activity to which the car parking and loading spaces relate. • Direct access to each loading space may be allowed from any vested service lane • All loading spaces are required to be formed and surfaced in accordance with the Code of Practice for Civil Engineering Works. 		Floor-area	Loading spaces required	(a)	Between 100m ² and 1000m ²	1-space	(b)	Between 1001m ² and 2000m ²	2 spaces	(c)	More than 2000m ²	2 spaces or 4 spaces if the building is used as a retail store
	Floor-area	Loading spaces required													
(a)	Between 100m ² and 1000m ²	1-space													
(b)	Between 1001m ² and 2000m ²	2 spaces													
(c)	More than 2000m ²	2 spaces or 4 spaces if the building is used as a retail store													
			<p>COMZ-S7 <i>Policies</i> NATC-P1</p> <p>Water supply, stormwater and wastewater</p> <p>(1) All activities shall comply with the water supply, stormwater and wastewater standards in the Code of Practice for Civil Engineering Works.</p>												
			<p>COMZ-S8 <i>Policies</i> COMZ-P1, COMZ-P3</p> <p>Screening</p> <p>(1) Sites adjoining a Residential or Open Space-Zone shall be fenced on the common boundary by a solid 2m high fence.</p>												

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
			<p>Exemption:</p> <p>(2) The land identified in COMZ Figure1 is exempt from the screening specified above, but outdoor storage areas on land identified in COMZ Figure1 shall be screened as follows:</p> <p>(a) Outdoor storage areas shall be screened by a close boarded fence, a solid wall or dense planting of vegetation. The screening shall be no less than 1.8m in height.</p>
		<p>COMZ S9 <i>Policies</i> COMZ P1, COMZ P2</p>	<p>Landscaping</p> <p>(1) If a building is required to be set back from the road boundary, the set back area between the road boundary and the building shall be landscaped unless it is used for access or car parking purposes. If car parking or accessways are provided between the road boundary and the building, a landscape strip with a minimum width of 0.6m shall be provided within the site along the road boundary.</p> <p>(2) Where a site adjoins a Residential, Rural, Open Space or Special Activity Zone (excluding road boundaries) or is within 25m of a General Residential or Open Space Zone, a landscape buffer with a minimum width of 0.6m shall be provided within the site between the zone boundary and the buildings.</p> <p>Exemption:</p> <p>(3) The land identified in COMZ Figure1 is exempt from the landscaping specified in (2) above except that it shall apply to the common rear boundary of the land identified in COMZ Figure1 and Lots 8 to 11 DP 399832 of the Cosgrove Rise subdivision.</p>
		<p>COMZ S10 <i>Policies</i> COMZ P1</p>	<p>Car parking areas</p> <p>(1) Any car parking provided on a site shall be primarily for the purposes of meeting the car parking demand generated by the use of that site.</p>
		<p>COMZ S11 <i>Policy</i> COMZ P1</p>	<p>Hours of operation for activities adjoining the General Residential Zone</p> <p>(1) Any activity which is open to the public (including licenced premises, places of assembly, shops, restaurants and takeaway food outlets) and adjoins a site which is zoned Residential, shall not be open to the public outside the hours of 7am – 11pm Sunday to Thursday (inclusive) and until 1am the following day on Friday, Saturday, Christmas Eve and New Year's Eve.</p>

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change									
			<p>Restricted Discretionary Activities</p> <table border="1"> <tr> <td> <p>COMZ R11 <i>Policies</i> <i>COMZ P1,</i> <i>COMZ P2</i></p> </td> <td> <p>Buildings which do not comply with permitted or controlled activity standards</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <ul style="list-style-type: none"> (1) Height, boundary setbacks and sunlight access. (2) Provision of and effects on utilities and/or services. (3) Landscaping and screening. (4) Standard, construction and layout of vehicular access. (5) Car parking. (6) Effects on adjoining residential properties. (7) Effects on the amenity of the surrounding area. (8) Financial contributions. </td> <td>RDIS</td> </tr> <tr> <td> <p>COMZ R12 <i>Policy</i> <i>TP P3</i></p> </td> <td> <p>Activities otherwise permitted or controlled which do not comply with the access standards in COMZ-51</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <ul style="list-style-type: none"> (1) The extent to which the activity will adversely affect traffic and pedestrian safety. (2) The extent to which the activity will adversely affect the efficient functioning of the roading network. </td> <td>RDIS</td> </tr> </table>	<p>COMZ R11 <i>Policies</i> <i>COMZ P1,</i> <i>COMZ P2</i></p>	<p>Buildings which do not comply with permitted or controlled activity standards</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <ul style="list-style-type: none"> (1) Height, boundary setbacks and sunlight access. (2) Provision of and effects on utilities and/or services. (3) Landscaping and screening. (4) Standard, construction and layout of vehicular access. (5) Car parking. (6) Effects on adjoining residential properties. (7) Effects on the amenity of the surrounding area. (8) Financial contributions. 	RDIS	<p>COMZ R12 <i>Policy</i> <i>TP P3</i></p>	<p>Activities otherwise permitted or controlled which do not comply with the access standards in COMZ-51</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <ul style="list-style-type: none"> (1) The extent to which the activity will adversely affect traffic and pedestrian safety. (2) The extent to which the activity will adversely affect the efficient functioning of the roading network. 	RDIS			
<p>COMZ R11 <i>Policies</i> <i>COMZ P1,</i> <i>COMZ P2</i></p>	<p>Buildings which do not comply with permitted or controlled activity standards</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <ul style="list-style-type: none"> (1) Height, boundary setbacks and sunlight access. (2) Provision of and effects on utilities and/or services. (3) Landscaping and screening. (4) Standard, construction and layout of vehicular access. (5) Car parking. (6) Effects on adjoining residential properties. (7) Effects on the amenity of the surrounding area. (8) Financial contributions. 	RDIS										
<p>COMZ R12 <i>Policy</i> <i>TP P3</i></p>	<p>Activities otherwise permitted or controlled which do not comply with the access standards in COMZ-51</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <ul style="list-style-type: none"> (1) The extent to which the activity will adversely affect traffic and pedestrian safety. (2) The extent to which the activity will adversely affect the efficient functioning of the roading network. 	RDIS										
			<p>Discretionary Activities</p> <table border="1"> <tr> <td>COMZ R13</td> <td>Garden centres and all activities other than retail activity, restaurants, offices, early childhood centres and residential accommodation (including at ground level) on land identified in COMZ Figure1</td> <td>DIS</td> </tr> <tr> <td>COMZ R14</td> <td>Warehouses</td> <td>DIS</td> </tr> <tr> <td>COMZ R15</td> <td>Service stations and motor vehicle garages</td> <td>DIS</td> </tr> </table>	COMZ R13	Garden centres and all activities other than retail activity, restaurants, offices, early childhood centres and residential accommodation (including at ground level) on land identified in COMZ Figure1	DIS	COMZ R14	Warehouses	DIS	COMZ R15	Service stations and motor vehicle garages	DIS
COMZ R13	Garden centres and all activities other than retail activity, restaurants, offices, early childhood centres and residential accommodation (including at ground level) on land identified in COMZ Figure1	DIS										
COMZ R14	Warehouses	DIS										
COMZ R15	Service stations and motor vehicle garages	DIS										


IPI - PROPOSED AMENDMENTS															
#	Chapter	Change	Track Change												
			<table border="1"> <tr> <td>COMZ R16</td> <td>Public car parks</td> <td>DIS</td> </tr> <tr> <td>COMZ R17</td> <td>The sale and hire of motor vehicles, boats, caravans, motor homes and accessories and motor vehicle spare part</td> <td>DIS</td> </tr> <tr> <td>COMZ R18</td> <td>Residential accommodation at ground floor level</td> <td>DIS</td> </tr> <tr> <td>COMZ R19</td> <td>Activities otherwise permitted or controlled, which do not comply with the relevant standards in this chapter, except where otherwise specified in this Chapter or in the District wide matters of the Plan</td> <td>DIS</td> </tr> </table>	COMZ R16	Public car parks	DIS	COMZ R17	The sale and hire of motor vehicles, boats, caravans, motor homes and accessories and motor vehicle spare part	DIS	COMZ R18	Residential accommodation at ground floor level	DIS	COMZ R19	Activities otherwise permitted or controlled, which do not comply with the relevant standards in this chapter, except where otherwise specified in this Chapter or in the District wide matters of the Plan	DIS
COMZ R16	Public car parks	DIS													
COMZ R17	The sale and hire of motor vehicles, boats, caravans, motor homes and accessories and motor vehicle spare part	DIS													
COMZ R18	Residential accommodation at ground floor level	DIS													
COMZ R19	Activities otherwise permitted or controlled, which do not comply with the relevant standards in this chapter, except where otherwise specified in this Chapter or in the District wide matters of the Plan	DIS													
			<table border="1"> <tr> <td colspan="3">Non-Complying Activities</td> </tr> <tr> <td>COMZ R20</td> <td>Motor vehicle wrecking</td> <td>NC</td> </tr> <tr> <td>COMZ R21</td> <td>Every activity listed as an offensive trade in the third schedule of the Health Act 1956</td> <td>NC</td> </tr> </table>	Non-Complying Activities			COMZ R20	Motor vehicle wrecking	NC	COMZ R21	Every activity listed as an offensive trade in the third schedule of the Health Act 1956	NC			
Non-Complying Activities															
COMZ R20	Motor vehicle wrecking	NC													
COMZ R21	Every activity listed as an offensive trade in the third schedule of the Health Act 1956	NC													
			<table border="1"> <tr> <td colspan="3">Matters for Consideration</td> </tr> <tr> <td colspan="3">Matters that may be relevant in the consideration of any Discretionary or Non-Complying Activity resource consent may include the following:</td> </tr> <tr> <td>COMZ MC1</td> <td colspan="2"> Access <ol style="list-style-type: none"> (1) Accessibility for public transport, cyclists and pedestrians. (2) Compliance with the Code of Practice for Civil Engineering Works. (3) Whether the topography, size or shape of the site or the location of any natural or built feature(s) on the site or other requirements such as easements, rights of way or restrictive covenants impose constraints that make compliance impracticable. (4) Whether the activities proposed will not generate a demand for servicing facilities. (5) Whether suitable alternative provision for servicing can be made. (6) Whether the nature of adjacent roads is such that the entry, exit and manoeuvring of vehicles can be conducted safely. </td> </tr> </table>	Matters for Consideration			Matters that may be relevant in the consideration of any Discretionary or Non-Complying Activity resource consent may include the following:			COMZ MC1	Access <ol style="list-style-type: none"> (1) Accessibility for public transport, cyclists and pedestrians. (2) Compliance with the Code of Practice for Civil Engineering Works. (3) Whether the topography, size or shape of the site or the location of any natural or built feature(s) on the site or other requirements such as easements, rights of way or restrictive covenants impose constraints that make compliance impracticable. (4) Whether the activities proposed will not generate a demand for servicing facilities. (5) Whether suitable alternative provision for servicing can be made. (6) Whether the nature of adjacent roads is such that the entry, exit and manoeuvring of vehicles can be conducted safely. 				
Matters for Consideration															
Matters that may be relevant in the consideration of any Discretionary or Non-Complying Activity resource consent may include the following:															
COMZ MC1	Access <ol style="list-style-type: none"> (1) Accessibility for public transport, cyclists and pedestrians. (2) Compliance with the Code of Practice for Civil Engineering Works. (3) Whether the topography, size or shape of the site or the location of any natural or built feature(s) on the site or other requirements such as easements, rights of way or restrictive covenants impose constraints that make compliance impracticable. (4) Whether the activities proposed will not generate a demand for servicing facilities. (5) Whether suitable alternative provision for servicing can be made. (6) Whether the nature of adjacent roads is such that the entry, exit and manoeuvring of vehicles can be conducted safely. 														

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
			<p>COMZ MC2 Site Layout</p> <p>(1) The arrangement of buildings, car parks and vehicle movements on site.</p> <p>(2) The nature and extent of landscaping and screening.</p> <p>(3) Whether the topography of the site has been taken into account.</p> <p>(4) Whether a better standard of development can be achieved by varying the design.</p>
			<p>COMZ MC3 Bulk and location of buildings</p> <p>(1) Whether the buildings will cause a loss of privacy, interfere with sunlight access or create shadows on residential units on adjoining Residentially zoned sites.</p> <p>(2) Whether the building design, appearance and scale will detrimentally affect the character of the surrounding area.</p>
			<p>COMZ MC4 Traffic generation</p> <p>(1) Whether activities which generate significant traffic flows have the necessary access, do not adversely impact upon the street environment, and maintain public safety.</p>
			<p>COMZ MC5 Non-business activities</p> <p>(1) Whether the buildings, structures or other works are of an appropriate scale having regard to the local amenity.</p> <p>(2) The extent to which the amenities and the quality of the business environment can be maintained and enhanced.</p>
			<p>COMZ MC6 Nuisance</p> <p>(1) The potential impacts of noise, dust, glare, vibration, fumes, smoke, other discharges or pollutants or the excavation or deposition of earth</p>
			<p>COMZ MC7 Infrastructure</p> <p>(1) The existing capacity of the infrastructure.</p>

IPI - PROPOSED AMENDMENTS											
#	Chapter	Change	Track Change								
			<table border="1"> <tr> <td>COMZ-MC8</td> <td>Cumulative effects (1) Whether cumulative effects such as pollution, risks to public safety and nuisances have been assessed.</td> <td></td> <td></td> </tr> <tr> <td>COMZ-MC9</td> <td>Retail activities (1) The effects of retail activities on the vitality and economic viability of the City Centre Zone (Central Business District), and neighbourhood centres. (2) Whether the nature and scale of retail activities compliments activities occurring on surrounding sites</td> <td></td> <td></td> </tr> </table>	COMZ-MC8	Cumulative effects (1) Whether cumulative effects such as pollution, risks to public safety and nuisances have been assessed.			COMZ-MC9	Retail activities (1) The effects of retail activities on the vitality and economic viability of the City Centre Zone (Central Business District), and neighbourhood centres. (2) Whether the nature and scale of retail activities compliments activities occurring on surrounding sites		
COMZ-MC8	Cumulative effects (1) Whether cumulative effects such as pollution, risks to public safety and nuisances have been assessed.										
COMZ-MC9	Retail activities (1) The effects of retail activities on the vitality and economic viability of the City Centre Zone (Central Business District), and neighbourhood centres. (2) Whether the nature and scale of retail activities compliments activities occurring on surrounding sites										
			<table border="1"> <tr> <td colspan="4">Prohibited Activities</td> </tr> <tr> <td>COMZ-R22</td> <td>Gang fortifications</td> <td></td> <td>PR</td> </tr> </table>	Prohibited Activities				COMZ-R22	Gang fortifications		PR
Prohibited Activities											
COMZ-R22	Gang fortifications		PR								
			<table border="1"> <tr> <td colspan="4">Advice Note</td> </tr> <tr> <td colspan="4">For any activity within the Stream/River Corridor, Overflow Path, Ponding Area or Erosion Hazard Area, applicants are advised to consult the Wellington Regional Council to determine if regional consent is also required.</td> </tr> </table>	Advice Note				For any activity within the Stream/River Corridor, Overflow Path, Ponding Area or Erosion Hazard Area , applicants are advised to consult the Wellington Regional Council to determine if regional consent is also required.			
Advice Note											
For any activity within the Stream/River Corridor, Overflow Path, Ponding Area or Erosion Hazard Area , applicants are advised to consult the Wellington Regional Council to determine if regional consent is also required.											
			<p>Methods</p> <p>COMZ-M1 District Plan provisions consisting of the following:</p> <ol style="list-style-type: none"> (1) Commercial Zones identifying the commercial environments within the City. These are the Commercial Zone and the City Centre Zone. (2) Rules and performance standards to avoid, remedy or mitigate adverse effects. <p>COMZ-M2 Code of Practice for Civil Engineering Works.</p> <p>COMZ-M3 Abatement notices and enforcement orders may be issued where it is necessary to enforce the performance standards and mitigate any adverse effects of activities.</p>								

IPI - PROPOSED AMENDMENTS																											
#	Chapter	Change	Track Change																								
			<p>COMZ-M4 Consultation with businesses and landowners to promote new developments which avoid, remedy or mitigate the potential adverse effects of all activities.</p> <p>COMZ-M5 Management Plans prepared under relevant legislation.</p> <p>COMZ-M6 District Plan rules setting standards to protect adjacent properties from adverse shading effects.</p> <p>COMZ-M7 District Plan rules prohibiting gang fortifications because of their adverse effects on the environment.</p> <p>Anticipated environmental results</p> <p>The following results are expected to be achieved by the objectives, policies and methods of this chapter. The means of monitoring whether this Plan achieves the anticipated environmental results are also set out below.</p> <table border="1"> <thead> <tr> <th colspan="2">Anticipated environmental results</th> <th>Monitoring indicators</th> <th>Data source</th> </tr> </thead> <tbody> <tr> <td>COMZ-AER1</td> <td>Development within the Commercial Zone which reflects the location, scale and intensity of development in the surrounding environment</td> <td>Density within the Commercial Zone Number of resource consents by type</td> <td>Council records</td> </tr> <tr> <td>COMZ-AER2</td> <td>Management of the Commercial Zone so that activities do not unduly affect adjacent land users</td> <td>Number of resource consents by type Complaints and abatement/enforcement proceedings</td> <td>Council records Complaints register</td> </tr> <tr> <td>COMZ-AER3</td> <td>A CBD which is safe, convenient and attractive</td> <td>Complaints and abatement/enforcement proceedings</td> <td>Complaints register Field work</td> </tr> <tr> <td>COMZ-AER4</td> <td>A consolidated Commercial Zone that continues to maximise resources and existing infrastructure</td> <td>Density within the Commercial Zone Number of resource consents by type</td> <td>Council records</td> </tr> <tr> <td>COMZ-AER5</td> <td>Retail activities are appropriately located to not adversely affect the economic viability of the CBD and to ensure that the industrial land resource</td> <td>Number of resource consents by type The spatial development of retail activities</td> <td>Council records Field work</td> </tr> </tbody> </table>	Anticipated environmental results		Monitoring indicators	Data source	COMZ-AER1	Development within the Commercial Zone which reflects the location, scale and intensity of development in the surrounding environment	Density within the Commercial Zone Number of resource consents by type	Council records	COMZ-AER2	Management of the Commercial Zone so that activities do not unduly affect adjacent land users	Number of resource consents by type Complaints and abatement/enforcement proceedings	Council records Complaints register	COMZ-AER3	A CBD which is safe, convenient and attractive	Complaints and abatement/enforcement proceedings	Complaints register Field work	COMZ-AER4	A consolidated Commercial Zone that continues to maximise resources and existing infrastructure	Density within the Commercial Zone Number of resource consents by type	Council records	COMZ-AER5	Retail activities are appropriately located to not adversely affect the economic viability of the CBD and to ensure that the industrial land resource	Number of resource consents by type The spatial development of retail activities	Council records Field work
Anticipated environmental results		Monitoring indicators	Data source																								
COMZ-AER1	Development within the Commercial Zone which reflects the location, scale and intensity of development in the surrounding environment	Density within the Commercial Zone Number of resource consents by type	Council records																								
COMZ-AER2	Management of the Commercial Zone so that activities do not unduly affect adjacent land users	Number of resource consents by type Complaints and abatement/enforcement proceedings	Council records Complaints register																								
COMZ-AER3	A CBD which is safe, convenient and attractive	Complaints and abatement/enforcement proceedings	Complaints register Field work																								
COMZ-AER4	A consolidated Commercial Zone that continues to maximise resources and existing infrastructure	Density within the Commercial Zone Number of resource consents by type	Council records																								
COMZ-AER5	Retail activities are appropriately located to not adversely affect the economic viability of the CBD and to ensure that the industrial land resource	Number of resource consents by type The spatial development of retail activities	Council records Field work																								

IPI - PROPOSED AMENDMENTS											
#	Chapter	Change	Track Change								
			<table border="1"> <tr> <td></td> <td>of the City is used primarily for industrial purposes</td> <td>The use, occupation and vacancy rate of industrial land and buildings</td> <td></td> </tr> <tr> <td>COMZ AER6</td> <td>A built environment which supports the health and safety of the City's residents</td> <td>Resource consents and type and effect on health and safety issues Consultation and community initiatives</td> <td>Council records</td> </tr> </table>		of the City is used primarily for industrial purposes	The use, occupation and vacancy rate of industrial land and buildings		COMZ AER6	A built environment which supports the health and safety of the City's residents	Resource consents and type and effect on health and safety issues Consultation and community initiatives	Council records
	of the City is used primarily for industrial purposes	The use, occupation and vacancy rate of industrial land and buildings									
COMZ AER6	A built environment which supports the health and safety of the City's residents	Resource consents and type and effect on health and safety issues Consultation and community initiatives	Council records								
		<p>COMZ Figure1 Riverstone Terrace Site</p> 									

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
NCZ – Neighbourhood Centre Zone			
New NCZ - Neighbourhood Centre Zone	Introduce new Chapter Heading and Introduction	<p>NCZ - Neighbourhood Centre Zone</p> <p>The Neighbourhood Centre Zone provides for a range of small scale commercial activities that service the day-to-day needs of the immediate residential neighbourhood. Neighbourhood Centres accommodate a range of commercial, retail and community services and provide a limited range of services, employment and living opportunities.</p> <p>Neighbourhood Centres are of a scale that aligns well with the medium density of the surrounding residential neighbourhoods. Most Neighbourhood Centres comprise of two to three small scale shops but can be as small as a single dairy. Buildings in the Neighbourhood Centre Zone usually are of a similar scale to the surrounding residential neighbourhood. Typically buildings are built up to the road frontage, with commercial windows along the frontage and carparking available on the street. Residential units are located either above the ground floor or towards the rear of the site.</p> <p>Due to their location within residential neighbourhoods, non-residential activities and development have the potential to generate adverse effects where they are directly adjoining Residential and Open Space and Recreation areas. To manage these potential effects buildings need to be set back and outdoor storage and parking areas need to be screened.</p>	
New NCZ - Neighbourhood Centre Zone	Introduce new Objective NCZ-O1	<p>Objectives</p> <p>NCZ-O1 Purpose of the Neighbourhood Centre Zone</p> <p>Neighbourhood Centres are small-scale commercial sites and centres that service the day-to-day needs of surrounding residential neighbourhoods. They accommodate a range of small-scale commercial and community activities as well as residential activities.</p>	
New NCZ - Neighbourhood Centre Zone	Introduce new Objective NCZ-O2	<p>NCZ-O2 Character and Amenity Values of the Neighbourhood Centre Zone</p> <p>Built development in the Neighbourhood Centre Zone is of medium density and reflects the anticipated planned urban built character form of the surrounding residential neighbourhood. It is well-designed and contributes positively to the surrounding residential environment.</p>	
New NCZ - Neighbourhood Centre Zone	Introduce new Objective NCZ-O3	<p>NCZ-O3 Managing Effects at the Zone Interface</p> <p>Use and development within the Neighbourhood Centre Zone are of an appropriate scale and proportion for the purpose and anticipated character of the zone and the surrounding residential environment and have minimal adverse effects on the amenity values of adjacent sites in Residential Zones and Open Space and Recreation Zones.</p>	

Commented [MM179]: S58.173 - Kianga Ora: Homes and Communities.

Commented [MM180]: S58.175 - Kianga Ora: Homes and Communities.

Commented [MM181]: S58.175 - Kianga Ora: Homes and Communities.

Commented [MM182]: S58.175 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS											
#	Chapter	Change	Track Change								
	New NCZ – Neighbourhood Centre Zone	Introduce new Objective NCZ-04	<table border="1"> <tr> <td>NCZ-04</td> <td>Hydraulic neutrality</td> </tr> <tr> <td colspan="2">There is no increase in the peak demand on stormwater management systems and increase in flooding from subdivision and development.</td> </tr> </table>	NCZ-04	Hydraulic neutrality	There is no increase in the peak demand on stormwater management systems and increase in flooding from subdivision and development .					
NCZ-04	Hydraulic neutrality										
There is no increase in the peak demand on stormwater management systems and increase in flooding from subdivision and development .											
	New NCZ - Neighbourhood Centre Zone	Introduce new Policy NCZ-P1	<table border="1"> <tr> <td colspan="2">Policies</td> </tr> <tr> <td>NCZ-P1</td> <td>Appropriate activities</td> </tr> <tr> <td colspan="2">Enable appropriate activities that:</td> </tr> <tr> <td colspan="2"> <ol style="list-style-type: none"> Are compatible with the anticipated purpose and character planned urban built form of the Neighbourhood Centre Zone; Provide for the day-to-day needs of the immediate residential neighbourhood; and Minimise adverse effects on adjoining residential, recreational and open space sites. </td> </tr> </table>	Policies		NCZ-P1	Appropriate activities	Enable appropriate activities that:		<ol style="list-style-type: none"> Are compatible with the anticipated purpose and character planned urban built form of the Neighbourhood Centre Zone; Provide for the day-to-day needs of the immediate residential neighbourhood; and Minimise adverse effects on adjoining residential, recreational and open space sites. 	
Policies											
NCZ-P1	Appropriate activities										
Enable appropriate activities that:											
<ol style="list-style-type: none"> Are compatible with the anticipated purpose and character planned urban built form of the Neighbourhood Centre Zone; Provide for the day-to-day needs of the immediate residential neighbourhood; and Minimise adverse effects on adjoining residential, recreational and open space sites. 											
	New NCZ - Neighbourhood Centre Zone	Introduce new Policy NCZ-P2	<table border="1"> <tr> <td>NCZ-P2</td> <td>Residential activity</td> </tr> <tr> <td colspan="2">Provide for residential activity where:</td> </tr> <tr> <td colspan="2"> <ol style="list-style-type: none"> The residential units are located either above ground floor or to the rear of a commercial activity; It does not compromise an active commercial frontage that addresses the street. Any residential units are designed to: <ol style="list-style-type: none"> Achieve adequate indoor noise and ventilation levels for occupants; and Provide appropriate amenity for occupants; and Reverse sensitivity effects on commercial activities are minimised. </td> </tr> </table>	NCZ-P2	Residential activity	Provide for residential activity where:		<ol style="list-style-type: none"> The residential units are located either above ground floor or to the rear of a commercial activity; It does not compromise an active commercial frontage that addresses the street. Any residential units are designed to: <ol style="list-style-type: none"> Achieve adequate indoor noise and ventilation levels for occupants; and Provide appropriate amenity for occupants; and Reverse sensitivity effects on commercial activities are minimised. 			
NCZ-P2	Residential activity										
Provide for residential activity where:											
<ol style="list-style-type: none"> The residential units are located either above ground floor or to the rear of a commercial activity; It does not compromise an active commercial frontage that addresses the street. Any residential units are designed to: <ol style="list-style-type: none"> Achieve adequate indoor noise and ventilation levels for occupants; and Provide appropriate amenity for occupants; and Reverse sensitivity effects on commercial activities are minimised. 											
	New NCZ - Neighbourhood Centre Zone	Introduce new Policy NCZ-P3	<table border="1"> <tr> <td>NCZ-P3</td> <td>Other activities</td> </tr> <tr> <td colspan="2">Only allow for other activities, including larger scale commercial and retail activities where:</td> </tr> <tr> <td colspan="2"> <ol style="list-style-type: none"> Any adverse effects can be managed; </td> </tr> </table>	NCZ-P3	Other activities	Only allow for other activities , including larger scale commercial and retail activities where:		<ol style="list-style-type: none"> Any adverse effects can be managed; 			
NCZ-P3	Other activities										
Only allow for other activities , including larger scale commercial and retail activities where:											
<ol style="list-style-type: none"> Any adverse effects can be managed; 											

Commented [MM183]: S58.177 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<ol style="list-style-type: none"> The scale and intensity of the activity is consistent with the anticipated character planned urban build form and function of the Neighbourhood Centre Zone; The design and layout of the activity does not compromise the streetscape, amenity or safety; The nature, size, intensity and scale of the activity does not compromise other activities that are enabled and anticipated in the zone; and The location of the activity in the Neighbourhood Centre Zone does not undermine the role and function of the City Centre Zone. 		
	New NCZ - Neighbourhood Centre Zone	Introduce new Policy NCZ-P4	<table border="1"> <tr> <td>NCZ-P4</td> <td>Inappropriate activities</td> </tr> </table> <p>Avoid activities that are incompatible with the size, purpose and anticipated function of the Neighbourhood Centre Zone and the surrounding environment.</p>	NCZ-P4	Inappropriate activities
NCZ-P4	Inappropriate activities				
	New NCZ - Neighbourhood Centre Zone	Introduce new Policy NCZ-P5	<table border="1"> <tr> <td>NCZ-P5</td> <td>Built development</td> </tr> </table> <p>Provide for medium-density development that</p> <ol style="list-style-type: none"> Reflects the purpose and is consistent with the anticipated density and planned built urban form of the Neighbourhood Centre Zone; Is commensurate with the anticipated level of commercial activities and community services in the Neighbourhood Centre Zone; Is compatible with the planned built form of medium density residential development within the surrounding residential environment; and Is well designed and contributes to an attractive well-functioning urban environment. 	NCZ-P5	Built development
NCZ-P5	Built development				
	New NCZ - Neighbourhood Centre Zone	Introduce new Policy NCZ-P6	<table border="1"> <tr> <td>NCZ-P6</td> <td>Public space interface</td> </tr> </table> <p>Encourage development that creates attractive and safe streets and public open spaces.</p> <p>Require new development to create a positive interface with the public space through the provision of:</p> <ol style="list-style-type: none"> Display windows; Obvious entrances; and 	NCZ-P6	Public space interface
NCZ-P6	Public space interface				

Commented [MM184]: S58.179 - Kianga Ora: Homes and Communities.

Commented [MM185]: S58.181Kainga Ora: Homes and Communities

Commented [MM186]: S64.83 - Retirement Villages Association of New Zealand

IPI - PROPOSED AMENDMENTS													
#	Chapter	Change	Track Change										
			3. <u>Well designed and unobtrusive parking, loading and storage areas.</u>										
	New NCZ - Neighbourhood Centre Zone	Introduce new Policy NCZ-P7	<table border="1"> <tr> <td>NCZ-P7</td> <td>Interface with Residential Zones and Open Space and Recreation Zones</td> </tr> <tr> <td colspan="2"><u>Minimise the adverse effects from commercial activities and development on directly adjoining sites that are zoned Residential or Open Space and Recreation through:</u></td> </tr> <tr> <td colspan="2">1. <u>Requiring new buildings and activities to be located and designed to manage any shading and privacy effects on neighbouring sites zoned Residential or Open Space and Recreation;</u></td> </tr> <tr> <td colspan="2">2. <u>Limiting the height, bulk and form of new buildings along boundaries with sites zoned Residential or Open Space and Recreation to minimise dominance effects; and</u></td> </tr> <tr> <td colspan="2">3. <u>Requiring the use of landscaping and screening to minimise adverse visual effects on adjoining sites zoned Residential or Open Space and Recreation.</u></td> </tr> </table>	NCZ-P7	Interface with Residential Zones and Open Space and Recreation Zones	<u>Minimise the adverse effects from commercial activities and development on directly adjoining sites that are zoned Residential or Open Space and Recreation through:</u>		1. <u>Requiring new buildings and activities to be located and designed to manage any shading and privacy effects on neighbouring sites zoned Residential or Open Space and Recreation;</u>		2. <u>Limiting the height, bulk and form of new buildings along boundaries with sites zoned Residential or Open Space and Recreation to minimise dominance effects; and</u>		3. <u>Requiring the use of landscaping and screening to minimise adverse visual effects on adjoining sites zoned Residential or Open Space and Recreation.</u>	
NCZ-P7	Interface with Residential Zones and Open Space and Recreation Zones												
<u>Minimise the adverse effects from commercial activities and development on directly adjoining sites that are zoned Residential or Open Space and Recreation through:</u>													
1. <u>Requiring new buildings and activities to be located and designed to manage any shading and privacy effects on neighbouring sites zoned Residential or Open Space and Recreation;</u>													
2. <u>Limiting the height, bulk and form of new buildings along boundaries with sites zoned Residential or Open Space and Recreation to minimise dominance effects; and</u>													
3. <u>Requiring the use of landscaping and screening to minimise adverse visual effects on adjoining sites zoned Residential or Open Space and Recreation.</u>													
	New NCZ - Neighbourhood Centre Zone	Introduce new Policy NCZ-P8	<table border="1"> <tr> <td>NCZ-P8</td> <td>Hydraulic neutrality</td> </tr> <tr> <td colspan="2"><u>Require New buildings and development will to be designed to achieve hydraulic neutrality.</u></td> </tr> </table>	NCZ-P8	Hydraulic neutrality	<u>Require New buildings and development will to be designed to achieve hydraulic neutrality.</u>							
NCZ-P8	Hydraulic neutrality												
<u>Require New buildings and development will to be designed to achieve hydraulic neutrality.</u>													
	New NCZ - Neighbourhood Centre Zone	Introduce new Rules Advice Note	<p>Rules</p> <p><u>Note: There may be a number of provisions that apply to an activity, building, structure or site. Resource consent may therefore be required under rules in this chapter as well as other chapters. Unless specifically stated in a rule, resource consent is required under each relevant rule. The steps to determine the status of an activity are set out in Chapter 2 How the Plan Works.</u></p> <p><u>Rules relating to subdivision are found in the SUB-GEN (General Subdivision Provisions that Apply in All Zones) and the SUB-CMU (Subdivision in Commercial and Mixed Use Zones) chapters.</u></p> <p><u>Each activity in the Neighbourhood Centre Zone shall comply with the relevant qualifying matter areas, and permitted activity standards in the district-wide matters of the Plan as listed below.</u></p> <table border="1"> <tr> <td>District-wide matters</td> </tr> <tr> <td><u>NU – Network Utilities</u></td> </tr> <tr> <td><u>REG - Renewable Energy Generation</u></td> </tr> </table>	District-wide matters	<u>NU – Network Utilities</u>	<u>REG - Renewable Energy Generation</u>							
District-wide matters													
<u>NU – Network Utilities</u>													
<u>REG - Renewable Energy Generation</u>													

Commented [MM187]: S58.184 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
			<u>TP – Transport and Parking</u>
			<u>CL – Contaminated Land</u>
			<u>HS - Hazardous Substances</u>
			<u>NH - Natural Hazards</u>
			<u>WM – Waste Management</u>
			<u>HH - Historical Heritage</u>
			<u>TREE - Notable Trees</u>
			<u>UTG - Urban Tree Groups</u>
			<u>ECO - Ecosystems and Indigenous Biodiversity</u>
			<u>NATC – Natural Character</u>
			<u>NFL - Natural Features and Landscapes</u>
			<u>PA – Public Access</u>
			<u>SUB - Subdivision</u>
			<u>DC – Development Contributions</u>
			<u>AIR - Air</u>
			<u>PK – Papakāinga</u>
			<u>ASW - Activities on the Surface of Water</u>
			<u>EW - Earthworks</u>
			<u>LIGHT - Light</u>
			<u>NOISE - Noise</u>
			<u>SIGN - Signs</u>
			<u>TEMP - Temporary Activities</u>

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R1	<table border="1"> <tr> <td>NCZ-R1</td> <td>Buildings and structures, including additions and alterations</td> </tr> <tr> <td colspan="2"> <p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. The gross floor area of the new building does not exceed 500m²;</p> <p>b. Any addition to an existing building does not result in the gross floor area of the building exceeding 500m²; and</p> <p>c. Compliance is achieved with:</p> <p>i. NCZ-S1 (Height);</p> <p>ii. NCZ-S2 (Height in Relation to Boundary);</p> <p>iii. NCZ-S3 (Setbacks);</p> <p>iv. NCZ-S4 (Active Frontages);</p> <p>v. NCZ-S5 (Location of Residential Units);</p> <p>vi. NCZ-S6 (Noise and Ventilation)</p> <p>vii. NCZ-S7 (Outdoor Living Space);</p> <p>viii. NCZ-S8 (Landscaping and Screening);</p> <p>ix. NCZ-S9 (Water Supply, Stormwater and Wastewater); and</p> <p>x. NCZ-S10 – (Hydraulic neutrality).</p> </td> </tr> <tr> <td colspan="2"> <p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with NCZ-R1-1.a or NCZ-R1-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <p>1. The extent to which the size and scale of the building is commensurate with the anticipated level of commercial activities and community services in the Neighbourhood Centre Zone;</p> <p>2. The extent to which the size and scale of the building may adversely impact on the amenity of the</p> </td> </tr> </table>	NCZ-R1	Buildings and structures, including additions and alterations	<p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. The gross floor area of the new building does not exceed 500m²;</p> <p>b. Any addition to an existing building does not result in the gross floor area of the building exceeding 500m²; and</p> <p>c. Compliance is achieved with:</p> <p>i. NCZ-S1 (Height);</p> <p>ii. NCZ-S2 (Height in Relation to Boundary);</p> <p>iii. NCZ-S3 (Setbacks);</p> <p>iv. NCZ-S4 (Active Frontages);</p> <p>v. NCZ-S5 (Location of Residential Units);</p> <p>vi. NCZ-S6 (Noise and Ventilation)</p> <p>vii. NCZ-S7 (Outdoor Living Space);</p> <p>viii. NCZ-S8 (Landscaping and Screening);</p> <p>ix. NCZ-S9 (Water Supply, Stormwater and Wastewater); and</p> <p>x. NCZ-S10 – (Hydraulic neutrality).</p>		<p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with NCZ-R1-1.a or NCZ-R1-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <p>1. The extent to which the size and scale of the building is commensurate with the anticipated level of commercial activities and community services in the Neighbourhood Centre Zone;</p> <p>2. The extent to which the size and scale of the building may adversely impact on the amenity of the</p>	
NCZ-R1	Buildings and structures, including additions and alterations								
<p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. The gross floor area of the new building does not exceed 500m²;</p> <p>b. Any addition to an existing building does not result in the gross floor area of the building exceeding 500m²; and</p> <p>c. Compliance is achieved with:</p> <p>i. NCZ-S1 (Height);</p> <p>ii. NCZ-S2 (Height in Relation to Boundary);</p> <p>iii. NCZ-S3 (Setbacks);</p> <p>iv. NCZ-S4 (Active Frontages);</p> <p>v. NCZ-S5 (Location of Residential Units);</p> <p>vi. NCZ-S6 (Noise and Ventilation)</p> <p>vii. NCZ-S7 (Outdoor Living Space);</p> <p>viii. NCZ-S8 (Landscaping and Screening);</p> <p>ix. NCZ-S9 (Water Supply, Stormwater and Wastewater); and</p> <p>x. NCZ-S10 – (Hydraulic neutrality).</p>									
<p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with NCZ-R1-1.a or NCZ-R1-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <p>1. The extent to which the size and scale of the building is commensurate with the anticipated level of commercial activities and community services in the Neighbourhood Centre Zone;</p> <p>2. The extent to which the size and scale of the building may adversely impact on the amenity of the</p>									

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			<p><u>Neighbourhood Centre Zone or adjacent properties.</u></p> <ol style="list-style-type: none"> 3. <u>Whether the building is well designed and contributes to an attractive urban environment.</u> 4. <u>The effects of the size and scale of the building on the existing and anticipated function and role of the Neighbourhood Centre Zone.</u> 5. <u>The potential of the size and scale of the building to compromise activities that are enabled in the Neighbourhood Centre Zone.</u> 6. <u>The potential of the size and scale of the building to undermine the role and function of the City Centre Zone.</u> 7. <u>The extent to which the adverse effects of the size and scale of the building can be avoided, or appropriately remedied or mitigated.</u> <p>b. <u>Compliance is not achieved with NCZ-R1-1.c</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The matters of discretion of any infringed standard.</u> <p>Notification:</p> <p><u>An application under this rule where compliance is not achieved with NCZ-S2, NCZ-S3, NCZ-S4, NCZ-S5, NCZ-S6 or NCZ-S8 is precluded from being publicly notified in accordance with section 95A of the RMA.</u></p> <p><u>An application under this rule where compliance is not achieved with NCZ-S7 is precluded from being publicly or limited notified in accordance with section 95A of the RMA.</u></p>						
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R2	<table border="1"> <tr> <td>NCZ-R2</td> <td>Minor structures</td> </tr> <tr> <td>1.</td> <td>Activity status: Permitted</td> </tr> </table>	NCZ-R2	Minor structures	1.	Activity status: Permitted		
NCZ-R2	Minor structures								
1.	Activity status: Permitted								
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R3	<table border="1"> <tr> <td>NCZ-R3</td> <td>Demolition</td> </tr> <tr> <td>1.</td> <td>Activity status: Permitted</td> </tr> <tr> <td colspan="2">Note: <u>Prior to demolition commencing, confirm whether rules in chapter HH-Historic Heritage apply.</u></td> </tr> </table>	NCZ-R3	Demolition	1.	Activity status: Permitted	Note: <u>Prior to demolition commencing, confirm whether rules in chapter HH-Historic Heritage apply.</u>	
NCZ-R3	Demolition								
1.	Activity status: Permitted								
Note: <u>Prior to demolition commencing, confirm whether rules in chapter HH-Historic Heritage apply.</u>									

Commented [MM188]: S72.12 - Te Rūnanga o Toa Rangatira Inc

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change						
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R3	<table border="1"> <thead> <tr> <th data-bbox="528 373 674 410">NCZ-R4</th> <th data-bbox="674 373 1668 410">Retail Activity</th> </tr> </thead> <tbody> <tr> <td data-bbox="528 410 674 580">1.</td> <td data-bbox="674 410 1668 580"> <p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 150m²; and</p> <p>b. Compliance is achieved with NCZ-S8 (Landscaping and Screening).</p> </td> </tr> <tr> <td data-bbox="528 580 674 1284">2.</td> <td data-bbox="674 580 1668 1284"> <p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with NCZ-R4-1.a</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Neighbourhood Centre Zone or adjacent properties. The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Neighbourhood Centre Zone. The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Neighbourhood Centre Zone. The potential of the location of the activity in the Neighbourhood Centre Zone to undermine the role and function of the City Centre Zone. The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated. <p>b. Compliance is not achieved with NCZ-R4-1.b</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The matters of discretion of the infringed standard. <p>Notification:</p> <ul style="list-style-type: none"> An application under NCZ-R4-2.b is precluded from being publicly notified in accordance with section 95A of the RMA. </td> </tr> </tbody> </table>	NCZ-R4	Retail Activity	1.	<p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 150m²; and</p> <p>b. Compliance is achieved with NCZ-S8 (Landscaping and Screening).</p>	2.	<p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with NCZ-R4-1.a</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Neighbourhood Centre Zone or adjacent properties. The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Neighbourhood Centre Zone. The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Neighbourhood Centre Zone. The potential of the location of the activity in the Neighbourhood Centre Zone to undermine the role and function of the City Centre Zone. The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated. <p>b. Compliance is not achieved with NCZ-R4-1.b</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The matters of discretion of the infringed standard. <p>Notification:</p> <ul style="list-style-type: none"> An application under NCZ-R4-2.b is precluded from being publicly notified in accordance with section 95A of the RMA.
NCZ-R4	Retail Activity								
1.	<p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 150m²; and</p> <p>b. Compliance is achieved with NCZ-S8 (Landscaping and Screening).</p>								
2.	<p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with NCZ-R4-1.a</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Neighbourhood Centre Zone or adjacent properties. The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Neighbourhood Centre Zone. The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Neighbourhood Centre Zone. The potential of the location of the activity in the Neighbourhood Centre Zone to undermine the role and function of the City Centre Zone. The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated. <p>b. Compliance is not achieved with NCZ-R4-1.b</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The matters of discretion of the infringed standard. <p>Notification:</p> <ul style="list-style-type: none"> An application under NCZ-R4-2.b is precluded from being publicly notified in accordance with section 95A of the RMA. 								

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R5	<table border="1"> <thead> <tr> <th>NCZ-R5</th> <th>Commercial Service Activity</th> </tr> </thead> <tbody> <tr> <td>1.</td> <td> <p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 150m²; and</p> <p>b. Compliance is achieved with NCZ-S8 (Landscaping and Screening).</p> </td> </tr> <tr> <td>2.</td> <td> <p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with NCZ-R5-1.a</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Neighbourhood Centre Zone or adjacent properties. The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Neighbourhood Centre Zone. The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Neighbourhood Centre Zone. The potential of the location of the activity in the Neighbourhood Centre Zone to undermine the role and function of the City Centre Zone. The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated. <p>b. Compliance is not achieved with NCZ-R5-1.b</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The matters of discretion of the infringed standard. <p>Notification:</p> <ul style="list-style-type: none"> An application under NCZ-R5-2.b is precluded from being publicly notified in accordance with section 95A of the RMA. </td> </tr> </tbody> </table>	NCZ-R5	Commercial Service Activity	1.	<p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 150m²; and</p> <p>b. Compliance is achieved with NCZ-S8 (Landscaping and Screening).</p>	2.	<p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with NCZ-R5-1.a</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Neighbourhood Centre Zone or adjacent properties. The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Neighbourhood Centre Zone. The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Neighbourhood Centre Zone. The potential of the location of the activity in the Neighbourhood Centre Zone to undermine the role and function of the City Centre Zone. The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated. <p>b. Compliance is not achieved with NCZ-R5-1.b</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The matters of discretion of the infringed standard. <p>Notification:</p> <ul style="list-style-type: none"> An application under NCZ-R5-2.b is precluded from being publicly notified in accordance with section 95A of the RMA.
NCZ-R5	Commercial Service Activity								
1.	<p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 150m²; and</p> <p>b. Compliance is achieved with NCZ-S8 (Landscaping and Screening).</p>								
2.	<p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with NCZ-R5-1.a</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Neighbourhood Centre Zone or adjacent properties. The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Neighbourhood Centre Zone. The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Neighbourhood Centre Zone. The potential of the location of the activity in the Neighbourhood Centre Zone to undermine the role and function of the City Centre Zone. The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated. <p>b. Compliance is not achieved with NCZ-R5-1.b</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The matters of discretion of the infringed standard. <p>Notification:</p> <ul style="list-style-type: none"> An application under NCZ-R5-2.b is precluded from being publicly notified in accordance with section 95A of the RMA. 								

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R6	<table border="1"> <thead> <tr> <th>NCZ-R6</th> <th>Food and Beverage Activity</th> </tr> </thead> <tbody> <tr> <td>1.</td> <td> <p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 150m²; and</p> <p>b. Compliance is achieved with NCZ-S8 (Landscaping and Screening).</p> </td> </tr> <tr> <td>2.</td> <td> <p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with NCZ-R6-1.a</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Neighbourhood Centre Zone or adjacent properties. The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Neighbourhood Centre Zone. The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Neighbourhood Centre Zone. The potential of the location of the activity in the Neighbourhood Centre Zone to undermine the role and function of the City Centre Zone. The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated. <p>b. Compliance is not achieved with NCZ-R6-1.b</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The matters of discretion of the infringed standard. <p>Notification:</p> <ul style="list-style-type: none"> An application under NCZ-R6-2.b is precluded from being publicly notified in accordance with section 95A of the RMA. </td> </tr> </tbody> </table>	NCZ-R6	Food and Beverage Activity	1.	<p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 150m²; and</p> <p>b. Compliance is achieved with NCZ-S8 (Landscaping and Screening).</p>	2.	<p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with NCZ-R6-1.a</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Neighbourhood Centre Zone or adjacent properties. The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Neighbourhood Centre Zone. The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Neighbourhood Centre Zone. The potential of the location of the activity in the Neighbourhood Centre Zone to undermine the role and function of the City Centre Zone. The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated. <p>b. Compliance is not achieved with NCZ-R6-1.b</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The matters of discretion of the infringed standard. <p>Notification:</p> <ul style="list-style-type: none"> An application under NCZ-R6-2.b is precluded from being publicly notified in accordance with section 95A of the RMA.
NCZ-R6	Food and Beverage Activity								
1.	<p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 150m²; and</p> <p>b. Compliance is achieved with NCZ-S8 (Landscaping and Screening).</p>								
2.	<p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with NCZ-R6-1.a</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Neighbourhood Centre Zone or adjacent properties. The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Neighbourhood Centre Zone. The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Neighbourhood Centre Zone. The potential of the location of the activity in the Neighbourhood Centre Zone to undermine the role and function of the City Centre Zone. The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated. <p>b. Compliance is not achieved with NCZ-R6-1.b</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The matters of discretion of the infringed standard. <p>Notification:</p> <ul style="list-style-type: none"> An application under NCZ-R6-2.b is precluded from being publicly notified in accordance with section 95A of the RMA. 								

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R7	<table border="1"> <thead> <tr> <th>NCZ-R7</th> <th>Community Facility</th> </tr> </thead> <tbody> <tr> <td colspan="2"> <p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. The gross floor area per facility does not exceed 150m²; and</p> <p>b. Compliance is achieved with NCZ-S8 (Landscaping and Screening).</p> </td> </tr> <tr> <td colspan="2"> <p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with NCZ-R7-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the <u>Neighbourhood Centre Zone or adjacent properties.</u> The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the <u>Neighbourhood Centre Zone.</u> The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the <u>Neighbourhood Centre Zone.</u> The potential of the location of the activity in the Neighbourhood Centre Zone to undermine the role and function of the <u>City Centre Zone.</u> The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated. <p>b. Compliance is not achieved with NCZ-R7-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> The matters of discretion of the infringed standard. <p>Notification:</p> <ul style="list-style-type: none"> An application under NCZ-R7-2.b is precluded from being publicly notified in accordance with section 95A of the RMA. </td> </tr> </tbody> </table>	NCZ-R7	Community Facility	<p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. The gross floor area per facility does not exceed 150m²; and</p> <p>b. Compliance is achieved with NCZ-S8 (Landscaping and Screening).</p>		<p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with NCZ-R7-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the <u>Neighbourhood Centre Zone or adjacent properties.</u> The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the <u>Neighbourhood Centre Zone.</u> The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the <u>Neighbourhood Centre Zone.</u> The potential of the location of the activity in the Neighbourhood Centre Zone to undermine the role and function of the <u>City Centre Zone.</u> The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated. <p>b. Compliance is not achieved with NCZ-R7-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> The matters of discretion of the infringed standard. <p>Notification:</p> <ul style="list-style-type: none"> An application under NCZ-R7-2.b is precluded from being publicly notified in accordance with section 95A of the RMA. 	
NCZ-R7	Community Facility								
<p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. The gross floor area per facility does not exceed 150m²; and</p> <p>b. Compliance is achieved with NCZ-S8 (Landscaping and Screening).</p>									
<p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with NCZ-R7-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the <u>Neighbourhood Centre Zone or adjacent properties.</u> The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the <u>Neighbourhood Centre Zone.</u> The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the <u>Neighbourhood Centre Zone.</u> The potential of the location of the activity in the Neighbourhood Centre Zone to undermine the role and function of the <u>City Centre Zone.</u> The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated. <p>b. Compliance is not achieved with NCZ-R7-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> The matters of discretion of the infringed standard. <p>Notification:</p> <ul style="list-style-type: none"> An application under NCZ-R7-2.b is precluded from being publicly notified in accordance with section 95A of the RMA. 									

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R7	<table border="1"> <thead> <tr> <th>NCZ-R8</th> <th>Residential Activity</th> </tr> </thead> <tbody> <tr> <td>1.</td> <td> <p>Activity status: Permitted</p> <p>Where:</p> <p>a. No more than six residential units occupy the site; and</p> <p>b. Compliance is achieved with</p> <ul style="list-style-type: none"> i. <u>NCZ-S5 (Location of Residential Units);</u> ii. <u>NCZ-S6 (Noise and Ventilation); and</u> iii. <u>NCZ-S7 (Outdoor Living Space).</u> </td> </tr> <tr> <td>2.</td> <td> <p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with NCZ-R8-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ul style="list-style-type: none"> 1. <u>The effects of the residential activity on the existing and anticipated function and role of the Neighbourhood Centre Zone.</u> 2. <u>The potential of the residential activity to compromise activities that are enabled in the Neighbourhood Centre Zone.</u> 3. <u>The amenity for the occupiers of the residential units.</u> <p>b. Compliance is not achieved with NCZ-R8-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ul style="list-style-type: none"> 1. <u>The matters of discretion of the infringed standard.</u> <p>Notification</p> <p><u>An application under this rule where compliance is not achieved with NCZ-S5 or NCZ-S6 is precluded from being publicly notified in accordance with section 95A of the RMA.</u></p> <p><u>An application under this rule where compliance is not achieved with NCZ-S7 is precluded from being publicly or limited</u></p> </td> </tr> </tbody> </table>	NCZ-R8	Residential Activity	1.	<p>Activity status: Permitted</p> <p>Where:</p> <p>a. No more than six residential units occupy the site; and</p> <p>b. Compliance is achieved with</p> <ul style="list-style-type: none"> i. <u>NCZ-S5 (Location of Residential Units);</u> ii. <u>NCZ-S6 (Noise and Ventilation); and</u> iii. <u>NCZ-S7 (Outdoor Living Space).</u> 	2.	<p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with NCZ-R8-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ul style="list-style-type: none"> 1. <u>The effects of the residential activity on the existing and anticipated function and role of the Neighbourhood Centre Zone.</u> 2. <u>The potential of the residential activity to compromise activities that are enabled in the Neighbourhood Centre Zone.</u> 3. <u>The amenity for the occupiers of the residential units.</u> <p>b. Compliance is not achieved with NCZ-R8-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ul style="list-style-type: none"> 1. <u>The matters of discretion of the infringed standard.</u> <p>Notification</p> <p><u>An application under this rule where compliance is not achieved with NCZ-S5 or NCZ-S6 is precluded from being publicly notified in accordance with section 95A of the RMA.</u></p> <p><u>An application under this rule where compliance is not achieved with NCZ-S7 is precluded from being publicly or limited</u></p>
NCZ-R8	Residential Activity								
1.	<p>Activity status: Permitted</p> <p>Where:</p> <p>a. No more than six residential units occupy the site; and</p> <p>b. Compliance is achieved with</p> <ul style="list-style-type: none"> i. <u>NCZ-S5 (Location of Residential Units);</u> ii. <u>NCZ-S6 (Noise and Ventilation); and</u> iii. <u>NCZ-S7 (Outdoor Living Space).</u> 								
2.	<p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with NCZ-R8-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ul style="list-style-type: none"> 1. <u>The effects of the residential activity on the existing and anticipated function and role of the Neighbourhood Centre Zone.</u> 2. <u>The potential of the residential activity to compromise activities that are enabled in the Neighbourhood Centre Zone.</u> 3. <u>The amenity for the occupiers of the residential units.</u> <p>b. Compliance is not achieved with NCZ-R8-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ul style="list-style-type: none"> 1. <u>The matters of discretion of the infringed standard.</u> <p>Notification</p> <p><u>An application under this rule where compliance is not achieved with NCZ-S5 or NCZ-S6 is precluded from being publicly notified in accordance with section 95A of the RMA.</u></p> <p><u>An application under this rule where compliance is not achieved with NCZ-S7 is precluded from being publicly or limited</u></p>								


IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			<p><u>notified in accordance with section 95A of the RMA.</u></p>						
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R9	<table border="1"> <thead> <tr> <th>NCZ-R9</th> <th>Healthcare Activity</th> </tr> </thead> <tbody> <tr> <td>1.</td> <td> <p><u>Activity status: Restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is achieved with NCZ-S8 (Landscaping and Screening).</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the activity may adversely impact on the amenity of the Neighbourhood Centre Zone or adjacent properties.</u> <u>The effects of the activity on the existing and anticipated function and role of the Neighbourhood Centre Zone.</u> <u>The potential of the activity to compromise activities that are enabled in the Neighbourhood Centre Zone.</u> <u>The potential of the location of the activity in the Neighbourhood Centre Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated.</u> </td> </tr> <tr> <td>2.</td> <td> <p><u>Activity status: Discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with NCZ-R9-1.a</u></p> </td> </tr> </tbody> </table>	NCZ-R9	Healthcare Activity	1.	<p><u>Activity status: Restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is achieved with NCZ-S8 (Landscaping and Screening).</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the activity may adversely impact on the amenity of the Neighbourhood Centre Zone or adjacent properties.</u> <u>The effects of the activity on the existing and anticipated function and role of the Neighbourhood Centre Zone.</u> <u>The potential of the activity to compromise activities that are enabled in the Neighbourhood Centre Zone.</u> <u>The potential of the location of the activity in the Neighbourhood Centre Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated.</u> 	2.	<p><u>Activity status: Discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with NCZ-R9-1.a</u></p>
NCZ-R9	Healthcare Activity								
1.	<p><u>Activity status: Restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is achieved with NCZ-S8 (Landscaping and Screening).</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the activity may adversely impact on the amenity of the Neighbourhood Centre Zone or adjacent properties.</u> <u>The effects of the activity on the existing and anticipated function and role of the Neighbourhood Centre Zone.</u> <u>The potential of the activity to compromise activities that are enabled in the Neighbourhood Centre Zone.</u> <u>The potential of the location of the activity in the Neighbourhood Centre Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated.</u> 								
2.	<p><u>Activity status: Discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with NCZ-R9-1.a</u></p>								
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R10	<table border="1"> <thead> <tr> <th>NCZ-R10</th> <th>Educational Facility</th> </tr> </thead> <tbody> <tr> <td>1.</td> <td> <p><u>Activity status: Restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is achieved with NCZ-S8 (Landscaping and Screening).</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the activity may adversely impact on the amenity of the Neighbourhood Centre Zone or</u> </td> </tr> </tbody> </table>	NCZ-R10	Educational Facility	1.	<p><u>Activity status: Restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is achieved with NCZ-S8 (Landscaping and Screening).</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the activity may adversely impact on the amenity of the Neighbourhood Centre Zone or</u> 		
NCZ-R10	Educational Facility								
1.	<p><u>Activity status: Restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is achieved with NCZ-S8 (Landscaping and Screening).</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the activity may adversely impact on the amenity of the Neighbourhood Centre Zone or</u> 								

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<p><u>adjacent properties.</u></p> <ol style="list-style-type: none"> 2. <u>The effects of the activity on the existing and anticipated function and role of the Neighbourhood Centre Zone.</u> 3. <u>The potential of the activity to compromise activities that are enabled in the Neighbourhood Centre Zone.</u> 4. <u>The potential of the location of the activity in the Neighbourhood Centre Zone to undermine the role and function of the City Centre Zone.</u> 5. <u>The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>2. <u>Activity status: Discretionary</u></p> <p><u>Where:</u></p> <ol style="list-style-type: none"> a. <u>Compliance is not achieved with NCZ-R10-1.a</u> 				
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R11	<table border="1"> <thead> <tr> <th><u>NCZ-R11</u></th> <th><u>Emergency Service Facility</u></th> </tr> </thead> <tbody> <tr> <td colspan="2"> <p>1. <u>Activity status: Restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is achieved with NCZ-S8 (Landscaping and Screening).</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The extent to which the activity may adversely impact on the amenity of the Neighbourhood Centre Zone or adjacent properties.</u> 2. <u>The effects of the of the activity on the existing and anticipated function and role of the Neighbourhood Centre Zone.</u> 3. <u>The potential of the activity to compromise activities that are enabled in the Neighbourhood Centre Zone.</u> 4. <u>The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated.</u> 5. <u>The functional need or operational need for the Emergency Service Facility to be located in the Neighbourhood Centre Zone.</u> <p>Notification:</p> </td> </tr> </tbody> </table>	<u>NCZ-R11</u>	<u>Emergency Service Facility</u>	<p>1. <u>Activity status: Restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is achieved with NCZ-S8 (Landscaping and Screening).</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The extent to which the activity may adversely impact on the amenity of the Neighbourhood Centre Zone or adjacent properties.</u> 2. <u>The effects of the of the activity on the existing and anticipated function and role of the Neighbourhood Centre Zone.</u> 3. <u>The potential of the activity to compromise activities that are enabled in the Neighbourhood Centre Zone.</u> 4. <u>The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated.</u> 5. <u>The functional need or operational need for the Emergency Service Facility to be located in the Neighbourhood Centre Zone.</u> <p>Notification:</p>	
<u>NCZ-R11</u>	<u>Emergency Service Facility</u>						
<p>1. <u>Activity status: Restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is achieved with NCZ-S8 (Landscaping and Screening).</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The extent to which the activity may adversely impact on the amenity of the Neighbourhood Centre Zone or adjacent properties.</u> 2. <u>The effects of the of the activity on the existing and anticipated function and role of the Neighbourhood Centre Zone.</u> 3. <u>The potential of the activity to compromise activities that are enabled in the Neighbourhood Centre Zone.</u> 4. <u>The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated.</u> 5. <u>The functional need or operational need for the Emergency Service Facility to be located in the Neighbourhood Centre Zone.</u> <p>Notification:</p>							


IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change				
			<ul style="list-style-type: none"> An application under this rule is precluded from being publicly notified in accordance with section 95A of the RMA. <p>2. Activity status: Discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with NCZ-R11-1.a</p>				
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R12	<table border="1"> <tr> <td>NCZ-R12</td> <td>Visitor Accommodation</td> </tr> <tr> <td colspan="2">1. Activity status: Discretionary</td> </tr> </table>	NCZ-R12	Visitor Accommodation	1. Activity status: Discretionary	
NCZ-R12	Visitor Accommodation						
1. Activity status: Discretionary							
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R13	<table border="1"> <tr> <td>NCZ-R13</td> <td>Sport and Active Recreation Activity</td> </tr> <tr> <td colspan="2">1. Activity status: Discretionary</td> </tr> </table>	NCZ-R13	Sport and Active Recreation Activity	1. Activity status: Discretionary	
NCZ-R13	Sport and Active Recreation Activity						
1. Activity status: Discretionary							
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R14	<table border="1"> <tr> <td>NCZ-R14</td> <td>Entertainment Facility</td> </tr> <tr> <td colspan="2">1. Activity status: Discretionary</td> </tr> </table>	NCZ-R14	Entertainment Facility	1. Activity status: Discretionary	
NCZ-R14	Entertainment Facility						
1. Activity status: Discretionary							
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R15	<table border="1"> <tr> <td>NCZ-R15</td> <td>Office Activity</td> </tr> <tr> <td colspan="2">1. Activity status: Discretionary</td> </tr> </table>	NCZ-R15	Office Activity	1. Activity status: Discretionary	
NCZ-R15	Office Activity						
1. Activity status: Discretionary							
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R16	<table border="1"> <tr> <td>NCZ-R16</td> <td>Large Format Retail Activity</td> </tr> <tr> <td colspan="2">1. Activity status: Discretionary</td> </tr> </table>	NCZ-R16	Large Format Retail Activity	1. Activity status: Discretionary	
NCZ-R16	Large Format Retail Activity						
1. Activity status: Discretionary							
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R17	<table border="1"> <tr> <td>NCZ-R17</td> <td>Drive-through Activity</td> </tr> <tr> <td colspan="2">1. Activity status: Discretionary</td> </tr> </table>	NCZ-R17	Drive-through Activity	1. Activity status: Discretionary	
NCZ-R17	Drive-through Activity						
1. Activity status: Discretionary							
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R18	<table border="1"> <tr> <td>NCZ-R18</td> <td>Retirement Village</td> </tr> <tr> <td colspan="2">1. Activity status: Discretionary</td> </tr> </table>	NCZ-R18	Retirement Village	1. Activity status: Discretionary	
NCZ-R18	Retirement Village						
1. Activity status: Discretionary							
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R19	<table border="1"> <tr> <td>NCZ-R19</td> <td>Any activity not otherwise listed as permitted, restricted discretionary, discretionary, or non-complying</td> </tr> <tr> <td colspan="2">1. Activity status: Discretionary</td> </tr> </table>	NCZ-R19	Any activity not otherwise listed as permitted, restricted discretionary, discretionary, or non-complying	1. Activity status: Discretionary	
NCZ-R19	Any activity not otherwise listed as permitted, restricted discretionary, discretionary, or non-complying						
1. Activity status: Discretionary							

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R20	<table border="1"> <tr> <td>NCZ-R20</td> <td>Industrial Activity</td> </tr> <tr> <td colspan="2">1. Activity status: Non-complying</td> </tr> </table>	NCZ-R20	Industrial Activity	1. Activity status: Non-complying			
NCZ-R20	Industrial Activity								
1. Activity status: Non-complying									
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R21	<table border="1"> <tr> <td>NCZ-R21</td> <td>Yard Sale Activity / Trade Supplier</td> </tr> <tr> <td colspan="2">1. Activity status: Non-complying</td> </tr> </table>	NCZ-R21	Yard Sale Activity / Trade Supplier	1. Activity status: Non-complying			
NCZ-R21	Yard Sale Activity / Trade Supplier								
1. Activity status: Non-complying									
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R22	<table border="1"> <tr> <td>NCZ-R22</td> <td>Motorised Recreation</td> </tr> <tr> <td colspan="2">1. Activity status: Non-complying</td> </tr> </table>	NCZ-R22	Motorised Recreation	1. Activity status: Non-complying			
NCZ-R22	Motorised Recreation								
1. Activity status: Non-complying									
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R23	<table border="1"> <tr> <td>NCZ-R23</td> <td>Rural Industry</td> </tr> <tr> <td colspan="2">1. Activity status: Non-complying</td> </tr> </table>	NCZ-R23	Rural Industry	1. Activity status: Non-complying			
NCZ-R23	Rural Industry								
1. Activity status: Non-complying									
	New NCZ - Neighbourhood Centre Zone	Introduce new Rule NCZ-R24	<table border="1"> <tr> <td>NCZ-R24</td> <td>Primary Production</td> </tr> <tr> <td colspan="2">1. Activity status: Non-complying</td> </tr> </table>	NCZ-R24	Primary Production	1. Activity status: Non-complying			
NCZ-R24	Primary Production								
1. Activity status: Non-complying									
	New NCZ - Neighbourhood Centre Zone	Introduce new Standard NCZ-S1	<table border="1"> <tr> <td colspan="2">Activity Standards</td> </tr> <tr> <td>NCZ-S1</td> <td>Height</td> </tr> <tr> <td> <p>1. Buildings must not exceed 11 metres in height, except that 50% of a building's roof in elevation, measured vertically from the junction between wall and roof, may exceed this height by 1 metre, where the entire roof slopes 15° or more, as shown on the following diagram:</p> </td> <td> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>The location, design and appearance of the building or structure.</u> 2. <u>Any adverse effects on the streetscape.</u> 3. <u>Visual dominance, shading and loss of privacy for adjoining Residential or Open Space and Recreation zoned sites.</u> 4. <u>Compatibility with the planned built urban form of buildings, structures and activities in the surrounding area.</u> </td> </tr> </table>	Activity Standards		NCZ-S1	Height	<p>1. Buildings must not exceed 11 metres in height, except that 50% of a building's roof in elevation, measured vertically from the junction between wall and roof, may exceed this height by 1 metre, where the entire roof slopes 15° or more, as shown on the following diagram:</p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>The location, design and appearance of the building or structure.</u> 2. <u>Any adverse effects on the streetscape.</u> 3. <u>Visual dominance, shading and loss of privacy for adjoining Residential or Open Space and Recreation zoned sites.</u> 4. <u>Compatibility with the planned built urban form of buildings, structures and activities in the surrounding area.</u>
Activity Standards									
NCZ-S1	Height								
<p>1. Buildings must not exceed 11 metres in height, except that 50% of a building's roof in elevation, measured vertically from the junction between wall and roof, may exceed this height by 1 metre, where the entire roof slopes 15° or more, as shown on the following diagram:</p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>The location, design and appearance of the building or structure.</u> 2. <u>Any adverse effects on the streetscape.</u> 3. <u>Visual dominance, shading and loss of privacy for adjoining Residential or Open Space and Recreation zoned sites.</u> 4. <u>Compatibility with the planned built urban form of buildings, structures and activities in the surrounding area.</u> 								

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			 <p>2. <u>Any fence or standalone wall along a side or rear boundary which adjoins a site zoned Residential or Open Space and Recreation must not exceed 2m in height.</u></p> <p>This standard does not apply to:</p> <ol style="list-style-type: none"> <u>Solar water heating components provided these do not exceed the height by more than 1m.</u> <u>Chimney structures not exceeding 1.1m in width on any elevation and provided these do not exceed the height by more than 1m.</u> <u>Antennas, aerials, and flues provided these do not exceed the height by more than 1m.</u> <u>Satellite dishes (less than 1m in diameter) and architectural features (e.g. finials, spires) provided these do not exceed the height by more than 1m.</u> <u>Lift overruns provided these do not exceed the height by more than 1m.</u> <p>5. <u>Whether the building height is commensurate with the anticipated level of commercial activities and community services in the Neighbourhood Centre Zone;</u></p> <p>6. <u>Whether an increase in building height results from a response to natural hazard mitigation.</u></p> <p>7. <u>Whether topographical or other site constraints make compliance with the standard impractical.</u></p>						
	New NCZ - Neighbourhood Centre Zone	Introduce new Standard NCZ-S2	<table border="1"> <tr> <td><u>NCZ-S2</u></td> <td><u>Height in Relation to Boundary</u></td> </tr> <tr> <td colspan="2">Where the side or rear boundary of a site adjoins a Residential Zone or Open Space and Recreation Zone the following Height in Relation to Boundary standard applies:</td> </tr> <tr> <td colspan="2">Matters of discretion are restricted to:</td> </tr> </table>	<u>NCZ-S2</u>	<u>Height in Relation to Boundary</u>	Where the side or rear boundary of a site adjoins a Residential Zone or Open Space and Recreation Zone the following Height in Relation to Boundary standard applies:		Matters of discretion are restricted to:	
<u>NCZ-S2</u>	<u>Height in Relation to Boundary</u>								
Where the side or rear boundary of a site adjoins a Residential Zone or Open Space and Recreation Zone the following Height in Relation to Boundary standard applies:									
Matters of discretion are restricted to:									

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
			<p>1. <u>Buildings must not project beyond a 60° recession plane measured from a point 4 metres vertically above ground level along all boundaries, as shown on the following diagram. Where the boundary forms part of a legal right of way, entrance strip, access site, or pedestrian access way, the height in relation to boundary applies from the farthest boundary of that legal right of way, entrance strip, access site, or pedestrian access way.</u></p>  <p>The diagram illustrates a 60-degree recession plane. A vertical dashed line represents the 'Boundary'. A horizontal line represents the 'Ground level'. A point is marked '4m' vertically above the ground level. A dashed line extends from this point at a 60-degree angle to the boundary. A solid line represents the 'Building' facade, which is shown to be within the recession plane. A vertical dimension of '1.1m' is shown for the building's height.</p> <p>This standard does not apply to:</p> <ol style="list-style-type: none"> <u>A boundary with a road.</u> <u>Existing or proposed internal boundaries within a site.</u> <u>Site boundaries where there is an existing common wall between 2 buildings on adjacent sites or where a common wall is proposed.</u> <u>Solar water heating components provided these do not exceed the height in relation to boundary by more than 1m.</u> <u>Chimney structures not exceeding 1.1m in width on any elevation and provided these do not exceed the height in relation to boundary by more than 1m.</u>

- Visual dominance, shading and loss of privacy for adjoining Residential or Open Space and Recreation zoned sites.
- The location, design and appearance of the building or structure.
- Whether an increase in height in relation to boundary results from a response to natural hazard mitigation.
- Whether any architectural features or steps are proposed in the building façade to provide an attractive appearance when viewed from adjoining Residential or Open Space and Recreation zoned sites.

IPI - PROPOSED AMENDMENTS													
#	Chapter	Change	Track Change										
			<p>f. Antennas, aerials, satellite dishes (less than 1m in diameter), flues, and architectural features (e.g. finials, spires) provided these do not exceed the height in relation to boundary by more than 3m measured vertically.</p>										
	New NCZ - Neighbourhood Centre Zone	Introduce new Standard NCZ-S3	<table border="1"> <thead> <tr> <th>NCZ-S3</th> <th>Setback</th> </tr> </thead> <tbody> <tr> <td> <p>Where the side or rear boundary of a site adjoins a Residential Zone or Open Space and Recreation Zone the following Setback standard applies:</p> <p>1. Buildings must be set back from the relevant boundary by the minimum depth listed in the yards table below:</p> <table border="1"> <thead> <tr> <th>Yard</th> <th>Minimum depth</th> </tr> </thead> <tbody> <tr> <td>Side</td> <td>1 metre</td> </tr> <tr> <td>Rear</td> <td>1 metre</td> </tr> </tbody> </table> <p>2. This standard does not apply to site boundaries where there is an existing common wall between 2 buildings on adjacent sites or where a common wall is proposed.</p> <p>3. This standard does not apply to:</p> <p>a. Accessory buildings less than 2m in height.</p> <p>b. Fences and standalone walls.</p> </td> <td> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>The visual amenity of adjoining Residential and Open Space and Recreation sites.</u> 2. <u>The location, design and appearance of the building or structure.</u> 3. <u>Whether any architectural features or steps are proposed in the building façade to provide an attractive appearance when viewed from adjoining Residential or Open Space and Recreation sites.</u> 4. <u>Any benefits, including the extent to which the reduced setback will result in a more efficient, practical and better use of the balance of the site.</u> </td> </tr> </tbody> </table>	NCZ-S3	Setback	<p>Where the side or rear boundary of a site adjoins a Residential Zone or Open Space and Recreation Zone the following Setback standard applies:</p> <p>1. Buildings must be set back from the relevant boundary by the minimum depth listed in the yards table below:</p> <table border="1"> <thead> <tr> <th>Yard</th> <th>Minimum depth</th> </tr> </thead> <tbody> <tr> <td>Side</td> <td>1 metre</td> </tr> <tr> <td>Rear</td> <td>1 metre</td> </tr> </tbody> </table> <p>2. This standard does not apply to site boundaries where there is an existing common wall between 2 buildings on adjacent sites or where a common wall is proposed.</p> <p>3. This standard does not apply to:</p> <p>a. Accessory buildings less than 2m in height.</p> <p>b. Fences and standalone walls.</p>	Yard	Minimum depth	Side	1 metre	Rear	1 metre	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>The visual amenity of adjoining Residential and Open Space and Recreation sites.</u> 2. <u>The location, design and appearance of the building or structure.</u> 3. <u>Whether any architectural features or steps are proposed in the building façade to provide an attractive appearance when viewed from adjoining Residential or Open Space and Recreation sites.</u> 4. <u>Any benefits, including the extent to which the reduced setback will result in a more efficient, practical and better use of the balance of the site.</u>
NCZ-S3	Setback												
<p>Where the side or rear boundary of a site adjoins a Residential Zone or Open Space and Recreation Zone the following Setback standard applies:</p> <p>1. Buildings must be set back from the relevant boundary by the minimum depth listed in the yards table below:</p> <table border="1"> <thead> <tr> <th>Yard</th> <th>Minimum depth</th> </tr> </thead> <tbody> <tr> <td>Side</td> <td>1 metre</td> </tr> <tr> <td>Rear</td> <td>1 metre</td> </tr> </tbody> </table> <p>2. This standard does not apply to site boundaries where there is an existing common wall between 2 buildings on adjacent sites or where a common wall is proposed.</p> <p>3. This standard does not apply to:</p> <p>a. Accessory buildings less than 2m in height.</p> <p>b. Fences and standalone walls.</p>	Yard	Minimum depth	Side	1 metre	Rear	1 metre	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>The visual amenity of adjoining Residential and Open Space and Recreation sites.</u> 2. <u>The location, design and appearance of the building or structure.</u> 3. <u>Whether any architectural features or steps are proposed in the building façade to provide an attractive appearance when viewed from adjoining Residential or Open Space and Recreation sites.</u> 4. <u>Any benefits, including the extent to which the reduced setback will result in a more efficient, practical and better use of the balance of the site.</u> 						
Yard	Minimum depth												
Side	1 metre												
Rear	1 metre												
	New NCZ - Neighbourhood Centre Zone	Introduce new Standard NCZ-S4	<table border="1"> <thead> <tr> <th>NCZ-S4</th> <th>Active Frontages</th> </tr> </thead> <tbody> <tr> <td> <p>1. All new buildings must be built up to and oriented towards the front boundary of the site.</p> <p>2. At least 55% of the ground floor frontage of a building fronting a street, pedestrian mall or other public space must display windows or transparent glazing.</p> </td> <td> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>The effects on the amenity and quality of the streetscape.</u> 2. <u>The design and appearance of the street frontage.</u> </td> </tr> </tbody> </table>	NCZ-S4	Active Frontages	<p>1. All new buildings must be built up to and oriented towards the front boundary of the site.</p> <p>2. At least 55% of the ground floor frontage of a building fronting a street, pedestrian mall or other public space must display windows or transparent glazing.</p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>The effects on the amenity and quality of the streetscape.</u> 2. <u>The design and appearance of the street frontage.</u> 						
NCZ-S4	Active Frontages												
<p>1. All new buildings must be built up to and oriented towards the front boundary of the site.</p> <p>2. At least 55% of the ground floor frontage of a building fronting a street, pedestrian mall or other public space must display windows or transparent glazing.</p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>The effects on the amenity and quality of the streetscape.</u> 2. <u>The design and appearance of the street frontage.</u> 												

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<p>3. <u>The principal public entrance to the building must be located on the front boundary.</u></p> <p>3. <u>The ability to reuse and adapt the building for a variety of activities.</u></p>				
	New NCZ - Neighbourhood Centre Zone	Introduce new Standard NCZ-S5	<table border="1"> <thead> <tr> <th>NCZ-S5</th> <th>Location of Residential Units</th> </tr> </thead> <tbody> <tr> <td> <p>1. All residential units must be located above ground floor level, except that residential units may be located on the ground floor where:</p> <p>a. <u>No part of the residential unit fronts onto a public open space, including roads; and</u></p> <p>b. <u>They do not interrupt or prevent an active frontage as required by NCZ-S4.</u></p> </td> <td> <p>Matters of discretion are restricted to:</p> <p>1. <u>The effects on the amenity and quality of the streetscape.</u></p> <p>2. <u>The amenity for the occupiers of the residential units.</u></p> </td> </tr> </tbody> </table>	NCZ-S5	Location of Residential Units	<p>1. All residential units must be located above ground floor level, except that residential units may be located on the ground floor where:</p> <p>a. <u>No part of the residential unit fronts onto a public open space, including roads; and</u></p> <p>b. <u>They do not interrupt or prevent an active frontage as required by NCZ-S4.</u></p>	<p>Matters of discretion are restricted to:</p> <p>1. <u>The effects on the amenity and quality of the streetscape.</u></p> <p>2. <u>The amenity for the occupiers of the residential units.</u></p>
NCZ-S5	Location of Residential Units						
<p>1. All residential units must be located above ground floor level, except that residential units may be located on the ground floor where:</p> <p>a. <u>No part of the residential unit fronts onto a public open space, including roads; and</u></p> <p>b. <u>They do not interrupt or prevent an active frontage as required by NCZ-S4.</u></p>	<p>Matters of discretion are restricted to:</p> <p>1. <u>The effects on the amenity and quality of the streetscape.</u></p> <p>2. <u>The amenity for the occupiers of the residential units.</u></p>						
	New NCZ - Neighbourhood Centre Zone	Introduce new Standard NCZ-S6	<table border="1"> <thead> <tr> <th>NCZ-S6</th> <th>Noise and Ventilation</th> </tr> </thead> <tbody> <tr> <td> <p>1. All residential units must meet the following standards:</p> <p>a. <u>All habitable rooms must be designed and constructed to meet internal sound insulation levels achieving DnT,w+Ctr >30dB with an acoustic design certificate signed by a qualified acoustic engineer stating compliance will be achieved; and</u></p> <p>b. <u>All habitable rooms must have a positive supplementary source of fresh air ducted from outside. The supplementary source of air is to achieve a minimum of 7.5 litres per second per person.</u></p> </td> <td> <p>Matters of discretion are restricted to:</p> <p>1. <u>Any potential reverse sensitivity effects on the continued operation of non- residential activities.</u></p> <p>2. <u>The amenity for the occupiers of the residential units.</u></p> </td> </tr> </tbody> </table>	NCZ-S6	Noise and Ventilation	<p>1. All residential units must meet the following standards:</p> <p>a. <u>All habitable rooms must be designed and constructed to meet internal sound insulation levels achieving DnT,w+Ctr >30dB with an acoustic design certificate signed by a qualified acoustic engineer stating compliance will be achieved; and</u></p> <p>b. <u>All habitable rooms must have a positive supplementary source of fresh air ducted from outside. The supplementary source of air is to achieve a minimum of 7.5 litres per second per person.</u></p>	<p>Matters of discretion are restricted to:</p> <p>1. <u>Any potential reverse sensitivity effects on the continued operation of non- residential activities.</u></p> <p>2. <u>The amenity for the occupiers of the residential units.</u></p>
NCZ-S6	Noise and Ventilation						
<p>1. All residential units must meet the following standards:</p> <p>a. <u>All habitable rooms must be designed and constructed to meet internal sound insulation levels achieving DnT,w+Ctr >30dB with an acoustic design certificate signed by a qualified acoustic engineer stating compliance will be achieved; and</u></p> <p>b. <u>All habitable rooms must have a positive supplementary source of fresh air ducted from outside. The supplementary source of air is to achieve a minimum of 7.5 litres per second per person.</u></p>	<p>Matters of discretion are restricted to:</p> <p>1. <u>Any potential reverse sensitivity effects on the continued operation of non- residential activities.</u></p> <p>2. <u>The amenity for the occupiers of the residential units.</u></p>						
	New NCZ - Neighbourhood Centre Zone	Introduce new Standard NCZ-S7	<table border="1"> <thead> <tr> <th>NCZ-S7</th> <th>Outdoor Living Space</th> </tr> </thead> <tbody> <tr> <td> <p>1. Each residential unit at ground floor level must have an outdoor living space that is at least 20 square metres and that comprises ground floor, balcony, patio, or roof terrace space that,—</p> </td> <td> <p>Matters of discretion are restricted to:</p> <p>1. <u>Whether adequate useable space is provided to accommodate outdoor activities.</u></p> </td> </tr> </tbody> </table>	NCZ-S7	Outdoor Living Space	<p>1. Each residential unit at ground floor level must have an outdoor living space that is at least 20 square metres and that comprises ground floor, balcony, patio, or roof terrace space that,—</p>	<p>Matters of discretion are restricted to:</p> <p>1. <u>Whether adequate useable space is provided to accommodate outdoor activities.</u></p>
NCZ-S7	Outdoor Living Space						
<p>1. Each residential unit at ground floor level must have an outdoor living space that is at least 20 square metres and that comprises ground floor, balcony, patio, or roof terrace space that,—</p>	<p>Matters of discretion are restricted to:</p> <p>1. <u>Whether adequate useable space is provided to accommodate outdoor activities.</u></p>						

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>a. where located at ground level, has no dimension less than 3 metres; and</p> <p>b. where provided in the form of a balcony, patio, or roof terrace, is at least 8 square metres and has a minimum dimension of 1.8 metres; and</p> <p>e. is accessible from the residential unit; and</p> <p>d. may be —</p> <p>i. grouped cumulatively by area in 1 communally accessible location; or</p> <p>ii. located directly adjacent to the unit; and</p> <p>e. is free of buildings, parking spaces, and servicing and manoeuvring areas.</p> <p>2. Each residential unit located above ground floor level must have an outdoor living space in the form of a balcony, patio, or roof terrace that —</p> <p>a. is at least 8 square metres and has a minimum dimension of 1.8 metres; and</p> <p>b. is accessible from the residential unit; and</p> <p>e. may be —</p> <p>i. grouped cumulatively by area in 1 communally accessible location, in which case it may be located at ground level; or</p> <p>ii. located directly adjacent to the unit.</p> <p>3. For multi-unit housing, the outdoor living space can be provided as private space and shared space where:</p> <p>a. Each residential unit is provided with a private outdoor living space that has a minimum area of 8m²</p> <p>2. <u>Whether there are topographical or other site constraints that make compliance with the standard impractical.</u></p> <p>3. <u>The proximity of the residential unit to accessible public open space.</u></p>

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change									
			<p>with a minimum dimension of 1.8m, that is directly accessible from the residential unit to which it relates;</p> <p>b. The shared outdoor living space has a minimum area of 20m² with a minimum dimension of 3m; and</p> <p>c. Any ground floor outdoor living space is free of buildings, parking spaces and manoeuvring areas.</p> <p><u>1. Each residential unit, including any dual key unit, must be provided with either a private outdoor living space or access to a communal outdoor living space;</u></p> <p><u>2. Where private outdoor living space is provided it must be:</u></p> <ul style="list-style-type: none"> <u>i For the exclusive use of residents;</u> <u>ii Directly accessible from a habitable room;</u> <u>iii A single contiguous space; and</u> <u>iv Of the minimum area and dimension specified in the table below;</u> <p><u>3. Where communal outdoor living space is provided it does not need to be in a single continuous space, but it must be:</u></p> <ul style="list-style-type: none"> <u>i Accessible from the residential units it serves;</u> <u>ii Of the minimum area and dimension specified in the table below; and</u> <u>iii Free of buildings, parking spaces, and servicing and manoeuvring areas.</u> <table border="1"> <thead> <tr> <th><u>Living Space Type</u></th> <th><u>Minimum area</u></th> <th><u>Minimum dimension</u></th> </tr> </thead> <tbody> <tr> <td><u>1. Private</u></td> <td></td> <td></td> </tr> <tr> <td><u>i Studio unit & 1 bedroom unit</u></td> <td><u>5m²</u></td> <td><u>1.8m</u></td> </tr> </tbody> </table>	<u>Living Space Type</u>	<u>Minimum area</u>	<u>Minimum dimension</u>	<u>1. Private</u>			<u>i Studio unit & 1 bedroom unit</u>	<u>5m²</u>	<u>1.8m</u>
<u>Living Space Type</u>	<u>Minimum area</u>	<u>Minimum dimension</u>										
<u>1. Private</u>												
<u>i Studio unit & 1 bedroom unit</u>	<u>5m²</u>	<u>1.8m</u>										

Commented [MM189]: S58.216 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS												
#	Chapter	Change	Track Change									
			<table border="1"> <tr> <td>ii 2+ bedroom unit</td> <td>8m²</td> <td>1.8m</td> </tr> <tr> <td>1. Communal</td> <td></td> <td></td> </tr> <tr> <td>For every 5 units</td> <td>10m² (per residential unit)</td> <td>8m diameter</td> </tr> </table>	ii 2+ bedroom unit	8m ²	1.8m	1. Communal			For every 5 units	10m ² (per residential unit)	8m diameter
ii 2+ bedroom unit	8m ²	1.8m										
1. Communal												
For every 5 units	10m ² (per residential unit)	8m diameter										
New NCZ - Neighbourhood Centre Zone	Introduce new Standard NCZ-S8	<p>NCZ-S8 Screening and Landscaping of Service Areas, Outdoor Storage Areas and Parking Areas</p> <p>1. <u>Any on-site service areas, including rubbish collection areas, and areas for the outdoor storage of goods or materials must, without preventing the provision of an entry point to the site, be adequately screened by a fence or landscaping where they are visible from any:</u></p> <p>a. <u>Public road;</u></p> <p>b. <u>Other public space; or</u></p> <p>c. <u>Directly adjoining site zoned Residential or Open Space and Recreation.</u></p> <p>2. <u>Any on-site parking areas must be adequately screened by a fence or landscaping from any directly adjoining site zoned Residential or Open Space and Recreation.</u></p>	<p><u>Matters of discretion are restricted to:</u></p> <p>1. <u>Any adverse effects on the streetscape.</u></p> <p>2. <u>The visual amenity of adjoining Residential and Open Space and Recreation zoned sites including shading.</u></p> <p>3. <u>The service, storage and parking needs of the activity.</u></p> <p>4. <u>The size and location of service, storage and any parking areas.</u></p>									
New NCZ - Neighbourhood Centre Zone	Introduce new Standard NCZ-S9	<p>NCZ-S9 Water Supply, Stormwater and Wastewater</p> <p>1. <u>All activities must comply with the water supply, stormwater and wastewater standards in the Code of Practice for Civil Engineering Works.</u></p>	<p><u>Matters of discretion are restricted to:</u></p> <p>1. <u>Whether the Water Supply, Stormwater and Wastewater infrastructure has sufficient capacity to accommodate the activity.</u></p> <p>2. <u>Any alternative measures proposed to mitigate adverse effects on the Water Supply, Stormwater and Wastewater infrastructure network.</u></p>									

Commented [MM190]: S58.216 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			<p>3. <u>Whether the additional demand generated will necessitate additional unplanned public investment in, or expansion of, the Water Supply, Stormwater and Wastewater infrastructure network or compromise its ability to service other activities permitted within the zone.</u></p> <p>4. <u>Whether the development can achieve hydraulic neutrality.</u></p> <p>5. <u>The extent to which the development incorporates stormwater management techniques or controls to mitigate any increase in pre-development peak stormwater runoff.</u></p>						
	New NCZ - Neighbourhood Centre Zone	Introduce new standard NCZ-S10	<table border="1"> <tr> <td>NCZ-S10</td> <td>Hydraulic neutrality</td> </tr> <tr> <td colspan="2"> <p>New buildings and development must be designed to achieve hydraulic neutrality ensure that the stormwater runoff from all new impermeable surfaces will be disposed of or stored on-site and released at a rate that does not exceed the peak stormwater runoff when compared to the pre-development situation for the 10% and 1% rainfall Annual Exceedance Probability event.</p> </td> </tr> <tr> <td colspan="2"> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Methods to avoid, remedy or mitigate any adverse effects resulting from any increase in pre-development peak stormwater runoff.</u> 2. <u>Cumulative effects.</u> </td> </tr> </table>	NCZ-S10	Hydraulic neutrality	<p>New buildings and development must be designed to achieve hydraulic neutrality ensure that the stormwater runoff from all new impermeable surfaces will be disposed of or stored on-site and released at a rate that does not exceed the peak stormwater runoff when compared to the pre-development situation for the 10% and 1% rainfall Annual Exceedance Probability event.</p>		<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Methods to avoid, remedy or mitigate any adverse effects resulting from any increase in pre-development peak stormwater runoff.</u> 2. <u>Cumulative effects.</u> 	
NCZ-S10	Hydraulic neutrality								
<p>New buildings and development must be designed to achieve hydraulic neutrality ensure that the stormwater runoff from all new impermeable surfaces will be disposed of or stored on-site and released at a rate that does not exceed the peak stormwater runoff when compared to the pre-development situation for the 10% and 1% rainfall Annual Exceedance Probability event.</p>									
<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Methods to avoid, remedy or mitigate any adverse effects resulting from any increase in pre-development peak stormwater runoff.</u> 2. <u>Cumulative effects.</u> 									
	New NCZ - Neighbourhood Centre Zone	Introduce new NCZ – Site Specific Controls	<p>NCZ – Site Specific Controls</p> <p>The following site specific controls apply to the site identified in NCZ-Figure1 below. The controls apply in addition to the provisions of the underlying Neighbourhood Centre Zone. Where there is any conflict between the provisions the site specific controls shall prevail.</p> <table border="1"> <tr> <td colspan="2">Rules</td> </tr> <tr> <td>NCZ-SSC-R1</td> <td>Retail activity not exceeding 500m² gross floor area, restaurants, office activities, early childhood centre, residential accommodation (including at ground level)</td> </tr> </table>	Rules		NCZ-SSC-R1	Retail activity not exceeding 500m ² gross floor area, restaurants, office activities, early childhood centre, residential accommodation (including at ground level)		
Rules									
NCZ-SSC-R1	Retail activity not exceeding 500m ² gross floor area, restaurants, office activities, early childhood centre, residential accommodation (including at ground level)								

Commented [MM191]: S58.219 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS											
#	Chapter	Change	Track Change								
			<p>1. Activity status: Permitted</p>								
		NCZ-SSC-R2	Garden centres and all activities other than retail activity, restaurants, offices activities, early childhood centres and residential accommodation (including at ground level)								
			1. Activity Status: Discretionary								
			Activity Standards								
		NCZ-SSC-S1	Setback from boundaries								
			1. The setback distance for buildings from boundaries shall be not less than:								
			<table border="1"> <tbody> <tr> <td>a. Front boundary</td> <td>4m</td> </tr> <tr> <td>b. Side boundary</td> <td>0m</td> </tr> <tr> <td>c. Minimum building and structure setback from the power pylon and electricity transmission lines on the site</td> <td>12m</td> </tr> <tr> <td>d. Rear boundaries except where the rear boundary adjoins a Reserve in which case an exemption from the rear boundary setback applies</td> <td>3m</td> </tr> </tbody> </table>	a. Front boundary	4m	b. Side boundary	0m	c. Minimum building and structure setback from the power pylon and electricity transmission lines on the site	12m	d. Rear boundaries except where the rear boundary adjoins a Reserve in which case an exemption from the rear boundary setback applies	3m
a. Front boundary	4m										
b. Side boundary	0m										
c. Minimum building and structure setback from the power pylon and electricity transmission lines on the site	12m										
d. Rear boundaries except where the rear boundary adjoins a Reserve in which case an exemption from the rear boundary setback applies	3m										
		NCZ-SSC-S2	Building coverage								
			1. The maximum coverage by buildings on the net area of a site shall not exceed 20%.								
		NCZ-SSC-S3	Screening								
			1. Outdoor storage areas shall be screened by a close-boarded fence, a solid wall or dense planting of vegetation. The screening shall be no less than 1.8m in height .								
		NCZ-SSC-S4	Landscaping								
			1. Along the common rear boundary of the land identified in COMZ-Figure1 and Lots 8 to 11 DP 399832 of the Cosgrove Rise subdivision a landscape buffer with a minimum width of 0.6m shall be provided within the site between the zone boundary and the buildings .								

Commented [MM192]: S27.30 - Transpower New Zealand Limited

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p><u>NCZ-Figure1 – Neighbourhood Centre Zone at Riverstone Terrace</u></p> 
LCZ – Local Centre Zone			
	New LCZ - Local Centre Zone	Introduce new Chapter Heading and Introduction	<p><u>LCZ - Local Centre Zone</u></p> <p><u>The Local Centre Zone provides for medium-scale commercial centres that are conveniently located to service the needs of the surrounding commercial catchment. Local Centres accommodate a range of retail, commercial and community activities while also offering services, employment and residential opportunities. The size of the centres depends largely on their location and the size of the surrounding catchment. Most Local Centres have potential for growth and intensification, which allows them to provide for the expected growth of surrounding residential areas, while not undermining the primary function and vitality of the City Centre Zone.</u></p> <p><u>The Local Centre Zone allows for residential activities if they are located above ground floor along identified street frontages. Large format retail, car oriented activities, larger commercial activities and office activities and light industrial activities are not anticipated in this zone but are encouraged to establish in more appropriate locations such as the Mixed Use Zone, the City Centre Zone or the General Industrial Zone.</u></p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>The built form and density of Local Centres is anticipated to align with the expected high density of surrounding residential areas. Most Local Centres are located along main transport routes and buildings front the street edge with verandahs and display windows. While the scale and density of buildings vary between centres they are expected to change and intensify over time. Parking is usually available on the street or in dedicated and ideally shared on-site parking areas.</p> <p>Non-residential activities and development have the potential to generate adverse effects where they are directly adjoining Residential and Open Space and Recreation areas. To manage these potential effects buildings have to be set back and outdoor storage and parking areas need to be screened.</p>
	New LCZ - Local Centre Zone	Introduce new Objective LCZ-O1	<p>Objectives</p> <p>LCZ-O1 Purpose of the Local Centre Zone</p> <p>Local Centres are medium scale commercial centres that service the needs of the surrounding residential catchment and accommodate a range of medium scale commercial and community activities as well as residential activities.</p>
	New LCZ - Local Centre Zone	Introduce new Objective LCZ-O2	<p>LCZ-O2 Character: Urban Built Form and Amenity Values of the Local Centre Zone</p> <p>Local Centres are safe and attractive urban environments. The built environment is of a scale that reflects the planned built form of the medium to high density surrounding residential environment and contributes positively to the surrounding streetscape and commercial and residential environment.</p>
	New LCZ - Local Centre Zone	Introduce new Objective LCZ-O3	<p>LCZ-O3 Managing Effects at the Zone Interface</p> <p>Use and development within the Local Centre Zone are of an appropriate scale and reflect the purpose, anticipated character and planned urban built form of the zone and the surrounding residential environment while managing potential adverse effects on the amenity values of adjoining sites in Residential and Open Space and Recreation Zones.</p>
	New LCZ - Local Centre Zone	Introduce new Objective LCZ-O4	<p>LCZ-O4 Hydraulic neutrality</p> <p>There is no increase in the peak demand on stormwater management systems and increase in flooding from subdivision and development.</p>
	New LCZ - Local Centre Zone	Introduce new Policy LCZ-P1	<p>Policies</p> <p>LCZ-P1 Appropriate activities</p> <p>Enable appropriate activities that:</p>

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<ol style="list-style-type: none"> 1. <u>Are compatible with the anticipated purpose, character and amenity values of the Local Centre Zone;</u> 2. <u>Service the needs of the surrounding residential catchment; and</u> 3. <u>Minimise adverse effects on the amenity of adjoining residential, recreational and open space sites.</u> 		
	New LCZ - Local Centre Zone	Introduce new Policy LCZ-P2	<table border="1"> <tr> <td><u>LCZ-P2</u></td> <td><u>Residential activity</u></td> </tr> </table> <p><u>Provide for residential activity and development where:</u></p> <ol style="list-style-type: none"> 1. <u>The residential units are located above ground floor, where located along an active frontage identified on the planning maps;</u> 2. <u>It does not interrupt or preclude an attractive and active frontage that provides a positive interface with the public space;</u> 3. Residential units are designed to: <ol style="list-style-type: none"> a. <u>Achieve adequate indoor noise and ventilation levels for occupants; and</u> b. <u>Provide appropriate amenity for occupants; and</u> 4. Reverse sensitivity effects on commercial activities are minimised 	<u>LCZ-P2</u>	<u>Residential activity</u>
<u>LCZ-P2</u>	<u>Residential activity</u>				
	New LCZ - Local Centre Zone	Introduce new Policy LCZ-P3	<table border="1"> <tr> <td><u>LCZ-P3</u></td> <td><u>Other activities</u></td> </tr> </table> <p><u>Only allow for other activities, including larger scale activities, where:</u></p> <ol style="list-style-type: none"> 1. <u>Any adverse effects can be managed;</u> 2. <u>The scale and intensity of the activity is consistent with the anticipated character of the Local Centre Zone;</u> 3. <u>The design and layout of the activity does not compromise the streetscape, amenity or safety;</u> 4. <u>The size, intensity and scale of the activity does not compromise other activities that are anticipated and enabled within the Local Centre Zone; and</u> 5. <u>The location of the activity in the Local Centre Zone does not undermine the role and function of the City Centre Zone.</u> 	<u>LCZ-P3</u>	<u>Other activities</u>
<u>LCZ-P3</u>	<u>Other activities</u>				
	New LCZ - Local Centre Zone	Introduce new Policy LCZ-P4	<table border="1"> <tr> <td><u>LCZ-P4</u></td> <td><u>Inappropriate activities</u></td> </tr> </table>	<u>LCZ-P4</u>	<u>Inappropriate activities</u>
<u>LCZ-P4</u>	<u>Inappropriate activities</u>				

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<u>Avoid activities that are incompatible with the anticipated purpose, role and function of the Local Centre Zone and the surrounding environment.</u>		
	New LCZ - Local Centre Zone	Introduce new Policy LCZ-P5	<table border="1"> <tr> <td>LCZ-P5</td> <td>Built development</td> </tr> </table> <p><u>Provide for medium to higher density development that:</u></p> <ol style="list-style-type: none"> <u>Is compatible with the planned built urban form and the anticipated role, character and density of the Local Centre Zone;</u> <u>Is commensurate with the anticipated level of commercial activities and community services in the Local Centre Zone;</u> <u>Reflects the anticipated medium to high density of the surrounding residential environment,</u> <u>Is well designed and contributes to an attractive well-functioning urban environment; and</u> <u>Provides active and attractive street frontages.</u> 	LCZ-P5	Built development
LCZ-P5	Built development				
	New LCZ - Local Centre Zone	Introduce new Policy LCZ-P6	<table border="1"> <tr> <td>LCZ-P6</td> <td>Public space interface and Active Street Frontages</td> </tr> </table> <p><u>Provide for new development that creates an attractive interface with the public space through high quality building design.</u></p> <p><u>Where located along identified active frontages, require new built development and activities to provide a positive interface with the public space through:</u></p> <ol style="list-style-type: none"> <u>Being built up to and oriented towards the front boundary of the site;</u> <u>Providing verandahs or other adequate forms of pedestrian shelter;</u> <u>Providing display windows and obvious public entrances; and</u> <u>Requiring parking, storage and servicing areas to be visually unobtrusive.</u> 	LCZ-P6	Public space interface and Active Street Frontages
LCZ-P6	Public space interface and Active Street Frontages				
	New LCZ - Local Centre Zone	Introduce new Policy LCZ-P7	<table border="1"> <tr> <td>LCZ-P7</td> <td>Interface with Residential Zones and Open Space and Recreation Zones</td> </tr> </table> <p><u>Minimise the adverse effects from commercial activities and development on directly adjoining sites that are zoned Residential or Open Space and Recreation through:</u></p> <ol style="list-style-type: none"> <u>Requiring new buildings and activities to be located and designed to manage any shading and privacy effects on neighbouring sites zoned Residential or Open Space and Recreation;</u> 	LCZ-P7	Interface with Residential Zones and Open Space and Recreation Zones
LCZ-P7	Interface with Residential Zones and Open Space and Recreation Zones				

Commented [MM193]: S58.234 - Kāinga Ora: Homes and Communities

Commented [MM194]: S64.83 - Retirement Villages Association of New Zealand

IPI - PROPOSED AMENDMENTS												
#	Chapter	Change	Track Change									
			<ol style="list-style-type: none"> 2. Limiting the height, bulk and form of new buildings along boundaries with sites zoned Residential or Open Space and Recreation to minimise dominance effects; and 3. Requiring the use of landscaping and screening to minimise adverse visual effects on adjoining sites zoned Residential or Open Space and Recreation. 									
	New LCZ - Local Centre Zone	Introduce new Policy LCZ-P8	<table border="1"> <tr> <td>LCZ-P8</td> <td>Hydraulic neutrality</td> </tr> <tr> <td colspan="2"><i>New buildings and development will be designed to achieve hydraulic neutrality.</i></td> </tr> </table>	LCZ-P8	Hydraulic neutrality	<i>New buildings and development will be designed to achieve hydraulic neutrality.</i>						
LCZ-P8	Hydraulic neutrality											
<i>New buildings and development will be designed to achieve hydraulic neutrality.</i>												
	New LCZ - Local Centre Zone	Introduce new Rules Advice Note	<p>Rules</p> <p>Note: There may be a number of provisions that apply to an activity, building, structure or site. Resource consent may therefore be required under rules in this chapter as well as other chapters. Unless specifically stated in a rule, resource consent is required under each relevant rule. The steps to determine the status of an activity are set out in Chapter 2 How the Plan Works.</p> <p>Rules relating to subdivision are found in the SUB-GEN (General Subdivision Provisions that Apply in All Zones) and the SUB-CMU (Subdivision in Commercial and Mixed Use Zones) chapters.</p> <p>Each activity in the Local Centre Zone shall comply with the relevant qualifying matter area provisions and permitted activity standards in the district-wide matters of the Plan as listed below.</p> <table border="1"> <tr> <td>District-wide matters</td> </tr> <tr> <td><u>NU – Network Utilities</u></td> </tr> <tr> <td><u>REG - Renewable Energy Generation</u></td> </tr> <tr> <td><u>TP – Transport and Parking</u></td> </tr> <tr> <td><u>CL – Contaminated Land</u></td> </tr> <tr> <td><u>HS - Hazardous Substances</u></td> </tr> <tr> <td><u>NH - Natural Hazards</u></td> </tr> <tr> <td><u>WM – Waste Management</u></td> </tr> <tr> <td><u>HH - Historical Heritage</u></td> </tr> </table>	District-wide matters	<u>NU – Network Utilities</u>	<u>REG - Renewable Energy Generation</u>	<u>TP – Transport and Parking</u>	<u>CL – Contaminated Land</u>	<u>HS - Hazardous Substances</u>	<u>NH - Natural Hazards</u>	<u>WM – Waste Management</u>	<u>HH - Historical Heritage</u>
District-wide matters												
<u>NU – Network Utilities</u>												
<u>REG - Renewable Energy Generation</u>												
<u>TP – Transport and Parking</u>												
<u>CL – Contaminated Land</u>												
<u>HS - Hazardous Substances</u>												
<u>NH - Natural Hazards</u>												
<u>WM – Waste Management</u>												
<u>HH - Historical Heritage</u>												

IPI - PROPOSED AMENDMENTS																			
#	Chapter	Change	Track Change																
			<table border="1"> <tr><td><u>TREE - Notable Trees</u></td></tr> <tr><td><u>UTG - Urban Tree Groups</u></td></tr> <tr><td><u>ECO - Ecosystems and Indigenous Biodiversity</u></td></tr> <tr><td><u>NATC – Natural Character</u></td></tr> <tr><td><u>NFL - Natural Features and Landscapes</u></td></tr> <tr><td><u>PA – Public Access</u></td></tr> <tr><td><u>SUB - Subdivision</u></td></tr> <tr><td><u>DC – Development Contributions</u></td></tr> <tr><td><u>AIR - Air</u></td></tr> <tr><td><u>PK – Papakāinga</u></td></tr> <tr><td><u>ASW - Activities on the Surface of Water</u></td></tr> <tr><td><u>EW - Earthworks</u></td></tr> <tr><td><u>LIGHT - Light</u></td></tr> <tr><td><u>NOISE - Noise</u></td></tr> <tr><td><u>SIGN - Signs</u></td></tr> <tr><td><u>TEMP - Temporary Activities</u></td></tr> </table>	<u>TREE - Notable Trees</u>	<u>UTG - Urban Tree Groups</u>	<u>ECO - Ecosystems and Indigenous Biodiversity</u>	<u>NATC – Natural Character</u>	<u>NFL - Natural Features and Landscapes</u>	<u>PA – Public Access</u>	<u>SUB - Subdivision</u>	<u>DC – Development Contributions</u>	<u>AIR - Air</u>	<u>PK – Papakāinga</u>	<u>ASW - Activities on the Surface of Water</u>	<u>EW - Earthworks</u>	<u>LIGHT - Light</u>	<u>NOISE - Noise</u>	<u>SIGN - Signs</u>	<u>TEMP - Temporary Activities</u>
<u>TREE - Notable Trees</u>																			
<u>UTG - Urban Tree Groups</u>																			
<u>ECO - Ecosystems and Indigenous Biodiversity</u>																			
<u>NATC – Natural Character</u>																			
<u>NFL - Natural Features and Landscapes</u>																			
<u>PA – Public Access</u>																			
<u>SUB - Subdivision</u>																			
<u>DC – Development Contributions</u>																			
<u>AIR - Air</u>																			
<u>PK – Papakāinga</u>																			
<u>ASW - Activities on the Surface of Water</u>																			
<u>EW - Earthworks</u>																			
<u>LIGHT - Light</u>																			
<u>NOISE - Noise</u>																			
<u>SIGN - Signs</u>																			
<u>TEMP - Temporary Activities</u>																			
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R1	<table border="1"> <tr> <td><u>LCZ-R1</u></td> <td><u>Buildings and structures, including additions and alterations</u></td> </tr> <tr> <td colspan="2"> <p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. The gross floor area of the new building does not exceed 500m²;</p> <p>b. Any addition to an existing building does not result in the gross floor area of the building exceeding 500m²; and</p> <p>c. <u>Compliance is achieved with</u></p> </td> </tr> </table>	<u>LCZ-R1</u>	<u>Buildings and structures, including additions and alterations</u>	<p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. The gross floor area of the new building does not exceed 500m²;</p> <p>b. Any addition to an existing building does not result in the gross floor area of the building exceeding 500m²; and</p> <p>c. <u>Compliance is achieved with</u></p>													
<u>LCZ-R1</u>	<u>Buildings and structures, including additions and alterations</u>																		
<p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. The gross floor area of the new building does not exceed 500m²;</p> <p>b. Any addition to an existing building does not result in the gross floor area of the building exceeding 500m²; and</p> <p>c. <u>Compliance is achieved with</u></p>																			

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
			<p>i. <u>LCZ-S1 (Height);</u></p> <p>ii. <u>LCZ-S2 (Height in Relation to Boundary);</u></p> <p>iii. <u>LCZ-S3 (Setbacks);</u></p> <p>iv. <u>LCZ-S4 (Active Frontages);</u></p> <p>v. <u>LCZ-S5 (Location of Residential Units);</u></p> <p>vi. <u>LCZ-S6 (Noise and Ventilation)</u></p> <p>vii. <u>LCZ-S7 (Outdoor Living Space);</u></p> <p>viii. <u>LCZ-S8 (Landscaping and Screening);</u></p> <p>ix. <u>LCZ-S9 (Water Supply, Stormwater and Wastewater); and</u></p> <p>x. <u>LCZ-S10 (Hydraulic neutrality).</u></p> <p>2. <u>Activity status: Restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with LCZ-R1-1.a or LCZ-R1-1.b</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The extent to which the size and scale of the building is commensurate with the anticipated level of commercial activities and community services in the Local Centre Zone;</u> 2. <u>The extent to which the size and scale of the building may adversely impact on the amenity of the Local Centre Zone or adjacent properties.</u> 3. <u>Whether the building is well designed and contributes to an attractive urban environment.</u> 4. <u>The effects of the size and scale of the building on the existing and anticipated function and role of the Local Centre Zone.</u> 5. <u>The potential of the size and scale of the building to compromise activities that are enabled in the Local Centre Zone.</u> 6. <u>The potential of the location of the activity in the Local Centre Zone to undermine the role and function of</u>

IPI - PROPOSED AMENDMENTS															
#	Chapter	Change	Track Change												
			<p>the City Centre Zone.</p> <p>7. <u>The extent to which the adverse effects of the size and scale of the building can be avoided, or appropriately remedied or mitigated.</u></p> <p>b. <u>Compliance is not achieved with one or more of the standards under LCZ-R1-1.c</u></p> <p><u>Matters of discretion are restricted to:</u></p> <p>1. <u>The matters of discretion of any infringed standard.</u></p> <p>Notification:</p> <p><u>An application under this rule where compliance is not achieved with LCZ-S2, LCZ-S3, LCZ-S4, LCZ-S5, LCZ-S6 or LCZ-S8 is precluded from being publicly notified in accordance with section 95A of the RMA.</u></p> <p><u>An application under this rule where compliance is not achieved with LCZ-S7 is precluded from being publicly or limited notified in accordance with section 95A of the RMA.</u></p>												
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R2	<table border="1"> <tr> <td>LCZ-R2</td> <td>Minor structures</td> </tr> <tr> <td colspan="2">1. Activity status: Permitted</td> </tr> </table>	LCZ-R2	Minor structures	1. Activity status: Permitted									
LCZ-R2	Minor structures														
1. Activity status: Permitted															
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R3	<table border="1"> <tr> <td>LCZ-R3</td> <td>Demolition</td> </tr> <tr> <td colspan="2">1. Activity status: Permitted</td> </tr> <tr> <td colspan="2">Note: <u>Prior to demolition commencing, confirm whether rules in chapter HH-Historic Heritage apply.</u></td> </tr> </table>	LCZ-R3	Demolition	1. Activity status: Permitted		Note: <u>Prior to demolition commencing, confirm whether rules in chapter HH-Historic Heritage apply.</u>							
LCZ-R3	Demolition														
1. Activity status: Permitted															
Note: <u>Prior to demolition commencing, confirm whether rules in chapter HH-Historic Heritage apply.</u>															
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R4	<table border="1"> <tr> <td>LCZ-R4</td> <td>Retail Activity</td> </tr> <tr> <td colspan="2">1. Activity status: Permitted</td> </tr> <tr> <td colspan="2"><u>Where:</u></td> </tr> <tr> <td colspan="2">a. <u>The gross floor area per tenancy does not exceed 250m²; and</u></td> </tr> <tr> <td colspan="2">b. <u>Compliance is achieved with LCZ-S8 (Landscaping and Screening).</u></td> </tr> <tr> <td colspan="2">2. Activity status: Restricted discretionary</td> </tr> </table>	LCZ-R4	Retail Activity	1. Activity status: Permitted		<u>Where:</u>		a. <u>The gross floor area per tenancy does not exceed 250m²; and</u>		b. <u>Compliance is achieved with LCZ-S8 (Landscaping and Screening).</u>		2. Activity status: Restricted discretionary	
LCZ-R4	Retail Activity														
1. Activity status: Permitted															
<u>Where:</u>															
a. <u>The gross floor area per tenancy does not exceed 250m²; and</u>															
b. <u>Compliance is achieved with LCZ-S8 (Landscaping and Screening).</u>															
2. Activity status: Restricted discretionary															

Commented [MM195]: S72.12 - Te Rūnanga o Toa Rangatira Inc

IPI - PROPOSED AMENDMENTS											
#	Chapter	Change	Track Change								
			<p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with LCZ-R4-1.a</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Local Centre Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Local Centre Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Local Centre Zone.</u> <u>The potential of the location of the activity in the Local Centre Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. <u>Compliance is not achieved with LCZ-R4-1.b</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> <u>An application under LCZ-R4-2.b is precluded from being publicly notified in accordance with section 95A of the RMA.</u> 								
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R5	<table border="1"> <thead> <tr> <th>LCZ-R5</th> <th>Commercial Service Activity</th> </tr> </thead> <tbody> <tr> <td>1.</td> <td>Activity status: Permitted</td> </tr> <tr> <td></td> <td> <p><u>Where:</u></p> <p>a. <u>The gross floor area per tenancy does not exceed 250m²; and</u></p> <p>b. <u>Compliance is achieved with LCZ-S8 (Landscaping and Screening).</u></p> </td> </tr> <tr> <td>2.</td> <td>Activity status: Restricted discretionary</td> </tr> </tbody> </table>	LCZ-R5	Commercial Service Activity	1.	Activity status: Permitted		<p><u>Where:</u></p> <p>a. <u>The gross floor area per tenancy does not exceed 250m²; and</u></p> <p>b. <u>Compliance is achieved with LCZ-S8 (Landscaping and Screening).</u></p>	2.	Activity status: Restricted discretionary
LCZ-R5	Commercial Service Activity										
1.	Activity status: Permitted										
	<p><u>Where:</u></p> <p>a. <u>The gross floor area per tenancy does not exceed 250m²; and</u></p> <p>b. <u>Compliance is achieved with LCZ-S8 (Landscaping and Screening).</u></p>										
2.	Activity status: Restricted discretionary										

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			<p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with LCZ-R5-1.a</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Local Centre Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Local Centre Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Local Centre Zone.</u> <u>The potential of the location of the activity in the Local Centre Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. <u>Compliance is not achieved with LCZ-R5-1.b</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> <u>An application under LCZ-R5-2.b is precluded from being publicly notified in accordance with section 95A of the RMA.</u> 						
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R6	<table border="1"> <tr> <td>LCZ-R6</td> <td>Food and Beverage Activity</td> </tr> <tr> <td colspan="2"> <p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>The gross floor area per tenancy does not exceed 250m²; and</u></p> <p>b. <u>Compliance is achieved with LCZ-S8 (Landscaping and Screening).</u></p> </td> </tr> <tr> <td colspan="2"> <p>2. Activity status: Restricted discretionary</p> </td> </tr> </table>	LCZ-R6	Food and Beverage Activity	<p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>The gross floor area per tenancy does not exceed 250m²; and</u></p> <p>b. <u>Compliance is achieved with LCZ-S8 (Landscaping and Screening).</u></p>		<p>2. Activity status: Restricted discretionary</p>	
LCZ-R6	Food and Beverage Activity								
<p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>The gross floor area per tenancy does not exceed 250m²; and</u></p> <p>b. <u>Compliance is achieved with LCZ-S8 (Landscaping and Screening).</u></p>									
<p>2. Activity status: Restricted discretionary</p>									

IPI - PROPOSED AMENDMENTS											
#	Chapter	Change	Track Change								
			<p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with LCZ-R6-1.a</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Local Centre Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Local Centre Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Local Centre Zone.</u> <u>The potential of the location of the activity in the Local Centre Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. <u>Compliance is not achieved with LCZ-R6-1.b</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> <u>An application under LCZ-R6-2.b is precluded from being publicly notified in accordance with section 95A of the RMA.</u> 								
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R7	<table border="1"> <thead> <tr> <th><u>LCZ-R7</u></th> <th><u>Community Facility</u></th> </tr> </thead> <tbody> <tr> <td>1.</td> <td>Activity status: Permitted</td> </tr> <tr> <td></td> <td> <p><u>Where:</u></p> <p>a. <u>The gross floor area per facility does not exceed 250m²; and</u></p> <p>b. <u>Compliance is achieved with LCZ-S8 (Landscaping and Screening).</u></p> </td> </tr> <tr> <td>2.</td> <td>Activity status: Restricted discretionary</td> </tr> </tbody> </table>	<u>LCZ-R7</u>	<u>Community Facility</u>	1.	Activity status: Permitted		<p><u>Where:</u></p> <p>a. <u>The gross floor area per facility does not exceed 250m²; and</u></p> <p>b. <u>Compliance is achieved with LCZ-S8 (Landscaping and Screening).</u></p>	2.	Activity status: Restricted discretionary
<u>LCZ-R7</u>	<u>Community Facility</u>										
1.	Activity status: Permitted										
	<p><u>Where:</u></p> <p>a. <u>The gross floor area per facility does not exceed 250m²; and</u></p> <p>b. <u>Compliance is achieved with LCZ-S8 (Landscaping and Screening).</u></p>										
2.	Activity status: Restricted discretionary										

IPI - PROPOSED AMENDMENTS											
#	Chapter	Change	Track Change								
			<p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with LCZ-R7-1.a</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Local Centre Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Local Centre Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Local Centre Zone.</u> <u>The potential of the location of the activity in the Local Centre Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. <u>Compliance is not achieved with LCZ-R7-1.b</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> <u>An application under LCZ-R7-2.b is precluded from being publicly notified in accordance with section 95A of the RMA.</u> 								
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R8	<table border="1"> <thead> <tr> <th><u>LCZ-R8</u></th> <th><u>Healthcare Activity</u></th> </tr> </thead> <tbody> <tr> <td>1.</td> <td>Activity status: Permitted</td> </tr> <tr> <td></td> <td> <p><u>Where:</u></p> <p>a. <u>The gross floor area per tenancy does not exceed 250m²; and</u></p> <p>b. <u>Compliance is achieved with LCZ-S8 (Landscaping and Screening).</u></p> </td> </tr> <tr> <td>2.</td> <td>Activity status: Restricted discretionary</td> </tr> </tbody> </table>	<u>LCZ-R8</u>	<u>Healthcare Activity</u>	1.	Activity status: Permitted		<p><u>Where:</u></p> <p>a. <u>The gross floor area per tenancy does not exceed 250m²; and</u></p> <p>b. <u>Compliance is achieved with LCZ-S8 (Landscaping and Screening).</u></p>	2.	Activity status: Restricted discretionary
<u>LCZ-R8</u>	<u>Healthcare Activity</u>										
1.	Activity status: Permitted										
	<p><u>Where:</u></p> <p>a. <u>The gross floor area per tenancy does not exceed 250m²; and</u></p> <p>b. <u>Compliance is achieved with LCZ-S8 (Landscaping and Screening).</u></p>										
2.	Activity status: Restricted discretionary										

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			<p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with LCZ-R8-1.a</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Local Centre Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Local Centre Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Local Centre Zone.</u> <u>The potential of the location of the activity in the Local Centre Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. <u>Compliance is not achieved with LCZ-R8-1.b</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> <u>An application under LCZ-R8-2.b is precluded from being publicly notified in accordance with section 95A of the RMA.</u> 						
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R9	<table border="1"> <tr> <td>LCZ-R9</td> <td>Educational Facility</td> </tr> <tr> <td colspan="2"> <p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>The gross floor area per facility does not exceed 250m²; and</u></p> <p>b. <u>Compliance is achieved with LCZ-S8 (Landscaping and Screening).</u></p> </td> </tr> <tr> <td colspan="2"> <p>2. Activity status: Restricted discretionary</p> </td> </tr> </table>	LCZ-R9	Educational Facility	<p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>The gross floor area per facility does not exceed 250m²; and</u></p> <p>b. <u>Compliance is achieved with LCZ-S8 (Landscaping and Screening).</u></p>		<p>2. Activity status: Restricted discretionary</p>	
LCZ-R9	Educational Facility								
<p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>The gross floor area per facility does not exceed 250m²; and</u></p> <p>b. <u>Compliance is achieved with LCZ-S8 (Landscaping and Screening).</u></p>									
<p>2. Activity status: Restricted discretionary</p>									

IPI - PROPOSED AMENDMENTS															
#	Chapter	Change	Track Change												
			<p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with LCZ-R9-1.a</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Local Centre Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Local Centre Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Local Centre Zone.</u> <u>The potential of the location of the activity in the Local Centre Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. <u>Compliance is not achieved with LCZ-R9-1.b</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> <u>An application under LCZ-R9-2.b is precluded from being publicly notified in accordance with section 95A of the RMA.</u> 												
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R10	<table border="1"> <tr> <td>LCZ-R10</td> <td>Office activity</td> </tr> <tr> <td colspan="2">1. Activity status: Permitted</td> </tr> <tr> <td colspan="2"><u>Where:</u></td> </tr> <tr> <td colspan="2">a. <u>The gross floor area per tenancy does not exceed 150m²; and</u></td> </tr> <tr> <td colspan="2">b. <u>Compliance is achieved with LCZ-S8 (Landscaping and Screening).</u></td> </tr> <tr> <td colspan="2">2. Activity status: Restricted discretionary</td> </tr> </table>	LCZ-R10	Office activity	1. Activity status: Permitted		<u>Where:</u>		a. <u>The gross floor area per tenancy does not exceed 150m²; and</u>		b. <u>Compliance is achieved with LCZ-S8 (Landscaping and Screening).</u>		2. Activity status: Restricted discretionary	
LCZ-R10	Office activity														
1. Activity status: Permitted															
<u>Where:</u>															
a. <u>The gross floor area per tenancy does not exceed 150m²; and</u>															
b. <u>Compliance is achieved with LCZ-S8 (Landscaping and Screening).</u>															
2. Activity status: Restricted discretionary															

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with LCZ-R10-1.a</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Local Centre Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Local Centre Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Local Centre Zone.</u> <u>The potential of the location of the activity in the Local Centre Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. <u>Compliance is not achieved with LCZ-R10-1.b</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> <u>An application under LCZ-R10-2.b is precluded from being publicly notified in accordance with section 95A of the RMA.</u> 		
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R11	<table border="1"> <tr> <td>LCZ-R11</td> <td>Visitor Accommodation</td> </tr> </table> <p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <ol style="list-style-type: none"> <u>The gross floor area per tenancy does not exceed 250m²;</u> <u>All habitable rooms comply with LCZ-S5 (Location of Residential Units) and LCZ-S6 (Noise and Ventilation); and</u> <u>Compliance is achieved with LCZ-S8 (Landscaping and Screening).</u> 	LCZ-R11	Visitor Accommodation
LCZ-R11	Visitor Accommodation				




IPI - PROPOSED AMENDMENTS													
#	Chapter	Change	Track Change										
			<p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with LCZ-R11-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Local Centre Zone or adjacent properties.</u> 2. <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Local Centre Zone.</u> 3. <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Local Centre Zone.</u> 4. <u>The potential of the location of the activity in the Local Centre Zone to undermine the role and function of the City Centre Zone.</u> 5. <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or <u>appropriately remedied or mitigated.</u></u> <p>b. Compliance is not achieved with LCZ-R11-1.b or LCZ-R11-1.c</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> • <u>An application under LCZ-R11-2.b is precluded from being publicly notified in accordance with section 95A of the RMA.</u> 										
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R12	<table border="1"> <thead> <tr> <th><u>LCZ-R12</u></th> <th><u>Residential Activity</u></th> </tr> </thead> <tbody> <tr> <td>1. Activity status: Permitted</td> <td></td> </tr> <tr> <td><u>Where:</u></td> <td></td> </tr> <tr> <td>a. <u>No more than six residential units occupy the site; and</u></td> <td></td> </tr> <tr> <td>b. <u>Compliance is achieved with</u></td> <td></td> </tr> </tbody> </table>	<u>LCZ-R12</u>	<u>Residential Activity</u>	1. Activity status: Permitted		<u>Where:</u>		a. <u>No more than six residential units occupy the site; and</u>		b. <u>Compliance is achieved with</u>	
<u>LCZ-R12</u>	<u>Residential Activity</u>												
1. Activity status: Permitted													
<u>Where:</u>													
a. <u>No more than six residential units occupy the site; and</u>													
b. <u>Compliance is achieved with</u>													

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<ul style="list-style-type: none"> i. <u>LCZ-S5 (Location of Residential Units);</u> ii. <u>LCZ-S6 (Noise and Ventilation); and</u> iii. <u>LCZ-S7 (Outdoor Living Space).</u> <p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <ul style="list-style-type: none"> a. Compliance is not achieved with LCZ-R12-1.a <p><u>Matters of discretion are restricted to:</u></p> <ul style="list-style-type: none"> 1. <u>The effects of the residential activity on the existing and anticipated function and role of the Local Centre Zone.</u> 2. <u>The potential of the residential activity to compromise activities that are enabled in the Local Centre Zone.</u> 3. <u>The amenity for the occupiers of the residential units.</u> <ul style="list-style-type: none"> b. Compliance is not achieved with LCZ-R12-1.b <p><u>Matters of discretion are restricted to:</u></p> <ul style="list-style-type: none"> 1. <u>The matters of discretion of the infringed standard.</u> <p>Notification</p> <p><u>An application under this rule where compliance is not achieved with LCZ-S5 or LCZ-S6 is precluded from being publicly notified in accordance with section 95A of the RMA.</u></p> <p><u>An application under this rule where compliance is not achieved with LCZ-S7 is precluded from being publicly or limited notified in accordance with section 95A of the RMA.</u></p>		
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R13	<table border="1"> <tr> <td><u>LCZ-R13</u></td> <td><u>Supermarket</u></td> </tr> </table> <p>1. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <ul style="list-style-type: none"> a. <u>The gross floor area does not exceed 1500m²; and</u> 	<u>LCZ-R13</u>	<u>Supermarket</u>
<u>LCZ-R13</u>	<u>Supermarket</u>				

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<p>b. <u>Compliance is achieved with LCZ-S7 (Landscaping and Screening).</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the activity may adversely impact on the amenity of the Local Centre Zone or adjacent properties.</u> <u>The effects of the of the activity on the existing and anticipated function and role of the Local Centre Zone.</u> <u>The potential of the activity to compromise activities that are enabled in the Local Centre Zone.</u> <u>The potential of the location of the activity in the Local Centre Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>2. <u>Activity status: Discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with LCZ-R13-1.a or LCZ-R13-1.b</u></p>				
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R14	<table border="1"> <thead> <tr> <th><u>LCZ-R14</u></th> <th><u>Emergency Service Facility</u></th> </tr> </thead> <tbody> <tr> <td colspan="2"> <p>1. <u>Activity status: Restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is achieved with LCZ-S7 (Landscaping and Screening).</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the activity may adversely impact on the amenity of the Local Centre Zone or adjacent properties.</u> <u>The effects of the of the activity on the existing and anticipated function and role of the Local Centre Zone.</u> <u>The potential of the activity to compromise activities that are enabled in the Local Centre Zone.</u> <u>The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated.</u> <u>The functional need or operational need for the Emergency Service Facility to be located in the Local Centre</u> </td> </tr> </tbody> </table>	<u>LCZ-R14</u>	<u>Emergency Service Facility</u>	<p>1. <u>Activity status: Restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is achieved with LCZ-S7 (Landscaping and Screening).</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the activity may adversely impact on the amenity of the Local Centre Zone or adjacent properties.</u> <u>The effects of the of the activity on the existing and anticipated function and role of the Local Centre Zone.</u> <u>The potential of the activity to compromise activities that are enabled in the Local Centre Zone.</u> <u>The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated.</u> <u>The functional need or operational need for the Emergency Service Facility to be located in the Local Centre</u> 	
<u>LCZ-R14</u>	<u>Emergency Service Facility</u>						
<p>1. <u>Activity status: Restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is achieved with LCZ-S7 (Landscaping and Screening).</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the activity may adversely impact on the amenity of the Local Centre Zone or adjacent properties.</u> <u>The effects of the of the activity on the existing and anticipated function and role of the Local Centre Zone.</u> <u>The potential of the activity to compromise activities that are enabled in the Local Centre Zone.</u> <u>The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated.</u> <u>The functional need or operational need for the Emergency Service Facility to be located in the Local Centre</u> 							


IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change				
			<p style="text-align: center;"><u>Zone.</u></p> <p>Notification:</p> <ul style="list-style-type: none"> An application under this rule is precluded from being publicly notified in accordance with section 95A of the RMA. <p>2. Activity status: Discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with LCZ-R14-1.a</p>				
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R15	<table border="1"> <tr> <td>LCZ-R15</td> <td>Entertainment Facility</td> </tr> <tr> <td colspan="2">1. Activity status: Discretionary</td> </tr> </table>	LCZ-R15	Entertainment Facility	1. Activity status: Discretionary	
LCZ-R15	Entertainment Facility						
1. Activity status: Discretionary							
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R16	<table border="1"> <tr> <td>LCZ-R16</td> <td>Sport and Active Recreation</td> </tr> <tr> <td colspan="2">1. Activity status: Discretionary</td> </tr> </table>	LCZ-R16	Sport and Active Recreation	1. Activity status: Discretionary	
LCZ-R16	Sport and Active Recreation						
1. Activity status: Discretionary							
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R17	<table border="1"> <tr> <td>LCZ-R17</td> <td>Large Format Retail Activity, excluding Supermarkets</td> </tr> <tr> <td colspan="2">1. Activity status: Discretionary</td> </tr> </table>	LCZ-R17	Large Format Retail Activity, excluding Supermarkets	1. Activity status: Discretionary	
LCZ-R17	Large Format Retail Activity, excluding Supermarkets						
1. Activity status: Discretionary							
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R18	<table border="1"> <tr> <td>LCZ-R18</td> <td>Drive-through Activity</td> </tr> <tr> <td colspan="2">1. Activity status: Discretionary</td> </tr> </table>	LCZ-R18	Drive-through Activity	1. Activity status: Discretionary	
LCZ-R18	Drive-through Activity						
1. Activity status: Discretionary							
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R19	<table border="1"> <tr> <td>LCZ-R19</td> <td>Retirement Village</td> </tr> <tr> <td colspan="2">1. Activity status: Discretionary</td> </tr> </table>	LCZ-R19	Retirement Village	1. Activity status: Discretionary	
LCZ-R19	Retirement Village						
1. Activity status: Discretionary							
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R20	<table border="1"> <tr> <td>LCZ-R20</td> <td>Any activity not otherwise listed as permitted, restricted discretionary, discretionary or non-complying</td> </tr> <tr> <td colspan="2">1. Activity status: Discretionary</td> </tr> </table>	LCZ-R20	Any activity not otherwise listed as permitted, restricted discretionary, discretionary or non-complying	1. Activity status: Discretionary	
LCZ-R20	Any activity not otherwise listed as permitted, restricted discretionary, discretionary or non-complying						
1. Activity status: Discretionary							
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R21	<table border="1"> <tr> <td>LCZ-R21</td> <td>Industrial Activity</td> </tr> <tr> <td colspan="2">1. Activity status: Non-complying</td> </tr> </table>	LCZ-R21	Industrial Activity	1. Activity status: Non-complying	
LCZ-R21	Industrial Activity						
1. Activity status: Non-complying							

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R22	<table border="1"> <tr> <td>LCZ-R22</td> <td>Yard Sale Activity / Trade Supplier</td> </tr> <tr> <td colspan="2">1. Activity status: Non-complying</td> </tr> </table>	LCZ-R22	Yard Sale Activity / Trade Supplier	1. Activity status: Non-complying			
LCZ-R22	Yard Sale Activity / Trade Supplier								
1. Activity status: Non-complying									
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R23	<table border="1"> <tr> <td>LCZ-R23</td> <td>Motorised Recreation</td> </tr> <tr> <td colspan="2">1. Activity status: Non-complying</td> </tr> </table>	LCZ-R23	Motorised Recreation	1. Activity status: Non-complying			
LCZ-R23	Motorised Recreation								
1. Activity status: Non-complying									
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R24	<table border="1"> <tr> <td>LCZ-R24</td> <td>Rural Industry</td> </tr> <tr> <td colspan="2">1. Activity status: Non-complying</td> </tr> </table>	LCZ-R24	Rural Industry	1. Activity status: Non-complying			
LCZ-R24	Rural Industry								
1. Activity status: Non-complying									
	New LCZ - Local Centre Zone	Introduce new Rule LCZ-R25	<table border="1"> <tr> <td>LCZ-R25</td> <td>Primary Production</td> </tr> <tr> <td colspan="2">1. Activity status: Non-complying</td> </tr> </table>	LCZ-R25	Primary Production	1. Activity status: Non-complying			
LCZ-R25	Primary Production								
1. Activity status: Non-complying									
	New LCZ - Local Centre Zone	Introduce new Standard LCZ-S1	<table border="1"> <tr> <td colspan="2">Activity Standards</td> </tr> <tr> <td>LCZ-S1</td> <td>Height</td> </tr> <tr> <td> <p>1. Buildings must not exceed 26 metres in height, except that 50% of a building's roof in elevation, measured vertically from the junction between wall and roof, may exceed this height by 1 metre, where the entire roof slopes 15° or more, as shown on the following diagram:</p>  </td> <td> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>The location, design and appearance of the building or structure.</u> 2. <u>Any adverse effects on the streetscape.</u> 3. <u>Visual dominance, shading and loss of privacy for adjoining Residential or Open Space and Recreation zoned sites.</u> 4. <u>Compatibility with the planned built urban form of buildings, structures and activities in the surrounding area.</u> 5. <u>Whether the building height is commensurate with the anticipated level of commercial activities and community services in the Local Centre Zone.</u> </td> </tr> </table>	Activity Standards		LCZ-S1	Height	<p>1. Buildings must not exceed 26 metres in height, except that 50% of a building's roof in elevation, measured vertically from the junction between wall and roof, may exceed this height by 1 metre, where the entire roof slopes 15° or more, as shown on the following diagram:</p> 	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>The location, design and appearance of the building or structure.</u> 2. <u>Any adverse effects on the streetscape.</u> 3. <u>Visual dominance, shading and loss of privacy for adjoining Residential or Open Space and Recreation zoned sites.</u> 4. <u>Compatibility with the planned built urban form of buildings, structures and activities in the surrounding area.</u> 5. <u>Whether the building height is commensurate with the anticipated level of commercial activities and community services in the Local Centre Zone.</u>
Activity Standards									
LCZ-S1	Height								
<p>1. Buildings must not exceed 26 metres in height, except that 50% of a building's roof in elevation, measured vertically from the junction between wall and roof, may exceed this height by 1 metre, where the entire roof slopes 15° or more, as shown on the following diagram:</p> 	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>The location, design and appearance of the building or structure.</u> 2. <u>Any adverse effects on the streetscape.</u> 3. <u>Visual dominance, shading and loss of privacy for adjoining Residential or Open Space and Recreation zoned sites.</u> 4. <u>Compatibility with the planned built urban form of buildings, structures and activities in the surrounding area.</u> 5. <u>Whether the building height is commensurate with the anticipated level of commercial activities and community services in the Local Centre Zone.</u> 								

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>2. <u>Any fence or standalone wall along a side or rear boundary which adjoins a site zoned Residential or Open Space and Recreation must not exceed 2m in height.</u></p> <p>This standard does not apply to:</p> <ol style="list-style-type: none"> <u>Solar water heating components provided these do not exceed the height by more than 1m.</u> <u>Chimney structures not exceeding 1.1m in width on any elevation and provided these do not exceed the height by more than 1m.</u> <u>Antennas, aerials, and flues provided these do not exceed the height by more than 1m.</u> <u>Satellite dishes (less than 1m in diameter) and architectural features (e.g. finials, spires) provided these do not exceed the height by more than 1m.</u> <u>Lift overruns provided these do not exceed the height by more than 1m.</u> <p>6. <u>Whether an increase in building height results from a response to natural hazard mitigation.</u></p> <p>7. <u>Whether topographical or other site constraints make compliance with the standard impractical.</u></p>
New LCZ - Local Centre Zone	Introduce new Standard LCZ-S2	<p>LCZ-S2</p> <p>Height in Relation to Boundary</p> <p>Where the side or rear boundary of a site adjoins a Residential Zone or Open Space and Recreation Zone the following Height in Relation to Boundary standard applies:</p> <ol style="list-style-type: none"> Buildings must not project beyond a 60° recession plane measured from a point 4 metres vertically above ground level along all boundaries that adjoin a General Residential Zone of Open Space and Recreation Zone, as shown on the following diagram. Where the boundary forms part of a legal right of way, entrance strip, access site, or pedestrian access way, the height in relation to boundary applies from the farthest boundary of that legal right of way, entrance strip, access site, or pedestrian access way. 	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> <u>Visual dominance, shading and loss of privacy for adjoining Residential or Open Space and Recreation zoned sites.</u> <u>The location, design and appearance of the building or structure.</u> <u>Whether an increase in height in relation to boundary results from a response to natural hazard mitigation.</u> <u>Whether any architectural features or steps are proposed in the building façade to provide an attractive</u>

Commented [MM196]: S58.265 - Kāinga Ora: Homes and Communities

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p><u>2. Buildings must not project beyond a 60° recession plane measured from a point 5 metres vertically above ground level along all boundaries that adjoin a High Density Residential Zone. Where the boundary forms part of a legal right of way, entrance strip, access site, or pedestrian access way, the height in relation to boundary applies from the farthest boundary of that legal right of way, entrance strip, access site, or pedestrian access way.</u></p>  <p>This standard does not apply to:</p> <ol style="list-style-type: none"> A boundary with a road. Existing or proposed internal boundaries within a site. Site boundaries where there is an existing common wall between 2 buildings on adjacent sites or where a common wall is proposed. Solar water heating components provided these do not exceed the height in relation to boundary by more than 1m. Chimney structures not exceeding 1.1m in width on any elevation and provided these do not exceed the height in relation to boundary by more than 1m.

Commented [MM197]: S58.265 - Kāinga Ora: Homes and Communities

IPI - PROPOSED AMENDMENTS													
#	Chapter	Change	Track Change										
			<p>f. Antennas, aerials, satellite dishes (less than 1m in diameter), flues, and architectural features (e.g. finials, spires) provided these do not exceed the height in relation to boundary by more than 3m measured vertically.</p>										
	New LCZ - Local Centre Zone	Introduce new Standard LCZ-S3	<table border="1"> <thead> <tr> <th><u>LCZ-S3</u></th> <th><u>Setback</u></th> </tr> </thead> <tbody> <tr> <td> <p>Where the side or rear boundary of a site adjoins a Residential Zone or Open Space and Recreation Zone the following Setback standard applies:</p> <p>1. Buildings must be set back from the relevant boundary by the minimum depth listed in the yards table below:</p> <table border="1"> <thead> <tr> <th><u>Yard</u></th> <th><u>Minimum depth</u></th> </tr> </thead> <tbody> <tr> <td>Side</td> <td>1 metre</td> </tr> <tr> <td>Rear</td> <td>1 metre</td> </tr> </tbody> </table> <p>2. This standard does not apply to site boundaries where there is an existing common wall between 2 buildings on adjacent sites or where a common wall is proposed.</p> <p>3. This standard does not apply to:</p> <p>a. Accessory buildings less than 2m in height.</p> <p>b. Fences and standalone walls.</p> </td> <td> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>The visual amenity of adjoining Residential and Open Space and Recreation sites.</u> 2. <u>The location, design and appearance of the building or structure.</u> 3. <u>Whether any architectural features or steps are proposed in the building façade to provide an attractive appearance when viewed from adjoining Residential or Open Space and Recreation sites.</u> 4. <u>Any benefits, including the extent to which the reduced setback will result in a more efficient, practical and better use of the balance of the site.</u> </td> </tr> </tbody> </table>	<u>LCZ-S3</u>	<u>Setback</u>	<p>Where the side or rear boundary of a site adjoins a Residential Zone or Open Space and Recreation Zone the following Setback standard applies:</p> <p>1. Buildings must be set back from the relevant boundary by the minimum depth listed in the yards table below:</p> <table border="1"> <thead> <tr> <th><u>Yard</u></th> <th><u>Minimum depth</u></th> </tr> </thead> <tbody> <tr> <td>Side</td> <td>1 metre</td> </tr> <tr> <td>Rear</td> <td>1 metre</td> </tr> </tbody> </table> <p>2. This standard does not apply to site boundaries where there is an existing common wall between 2 buildings on adjacent sites or where a common wall is proposed.</p> <p>3. This standard does not apply to:</p> <p>a. Accessory buildings less than 2m in height.</p> <p>b. Fences and standalone walls.</p>	<u>Yard</u>	<u>Minimum depth</u>	Side	1 metre	Rear	1 metre	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>The visual amenity of adjoining Residential and Open Space and Recreation sites.</u> 2. <u>The location, design and appearance of the building or structure.</u> 3. <u>Whether any architectural features or steps are proposed in the building façade to provide an attractive appearance when viewed from adjoining Residential or Open Space and Recreation sites.</u> 4. <u>Any benefits, including the extent to which the reduced setback will result in a more efficient, practical and better use of the balance of the site.</u>
<u>LCZ-S3</u>	<u>Setback</u>												
<p>Where the side or rear boundary of a site adjoins a Residential Zone or Open Space and Recreation Zone the following Setback standard applies:</p> <p>1. Buildings must be set back from the relevant boundary by the minimum depth listed in the yards table below:</p> <table border="1"> <thead> <tr> <th><u>Yard</u></th> <th><u>Minimum depth</u></th> </tr> </thead> <tbody> <tr> <td>Side</td> <td>1 metre</td> </tr> <tr> <td>Rear</td> <td>1 metre</td> </tr> </tbody> </table> <p>2. This standard does not apply to site boundaries where there is an existing common wall between 2 buildings on adjacent sites or where a common wall is proposed.</p> <p>3. This standard does not apply to:</p> <p>a. Accessory buildings less than 2m in height.</p> <p>b. Fences and standalone walls.</p>	<u>Yard</u>	<u>Minimum depth</u>	Side	1 metre	Rear	1 metre	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>The visual amenity of adjoining Residential and Open Space and Recreation sites.</u> 2. <u>The location, design and appearance of the building or structure.</u> 3. <u>Whether any architectural features or steps are proposed in the building façade to provide an attractive appearance when viewed from adjoining Residential or Open Space and Recreation sites.</u> 4. <u>Any benefits, including the extent to which the reduced setback will result in a more efficient, practical and better use of the balance of the site.</u> 						
<u>Yard</u>	<u>Minimum depth</u>												
Side	1 metre												
Rear	1 metre												
	New LCZ - Local Centre Zone	Introduce new Standard LCZ-S4	<table border="1"> <thead> <tr> <th><u>LCZ-S4</u></th> <th><u>Active Frontages</u></th> </tr> </thead> <tbody> <tr> <td> <p>1. Along active frontages identified on the Planning Maps:</p> <p>a. All new buildings and ground level additions or alterations to existing buildings must be built up to the street edge and oriented towards the public space;</p> </td> <td> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>The effects on the amenity and quality of the streetscape.</u> 2. <u>The design and appearance of the street frontage.</u> </td> </tr> </tbody> </table>	<u>LCZ-S4</u>	<u>Active Frontages</u>	<p>1. Along active frontages identified on the Planning Maps:</p> <p>a. All new buildings and ground level additions or alterations to existing buildings must be built up to the street edge and oriented towards the public space;</p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>The effects on the amenity and quality of the streetscape.</u> 2. <u>The design and appearance of the street frontage.</u> 						
<u>LCZ-S4</u>	<u>Active Frontages</u>												
<p>1. Along active frontages identified on the Planning Maps:</p> <p>a. All new buildings and ground level additions or alterations to existing buildings must be built up to the street edge and oriented towards the public space;</p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>The effects on the amenity and quality of the streetscape.</u> 2. <u>The design and appearance of the street frontage.</u> 												

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<p>b. <u>A veranda must be provided that:</u></p> <p>i. <u>Extends along the entire length of the building frontage;</u></p> <p>ii. <u>Provides continuous shelter with any adjoining veranda; and</u></p> <p>iii. <u>Has a minimum setback of 500mm from any kerb face;</u></p> <p>c. <u>At least 55% of the ground floor building frontage must be display windows or transparent glazing; and</u></p> <p>d. <u>The principal public entrance to the building must be located on the front boundary.</u></p> <p>3. <u>The ability to reuse and adapt the building for a variety of activities.</u></p>				
	New LCZ - Local Centre Zone	Introduce new Standard LCZ-S5	<table border="1"> <thead> <tr> <th><u>LCZ-S5</u></th> <th><u>Location of Residential Units</u></th> </tr> </thead> <tbody> <tr> <td>1. <u>Along active frontages identified on the planning maps all residential units must be located above ground floor level.</u></td> <td> <p>Matters of discretion are restricted to:</p> <p>1. <u>The effects on the amenity and quality of the streetscape.</u></p> <p>2. <u>The amenity for the occupiers of the residential units.</u></p> </td> </tr> </tbody> </table>	<u>LCZ-S5</u>	<u>Location of Residential Units</u>	1. <u>Along active frontages identified on the planning maps all residential units must be located above ground floor level.</u>	<p>Matters of discretion are restricted to:</p> <p>1. <u>The effects on the amenity and quality of the streetscape.</u></p> <p>2. <u>The amenity for the occupiers of the residential units.</u></p>
<u>LCZ-S5</u>	<u>Location of Residential Units</u>						
1. <u>Along active frontages identified on the planning maps all residential units must be located above ground floor level.</u>	<p>Matters of discretion are restricted to:</p> <p>1. <u>The effects on the amenity and quality of the streetscape.</u></p> <p>2. <u>The amenity for the occupiers of the residential units.</u></p>						
	New LCZ - Local Centre Zone	Introduce new Standard LCZ-S6	<table border="1"> <thead> <tr> <th><u>LCZ-S6</u></th> <th><u>Noise and Ventilation</u></th> </tr> </thead> <tbody> <tr> <td> <p>1. <u>All residential units must meet the following standards:</u></p> <p>a. <u>All habitable rooms must be designed and constructed to meet internal sound insulation levels achieving $D_{nT,w} + C_{tr} > 30dB$ with an acoustic design certificate signed by a qualified acoustic engineer stating <u>compliance will be achieved; and</u></u></p> <p>b. <u>All habitable rooms must have a positive supplementary source of fresh air ducted from</u></p> </td> <td> <p>Matters of discretion are restricted to:</p> <p>1. <u>Any potential reverse sensitivity effects on the continued operation of non- residential activities.</u></p> <p>2. <u>The amenity for the occupiers of the residential units.</u></p> </td> </tr> </tbody> </table>	<u>LCZ-S6</u>	<u>Noise and Ventilation</u>	<p>1. <u>All residential units must meet the following standards:</u></p> <p>a. <u>All habitable rooms must be designed and constructed to meet internal sound insulation levels achieving $D_{nT,w} + C_{tr} > 30dB$ with an acoustic design certificate signed by a qualified acoustic engineer stating <u>compliance will be achieved; and</u></u></p> <p>b. <u>All habitable rooms must have a positive supplementary source of fresh air ducted from</u></p>	<p>Matters of discretion are restricted to:</p> <p>1. <u>Any potential reverse sensitivity effects on the continued operation of non- residential activities.</u></p> <p>2. <u>The amenity for the occupiers of the residential units.</u></p>
<u>LCZ-S6</u>	<u>Noise and Ventilation</u>						
<p>1. <u>All residential units must meet the following standards:</u></p> <p>a. <u>All habitable rooms must be designed and constructed to meet internal sound insulation levels achieving $D_{nT,w} + C_{tr} > 30dB$ with an acoustic design certificate signed by a qualified acoustic engineer stating <u>compliance will be achieved; and</u></u></p> <p>b. <u>All habitable rooms must have a positive supplementary source of fresh air ducted from</u></p>	<p>Matters of discretion are restricted to:</p> <p>1. <u>Any potential reverse sensitivity effects on the continued operation of non- residential activities.</u></p> <p>2. <u>The amenity for the occupiers of the residential units.</u></p>						

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<p><u>outside. The supplementary source of air is to achieve a minimum of 7.5 litres per second per person.</u></p>				
	New LCZ - Local Centre Zone	Introduce new Standard LCZ-S7	<table border="1"> <thead> <tr> <th>LCZ-S7</th> <th>Outdoor Living Space</th> </tr> </thead> <tbody> <tr> <td> <p>1. Each residential unit at ground floor level must have an outdoor living space that is at least 20 square metres and that comprises ground floor, balcony, patio, or roof terrace space that—</p> <p>a. where located at ground level, has no dimension less than 3 metres; and</p> <p>b. where provided in the form of a balcony, patio, or roof terrace, is at least 8 square metres and has a minimum dimension of 1.8 metres; and</p> <p>c. is accessible from the residential unit; and</p> <p>d. may be—</p> <p>i. grouped cumulatively by area in 1 communally accessible location; or</p> <p>ii. located directly adjacent to the unit; and</p> <p>e. is free of buildings, parking spaces, and servicing and manoeuvring areas.</p> <p>2. Each residential unit located above ground floor level must have an outdoor living space in the form of a balcony, patio, or roof terrace that—</p> <p>a. is at least 8 square metres and has a minimum dimension of 1.8 metres; and</p> <p>b. is accessible from the residential unit; and</p> <p>c. may be—</p> </td> <td> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Whether adequate useable space is provided to accommodate outdoor activities.</u> 2. <u>Whether there are topographical or other site constraints that make compliance with the standard impractical.</u> 3. <u>The proximity of the residential unit to accessible public open space.</u> </td> </tr> </tbody> </table>	LCZ-S7	Outdoor Living Space	<p>1. Each residential unit at ground floor level must have an outdoor living space that is at least 20 square metres and that comprises ground floor, balcony, patio, or roof terrace space that—</p> <p>a. where located at ground level, has no dimension less than 3 metres; and</p> <p>b. where provided in the form of a balcony, patio, or roof terrace, is at least 8 square metres and has a minimum dimension of 1.8 metres; and</p> <p>c. is accessible from the residential unit; and</p> <p>d. may be—</p> <p>i. grouped cumulatively by area in 1 communally accessible location; or</p> <p>ii. located directly adjacent to the unit; and</p> <p>e. is free of buildings, parking spaces, and servicing and manoeuvring areas.</p> <p>2. Each residential unit located above ground floor level must have an outdoor living space in the form of a balcony, patio, or roof terrace that—</p> <p>a. is at least 8 square metres and has a minimum dimension of 1.8 metres; and</p> <p>b. is accessible from the residential unit; and</p> <p>c. may be—</p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Whether adequate useable space is provided to accommodate outdoor activities.</u> 2. <u>Whether there are topographical or other site constraints that make compliance with the standard impractical.</u> 3. <u>The proximity of the residential unit to accessible public open space.</u>
LCZ-S7	Outdoor Living Space						
<p>1. Each residential unit at ground floor level must have an outdoor living space that is at least 20 square metres and that comprises ground floor, balcony, patio, or roof terrace space that—</p> <p>a. where located at ground level, has no dimension less than 3 metres; and</p> <p>b. where provided in the form of a balcony, patio, or roof terrace, is at least 8 square metres and has a minimum dimension of 1.8 metres; and</p> <p>c. is accessible from the residential unit; and</p> <p>d. may be—</p> <p>i. grouped cumulatively by area in 1 communally accessible location; or</p> <p>ii. located directly adjacent to the unit; and</p> <p>e. is free of buildings, parking spaces, and servicing and manoeuvring areas.</p> <p>2. Each residential unit located above ground floor level must have an outdoor living space in the form of a balcony, patio, or roof terrace that—</p> <p>a. is at least 8 square metres and has a minimum dimension of 1.8 metres; and</p> <p>b. is accessible from the residential unit; and</p> <p>c. may be—</p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Whether adequate useable space is provided to accommodate outdoor activities.</u> 2. <u>Whether there are topographical or other site constraints that make compliance with the standard impractical.</u> 3. <u>The proximity of the residential unit to accessible public open space.</u> 						

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>i. grouped cumulatively by area in 1 communally accessible location, in which case it may be located at ground level; or</p> <p>ii. located directly adjacent to the unit.</p> <p>2. For multi-unit housing, the outdoor living space can be provided as private space and shared space where:</p> <p>a. Each residential unit is provided with a private outdoor living space that has a minimum area of 8m² with a minimum dimension of 1.8m, that is directly accessible from the residential unit to which it relates;</p> <p>b. The shared outdoor living space has a minimum area of 20m² with a minimum dimension of 3m; and</p> <p>c. Any ground floor outdoor living space is free of buildings, parking spaces and manoeuvring areas.</p> <p><u>1. Each residential unit, including any dual key unit, must be provided with either a private outdoor living space or access to a communal outdoor living space;</u></p> <p><u>2. Where private outdoor living space is provided it must be:</u></p> <p><u>i For the exclusive use of residents;</u></p> <p><u>ii Directly accessible from a habitable room;</u></p> <p><u>iii A single contiguous space; and</u></p> <p><u>iv Of the minimum area and dimension specified in the table below;</u></p> <p><u>3. Where communal outdoor living space is provided it does not need to be in a single continuous space, but it must be:</u></p> <p><u>i Accessible from the residential units it serves;</u></p>

Commented [MM198]: S58.270 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS																					
#	Chapter	Change	Track Change																		
			<p>ii <u>Of the minimum area and dimension specified in the table below; and</u></p> <p>iii <u>Free of buildings, parking spaces, and servicing and manoeuvring areas.</u></p> <table border="1"> <thead> <tr> <th><u>Living Space Type</u></th> <th><u>Minimum area</u></th> <th><u>Minimum dimension</u></th> </tr> </thead> <tbody> <tr> <td><u>1. Private</u></td> <td></td> <td></td> </tr> <tr> <td>i <u>Studio unit & 1 bedroom unit</u></td> <td><u>5m²</u></td> <td><u>1.8m</u></td> </tr> <tr> <td>ii <u>2+ bedroom unit</u></td> <td><u>8m²</u></td> <td><u>1.8m</u></td> </tr> <tr> <td><u>2. Communal</u></td> <td></td> <td></td> </tr> <tr> <td><u>For every 5 units</u></td> <td><u>10m² (per residential unit)</u></td> <td><u>8m diameter</u></td> </tr> </tbody> </table>	<u>Living Space Type</u>	<u>Minimum area</u>	<u>Minimum dimension</u>	<u>1. Private</u>			i <u>Studio unit & 1 bedroom unit</u>	<u>5m²</u>	<u>1.8m</u>	ii <u>2+ bedroom unit</u>	<u>8m²</u>	<u>1.8m</u>	<u>2. Communal</u>			<u>For every 5 units</u>	<u>10m² (per residential unit)</u>	<u>8m diameter</u>
<u>Living Space Type</u>	<u>Minimum area</u>	<u>Minimum dimension</u>																			
<u>1. Private</u>																					
i <u>Studio unit & 1 bedroom unit</u>	<u>5m²</u>	<u>1.8m</u>																			
ii <u>2+ bedroom unit</u>	<u>8m²</u>	<u>1.8m</u>																			
<u>2. Communal</u>																					
<u>For every 5 units</u>	<u>10m² (per residential unit)</u>	<u>8m diameter</u>																			
New LCZ - Local Centre Zone	Introduce new Standard LCZ-S8	<p>LCZ-S8 Screening and Landscaping of Service Areas, Outdoor Storage Areas and Parking Areas</p> <p>1. Any on-site service areas, including rubbish collection areas, and areas for the outdoor storage of goods or materials must, without preventing the provision of an entry point to the site, be adequately screened by a fence or landscaping where they are visible from any:</p> <p>a. Public road;</p> <p>b. Other public space; and</p> <p>c. Directly adjoining site zoned Residential or Open Space and Recreation.</p> <p>2. Any on-site parking area must:</p> <p>a. Be adequately screened by a fence or landscaping from any directly adjoining site zoned Residential or Open Space and Recreation.</p>	<p>Matters of discretion are restricted to:</p> <p>1. Any adverse effects on the streetscape.</p> <p>2. The visual amenity of adjoining Residential and Open Space and Recreation zoned sites including shading.</p> <p>3. The service, storage and parking needs of the activity.</p> <p>4. The size and location of service, storage and any parking areas.</p>																		

Commented [MM199]: S58.270 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<p>b. <u>Where located along a street edge, provide a landscaping strip that extends at least 1.5m from the boundary with the road and comprise a mix of trees, shrubs and ground cover plants, without preventing the provision of an entry point to the site.</u></p> <p>Except that:</p> <ul style="list-style-type: none"> • <u>The landscaping requirement for on-site parking areas along a street edge does not apply to individual parking spaces for residential development, if provided.</u> 				
	New LCZ - Local Centre Zone	Introduce new Standard LCZ-S9	<table border="1"> <thead> <tr> <th>LCZ-S9</th> <th>Water Supply, Stormwater and Wastewater</th> </tr> </thead> <tbody> <tr> <td> <p>1. <u>All activities shall comply with the water supply, stormwater and wastewater standards in the Code of Practice for Civil Engineering Works.</u></p> </td> <td> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Whether the Water Supply, Stormwater and Wastewater infrastructure has sufficient capacity to accommodate the activity.</u> 2. <u>Any alternative measures proposed to mitigate adverse effects on the Water Supply, Stormwater and Wastewater infrastructure network.</u> 3. <u>Whether the additional demand generated will necessitate additional unplanned public investment in, or expansion of, the Water Supply, Stormwater and Wastewater infrastructure network or compromise its ability to service other activities permitted within the zone.</u> 4. <u>Whether the development can achieve hydraulic neutrality.</u> 5. <u>The extent to which the development incorporates stormwater management techniques or controls to mitigate any increase in pre-development peak stormwater runoff.</u> </td> </tr> </tbody> </table>	LCZ-S9	Water Supply, Stormwater and Wastewater	<p>1. <u>All activities shall comply with the water supply, stormwater and wastewater standards in the Code of Practice for Civil Engineering Works.</u></p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Whether the Water Supply, Stormwater and Wastewater infrastructure has sufficient capacity to accommodate the activity.</u> 2. <u>Any alternative measures proposed to mitigate adverse effects on the Water Supply, Stormwater and Wastewater infrastructure network.</u> 3. <u>Whether the additional demand generated will necessitate additional unplanned public investment in, or expansion of, the Water Supply, Stormwater and Wastewater infrastructure network or compromise its ability to service other activities permitted within the zone.</u> 4. <u>Whether the development can achieve hydraulic neutrality.</u> 5. <u>The extent to which the development incorporates stormwater management techniques or controls to mitigate any increase in pre-development peak stormwater runoff.</u>
LCZ-S9	Water Supply, Stormwater and Wastewater						
<p>1. <u>All activities shall comply with the water supply, stormwater and wastewater standards in the Code of Practice for Civil Engineering Works.</u></p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Whether the Water Supply, Stormwater and Wastewater infrastructure has sufficient capacity to accommodate the activity.</u> 2. <u>Any alternative measures proposed to mitigate adverse effects on the Water Supply, Stormwater and Wastewater infrastructure network.</u> 3. <u>Whether the additional demand generated will necessitate additional unplanned public investment in, or expansion of, the Water Supply, Stormwater and Wastewater infrastructure network or compromise its ability to service other activities permitted within the zone.</u> 4. <u>Whether the development can achieve hydraulic neutrality.</u> 5. <u>The extent to which the development incorporates stormwater management techniques or controls to mitigate any increase in pre-development peak stormwater runoff.</u> 						

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
	New LCZ - Local Centre Zone	Introduce new Standard LCZ-S10	<table border="1"> <tr> <td>LCZ-S10</td> <td>Hydraulic neutrality</td> </tr> <tr> <td colspan="2"> <p>New buildings and development must be designed to achieve hydraulic neutrality, ensure that the stormwater runoff from all new impermeable surfaces will be disposed of or stored on-site and released at a rate that does not exceed the peak stormwater runoff when compared to the pre-development situation for the 10% and 1% rainfall Annual Exceedance Probability event.</p> </td> </tr> <tr> <td colspan="2"> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Methods to avoid, remedy or mitigate any adverse effects resulting from any increase in pre-development peak stormwater runoff.</u> 2. <u>Cumulative effects.</u> </td> </tr> </table>	LCZ-S10	Hydraulic neutrality	<p>New buildings and development must be designed to achieve hydraulic neutrality, ensure that the stormwater runoff from all new impermeable surfaces will be disposed of or stored on-site and released at a rate that does not exceed the peak stormwater runoff when compared to the pre-development situation for the 10% and 1% rainfall Annual Exceedance Probability event.</p>		<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Methods to avoid, remedy or mitigate any adverse effects resulting from any increase in pre-development peak stormwater runoff.</u> 2. <u>Cumulative effects.</u> 	
LCZ-S10	Hydraulic neutrality								
<p>New buildings and development must be designed to achieve hydraulic neutrality, ensure that the stormwater runoff from all new impermeable surfaces will be disposed of or stored on-site and released at a rate that does not exceed the peak stormwater runoff when compared to the pre-development situation for the 10% and 1% rainfall Annual Exceedance Probability event.</p>									
<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Methods to avoid, remedy or mitigate any adverse effects resulting from any increase in pre-development peak stormwater runoff.</u> 2. <u>Cumulative effects.</u> 									
MUZ – Mixed Use Zone									
	New MUZ - Mixed Use Zone	Introduce new Chapter Heading and Introduction	<p>Mixed Use Zone</p> <p>The Mixed Use Zone provides for a wide range of activities ranging from residential over commercial to light industrial. It enables retail, large format retail, commercial, recreational and entertainment activities, while also providing for drive-through activities and light industrial activities.</p> <p>While anticipated and provided for in the Mixed Use Zone, light industrial activities are proposed to be assessed on a case by case basis through a resource consent process. This allows for an assessment of their suitability for the zone and provides the opportunity to manage potential adverse effects on existing or anticipated activities in the Mixed Use Zone.</p> <p>The mixture of residential and non-residential activities in the zone and the medium scale built form establish a safe, vibrant and attractive environment for workers, residents and customers.</p> <p>It needs to be noted that, due to the wide range of non-residential activities provided for and the potential for light industrial activities to establish, this zone may have fewer day-to-day conveniences and different amenity levels for residents than other Commercial or Residential Zones.</p>						
	New MUZ - Mixed Use Zone	Introduce new Objective MUZ-O1	<table border="1"> <tr> <th colspan="2">Objectives</th> </tr> <tr> <td>MUZ-O1</td> <td>Purpose of the Mixed Use Zone</td> </tr> <tr> <td colspan="2"> <p>The Mixed Use Zone accommodates a wide range of activities, including commercial, recreational, entertainment, large format retail and car focused activities as well as compatible light industrial activities and residential activities. The non-residential activities service the needs of business and surrounding residential catchments.</p> </td> </tr> </table>	Objectives		MUZ-O1	Purpose of the Mixed Use Zone	<p>The Mixed Use Zone accommodates a wide range of activities, including commercial, recreational, entertainment, large format retail and car focused activities as well as compatible light industrial activities and residential activities. The non-residential activities service the needs of business and surrounding residential catchments.</p>	
Objectives									
MUZ-O1	Purpose of the Mixed Use Zone								
<p>The Mixed Use Zone accommodates a wide range of activities, including commercial, recreational, entertainment, large format retail and car focused activities as well as compatible light industrial activities and residential activities. The non-residential activities service the needs of business and surrounding residential catchments.</p>									

Commented [MM200]: S58.273 - Kianga Ora: Home and Communities.

Commented [MM201]: S62.16 - Silverstream Land Holdings Limited

IPI - PROPOSED AMENDMENTS											
#	Chapter	Change	Track Change								
	New MUZ - Mixed Use Zone	Introduce new Objective MUZ-02	<table border="1"> <tr> <td>MUZ-02</td> <td>Character and Amenity Values of the Mixed Use Zone</td> </tr> <tr> <td colspan="2">Mixed Use Zones are vibrant, attractive and safe urban environments. The built environment is well-designed, reflects the wide mix of compatible activities and is generally of a medium to high scale and density.</td> </tr> </table>	MUZ-02	Character and Amenity Values of the Mixed Use Zone	Mixed Use Zones are vibrant, attractive and safe urban environments. The built environment is well-designed, reflects the wide mix of compatible activities and is generally of a medium to high scale and density.					
MUZ-02	Character and Amenity Values of the Mixed Use Zone										
Mixed Use Zones are vibrant, attractive and safe urban environments. The built environment is well-designed, reflects the wide mix of compatible activities and is generally of a medium to high scale and density.											
	New MUZ - Mixed Use Zone	Introduce new Objective MUZ-03	<table border="1"> <tr> <td>MUZ-03</td> <td>Managing Effects at the Zone Interface</td> </tr> <tr> <td colspan="2">Use and development within the Mixed Use Zone are of an appropriate scale and manage potential adverse effects on the amenity values of adjoining sites in Residential or Open Space and Recreation Zones.</td> </tr> </table>	MUZ-03	Managing Effects at the Zone Interface	Use and development within the Mixed Use Zone are of an appropriate scale and manage potential adverse effects on the amenity values of adjoining sites in Residential or Open Space and Recreation Zones.					
MUZ-03	Managing Effects at the Zone Interface										
Use and development within the Mixed Use Zone are of an appropriate scale and manage potential adverse effects on the amenity values of adjoining sites in Residential or Open Space and Recreation Zones.											
	New MUZ - Mixed Use Zone	Introduce new Objective MUZ-04	<table border="1"> <tr> <td>MUZ-04</td> <td>Hydraulic neutrality</td> </tr> <tr> <td colspan="2">There is no increase in the peak demand on stormwater management systems and increase in flooding from subdivision and development.</td> </tr> </table>	MUZ-04	Hydraulic neutrality	There is no increase in the peak demand on stormwater management systems and increase in flooding from subdivision and development .					
MUZ-04	Hydraulic neutrality										
There is no increase in the peak demand on stormwater management systems and increase in flooding from subdivision and development .											
	New MUZ - Mixed Use Zone	Introduce new Policy MUZ-P1	<table border="1"> <tr> <td colspan="2">Policies</td> </tr> <tr> <td>MUZ-P1</td> <td>Appropriate Activities</td> </tr> <tr> <td colspan="2">Enable appropriate activities that</td> </tr> <tr> <td colspan="2"> <ol style="list-style-type: none"> 1. <u>Are consistent with the anticipated role, function and character of the Mixed Use Zone;</u> 2. <u>Provide employment and services to businesses and surrounding residential catchments; and</u> 3. <u>Minimise any adverse effects on the amenity of adjoining residential, recreational and open space sites.</u> </td> </tr> </table>	Policies		MUZ-P1	Appropriate Activities	Enable appropriate activities that		<ol style="list-style-type: none"> 1. <u>Are consistent with the anticipated role, function and character of the Mixed Use Zone;</u> 2. <u>Provide employment and services to businesses and surrounding residential catchments; and</u> 3. <u>Minimise any adverse effects on the amenity of adjoining residential, recreational and open space sites.</u> 	
Policies											
MUZ-P1	Appropriate Activities										
Enable appropriate activities that											
<ol style="list-style-type: none"> 1. <u>Are consistent with the anticipated role, function and character of the Mixed Use Zone;</u> 2. <u>Provide employment and services to businesses and surrounding residential catchments; and</u> 3. <u>Minimise any adverse effects on the amenity of adjoining residential, recreational and open space sites.</u> 											
	New MUZ - Mixed Use Zone	Introduce new Policy MUZ-P2	<table border="1"> <tr> <td>MUZ-P2</td> <td>Residential Activities</td> </tr> <tr> <td colspan="2">Provide for residential activity where any residential units are designed to:</td> </tr> <tr> <td colspan="2"> <ol style="list-style-type: none"> 1. <u>Achieve adequate indoor noise and ventilation levels for occupants;</u> 2. <u>Provide a high level of amenity for occupants; and</u> 3. <u>Minimise reverse sensitivity effects on non-residential activities.</u> </td> </tr> </table>	MUZ-P2	Residential Activities	Provide for residential activity where any residential units are designed to:		<ol style="list-style-type: none"> 1. <u>Achieve adequate indoor noise and ventilation levels for occupants;</u> 2. <u>Provide a high level of amenity for occupants; and</u> 3. <u>Minimise reverse sensitivity effects on non-residential activities.</u> 			
MUZ-P2	Residential Activities										
Provide for residential activity where any residential units are designed to:											
<ol style="list-style-type: none"> 1. <u>Achieve adequate indoor noise and ventilation levels for occupants;</u> 2. <u>Provide a high level of amenity for occupants; and</u> 3. <u>Minimise reverse sensitivity effects on non-residential activities.</u> 											
	New MUZ - Mixed Use Zone	Introduce new Policy MUZ-P3	<table border="1"> <tr> <td>MUZ-P3</td> <td>Other Activities</td> </tr> </table>	MUZ-P3	Other Activities						
MUZ-P3	Other Activities										

Commented [MM202]: S33.20 - Fuel Companies.

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<p>Provide for other activities where:</p> <ol style="list-style-type: none"> Any significant adverse effects, including reverse sensitivity effects, can be managed; The design and location of parking areas, vehicle access and servicing arrangements: <ol style="list-style-type: none"> maintain streetscape amenity; and ensure that pedestrian safety is not compromised; The size, intensity and scale of the activity: <ol style="list-style-type: none"> Is consistent with the anticipated character and amenity values of the Mixed Use Zone; and Does not compromise other activities that are anticipated within the Mixed Use Zone; and The location of the activity in the Mixed Use Zone does not undermine the role and function of the City Centre Zone or the General Industrial Zone. 		
	New MUZ - Mixed Use Zone	Introduce new Policy MUZ-P4	<table border="1"> <tr> <td>MUZ-P4</td> <td>Inappropriate Activities</td> </tr> </table> <p>Avoid activities that area incompatible with the anticipated scale and character of the Mixed Use Zone and the surrounding environment.</p>	MUZ-P4	Inappropriate Activities
MUZ-P4	Inappropriate Activities				
	New MUZ - Mixed Use Zone	Introduce new Policy MUZ-P5	<table border="1"> <tr> <td>MUZ-P5</td> <td>Built Development</td> </tr> </table> <p>Provide for built development that:</p> <ol style="list-style-type: none"> Is consistent with the anticipated role, character, planned urban built form and density of the Mixed Use Zone; Is commensurate with the anticipated level of commercial activities and community services in the Mixed Use Zone; Is well designed; and Contributes to an attractive and safe well-functioning urban environment. 	MUZ-P5	Built Development
MUZ-P5	Built Development				
	New MUZ - Mixed Use Zone	Introduce new Policy MUZ-P6	<table border="1"> <tr> <td>MUZ-P6</td> <td>Public Space Interface</td> </tr> </table> <p>Provide for new development that creates an attractive interface with the public space and minimises adverse effects on the amenity and quality of the streetscape through:</p>	MUZ-P6	Public Space Interface
MUZ-P6	Public Space Interface				

Commented [MM203]: S58.285 - Kianga Ora: Homes and Communities.

Commented [MM204]: S64.97 - Retirement Villages Association of New Zealand.

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<ol style="list-style-type: none"> 1. <u>High quality building design;</u> 2. <u>Visually unobtrusive parking, storage and servicing areas;</u> 3. <u>The use of landscaping to minimise the effects of larger parking, service and storage areas.</u> <p><u>Encourage new buildings to be oriented towards the front boundary of the site and create a positive interface with the public space.</u></p>		
	New MUZ - Mixed Use Zone	Introduce new Policy MUZ-P7	<table border="1"> <tr> <td>MUZ-P7</td> <td>Interface with Residential and Open Space and Recreation Zones</td> </tr> </table> <p><u>Minimise the adverse effects from non-residential use and development on sites directly adjoining the Residential or Open Space and Recreation Zones through:</u></p> <ol style="list-style-type: none"> 1. <u>Requiring new buildings and activities to be located and designed to manage any shading and privacy effects on neighbouring sites zoned Residential or Open Space and Recreation;</u> 2. <u>Limiting the height, bulk and form of new buildings along boundaries with sites zoned Residential or Open Space and Recreation to minimise dominance effects; and</u> 3. <u>Requiring the use of screening and landscaping to minimise adverse visual effects on adjoining sites zoned Residential or Open Space and Recreation.</u> 	MUZ-P7	Interface with Residential and Open Space and Recreation Zones
MUZ-P7	Interface with Residential and Open Space and Recreation Zones				
	New MUZ - Mixed Use Zone	Introduce new Policy MUZ-P8	<table border="1"> <tr> <td>MUZ-P8</td> <td>Hydraulic neutrality</td> </tr> </table> <p><u><i>New buildings and development will be designed to achieve hydraulic neutrality.</i></u></p>	MUZ-P8	Hydraulic neutrality
MUZ-P8	Hydraulic neutrality				
	New MUZ - Mixed Use Zone	Introduce new Rules Advice Note	<table border="1"> <tr> <td>Rules</td> </tr> </table>	Rules	
Rules					

Note: There may be a number of provisions that apply to an **activity, building, structure or site**. Resource consent may therefore be required under rules in this chapter as well as other chapters. Unless specifically stated in a rule, resource consent is required under each relevant rule. The steps to determine the status of an **activity** are set out in Chapter 2 How the Plan Works.

Rules relating to **subdivision** are found in the SUB-GEN (General **Subdivision** Provisions that Apply in All Zones) and the SUB-CMU (**Subdivision in Commercial and Mixed Use Zones**) chapters.

Each **activity** in the Mixed Use Zone shall comply with the relevant **qualifying matter areas**, and permitted activity standards in the district-wide matters of the Plan as listed below.

<u>District-wide matters</u>
<u>NU – Network Utilities</u>
<u>REG - Renewable Energy Generation</u>
<u>TP – Transport and Parking</u>
<u>CL – Contaminated Land</u>
<u>HS - Hazardous Substances</u>
<u>NH - Natural Hazards</u>
<u>WM – Waste Management</u>
<u>HH - Historical Heritage</u>
<u>TREE - Notable Trees</u>
<u>UTG - Urban Tree Groups</u>
<u>ECO - Ecosystems and Indigenous Biodiversity</u>
<u>NATC – Natural Character</u>
<u>NFL - Natural Features and Landscapes</u>
<u>PA – Public Access</u>
<u>SUB - Subdivision</u>
<u>DC – Development Contributions</u>
<u>AIR - Air</u>
<u>PK – Papakāinga</u>

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			<table border="1"> <tr><td><u>ASW - Activities on the Surface of Water</u></td></tr> <tr><td><u>EW - Earthworks</u></td></tr> <tr><td><u>LIGHT - Light</u></td></tr> <tr><td><u>NOISE - Noise</u></td></tr> <tr><td><u>SIGN - Signs</u></td></tr> <tr><td><u>TEMP - Temporary Activities</u></td></tr> </table>	<u>ASW - Activities on the Surface of Water</u>	<u>EW - Earthworks</u>	<u>LIGHT - Light</u>	<u>NOISE - Noise</u>	<u>SIGN - Signs</u>	<u>TEMP - Temporary Activities</u>
<u>ASW - Activities on the Surface of Water</u>									
<u>EW - Earthworks</u>									
<u>LIGHT - Light</u>									
<u>NOISE - Noise</u>									
<u>SIGN - Signs</u>									
<u>TEMP - Temporary Activities</u>									
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R1	<table border="1"> <tr> <td><u>MUZ-R1</u></td> <td><u>Buildings and structures, including additions and alterations</u></td> </tr> <tr> <td colspan="2"> <p>1. Activity status: <u>Permitted</u></p> <p><u>Where:</u></p> <p>a. Compliance is achieved with</p> <ul style="list-style-type: none"> i. <u>MUZ-S1 (Height);</u> ii. <u>MUZ-S2 (Height in Relation to Boundary);</u> iii. <u>MUZ-S3 (Setbacks);</u> iv. <u>MUZ-S4 (Noise and Ventilation);</u> v. <u>MUZ-S5 (Outdoor Living Space);</u> vi. <u>MUZ-S6 (Landscaping and Screening);</u> vii. <u>MUZ-S7 (Water Supply, Stormwater and Wastewater); and</u> viii. <u>MUZ-S8 (Hydraulic neutrality).</u> </td> </tr> <tr> <td colspan="2"> <p>2. Activity status: <u>Restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with one or more of the standards under MUZ-R1-1.a</p> </td> </tr> </table>	<u>MUZ-R1</u>	<u>Buildings and structures, including additions and alterations</u>	<p>1. Activity status: <u>Permitted</u></p> <p><u>Where:</u></p> <p>a. Compliance is achieved with</p> <ul style="list-style-type: none"> i. <u>MUZ-S1 (Height);</u> ii. <u>MUZ-S2 (Height in Relation to Boundary);</u> iii. <u>MUZ-S3 (Setbacks);</u> iv. <u>MUZ-S4 (Noise and Ventilation);</u> v. <u>MUZ-S5 (Outdoor Living Space);</u> vi. <u>MUZ-S6 (Landscaping and Screening);</u> vii. <u>MUZ-S7 (Water Supply, Stormwater and Wastewater); and</u> viii. <u>MUZ-S8 (Hydraulic neutrality).</u> 		<p>2. Activity status: <u>Restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with one or more of the standards under MUZ-R1-1.a</p>	
<u>MUZ-R1</u>	<u>Buildings and structures, including additions and alterations</u>								
<p>1. Activity status: <u>Permitted</u></p> <p><u>Where:</u></p> <p>a. Compliance is achieved with</p> <ul style="list-style-type: none"> i. <u>MUZ-S1 (Height);</u> ii. <u>MUZ-S2 (Height in Relation to Boundary);</u> iii. <u>MUZ-S3 (Setbacks);</u> iv. <u>MUZ-S4 (Noise and Ventilation);</u> v. <u>MUZ-S5 (Outdoor Living Space);</u> vi. <u>MUZ-S6 (Landscaping and Screening);</u> vii. <u>MUZ-S7 (Water Supply, Stormwater and Wastewater); and</u> viii. <u>MUZ-S8 (Hydraulic neutrality).</u> 									
<p>2. Activity status: <u>Restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with one or more of the standards under MUZ-R1-1.a</p>									

IPI - PROPOSED AMENDMENTS																							
#	Chapter	Change	Track Change																				
			<p><u>Matters of discretion are restricted to:</u></p> <p>1. <u>The matters of discretion of any infringed standard.</u></p> <p>Notification:</p> <p><u>An application under this rule where compliance is not achieved with MUZ-S2, MU-S3, MUZ-S4 or MUZ-S6 is precluded from being publicly notified in accordance with section 95A of the RMA.</u></p> <p><u>An application under this rule where compliance is not achieved with MUZ-S5 is precluded from being publicly or limited notified in accordance with section 95A of the RMA.</u></p>																				
	New MUZ - Local Centre Zone	Introduce new Rule MUZ-R2	<table border="1"> <tr> <td>MUZ-R2</td> <td>Minor structures</td> </tr> <tr> <td colspan="2">1. Activity status: Permitted</td> </tr> </table>	MUZ-R2	Minor structures	1. Activity status: Permitted																	
MUZ-R2	Minor structures																						
1. Activity status: Permitted																							
	New MUZ - Local Centre Zone	Introduce new Rule MUZ-R3	<table border="1"> <tr> <td>MUZ-R3</td> <td>Demolition</td> </tr> <tr> <td colspan="2">1. Activity status: Permitted</td> </tr> <tr> <td colspan="2">Note: <u>Prior to demolition commencing, confirm whether rules in chapter HH-Historic Heritage apply.</u></td> </tr> </table>	MUZ-R3	Demolition	1. Activity status: Permitted		Note: <u>Prior to demolition commencing, confirm whether rules in chapter HH-Historic Heritage apply.</u>															
MUZ-R3	Demolition																						
1. Activity status: Permitted																							
Note: <u>Prior to demolition commencing, confirm whether rules in chapter HH-Historic Heritage apply.</u>																							
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R4	<table border="1"> <tr> <td>MUZ-R4</td> <td>Retail Activity and Large Format Retailing</td> </tr> <tr> <td colspan="2">1. Activity status: Permitted</td> </tr> <tr> <td colspan="2"><u>Where:</u></td> </tr> <tr> <td colspan="2">a. <u>Compliance is achieved with MUZ-S6 (Landscaping and Screening).</u></td> </tr> <tr> <td colspan="2">2. Activity status: Restricted discretionary</td> </tr> <tr> <td colspan="2"><u>Where:</u></td> </tr> <tr> <td colspan="2">a. <u>Compliance is not achieved with MUZ-R4-1.a</u></td> </tr> <tr> <td colspan="2"><u>Matters of discretion are restricted to:</u></td> </tr> <tr> <td colspan="2">1. <u>The matters of discretion of the infringed standard.</u></td> </tr> <tr> <td colspan="2">Notification:</td> </tr> </table>	MUZ-R4	Retail Activity and Large Format Retailing	1. Activity status: Permitted		<u>Where:</u>		a. <u>Compliance is achieved with MUZ-S6 (Landscaping and Screening).</u>		2. Activity status: Restricted discretionary		<u>Where:</u>		a. <u>Compliance is not achieved with MUZ-R4-1.a</u>		<u>Matters of discretion are restricted to:</u>		1. <u>The matters of discretion of the infringed standard.</u>		Notification:	
MUZ-R4	Retail Activity and Large Format Retailing																						
1. Activity status: Permitted																							
<u>Where:</u>																							
a. <u>Compliance is achieved with MUZ-S6 (Landscaping and Screening).</u>																							
2. Activity status: Restricted discretionary																							
<u>Where:</u>																							
a. <u>Compliance is not achieved with MUZ-R4-1.a</u>																							
<u>Matters of discretion are restricted to:</u>																							
1. <u>The matters of discretion of the infringed standard.</u>																							
Notification:																							

Commented [MM205]: S72.12 - Te Rūnanga o Toa Rangatira Inc

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			<ul style="list-style-type: none"> An application under this rule is precluded from being publicly notified in accordance with section 95A of the RMA 						
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R5	<table border="1"> <thead> <tr> <th>MUZ-R5</th> <th>Commercial Service Activity</th> </tr> </thead> <tbody> <tr> <td>1.</td> <td> <p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 500m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p> </td> </tr> <tr> <td>2.</td> <td> <p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with MUZ-R5-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> <u>The potential of the location of the activity in the Mixed Use Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. Compliance is not achieved with MUZ-R5-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> </td> </tr> </tbody> </table>	MUZ-R5	Commercial Service Activity	1.	<p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 500m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p>	2.	<p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with MUZ-R5-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> <u>The potential of the location of the activity in the Mixed Use Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. Compliance is not achieved with MUZ-R5-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p>
MUZ-R5	Commercial Service Activity								
1.	<p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 500m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p>								
2.	<p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with MUZ-R5-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> <u>The potential of the location of the activity in the Mixed Use Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. Compliance is not achieved with MUZ-R5-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p>								

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			<ul style="list-style-type: none"> An application under MUZ-R5-2.b is precluded from being publicly notified in accordance with section 95A of the RMA 						
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R6	<table border="1"> <thead> <tr> <th>MUZ-R6</th> <th>Food and Beverage Activity</th> </tr> </thead> <tbody> <tr> <td>1.</td> <td> <p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 500m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p> </td> </tr> <tr> <td>2.</td> <td> <p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with MUZ-R6-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> <u>The potential of the location of the activity in the Mixed Use Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. Compliance is not achieved with MUZ-R6-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> </td> </tr> </tbody> </table>	MUZ-R6	Food and Beverage Activity	1.	<p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 500m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p>	2.	<p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with MUZ-R6-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> <u>The potential of the location of the activity in the Mixed Use Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. Compliance is not achieved with MUZ-R6-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p>
MUZ-R6	Food and Beverage Activity								
1.	<p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 500m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p>								
2.	<p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with MUZ-R6-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> <u>The potential of the location of the activity in the Mixed Use Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. Compliance is not achieved with MUZ-R6-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p>								

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			<ul style="list-style-type: none"> An application under MUZ-R6-2.b is precluded from being publicly notified in accordance with section 95A of the RMA 						
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R7	<table border="1"> <thead> <tr> <th>MUZ-R7</th> <th>Community Facility</th> </tr> </thead> <tbody> <tr> <td colspan="2"> <p>1. Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per facility does not exceed 500m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p> </td> </tr> <tr> <td colspan="2"> <p>2. Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with MUZ-R7-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> <u>The potential of the location of the activity in the Mixed Use Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. Compliance is not achieved with MUZ-R7-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> </td> </tr> </tbody> </table>	MUZ-R7	Community Facility	<p>1. Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per facility does not exceed 500m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p>		<p>2. Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with MUZ-R7-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> <u>The potential of the location of the activity in the Mixed Use Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. Compliance is not achieved with MUZ-R7-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p>	
MUZ-R7	Community Facility								
<p>1. Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per facility does not exceed 500m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p>									
<p>2. Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with MUZ-R7-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> <u>The potential of the location of the activity in the Mixed Use Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. Compliance is not achieved with MUZ-R7-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p>									

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			<ul style="list-style-type: none"> An application under MUZ-R7-2.b is precluded from being publicly notified in accordance with section 95A of the RMA 						
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R8	<table border="1"> <thead> <tr> <th>MUZ-R8</th> <th>Healthcare Activity</th> </tr> </thead> <tbody> <tr> <td>1.</td> <td> <p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 500m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p> </td> </tr> <tr> <td>2.</td> <td> <p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with MUZ-R8-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> <u>The potential of the location of the activity in the Mixed Use Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. Compliance is not achieved with MUZ-R8-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> </td> </tr> </tbody> </table>	MUZ-R8	Healthcare Activity	1.	<p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 500m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p>	2.	<p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with MUZ-R8-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> <u>The potential of the location of the activity in the Mixed Use Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. Compliance is not achieved with MUZ-R8-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p>
MUZ-R8	Healthcare Activity								
1.	<p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 500m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p>								
2.	<p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with MUZ-R8-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> <u>The potential of the location of the activity in the Mixed Use Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. Compliance is not achieved with MUZ-R8-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p>								

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<ul style="list-style-type: none"> An application under MUZ-R8-2.b is precluded from being publicly notified in accordance with section 95A of the RMA
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R9	<p>MUZ-R9 Educational Facility, and Community Corrections Activity</p> <p>1. Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per facility does not exceed 500m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p> <hr/> <p>2. Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with MUZ-R9-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> <u>The potential of the location of the activity in the Mixed Use Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. Compliance is not achieved with MUZ-R9-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p>

Commented [MM206]: S28.8 - Ara Poutama Aotearoa – Department of Corrections

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			<ul style="list-style-type: none"> An application under MUZ-R9-2.b is precluded from being publicly notified in accordance with section 95A of the RMA 						
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R10	<table border="1"> <thead> <tr> <th>MUZ-R10</th> <th>Entertainment Facility</th> </tr> </thead> <tbody> <tr> <td>1.</td> <td> <p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 500m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p> </td> </tr> <tr> <td>2.</td> <td> <p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with MUZ-R10-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> <u>The potential of the location of the activity in the Mixed Use Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. Compliance is not achieved with MUZ-R10-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> </td> </tr> </tbody> </table>	MUZ-R10	Entertainment Facility	1.	<p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 500m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p>	2.	<p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with MUZ-R10-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> <u>The potential of the location of the activity in the Mixed Use Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. Compliance is not achieved with MUZ-R10-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p>
MUZ-R10	Entertainment Facility								
1.	<p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 500m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p>								
2.	<p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with MUZ-R10-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> <u>The potential of the location of the activity in the Mixed Use Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. Compliance is not achieved with MUZ-R10-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p>								

IPI - PROPOSED AMENDMENTS											
#	Chapter	Change	Track Change								
			<ul style="list-style-type: none"> An application under MUZ-R10-2.b is precluded from being publicly notified in accordance with section 95A of the RMA 								
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R11	<table border="1"> <thead> <tr> <th>MUZ-R11</th> <th>Sport and Active Recreation</th> </tr> </thead> <tbody> <tr> <td colspan="2"> <p>1. Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy including outdoor areas does not exceed 500m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p> </td> </tr> <tr> <td colspan="2"> <p>2. Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with MUZ-R11-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties. The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone. The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone. The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated. <p>b. Compliance is not achieved with MUZ-R11-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> The matters of discretion of the infringed standard. </td> </tr> <tr> <td colspan="2"> <p>Notification:</p> <ul style="list-style-type: none"> An application under MUZ-R11-2.b is precluded from being publicly notified in accordance with section 95A of the RMA </td> </tr> </tbody> </table>	MUZ-R11	Sport and Active Recreation	<p>1. Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy including outdoor areas does not exceed 500m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p>		<p>2. Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with MUZ-R11-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties. The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone. The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone. The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated. <p>b. Compliance is not achieved with MUZ-R11-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> The matters of discretion of the infringed standard. 		<p>Notification:</p> <ul style="list-style-type: none"> An application under MUZ-R11-2.b is precluded from being publicly notified in accordance with section 95A of the RMA 	
MUZ-R11	Sport and Active Recreation										
<p>1. Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy including outdoor areas does not exceed 500m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p>											
<p>2. Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with MUZ-R11-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties. The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone. The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone. The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated. <p>b. Compliance is not achieved with MUZ-R11-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> The matters of discretion of the infringed standard. 											
<p>Notification:</p> <ul style="list-style-type: none"> An application under MUZ-R11-2.b is precluded from being publicly notified in accordance with section 95A of the RMA 											

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change						
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R12	<table border="1"> <thead> <tr> <th>MUZ-R12</th> <th>Office activity</th> </tr> </thead> <tbody> <tr> <td>1.</td> <td> <p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 250m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p> </td> </tr> <tr> <td>2.</td> <td> <p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with MUZ-R12-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> <u>The potential of the location of the activity in the Mixed Use Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. Compliance is not achieved with MUZ-R12-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> <u>An application under MUZ-R12-2.b is precluded from being publicly notified in accordance with section 95A of the RMA</u> </td> </tr> </tbody> </table>	MUZ-R12	Office activity	1.	<p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 250m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p>	2.	<p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with MUZ-R12-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> <u>The potential of the location of the activity in the Mixed Use Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. Compliance is not achieved with MUZ-R12-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> <u>An application under MUZ-R12-2.b is precluded from being publicly notified in accordance with section 95A of the RMA</u>
MUZ-R12	Office activity								
1.	<p>Activity status: Permitted</p> <p>Where:</p> <p>a. The gross floor area per tenancy does not exceed 250m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p>								
2.	<p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with MUZ-R12-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> <u>The potential of the location of the activity in the Mixed Use Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. Compliance is not achieved with MUZ-R12-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> <u>An application under MUZ-R12-2.b is precluded from being publicly notified in accordance with section 95A of the RMA</u> 								

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R14	<table border="1"> <thead> <tr> <th>MUZ-R14</th> <th>Drive-through Activity</th> </tr> </thead> <tbody> <tr> <td colspan="2"> <p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>The gross floor area of the activity including parking and manoeuvring areas does not exceed 1500m²; and</u></p> <p>b. <u>Compliance is achieved with MUZ-S6 (Landscaping and Screening).</u></p> </td> </tr> <tr> <td colspan="2"> <p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with MUZ-R14-1.a</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. <u>Compliance is not achieved with MUZ-R14-1.b</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> <u>An application under MUZ-R14-2.b is precluded from being publicly notified in accordance with section 95A of the RMA</u> </td> </tr> </tbody> </table>	MUZ-R14	Drive-through Activity	<p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>The gross floor area of the activity including parking and manoeuvring areas does not exceed 1500m²; and</u></p> <p>b. <u>Compliance is achieved with MUZ-S6 (Landscaping and Screening).</u></p>		<p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with MUZ-R14-1.a</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. <u>Compliance is not achieved with MUZ-R14-1.b</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> <u>An application under MUZ-R14-2.b is precluded from being publicly notified in accordance with section 95A of the RMA</u> 	
MUZ-R14	Drive-through Activity								
<p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>The gross floor area of the activity including parking and manoeuvring areas does not exceed 1500m²; and</u></p> <p>b. <u>Compliance is achieved with MUZ-S6 (Landscaping and Screening).</u></p>									
<p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with MUZ-R14-1.a</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. <u>Compliance is not achieved with MUZ-R14-1.b</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> <u>An application under MUZ-R14-2.b is precluded from being publicly notified in accordance with section 95A of the RMA</u> 									
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R15	<table border="1"> <thead> <tr> <th>MUZ-R15</th> <th>Visitor Accommodation</th> </tr> </thead> <tbody> <tr> <td colspan="2"></td> </tr> </tbody> </table>	MUZ-R15	Visitor Accommodation				
MUZ-R15	Visitor Accommodation								

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
			<p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. The gross floor area per tenancy does not exceed 500m²;</p> <p>b. All habitable rooms comply with MUZ-S4 (Noise and Ventilation); and</p> <p>c. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p> <hr/> <p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with MUZ-R15-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u> 2. <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u> 3. <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Mixed Use Zone.</u> 4. <u>The potential of the location of the activity in the Mixed Use Zone to undermine the role and function of the City Centre Zone.</u> 5. <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. Compliance is not achieved with MUZ-R15-1.b or MUZ-R15-1.c</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> • <u>An application under MUZ-R15-2.b is precluded from being publicly notified in accordance with section 95A of the RMA</u>




IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R16	<table border="1"> <thead> <tr> <th>MUZ-R16</th> <th>Residential Activity</th> </tr> </thead> <tbody> <tr> <td>1.</td> <td> <p>Activity status: Permitted</p> <p>Where:</p> <p>a. <u>No more than six residential units occupy the site; and</u></p> <p>b. <u>Compliance is achieved with</u></p> <p>i. <u>MUZ-S4 (Noise and Ventilation); and</u></p> <p>ii. <u>MUZ-S5 (Outdoor Living Space).</u></p> </td> </tr> <tr> <td>2.</td> <td> <p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. <u>Compliance is not achieved with MUZ-R16-1.a</u></p> <p><u>Matters of discretion are restricted to:</u></p> <p>1. <u>The effects of the residential activity on the existing and anticipated function and role of the Mixed Use Zone.</u></p> <p>2. <u>The potential of the residential activity to compromise activities that are enabled in the zone.</u></p> <p>3. <u>The amenity for the occupiers of the residential units.</u></p> <p>b. <u>Compliance is not achieved with MUZ-R16-1.b</u></p> <p><u>Matters of discretion are restricted to:</u></p> <p>1. <u>The matters of discretion of the infringed standard.</u></p> <p>Notification:</p> <ul style="list-style-type: none"> <u>An application under MUZ-R16-2.b is precluded from being publicly notified in accordance with section 95A of the RMA.</u> </td> </tr> </tbody> </table>	MUZ-R16	Residential Activity	1.	<p>Activity status: Permitted</p> <p>Where:</p> <p>a. <u>No more than six residential units occupy the site; and</u></p> <p>b. <u>Compliance is achieved with</u></p> <p>i. <u>MUZ-S4 (Noise and Ventilation); and</u></p> <p>ii. <u>MUZ-S5 (Outdoor Living Space).</u></p>	2.	<p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. <u>Compliance is not achieved with MUZ-R16-1.a</u></p> <p><u>Matters of discretion are restricted to:</u></p> <p>1. <u>The effects of the residential activity on the existing and anticipated function and role of the Mixed Use Zone.</u></p> <p>2. <u>The potential of the residential activity to compromise activities that are enabled in the zone.</u></p> <p>3. <u>The amenity for the occupiers of the residential units.</u></p> <p>b. <u>Compliance is not achieved with MUZ-R16-1.b</u></p> <p><u>Matters of discretion are restricted to:</u></p> <p>1. <u>The matters of discretion of the infringed standard.</u></p> <p>Notification:</p> <ul style="list-style-type: none"> <u>An application under MUZ-R16-2.b is precluded from being publicly notified in accordance with section 95A of the RMA.</u>
MUZ-R16	Residential Activity								
1.	<p>Activity status: Permitted</p> <p>Where:</p> <p>a. <u>No more than six residential units occupy the site; and</u></p> <p>b. <u>Compliance is achieved with</u></p> <p>i. <u>MUZ-S4 (Noise and Ventilation); and</u></p> <p>ii. <u>MUZ-S5 (Outdoor Living Space).</u></p>								
2.	<p>Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. <u>Compliance is not achieved with MUZ-R16-1.a</u></p> <p><u>Matters of discretion are restricted to:</u></p> <p>1. <u>The effects of the residential activity on the existing and anticipated function and role of the Mixed Use Zone.</u></p> <p>2. <u>The potential of the residential activity to compromise activities that are enabled in the zone.</u></p> <p>3. <u>The amenity for the occupiers of the residential units.</u></p> <p>b. <u>Compliance is not achieved with MUZ-R16-1.b</u></p> <p><u>Matters of discretion are restricted to:</u></p> <p>1. <u>The matters of discretion of the infringed standard.</u></p> <p>Notification:</p> <ul style="list-style-type: none"> <u>An application under MUZ-R16-2.b is precluded from being publicly notified in accordance with section 95A of the RMA.</u> 								
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R17	<table border="1"> <thead> <tr> <th>MUZ-R17</th> <th>Retirement Village</th> </tr> </thead> <tbody> <tr> <td>1.</td> <td> <p>Activity status: Restricted discretionary</p> </td> </tr> </tbody> </table>	MUZ-R17	Retirement Village	1.	<p>Activity status: Restricted discretionary</p>		
MUZ-R17	Retirement Village								
1.	<p>Activity status: Restricted discretionary</p>								

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<p><u>Where:</u></p> <p>a. All habitable rooms comply with MUZ-S4 (Noise and Ventilation); and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> The extent to which the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties. The effects of the of the activity on the existing and anticipated function and role of the Mixed Use Zone. The potential of the activity to compromise activities that are enabled in the Mixed Use Zone. The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated. Any potential reverse sensitivity effects on the continued operation of non- residential activities. The amenity for the occupiers of residential units or habitable rooms. <hr/> <p>2. Activity status: Discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with MUZ-R17-1.a or MUZ-R17-1.b</p>				
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R18	<table border="1"> <thead> <tr> <th>MUZ-R18</th> <th>Light Industrial Activities</th> </tr> </thead> <tbody> <tr> <td colspan="2"> <p>1. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. The gross floor area does not exceed 3500m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> The extent to which the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties. The effects of the of the activity on the existing and anticipated function and role of the Mixed Use Zone. </td> </tr> </tbody> </table>	MUZ-R18	Light Industrial Activities	<p>1. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. The gross floor area does not exceed 3500m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> The extent to which the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties. The effects of the of the activity on the existing and anticipated function and role of the Mixed Use Zone. 	
MUZ-R18	Light Industrial Activities						
<p>1. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. The gross floor area does not exceed 3500m²; and</p> <p>b. Compliance is achieved with MUZ-S6 (Landscaping and Screening).</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> The extent to which the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties. The effects of the of the activity on the existing and anticipated function and role of the Mixed Use Zone. 							

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			<p>3. <u>The potential of the activity to compromise activities that are enabled in the Mixed Use Zone.</u></p> <p>4. <u>The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated.</u></p> <p>2. <u>Activity status: Discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with MUZ-R18-1.a or MUZ-R18-1.b</u></p>						
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R19	<table border="1"> <thead> <tr> <th>MUZ-R19</th> <th>Emergency Service Facility</th> </tr> </thead> <tbody> <tr> <td colspan="2"> <p>1. <u>Activity status: Restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is achieved with MUZ-S6 (Landscaping and Screening).</u></p> <p><u>Matters of discretion are restricted to:</u></p> <p>1. <u>The extent to which the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u></p> <p>2. <u>The effects of the of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u></p> <p>3. <u>The potential of the activity to compromise activities that are enabled in the Mixed Use Zone.</u></p> <p>4. <u>The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated.</u></p> <p>5. <u>The functional need or operational need for the Emergency Service Facility to be located in the Mixed Use Zone.</u></p> <p><u>Notification:</u></p> <ul style="list-style-type: none"> <u>An application under this rule is precluded from being publicly notified in accordance with section 95A of the RMA</u> </td> </tr> <tr> <td colspan="2"> <p>2. <u>Activity status: Discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with MUZ-R19-1.a</u></p> </td> </tr> </tbody> </table>	MUZ-R19	Emergency Service Facility	<p>1. <u>Activity status: Restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is achieved with MUZ-S6 (Landscaping and Screening).</u></p> <p><u>Matters of discretion are restricted to:</u></p> <p>1. <u>The extent to which the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u></p> <p>2. <u>The effects of the of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u></p> <p>3. <u>The potential of the activity to compromise activities that are enabled in the Mixed Use Zone.</u></p> <p>4. <u>The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated.</u></p> <p>5. <u>The functional need or operational need for the Emergency Service Facility to be located in the Mixed Use Zone.</u></p> <p><u>Notification:</u></p> <ul style="list-style-type: none"> <u>An application under this rule is precluded from being publicly notified in accordance with section 95A of the RMA</u> 		<p>2. <u>Activity status: Discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with MUZ-R19-1.a</u></p>	
MUZ-R19	Emergency Service Facility								
<p>1. <u>Activity status: Restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is achieved with MUZ-S6 (Landscaping and Screening).</u></p> <p><u>Matters of discretion are restricted to:</u></p> <p>1. <u>The extent to which the activity may adversely impact on the amenity of the Mixed Use Zone or adjacent properties.</u></p> <p>2. <u>The effects of the of the activity on the existing and anticipated function and role of the Mixed Use Zone.</u></p> <p>3. <u>The potential of the activity to compromise activities that are enabled in the Mixed Use Zone.</u></p> <p>4. <u>The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated.</u></p> <p>5. <u>The functional need or operational need for the Emergency Service Facility to be located in the Mixed Use Zone.</u></p> <p><u>Notification:</u></p> <ul style="list-style-type: none"> <u>An application under this rule is precluded from being publicly notified in accordance with section 95A of the RMA</u> 									
<p>2. <u>Activity status: Discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with MUZ-R19-1.a</u></p>									

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R19A	<table border="1"> <tr> <td>MUZ-R19A</td> <td>Any activity or combination of activities within Precinct 3 – Trentham Racecourse Precinct</td> </tr> <tr> <td colspan="2"> <p>1. Activity status: Restricted Discretionary</p> <p>Where:</p> <p>b. the activity or activities will generate more than 100 vehicles per hour measured by passenger car units (PCU).</p> <p>Matters of discretion are restricted to:</p> <p>Methods to avoid, remedy or mitigate adverse effects on the transportation network as identified by an integrated transport assessment.</p> </td> </tr> </table>	MUZ-R19A	Any activity or combination of activities within Precinct 3 – Trentham Racecourse Precinct	<p>1. Activity status: Restricted Discretionary</p> <p>Where:</p> <p>b. the activity or activities will generate more than 100 vehicles per hour measured by passenger car units (PCU).</p> <p>Matters of discretion are restricted to:</p> <p>Methods to avoid, remedy or mitigate adverse effects on the transportation network as identified by an integrated transport assessment.</p>	
MUZ-R19A	Any activity or combination of activities within Precinct 3 – Trentham Racecourse Precinct						
<p>1. Activity status: Restricted Discretionary</p> <p>Where:</p> <p>b. the activity or activities will generate more than 100 vehicles per hour measured by passenger car units (PCU).</p> <p>Matters of discretion are restricted to:</p> <p>Methods to avoid, remedy or mitigate adverse effects on the transportation network as identified by an integrated transport assessment.</p>							
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R20	<table border="1"> <tr> <td>MUZ-R20</td> <td>Warehouses</td> </tr> <tr> <td colspan="2"> <p>1. Activity status: Discretionary</p> </td> </tr> </table>	MUZ-R20	Warehouses	<p>1. Activity status: Discretionary</p>	
MUZ-R20	Warehouses						
<p>1. Activity status: Discretionary</p>							
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R21	<table border="1"> <tr> <td>MUZ-R21</td> <td>Yard Based Activity / Trade Supplier</td> </tr> <tr> <td colspan="2"> <p>1. Activity status: Discretionary</p> </td> </tr> </table>	MUZ-R21	Yard Based Activity / Trade Supplier	<p>1. Activity status: Discretionary</p>	
MUZ-R21	Yard Based Activity / Trade Supplier						
<p>1. Activity status: Discretionary</p>							
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R22	<table border="1"> <tr> <td>MUZ-R22</td> <td>Motorised Recreation</td> </tr> <tr> <td colspan="2"> <p>1. Activity status: Discretionary</p> </td> </tr> </table>	MUZ-R22	Motorised Recreation	<p>1. Activity status: Discretionary</p>	
MUZ-R22	Motorised Recreation						
<p>1. Activity status: Discretionary</p>							
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R23	<table border="1"> <tr> <td>MUZ-R23</td> <td>Any activity not otherwise listed as permitted, restricted discretionary, discretionary or non-complying</td> </tr> <tr> <td colspan="2"> <p>1. Activity status: Discretionary</p> </td> </tr> </table>	MUZ-R23	Any activity not otherwise listed as permitted, restricted discretionary, discretionary or non-complying	<p>1. Activity status: Discretionary</p>	
MUZ-R23	Any activity not otherwise listed as permitted, restricted discretionary, discretionary or non-complying						
<p>1. Activity status: Discretionary</p>							
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R24	<table border="1"> <tr> <td>MUZ-R24</td> <td>Industrial Activity, excluding Light Industrial Activities and Warehouses</td> </tr> <tr> <td colspan="2"> <p>1. Activity status: Non-complying</p> </td> </tr> </table>	MUZ-R24	Industrial Activity, excluding Light Industrial Activities and Warehouses	<p>1. Activity status: Non-complying</p>	
MUZ-R24	Industrial Activity, excluding Light Industrial Activities and Warehouses						
<p>1. Activity status: Non-complying</p>							
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R25	<table border="1"> <tr> <td>MUZ-R25</td> <td>Rural Industry</td> </tr> <tr> <td colspan="2"> <p>1. Activity status: Non-complying</p> </td> </tr> </table>	MUZ-R25	Rural Industry	<p>1. Activity status: Non-complying</p>	
MUZ-R25	Rural Industry						
<p>1. Activity status: Non-complying</p>							
	New MUZ - Mixed Use Zone	Introduce new Rule MUZ-R26	<table border="1"> <tr> <td>MUZ-R26</td> <td>Primary Production</td> </tr> </table>	MUZ-R26	Primary Production		
MUZ-R26	Primary Production						

Commented [MM207]: S69.1 - RACE Inc.

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			1. Activity status: Non-complying						
	New MUZ - Mixed Use Zone	Introduce new Standard MUZ-S1	<table border="1"> <thead> <tr> <th colspan="2">Standards</th> </tr> <tr> <th>MUZ-S1</th> <th>Height</th> </tr> </thead> <tbody> <tr> <td> <p>1. Buildings must not exceed 26 metres in height, except that 50% of a building's roof in elevation, measured vertically from the junction between wall and roof, may exceed this height by 1 metre, where the entire roof slopes 15° or more, as shown on the following diagram:</p>  <p>2. Any fence or standalone wall along a side or rear boundary which adjoins a site zoned Residential or Open Space and Recreation must not exceed 2m in height.</p> <p>This standard does not apply to:</p> <ol style="list-style-type: none"> Solar water heating components provided these do not exceed the height by more than 1m. Chimney structures not exceeding 1.1m in width on any elevation and provided these do not exceed the height by more than 1m. Antennas, aerials, and flues provided these do not exceed the height by more than 1m. </td> <td> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> <u>The location, design and appearance of the building or structure.</u> <u>Any adverse effects on the streetscape.</u> <u>Visual dominance, shading and loss of privacy for adjoining Residential or Open Space and Recreation zoned sites.</u> <u>Compatibility with the planned built urban form of buildings, structures and activities in the surrounding area.</u> <u>Whether the building height is commensurate with the anticipated level of commercial activities and community services in the Mixed Use Zone</u> <u>Whether an increase in building height results from a response to natural hazard mitigation.</u> <u>Whether topographical or other site constraints make compliance with the standard impractical.</u> </td> </tr> </tbody> </table>	Standards		MUZ-S1	Height	<p>1. Buildings must not exceed 26 metres in height, except that 50% of a building's roof in elevation, measured vertically from the junction between wall and roof, may exceed this height by 1 metre, where the entire roof slopes 15° or more, as shown on the following diagram:</p>  <p>2. Any fence or standalone wall along a side or rear boundary which adjoins a site zoned Residential or Open Space and Recreation must not exceed 2m in height.</p> <p>This standard does not apply to:</p> <ol style="list-style-type: none"> Solar water heating components provided these do not exceed the height by more than 1m. Chimney structures not exceeding 1.1m in width on any elevation and provided these do not exceed the height by more than 1m. Antennas, aerials, and flues provided these do not exceed the height by more than 1m. 	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> <u>The location, design and appearance of the building or structure.</u> <u>Any adverse effects on the streetscape.</u> <u>Visual dominance, shading and loss of privacy for adjoining Residential or Open Space and Recreation zoned sites.</u> <u>Compatibility with the planned built urban form of buildings, structures and activities in the surrounding area.</u> <u>Whether the building height is commensurate with the anticipated level of commercial activities and community services in the Mixed Use Zone</u> <u>Whether an increase in building height results from a response to natural hazard mitigation.</u> <u>Whether topographical or other site constraints make compliance with the standard impractical.</u>
Standards									
MUZ-S1	Height								
<p>1. Buildings must not exceed 26 metres in height, except that 50% of a building's roof in elevation, measured vertically from the junction between wall and roof, may exceed this height by 1 metre, where the entire roof slopes 15° or more, as shown on the following diagram:</p>  <p>2. Any fence or standalone wall along a side or rear boundary which adjoins a site zoned Residential or Open Space and Recreation must not exceed 2m in height.</p> <p>This standard does not apply to:</p> <ol style="list-style-type: none"> Solar water heating components provided these do not exceed the height by more than 1m. Chimney structures not exceeding 1.1m in width on any elevation and provided these do not exceed the height by more than 1m. Antennas, aerials, and flues provided these do not exceed the height by more than 1m. 	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> <u>The location, design and appearance of the building or structure.</u> <u>Any adverse effects on the streetscape.</u> <u>Visual dominance, shading and loss of privacy for adjoining Residential or Open Space and Recreation zoned sites.</u> <u>Compatibility with the planned built urban form of buildings, structures and activities in the surrounding area.</u> <u>Whether the building height is commensurate with the anticipated level of commercial activities and community services in the Mixed Use Zone</u> <u>Whether an increase in building height results from a response to natural hazard mitigation.</u> <u>Whether topographical or other site constraints make compliance with the standard impractical.</u> 								

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<p>d. <u>Satellite dishes (less than 1m in diameter) and architectural features (e.g. finials, spires) provided these do not exceed the height by more than 1m.</u></p> <p>e. <u>Lift overruns provided these do not exceed the height by more than 1m.</u></p>				
	New MUZ - Mixed Use Zone	Introduce new Standard MUZ-S2	<table border="1"> <thead> <tr> <th>MUZ-S2</th> <th>Height in Relation to Boundary</th> </tr> </thead> <tbody> <tr> <td> <p>Where the side or rear boundary of a site adjoins a Residential Zone or Open Space and Recreation Zone, <u>or where a boundary within Precinct 3 – Trentham Racecourse Precinct adjoins Lot 1 DP [569820]</u>, the following Height in Relation to Boundary standard applies:</p> <p>1. Buildings must not project beyond a 60° recession plane measured from a point 4 metres vertically above ground level along all boundaries, as shown on the following diagram. Where the boundary forms part of a legal right of way, entrance strip, access site, or pedestrian access way, the height in relation to boundary applies from the farthest boundary of that legal right of way, entrance strip, access site, or pedestrian access way.</p> <div data-bbox="654 970 976 1216" data-label="Diagram"> <p>The diagram illustrates a 60-degree recession plane. A vertical line on the left is labeled '4m' and represents the height from the ground level to the starting point of the recession plane. A horizontal line extends from this point to the right. A diagonal line representing the recession plane extends downwards and to the right at a 60-degree angle from the horizontal. A vertical dashed line on the right is labeled 'Boundary'. The angle between the horizontal line and the recession plane is marked as 60.0°.</p> </div> <p>This standard does not apply to:</p> </td> <td> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Visual dominance, shading and loss of privacy for adjoining Residential or Open Space and Recreation zoned sites, or Precinct 3 – Trentham Racecourse Precinct.</u> 2. <u>The location, design and appearance of the building or structure.</u> 3. <u>Whether an increase in height in relation to boundary results from a response to natural hazard mitigation.</u> 4. <u>Whether any architectural features or steps are proposed in the building façade to provide an attractive appearance when viewed from adjoining Residential or Open Space and Recreation zoned sites, or Precinct 3 – Trentham Racecourse Precinct.</u> </td> </tr> </tbody> </table>	MUZ-S2	Height in Relation to Boundary	<p>Where the side or rear boundary of a site adjoins a Residential Zone or Open Space and Recreation Zone, <u>or where a boundary within Precinct 3 – Trentham Racecourse Precinct adjoins Lot 1 DP [569820]</u>, the following Height in Relation to Boundary standard applies:</p> <p>1. Buildings must not project beyond a 60° recession plane measured from a point 4 metres vertically above ground level along all boundaries, as shown on the following diagram. Where the boundary forms part of a legal right of way, entrance strip, access site, or pedestrian access way, the height in relation to boundary applies from the farthest boundary of that legal right of way, entrance strip, access site, or pedestrian access way.</p> <div data-bbox="654 970 976 1216" data-label="Diagram"> <p>The diagram illustrates a 60-degree recession plane. A vertical line on the left is labeled '4m' and represents the height from the ground level to the starting point of the recession plane. A horizontal line extends from this point to the right. A diagonal line representing the recession plane extends downwards and to the right at a 60-degree angle from the horizontal. A vertical dashed line on the right is labeled 'Boundary'. The angle between the horizontal line and the recession plane is marked as 60.0°.</p> </div> <p>This standard does not apply to:</p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Visual dominance, shading and loss of privacy for adjoining Residential or Open Space and Recreation zoned sites, or Precinct 3 – Trentham Racecourse Precinct.</u> 2. <u>The location, design and appearance of the building or structure.</u> 3. <u>Whether an increase in height in relation to boundary results from a response to natural hazard mitigation.</u> 4. <u>Whether any architectural features or steps are proposed in the building façade to provide an attractive appearance when viewed from adjoining Residential or Open Space and Recreation zoned sites, or Precinct 3 – Trentham Racecourse Precinct.</u>
MUZ-S2	Height in Relation to Boundary						
<p>Where the side or rear boundary of a site adjoins a Residential Zone or Open Space and Recreation Zone, <u>or where a boundary within Precinct 3 – Trentham Racecourse Precinct adjoins Lot 1 DP [569820]</u>, the following Height in Relation to Boundary standard applies:</p> <p>1. Buildings must not project beyond a 60° recession plane measured from a point 4 metres vertically above ground level along all boundaries, as shown on the following diagram. Where the boundary forms part of a legal right of way, entrance strip, access site, or pedestrian access way, the height in relation to boundary applies from the farthest boundary of that legal right of way, entrance strip, access site, or pedestrian access way.</p> <div data-bbox="654 970 976 1216" data-label="Diagram"> <p>The diagram illustrates a 60-degree recession plane. A vertical line on the left is labeled '4m' and represents the height from the ground level to the starting point of the recession plane. A horizontal line extends from this point to the right. A diagonal line representing the recession plane extends downwards and to the right at a 60-degree angle from the horizontal. A vertical dashed line on the right is labeled 'Boundary'. The angle between the horizontal line and the recession plane is marked as 60.0°.</p> </div> <p>This standard does not apply to:</p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Visual dominance, shading and loss of privacy for adjoining Residential or Open Space and Recreation zoned sites, or Precinct 3 – Trentham Racecourse Precinct.</u> 2. <u>The location, design and appearance of the building or structure.</u> 3. <u>Whether an increase in height in relation to boundary results from a response to natural hazard mitigation.</u> 4. <u>Whether any architectural features or steps are proposed in the building façade to provide an attractive appearance when viewed from adjoining Residential or Open Space and Recreation zoned sites, or Precinct 3 – Trentham Racecourse Precinct.</u> 						

Commented [MM208]: S69.1 - RACE Inc

Commented [MM209]: S69.1 - RACE Inc

Commented [MM210]: S69.1 - RACE Inc

IPI - PROPOSED AMENDMENTS													
#	Chapter	Change	Track Change										
			<ul style="list-style-type: none"> a. <u>A boundary with a road.</u> b. <u>Existing or proposed internal boundaries within a site.</u> c. <u>Site boundaries where there is an existing common wall between 2 buildings on adjacent sites or where a common wall is proposed.</u> d. <u>Solar water heating components provided these do not exceed the height in relation to boundary by more than 1m.</u> e. <u>Chimney structures not exceeding 1.1m in width on any elevation and provided these do not exceed the height in relation to boundary by more than 1m.</u> f. <u>Antennas, aerials, satellite dishes (less than 1m in diameter), flues, and architectural features (e.g. finials, spires) provided these do not exceed the height in relation to boundary by more than 3m measured vertically.</u> 										
	New MUZ - Mixed Use Zone	Introduce new Standard MUZ-S3	<table border="1"> <thead> <tr> <th>MUZ-S3</th> <th>Setback</th> </tr> </thead> <tbody> <tr> <td> <p>Where the side or rear boundary of a site adjoins a Residential Zone or Open Space and Recreation Zone, <u>or where a boundary within Precinct 3 – Trentham Racecourse Precinct adjoins Lot 1 DP 569820</u>, the following Setback standard applies:</p> <p>1. <u>Buildings must be set back from the relevant boundary by the minimum depth listed in the yards table below:</u></p> <table border="1"> <thead> <tr> <th>Yard</th> <th>Minimum depth</th> </tr> </thead> <tbody> <tr> <td>Side</td> <td>1 metre</td> </tr> <tr> <td>Rear</td> <td>1 metre</td> </tr> </tbody> </table> </td> <td> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> <u>The visual amenity of adjoining Residential and Open Space and Recreation sites, or Precinct 3 – Trentham Racecourse Precinct.</u> <u>The location, design and appearance of the building or structure.</u> <u>Whether any architectural features or steps are proposed in the building façade to provide an attractive appearance when viewed from adjoining Residential or Open Space and Recreation sites, or Precinct 3 – Trentham Racecourse Precinct.</u> </td> </tr> </tbody> </table>	MUZ-S3	Setback	<p>Where the side or rear boundary of a site adjoins a Residential Zone or Open Space and Recreation Zone, <u>or where a boundary within Precinct 3 – Trentham Racecourse Precinct adjoins Lot 1 DP 569820</u>, the following Setback standard applies:</p> <p>1. <u>Buildings must be set back from the relevant boundary by the minimum depth listed in the yards table below:</u></p> <table border="1"> <thead> <tr> <th>Yard</th> <th>Minimum depth</th> </tr> </thead> <tbody> <tr> <td>Side</td> <td>1 metre</td> </tr> <tr> <td>Rear</td> <td>1 metre</td> </tr> </tbody> </table>	Yard	Minimum depth	Side	1 metre	Rear	1 metre	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> <u>The visual amenity of adjoining Residential and Open Space and Recreation sites, or Precinct 3 – Trentham Racecourse Precinct.</u> <u>The location, design and appearance of the building or structure.</u> <u>Whether any architectural features or steps are proposed in the building façade to provide an attractive appearance when viewed from adjoining Residential or Open Space and Recreation sites, or Precinct 3 – Trentham Racecourse Precinct.</u>
MUZ-S3	Setback												
<p>Where the side or rear boundary of a site adjoins a Residential Zone or Open Space and Recreation Zone, <u>or where a boundary within Precinct 3 – Trentham Racecourse Precinct adjoins Lot 1 DP 569820</u>, the following Setback standard applies:</p> <p>1. <u>Buildings must be set back from the relevant boundary by the minimum depth listed in the yards table below:</u></p> <table border="1"> <thead> <tr> <th>Yard</th> <th>Minimum depth</th> </tr> </thead> <tbody> <tr> <td>Side</td> <td>1 metre</td> </tr> <tr> <td>Rear</td> <td>1 metre</td> </tr> </tbody> </table>	Yard	Minimum depth	Side	1 metre	Rear	1 metre	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> <u>The visual amenity of adjoining Residential and Open Space and Recreation sites, or Precinct 3 – Trentham Racecourse Precinct.</u> <u>The location, design and appearance of the building or structure.</u> <u>Whether any architectural features or steps are proposed in the building façade to provide an attractive appearance when viewed from adjoining Residential or Open Space and Recreation sites, or Precinct 3 – Trentham Racecourse Precinct.</u> 						
Yard	Minimum depth												
Side	1 metre												
Rear	1 metre												

Commented [MM211]: S69.1 - RACE Inc

Commented [MM212]: S69.1 - RACE Inc

Commented [MM213]: S69.1 - RACE Inc

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<p>2. This standard does not apply to site boundaries where there is an existing common wall between 2 buildings on adjacent sites or where a common wall is proposed.</p> <p>3. This standard does not apply to:</p> <ol style="list-style-type: none"> Accessory buildings less than 2m in height. Fences and standalone walls. <p>4. Any benefits, including the extent to which the reduced setback will result in a more efficient, practical and better use of the balance of the site.</p>				
	New MUZ - Mixed Use Zone	Introduce new Standard MUZ-S4	<table border="1"> <thead> <tr> <th>MUZ-S4</th> <th>Noise and Ventilation</th> </tr> </thead> <tbody> <tr> <td> <p>1. All residential units must meet all of the following standards:</p> <ol style="list-style-type: none"> All habitable rooms must be designed and constructed to meet internal sound insulation levels achieving $D_{nT,w}+C_{tr} >30dB$ with an acoustic design certificate signed by a qualified acoustic engineer stating compliance will be achieved; and All habitable rooms must have a positive supplementary source of fresh air ducted from outside. The supplementary source of air is to achieve a minimum of 7.5 litres per second per person. </td> <td> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> Any potential reverse sensitivity effects on the continued operation of non- residential activities. The amenity for the occupiers of the residential units. </td> </tr> </tbody> </table>	MUZ-S4	Noise and Ventilation	<p>1. All residential units must meet all of the following standards:</p> <ol style="list-style-type: none"> All habitable rooms must be designed and constructed to meet internal sound insulation levels achieving $D_{nT,w}+C_{tr} >30dB$ with an acoustic design certificate signed by a qualified acoustic engineer stating compliance will be achieved; and All habitable rooms must have a positive supplementary source of fresh air ducted from outside. The supplementary source of air is to achieve a minimum of 7.5 litres per second per person. 	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> Any potential reverse sensitivity effects on the continued operation of non- residential activities. The amenity for the occupiers of the residential units.
MUZ-S4	Noise and Ventilation						
<p>1. All residential units must meet all of the following standards:</p> <ol style="list-style-type: none"> All habitable rooms must be designed and constructed to meet internal sound insulation levels achieving $D_{nT,w}+C_{tr} >30dB$ with an acoustic design certificate signed by a qualified acoustic engineer stating compliance will be achieved; and All habitable rooms must have a positive supplementary source of fresh air ducted from outside. The supplementary source of air is to achieve a minimum of 7.5 litres per second per person. 	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> Any potential reverse sensitivity effects on the continued operation of non- residential activities. The amenity for the occupiers of the residential units. 						
	New MUZ - Mixed Use Zone	Introduce new Standard MUZ-S5	<table border="1"> <thead> <tr> <th>MUZ-S5</th> <th>Outdoor Living Space</th> </tr> </thead> <tbody> <tr> <td> <p>1. Each residential unit at ground floor level must have an outdoor living space that is at least 20 square metres and that comprises ground floor, balcony, patio, or roof terrace space that,</p> <ol style="list-style-type: none"> where located at ground level, has no dimension less than 3 metres; and </td> <td> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> Whether adequate useable space is provided to accommodate outdoor activities. Whether there are topographical or other site constraints that make compliance with the standard impractical. </td> </tr> </tbody> </table>	MUZ-S5	Outdoor Living Space	<p>1. Each residential unit at ground floor level must have an outdoor living space that is at least 20 square metres and that comprises ground floor, balcony, patio, or roof terrace space that,</p> <ol style="list-style-type: none"> where located at ground level, has no dimension less than 3 metres; and 	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> Whether adequate useable space is provided to accommodate outdoor activities. Whether there are topographical or other site constraints that make compliance with the standard impractical.
MUZ-S5	Outdoor Living Space						
<p>1. Each residential unit at ground floor level must have an outdoor living space that is at least 20 square metres and that comprises ground floor, balcony, patio, or roof terrace space that,</p> <ol style="list-style-type: none"> where located at ground level, has no dimension less than 3 metres; and 	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> Whether adequate useable space is provided to accommodate outdoor activities. Whether there are topographical or other site constraints that make compliance with the standard impractical. 						

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>b. — where provided in the form of a balcony, patio, or roof terrace, is at least 8 square metres and has a minimum dimension of 1.8 metres; and</p> <p>e. — is accessible from the residential unit; and</p> <p>d. — may be —</p> <p>i. — grouped cumulatively by area in 1 communally accessible location; or</p> <p>ii. — located directly adjacent to the unit; and</p> <p>e. — is free of buildings, parking spaces, and servicing and manoeuvring areas.</p> <p>2. — Each residential unit located above ground floor level must have an outdoor living space in the form of a balcony, patio, or roof terrace that —</p> <p>a. — is at least 8 square metres and has a minimum dimension of 1.8 metres; and</p> <p>b. — is accessible from the residential unit; and</p> <p>e. — may be —</p> <p>i. — grouped cumulatively by area in 1 communally accessible location, in which case it may be located at ground level; or</p> <p>ii. — located directly adjacent to the unit.</p> <p>2. — For multi-unit housing, the outdoor living space can be provided as private space and shared space where:</p> <p>a. — Each residential unit is provided with a private outdoor living space that has a minimum area of 8m² with a minimum dimension of 1.8m, that is directly accessible from the residential unit to which it relates;</p> <p>3. <u>The proximity of the residential unit to accessible public open space.</u></p>

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change												
			<p>b. The shared outdoor living space has a minimum area of 20m² with a minimum dimension of 3m; and</p> <p>c. Any ground floor outdoor living space is free of buildings, parking spaces and manoeuvring areas.</p> <p><u>1. Each residential unit, including any dual key unit, must be provided with either a private outdoor living space or access to a communal outdoor living space;</u></p> <p><u>2. Where private outdoor living space is provided it must be:</u></p> <ul style="list-style-type: none"> <u>i For the exclusive use of residents;</u> <u>ii Directly accessible from a habitable room;</u> <u>iii A single contiguous space; and</u> <u>iv Of the minimum area and dimension specified in the table below;</u> <p><u>3. Where communal outdoor living space is provided it does not need to be in a single continuous space, but it must be:</u></p> <ul style="list-style-type: none"> <u>i Accessible from the residential units it serves;</u> <u>ii Of the minimum area and dimension specified in the table below; and</u> <u>iii Free of buildings, parking spaces, and servicing and manoeuvring areas.</u> <table border="1"> <thead> <tr> <th><u>Living Space Type</u></th> <th><u>Minimum area</u></th> <th><u>Minimum dimension</u></th> </tr> </thead> <tbody> <tr> <td><u>1. Private</u></td> <td></td> <td></td> </tr> <tr> <td><u>i Studio unit & 1 bedroom unit</u></td> <td><u>5m²</u></td> <td><u>1.8m</u></td> </tr> <tr> <td><u>ii 2+ bedroom unit</u></td> <td></td> <td></td> </tr> </tbody> </table>	<u>Living Space Type</u>	<u>Minimum area</u>	<u>Minimum dimension</u>	<u>1. Private</u>			<u>i Studio unit & 1 bedroom unit</u>	<u>5m²</u>	<u>1.8m</u>	<u>ii 2+ bedroom unit</u>		
<u>Living Space Type</u>	<u>Minimum area</u>	<u>Minimum dimension</u>													
<u>1. Private</u>															
<u>i Studio unit & 1 bedroom unit</u>	<u>5m²</u>	<u>1.8m</u>													
<u>ii 2+ bedroom unit</u>															

Commented [MM214]: S58.319 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS												
#	Chapter	Change	Track Change									
			<table border="1"> <tr> <td></td> <td>8m²</td> <td>1.8m²</td> </tr> <tr> <td>2. Communal</td> <td></td> <td></td> </tr> <tr> <td>For every 5 units</td> <td>10m² (per residential unit)</td> <td>8m diameter</td> </tr> </table>		8m ²	1.8m ²	2. Communal			For every 5 units	10m ² (per residential unit)	8m diameter
	8m ²	1.8m ²										
2. Communal												
For every 5 units	10m ² (per residential unit)	8m diameter										
New MUZ - Mixed Use Zone	Introduce new Standard MUZ-S6	<p>MUZ-S6 Screening and Landscaping of Service Areas, Outdoor Storage Areas and Parking Areas</p> <p>1. Any on-site service areas, including rubbish collection areas, and areas for the outdoor storage of goods or materials must, without preventing the provision of an entry point to the site, be adequately screened by a fence or landscaping where they are visible from any:</p> <ol style="list-style-type: none"> Public road; Other public space; or The ground level of any Directly adjoining site zoned Residential or Open Space and Recreation. <p>2. Any on-site parking area must</p> <ol style="list-style-type: none"> Be fully screened by a fence or landscaping from the ground level of any directly adjoining site zoned Residential or Open Space and Recreation. Where located along a street edge, provide a landscaping strip that extends at least 1.5m from the boundary with the road and comprise a mix of trees, shrubs and ground cover plants, without preventing the provision of an entry point to the site. This does not apply to individual parking spaces for residential development, if provided. <p>3. At least 5% of any ground level parking area not contained within a building must be landscaped.</p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> Any adverse effects on the streetscape. The visual amenity of adjoining Residential and Open Space and Recreation zoned sites including shading. The service, storage and parking needs of the activity. The size and location of service, storage and any parking areas. 									

Commented [MM215]: S58.319 - Kianga Ora: Home and Communities.

Commented [MM216]: S32.9 - Z Energy Limited.

Commented [MM217]: S32.9 - Z Energy Limited.

Commented [MM218]: S32.9 - Z Energy Limited.

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
	New MUZ - Mixed Use Zone	Introduce new Standard MUZ-S7	<table border="1"> <thead> <tr> <th>MUZ-S7</th> <th>Water Supply, Stormwater and Wastewater</th> </tr> </thead> <tbody> <tr> <td> <p>1. All activities shall comply with the water supply, stormwater and wastewater standards in the Code of Practice for Civil Engineering Works.</p> </td> <td> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> Whether the Water Supply, Stormwater and Wastewater infrastructure has sufficient capacity to accommodate the activity. Any alternative measures proposed to mitigate adverse effects on the Water Supply, Stormwater and Wastewater infrastructure network. Whether the additional demand generated will necessitate additional unplanned public investment in, or expansion of, the Water Supply, Stormwater and Wastewater infrastructure network or compromise its ability to service other activities permitted within the zone. Whether the development can achieve hydraulic neutrality. The extent to which the development incorporates stormwater management techniques or controls to mitigate any increase in pre-development peak stormwater runoff. </td> </tr> </tbody> </table>	MUZ-S7	Water Supply, Stormwater and Wastewater	<p>1. All activities shall comply with the water supply, stormwater and wastewater standards in the Code of Practice for Civil Engineering Works.</p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> Whether the Water Supply, Stormwater and Wastewater infrastructure has sufficient capacity to accommodate the activity. Any alternative measures proposed to mitigate adverse effects on the Water Supply, Stormwater and Wastewater infrastructure network. Whether the additional demand generated will necessitate additional unplanned public investment in, or expansion of, the Water Supply, Stormwater and Wastewater infrastructure network or compromise its ability to service other activities permitted within the zone. Whether the development can achieve hydraulic neutrality. The extent to which the development incorporates stormwater management techniques or controls to mitigate any increase in pre-development peak stormwater runoff.
MUZ-S7	Water Supply, Stormwater and Wastewater						
<p>1. All activities shall comply with the water supply, stormwater and wastewater standards in the Code of Practice for Civil Engineering Works.</p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> Whether the Water Supply, Stormwater and Wastewater infrastructure has sufficient capacity to accommodate the activity. Any alternative measures proposed to mitigate adverse effects on the Water Supply, Stormwater and Wastewater infrastructure network. Whether the additional demand generated will necessitate additional unplanned public investment in, or expansion of, the Water Supply, Stormwater and Wastewater infrastructure network or compromise its ability to service other activities permitted within the zone. Whether the development can achieve hydraulic neutrality. The extent to which the development incorporates stormwater management techniques or controls to mitigate any increase in pre-development peak stormwater runoff. 						
	New MUZ - Mixed Use Zone	Introduce new Standard MUZ-S8	<table border="1"> <thead> <tr> <th>MUZ-S8</th> <th>Hydraulic neutrality</th> </tr> </thead> <tbody> <tr> <td> <p>New buildings and development must be designed to achieve hydraulic neutrality ensure that the stormwater runoff from all new impermeable surfaces will be disposed of or stored on site and released at a rate that does not exceed the peak stormwater runoff when compared to the pre development situation for the 10% and 1% rainfall Annual Exceedance Probability event.</p> </td> <td> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> Methods to avoid, remedy or mitigate any adverse effects resulting from any increase in pre-development peak stormwater runoff. Cumulative effects. </td> </tr> </tbody> </table>	MUZ-S8	Hydraulic neutrality	<p>New buildings and development must be designed to achieve hydraulic neutrality ensure that the stormwater runoff from all new impermeable surfaces will be disposed of or stored on site and released at a rate that does not exceed the peak stormwater runoff when compared to the pre development situation for the 10% and 1% rainfall Annual Exceedance Probability event.</p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> Methods to avoid, remedy or mitigate any adverse effects resulting from any increase in pre-development peak stormwater runoff. Cumulative effects.
MUZ-S8	Hydraulic neutrality						
<p>New buildings and development must be designed to achieve hydraulic neutrality ensure that the stormwater runoff from all new impermeable surfaces will be disposed of or stored on site and released at a rate that does not exceed the peak stormwater runoff when compared to the pre development situation for the 10% and 1% rainfall Annual Exceedance Probability event.</p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> Methods to avoid, remedy or mitigate any adverse effects resulting from any increase in pre-development peak stormwater runoff. Cumulative effects. 						

Commented [MM219]: For consistency as a consequential amendment re. S58.273 - Kianga Ora: Home and Communities. Clause 99, part 6, Schedule 1 RMA recommendation.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	New MUZ-Precinct 2 – St Patrick's Estate Precinct	Insert Precinct description	<p><u>Precinct 2 - St Patrick's Estate Precinct</u></p> <p><u>The St Patrick's Estate Precinct comprises approximately 45 hectares of undeveloped land bordering the Hutt River, and forms part of the flood plain. The St Patrick's Estate Precinct is within the walkable catchment of Silverstream Railway Station, and is located in proximity to State Highway 2. The Precinct provides a significant development opportunity within Upper Hutt, and therefore a mix of uses are provided for.</u></p> <p><u>Although part of the Mixed Use Zone, the Precinct is subject to a bespoke set of provisions that recognise the importance of the site as a significant contributor towards meeting housing demand in the City, while also providing for a mix of complementary non-residential activities that do not conflict with residential subdivision and development within the Precinct, or the role and function of the centres zones. Development within the Precinct needs to address potential transportation safety effects on the road network including the state highway, and the potential for reverse sensitivity effects, and therefore the Precinct provisions ensure these effects can be addressed as the Precinct is developed.</u></p> <p><u>The Precinct sits near the Southern gateway to the City and therefore subdivision and development of the Precinct provides an opportunity to enhance the entrance to the City via landscaping along Fergusson Drive and County Lane, and to ensure key active transport connections between the Hutt River and Silverstream Town Centre and rail station are provided.</u></p> <p><u>The indicative layout and scale of activities anticipated within the Precinct are identified within the St Patrick's Estate Precinct Structure Plan in Appendix 3.</u></p> <p><u>The following objectives, policies and rules apply within the St Patrick's Estate Precinct in addition to the provisions of the underlying Mixed Use Zone. Where there is any conflict between the provisions of the Mixed Use Zone and the St Patrick's Estate Precinct provisions, the St Patrick's Estate Precinct provisions shall prevail.</u></p>
	<u>Mixed Use Zone – Precinct 2 – St Patrick's Estate Precinct</u>	Insert Precinct Heading	<p><u>Precinct 2 - St Patrick's Estate Precinct</u></p>
	<u>Mixed Use Zone – Precinct 2 – St Patrick's Estate Precinct</u>	Insert Precinct Objectives	<p><u>Objectives</u></p> <p><u>In addition to MUZ-PREC2-01 and MUZ-PREC2-02 below, all objectives of the Mixed Use Zone apply.</u></p> <p><u>MUZ-PREC2-01 - St Patrick's Estate Precinct.</u></p>

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			<p>The St Patrick's Estate Precinct is recognised as a significant development site for a wide range of activities while transport effects, visual effects, effects on the role and function of other centres, and potential reverse sensitivity effects from subdivision, use and development are avoided, remedied, or mitigated.</p> <p>MUZ-PREC2-O2 – St Patrick's Estate Precinct Structure Plan Development and activities within the St Patrick's Estate Precinct are in general accordance with the St Patrick's Estate Precinct Structure Plan.</p>						
	Mixed Use Zone – Precinct 2 – St Patrick's Estate Precinct	Insert Precinct Policies	<p>Policies In addition to MUZ-PREC2-P1, MUZ-PREC2-P2, and MUZ-PREC2-P3 below, all policies of the Mixed Use Zone apply. Where there is any conflict between the MUZ-PREC2 policies and the Mixed Use Zone policies, the MUZ-PREC2 policies shall prevail.</p> <table border="1"> <tr> <td>MUZ-REC2-P1</td> <td>Provide for a wide range of compatible activities within the St Patrick's Estate Precinct that: <ul style="list-style-type: none"> (i) Are located and are of a scale that is in general accordance with the St Patrick's Estate Precinct Structure Plan in Appendix 3. (ii) Avoid significant adverse effects arising from potential inundation from the Hutt River and the Mawaihakona Stream. (iii) Provide for pedestrian linkages to the Hutt River walkway and Silverstream Railway Station. (iv) Enhance the southern entrance to the City via landscaping along the frontage of the site with Fergusson Drive and County Lane. (v) Avoid or remedy significant adverse effects on the safety, capacity, and function of the transport network. (vi) Avoid significant adverse effects on the role and function of the centres zones. (vii) Avoid or mitigate reverse sensitivity effects. </td> </tr> <tr> <td>MUZ-PREC2-P2</td> <td>Ensure that the actual and potential adverse effects on the transportation network from activities or groups of activities within the St Patrick's Estate Precinct are avoided, remedied or mitigated.</td> </tr> <tr> <td>MUZ-PREC2-P3</td> <td>Ensure subdivision, use and development that would result in reverse sensitivity effects appropriately avoids or mitigates such effects within the St Patrick's Estate Precinct or on adjacent sites.</td> </tr> </table>	MUZ-REC2-P1	Provide for a wide range of compatible activities within the St Patrick's Estate Precinct that: <ul style="list-style-type: none"> (i) Are located and are of a scale that is in general accordance with the St Patrick's Estate Precinct Structure Plan in Appendix 3. (ii) Avoid significant adverse effects arising from potential inundation from the Hutt River and the Mawaihakona Stream. (iii) Provide for pedestrian linkages to the Hutt River walkway and Silverstream Railway Station. (iv) Enhance the southern entrance to the City via landscaping along the frontage of the site with Fergusson Drive and County Lane. (v) Avoid or remedy significant adverse effects on the safety, capacity, and function of the transport network. (vi) Avoid significant adverse effects on the role and function of the centres zones. (vii) Avoid or mitigate reverse sensitivity effects. 	MUZ-PREC2-P2	Ensure that the actual and potential adverse effects on the transportation network from activities or groups of activities within the St Patrick's Estate Precinct are avoided, remedied or mitigated.	MUZ-PREC2-P3	Ensure subdivision, use and development that would result in reverse sensitivity effects appropriately avoids or mitigates such effects within the St Patrick's Estate Precinct or on adjacent sites.
MUZ-REC2-P1	Provide for a wide range of compatible activities within the St Patrick's Estate Precinct that: <ul style="list-style-type: none"> (i) Are located and are of a scale that is in general accordance with the St Patrick's Estate Precinct Structure Plan in Appendix 3. (ii) Avoid significant adverse effects arising from potential inundation from the Hutt River and the Mawaihakona Stream. (iii) Provide for pedestrian linkages to the Hutt River walkway and Silverstream Railway Station. (iv) Enhance the southern entrance to the City via landscaping along the frontage of the site with Fergusson Drive and County Lane. (v) Avoid or remedy significant adverse effects on the safety, capacity, and function of the transport network. (vi) Avoid significant adverse effects on the role and function of the centres zones. (vii) Avoid or mitigate reverse sensitivity effects. 								
MUZ-PREC2-P2	Ensure that the actual and potential adverse effects on the transportation network from activities or groups of activities within the St Patrick's Estate Precinct are avoided, remedied or mitigated.								
MUZ-PREC2-P3	Ensure subdivision, use and development that would result in reverse sensitivity effects appropriately avoids or mitigates such effects within the St Patrick's Estate Precinct or on adjacent sites.								
	Mixed Use Zone – Precinct 2 – St Patrick's Estate Precinct	Insert Precinct Rule	<p>Rules</p> <table border="1"> <tr> <td>MUZ-PREC2-R1</td> <td>All permitted activity rules and standards in the Mixed Use Zone apply unless specifically provided for in this table.</td> </tr> </table>	MUZ-PREC2-R1	All permitted activity rules and standards in the Mixed Use Zone apply unless specifically provided for in this table.				
MUZ-PREC2-R1	All permitted activity rules and standards in the Mixed Use Zone apply unless specifically provided for in this table.								

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
	Mixed Use Zone – Precinct 2 – St Patrick's Estate Precinct	Insert Precinct Rule	<table border="1"> <tr> <td>MUZ-PREC2-R2</td> <td>All restricted activity rules, standards, matters of discretion, and information requirements in the Mixed Use Zone apply unless specifically provided for in this table.</td> </tr> </table>	MUZ-PREC2-R2	All restricted activity rules, standards, matters of discretion, and information requirements in the Mixed Use Zone apply unless specifically provided for in this table.
MUZ-PREC2-R2	All restricted activity rules, standards, matters of discretion, and information requirements in the Mixed Use Zone apply unless specifically provided for in this table.				
	Mixed Use Zone – Precinct 2 – St Patrick's Estate Precinct	Insert Precinct Rule	<table border="1"> <tr> <td>MUZ-PREC2-R3</td> <td> <p>Any activity or combination of activities</p> <p>1. Activity status: Restricted Discretionary</p> <p>Where:</p> <p>a. <u>the activity or activities will generate more than 100 vehicle movements per hour.</u></p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> <u>Methods to avoid, remedy or mitigate adverse effects on the transportation network, including active and public transport, as identified by an integrated transport assessment.</u> <u>Any works or improvements necessary to mitigate effects on the transport network, including active and public transport.</u> <u>Whether activities which generate significant traffic flows have satisfactory access arrangements and sufficient network capacity.</u> <u>Impacts on public safety.</u> <u>Landscaping.</u> </td> </tr> </table>	MUZ-PREC2-R3	<p>Any activity or combination of activities</p> <p>1. Activity status: Restricted Discretionary</p> <p>Where:</p> <p>a. <u>the activity or activities will generate more than 100 vehicle movements per hour.</u></p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> <u>Methods to avoid, remedy or mitigate adverse effects on the transportation network, including active and public transport, as identified by an integrated transport assessment.</u> <u>Any works or improvements necessary to mitigate effects on the transport network, including active and public transport.</u> <u>Whether activities which generate significant traffic flows have satisfactory access arrangements and sufficient network capacity.</u> <u>Impacts on public safety.</u> <u>Landscaping.</u>
MUZ-PREC2-R3	<p>Any activity or combination of activities</p> <p>1. Activity status: Restricted Discretionary</p> <p>Where:</p> <p>a. <u>the activity or activities will generate more than 100 vehicle movements per hour.</u></p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> <u>Methods to avoid, remedy or mitigate adverse effects on the transportation network, including active and public transport, as identified by an integrated transport assessment.</u> <u>Any works or improvements necessary to mitigate effects on the transport network, including active and public transport.</u> <u>Whether activities which generate significant traffic flows have satisfactory access arrangements and sufficient network capacity.</u> <u>Impacts on public safety.</u> <u>Landscaping.</u> 				
	Mixed Use Zone – Precinct 2 – St Patrick's Estate Precinct	Insert Precinct Rule	<table border="1"> <tr> <td>MUZ-PREC2-R4</td> <td> <p>New vehicular access to Fergusson Drive or County Lane.</p> <p>1. Activity status: Restricted Discretionary</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> <u>Methods to avoid, remedy or mitigate adverse effects on the transportation network as identified by an integrated transport assessment.</u> <u>Accessibility for public transport and active modes.</u> <u>Any works or improvements necessary to mitigate effects on the transport network, including active and public transport.</u> </td> </tr> </table>	MUZ-PREC2-R4	<p>New vehicular access to Fergusson Drive or County Lane.</p> <p>1. Activity status: Restricted Discretionary</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> <u>Methods to avoid, remedy or mitigate adverse effects on the transportation network as identified by an integrated transport assessment.</u> <u>Accessibility for public transport and active modes.</u> <u>Any works or improvements necessary to mitigate effects on the transport network, including active and public transport.</u>
MUZ-PREC2-R4	<p>New vehicular access to Fergusson Drive or County Lane.</p> <p>1. Activity status: Restricted Discretionary</p> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> <u>Methods to avoid, remedy or mitigate adverse effects on the transportation network as identified by an integrated transport assessment.</u> <u>Accessibility for public transport and active modes.</u> <u>Any works or improvements necessary to mitigate effects on the transport network, including active and public transport.</u> 				

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<ul style="list-style-type: none"> 4. Impacts on public safety. 5. Landscaping. 				
	Mixed Use Zone – Precinct 2 – St Patrick’s Estate Precinct	Insert Precinct Rule	<table border="1"> <tr> <td>MUZ-PREC2-R5</td> <td>Large format retail, supermarket, and retail activity.</td> </tr> <tr> <td colspan="2"> <ul style="list-style-type: none"> 1. Activity status: Restricted Discretionary An application under this rule must provide a retail economic effects assessment prepared by a suitably qualified and experienced person that identifies the actual and potential effects on the role and function of the centres zones. <p>Matters of discretion are restricted to:</p> <ul style="list-style-type: none"> 1. Effects on the role and function of the centre zones. 2. The avoidance of significant adverse effects on the role and function of the centre zones. </td> </tr> </table>	MUZ-PREC2-R5	Large format retail, supermarket, and retail activity.	<ul style="list-style-type: none"> 1. Activity status: Restricted Discretionary An application under this rule must provide a retail economic effects assessment prepared by a suitably qualified and experienced person that identifies the actual and potential effects on the role and function of the centres zones. <p>Matters of discretion are restricted to:</p> <ul style="list-style-type: none"> 1. Effects on the role and function of the centre zones. 2. The avoidance of significant adverse effects on the role and function of the centre zones. 	
MUZ-PREC2-R5	Large format retail, supermarket, and retail activity.						
<ul style="list-style-type: none"> 1. Activity status: Restricted Discretionary An application under this rule must provide a retail economic effects assessment prepared by a suitably qualified and experienced person that identifies the actual and potential effects on the role and function of the centres zones. <p>Matters of discretion are restricted to:</p> <ul style="list-style-type: none"> 1. Effects on the role and function of the centre zones. 2. The avoidance of significant adverse effects on the role and function of the centre zones. 							
	Mixed Use Zone – Precinct 2 – St Patrick’s Estate Precinct	Insert Precinct Rule	<table border="1"> <tr> <td>MUZ-PREC2-R6</td> <td>Activities within the St Patrick’s Estate Precinct except Residential Activity permitted by MUZ-R16.</td> </tr> <tr> <td colspan="2"> <ul style="list-style-type: none"> 1. Activity status: Restricted Discretionary Where: <ul style="list-style-type: none"> (a) The location of activities, landscaping, and active transport routes are in general accordance with the St Patrick’s Estate Precinct Structure Plan in Appendix 3. <p>Matters of discretion are restricted to:</p> <ul style="list-style-type: none"> 1. Consistency with the St Patrick’s Estate Precinct Structure Plan in Appendix 3. </td> </tr> </table>	MUZ-PREC2-R6	Activities within the St Patrick’s Estate Precinct except Residential Activity permitted by MUZ-R16.	<ul style="list-style-type: none"> 1. Activity status: Restricted Discretionary Where: <ul style="list-style-type: none"> (a) The location of activities, landscaping, and active transport routes are in general accordance with the St Patrick’s Estate Precinct Structure Plan in Appendix 3. <p>Matters of discretion are restricted to:</p> <ul style="list-style-type: none"> 1. Consistency with the St Patrick’s Estate Precinct Structure Plan in Appendix 3. 	
MUZ-PREC2-R6	Activities within the St Patrick’s Estate Precinct except Residential Activity permitted by MUZ-R16.						
<ul style="list-style-type: none"> 1. Activity status: Restricted Discretionary Where: <ul style="list-style-type: none"> (a) The location of activities, landscaping, and active transport routes are in general accordance with the St Patrick’s Estate Precinct Structure Plan in Appendix 3. <p>Matters of discretion are restricted to:</p> <ul style="list-style-type: none"> 1. Consistency with the St Patrick’s Estate Precinct Structure Plan in Appendix 3. 							
	Mixed Use Zone – Precinct 2 – St Patrick’s Estate Precinct	Insert Precinct Rule	<table border="1"> <tr> <td>MUZ-PREC2-R7</td> <td>All discretionary activity rules in the Mixed Use Zone apply unless specifically stated in this table.</td> </tr> <tr> <td colspan="2"> <ul style="list-style-type: none"> 1. Activity status: Discretionary </td> </tr> </table>	MUZ-PREC2-R7	All discretionary activity rules in the Mixed Use Zone apply unless specifically stated in this table.	<ul style="list-style-type: none"> 1. Activity status: Discretionary 	
MUZ-PREC2-R7	All discretionary activity rules in the Mixed Use Zone apply unless specifically stated in this table.						
<ul style="list-style-type: none"> 1. Activity status: Discretionary 							
	Mixed Use Zone – Precinct 2 – St Patrick’s Estate Precinct	Insert Precinct Rule	<table border="1"> <tr> <td>MUZ-PREC2-R8</td> <td>Activities that do not fall under MUZ-PREC2-R6.</td> </tr> <tr> <td colspan="2"> <ul style="list-style-type: none"> 1. Activity status: Discretionary </td> </tr> </table>	MUZ-PREC2-R8	Activities that do not fall under MUZ-PREC2-R6.	<ul style="list-style-type: none"> 1. Activity status: Discretionary 	
MUZ-PREC2-R8	Activities that do not fall under MUZ-PREC2-R6.						
<ul style="list-style-type: none"> 1. Activity status: Discretionary 							

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	Mixed Use Zone – Precinct 2 – St Patrick's Estate Precinct	Insert Precinct Rule	MUZ-PREC2-R9 All non-complying rules in the Mixed Use Zone apply unless specifically stated in this table.
	Mixed Use Zone – Precinct 2 – St Patrick's Estate Precinct	Insert Precinct Rule	MUZ-PREC2-R10 All prohibited activity rules in the Mixed Use Zone apply unless specifically stated in this table.
TCZ – Town Centre Zone			
	New TCZ - Town Centre Zone	Introduce new Chapter Heading and Introduction	<p><u>TCZ - Town Centre Zone</u></p> <p>The Town Centre Zone applies to the Silverstream Centre. It provides for a medium to large scale suburban shopping centre that serves not only the surrounding residential catchment but also neighbouring suburbs. The Town Centre Zone accommodates a wide range of retail, commercial services and health care and community facilities. It also provides for employment opportunities as well as residential activities. Overall the Town Centre Zone is of a larger scale and has a wider focus than the Local Centre Zone while not undermining the primary function of the City Centre Zone.</p> <p>The Town Centre Zone provides for residential activities where it is located above ground floor along identified active street frontages. It does not encourage large format retail (except for supermarkets), car-oriented activities or light industrial activities.</p> <p>The Town Centre Zone is characterised by a high-density built environment that aligns well with the expected high-density of the surrounding residential environment. The Town Centre Zone is well serviced by public transport. Buildings are mostly built up to the road frontage with active frontages to provide a vibrant and attractive streetscape.</p> <p>Non-residential activities and development have the potential to generate adverse effects where they are directly adjoining residential and open space areas. To manage these potential effects buildings have to be set back and outdoor storage and parking areas need to be screened.</p>
	New TCZ - Town Centre Zone	Introduce new Objective TCZ-O1	<p><u>Objectives</u></p> <p><u>TCZ-O1</u> <u>Purpose of the Town Centre Zone</u></p> <p>The Town Centre Zone is a medium to large scale commercial centre that services the needs of the immediate and neighbouring suburbs and accommodates a wide range of commercial and community activities as well as residential activities.</p>
	New TCZ - Town Centre Zone	Introduce new Objective TCZ-O2	<p><u>TCZ-O2</u> <u>Character and Amenity Values of the Town Centre Zone</u></p>

IPI - PROPOSED AMENDMENTS											
#	Chapter	Change	Track Change								
			The Town Centre Zone is a vibrant, attractive and safe urban environment that is characterised by high-density urban development, well-designed buildings and high quality public spaces.								
	New TCZ - Town Centre Zone	Introduce new Objective TCZ-O3	<table border="1"> <tr> <td>TCZ-O3</td> <td>Managing Effects at the Zone Interface</td> </tr> <tr> <td colspan="2">Use and development within the Town Centre Zone are of an appropriate scale and manage potential adverse effects on the amenity values of adjoining sites in Residential and Open Space and Recreation Zones.</td> </tr> </table>	TCZ-O3	Managing Effects at the Zone Interface	Use and development within the Town Centre Zone are of an appropriate scale and manage potential adverse effects on the amenity values of adjoining sites in Residential and Open Space and Recreation Zones.					
TCZ-O3	Managing Effects at the Zone Interface										
Use and development within the Town Centre Zone are of an appropriate scale and manage potential adverse effects on the amenity values of adjoining sites in Residential and Open Space and Recreation Zones.											
	New TCZ - Town Centre Zone	Introduce new Objective TCZ-O4	<table border="1"> <tr> <td>TCZ-O4</td> <td>Hydraulic neutrality</td> </tr> <tr> <td colspan="2">There is no increase in the peak demand on stormwater management systems and increase in flooding from subdivision and development.</td> </tr> </table>	TCZ-O4	Hydraulic neutrality	There is no increase in the peak demand on stormwater management systems and increase in flooding from subdivision and development .					
TCZ-O4	Hydraulic neutrality										
There is no increase in the peak demand on stormwater management systems and increase in flooding from subdivision and development .											
	New TCZ - Town Centre Zone	Introduce new Policy TCZ-P1	<table border="1"> <tr> <td colspan="2">Policies</td> </tr> <tr> <td>TCZ-P1</td> <td>Appropriate activities</td> </tr> <tr> <td colspan="2">Enable appropriate activities that</td> </tr> <tr> <td colspan="2"> <ol style="list-style-type: none"> 1. <u>Are compatible with the anticipated purpose, character and amenity values of the Town Centre Zone;</u> 2. <u>Service the needs of the immediate and surrounding suburbs; and</u> 3. <u>Minimise any adverse effects on the amenity of adjoining residential, recreational and open space sites.</u> </td> </tr> </table>	Policies		TCZ-P1	Appropriate activities	Enable appropriate activities that		<ol style="list-style-type: none"> 1. <u>Are compatible with the anticipated purpose, character and amenity values of the Town Centre Zone;</u> 2. <u>Service the needs of the immediate and surrounding suburbs; and</u> 3. <u>Minimise any adverse effects on the amenity of adjoining residential, recreational and open space sites.</u> 	
Policies											
TCZ-P1	Appropriate activities										
Enable appropriate activities that											
<ol style="list-style-type: none"> 1. <u>Are compatible with the anticipated purpose, character and amenity values of the Town Centre Zone;</u> 2. <u>Service the needs of the immediate and surrounding suburbs; and</u> 3. <u>Minimise any adverse effects on the amenity of adjoining residential, recreational and open space sites.</u> 											
	New TCZ - Town Centre Zone	Introduce new Policy TCZ-P2	<table border="1"> <tr> <td>TCZ-P2</td> <td>Residential activity</td> </tr> <tr> <td colspan="2">Provide for medium to high density residential development and activity where:</td> </tr> <tr> <td colspan="2"> <ol style="list-style-type: none"> 1. <u>The residential units are located above ground floor, where located along an active frontage identified on the planning maps;</u> 2. <u>It does not interrupt or preclude an attractive frontage that provides a positive interface with the public space;</u> 3. <u>Any residential units are designed to:</u> <ol style="list-style-type: none"> a. <u>Achieve adequate indoor noise and ventilation levels for occupants; and</u> b. <u>Provide appropriate amenity for occupants; and</u> </td> </tr> </table>	TCZ-P2	Residential activity	Provide for medium to high density residential development and activity where:		<ol style="list-style-type: none"> 1. <u>The residential units are located above ground floor, where located along an active frontage identified on the planning maps;</u> 2. <u>It does not interrupt or preclude an attractive frontage that provides a positive interface with the public space;</u> 3. <u>Any residential units are designed to:</u> <ol style="list-style-type: none"> a. <u>Achieve adequate indoor noise and ventilation levels for occupants; and</u> b. <u>Provide appropriate amenity for occupants; and</u> 			
TCZ-P2	Residential activity										
Provide for medium to high density residential development and activity where:											
<ol style="list-style-type: none"> 1. <u>The residential units are located above ground floor, where located along an active frontage identified on the planning maps;</u> 2. <u>It does not interrupt or preclude an attractive frontage that provides a positive interface with the public space;</u> 3. <u>Any residential units are designed to:</u> <ol style="list-style-type: none"> a. <u>Achieve adequate indoor noise and ventilation levels for occupants; and</u> b. <u>Provide appropriate amenity for occupants; and</u> 											

IPI - PROPOSED AMENDMENTS																	
#	Chapter	Change	Track Change														
			4. <u>Reverse sensitivity effects on commercial activities</u> are minimised.														
	New TCZ - Town Centre Zone	Introduce new Policy TCZ-P3	<table border="1"> <tr> <td>TCZ-P3</td> <td>Other activities</td> </tr> <tr> <td colspan="2">Only allow for other activities, including larger scale activities, where:</td> </tr> <tr> <td colspan="2">1. <u>Any adverse effects</u> can be managed;</td> </tr> <tr> <td colspan="2">2. <u>The scale and intensity of the activity</u> is consistent with the anticipated character of the Town Centre Zone;</td> </tr> <tr> <td colspan="2">3. <u>The design and layout of the activity</u> does not compromise the streetscape, amenity or safety;</td> </tr> <tr> <td colspan="2">4. <u>The size, intensity and scale of the activity</u> does not compromise other activities that are anticipated and enabled within the Town Centre Zone; and</td> </tr> <tr> <td colspan="2">5. <u>The location of the activity</u> in the Town Centre Zone does not undermine the role and function of the City Centre Zone.</td> </tr> </table>	TCZ-P3	Other activities	Only allow for other activities , including larger scale activities , where:		1. <u>Any adverse effects</u> can be managed;		2. <u>The scale and intensity of the activity</u> is consistent with the anticipated character of the Town Centre Zone;		3. <u>The design and layout of the activity</u> does not compromise the streetscape, amenity or safety;		4. <u>The size, intensity and scale of the activity</u> does not compromise other activities that are anticipated and enabled within the Town Centre Zone; and		5. <u>The location of the activity</u> in the Town Centre Zone does not undermine the role and function of the City Centre Zone.	
TCZ-P3	Other activities																
Only allow for other activities , including larger scale activities , where:																	
1. <u>Any adverse effects</u> can be managed;																	
2. <u>The scale and intensity of the activity</u> is consistent with the anticipated character of the Town Centre Zone;																	
3. <u>The design and layout of the activity</u> does not compromise the streetscape, amenity or safety;																	
4. <u>The size, intensity and scale of the activity</u> does not compromise other activities that are anticipated and enabled within the Town Centre Zone; and																	
5. <u>The location of the activity</u> in the Town Centre Zone does not undermine the role and function of the City Centre Zone.																	
	New TCZ - Town Centre Zone	Introduce new Policy TCZ-P4	<table border="1"> <tr> <td>TCZ-P4</td> <td>Inappropriate activities</td> </tr> <tr> <td colspan="2">Avoid activities that are incompatible with the anticipated purpose, character and amenity values of the Town Centre Zone and the surrounding environment.</td> </tr> </table>	TCZ-P4	Inappropriate activities	Avoid activities that are incompatible with the anticipated purpose, character and amenity values of the Town Centre Zone and the surrounding environment.											
TCZ-P4	Inappropriate activities																
Avoid activities that are incompatible with the anticipated purpose, character and amenity values of the Town Centre Zone and the surrounding environment.																	
	New TCZ - Town Centre Zone	Introduce new Policy TCZ-P5	<table border="1"> <tr> <td>TCZ-P5</td> <td>Built development</td> </tr> <tr> <td colspan="2">Provide for high-density development that</td> </tr> <tr> <td colspan="2">1. <u>Is compatible with the anticipated role, character and function of the Town Centre Zone;</u></td> </tr> <tr> <td colspan="2">2. <u>Is commensurate with the anticipated level of commercial activities and community services in the Town Centre Zone;</u></td> </tr> <tr> <td colspan="2">3. <u>Reflects the anticipated high-density built environment of the Town Centre Zone;</u></td> </tr> <tr> <td colspan="2">4. <u>Is well designed and contributes to an attractive urban environment; and</u></td> </tr> <tr> <td colspan="2">5. <u>Provides active and attractive street frontages.</u></td> </tr> </table>	TCZ-P5	Built development	Provide for high-density development that		1. <u>Is compatible with the anticipated role, character and function of the Town Centre Zone;</u>		2. <u>Is commensurate with the anticipated level of commercial activities and community services in the Town Centre Zone;</u>		3. <u>Reflects the anticipated high-density built environment of the Town Centre Zone;</u>		4. <u>Is well designed and contributes to an attractive urban environment; and</u>		5. <u>Provides active and attractive street frontages.</u>	
TCZ-P5	Built development																
Provide for high-density development that																	
1. <u>Is compatible with the anticipated role, character and function of the Town Centre Zone;</u>																	
2. <u>Is commensurate with the anticipated level of commercial activities and community services in the Town Centre Zone;</u>																	
3. <u>Reflects the anticipated high-density built environment of the Town Centre Zone;</u>																	
4. <u>Is well designed and contributes to an attractive urban environment; and</u>																	
5. <u>Provides active and attractive street frontages.</u>																	
	New TCZ - Town Centre Zone	Introduce new Policy TCZ-P6	<table border="1"> <tr> <td>TCZ-P6</td> <td>Public Space Interface and Active Street Frontages</td> </tr> <tr> <td colspan="2">Provide for new development that creates a positive interface with the public space through high quality building design.</td> </tr> </table>	TCZ-P6	Public Space Interface and Active Street Frontages	Provide for new development that creates a positive interface with the public space through high quality building design .											
TCZ-P6	Public Space Interface and Active Street Frontages																
Provide for new development that creates a positive interface with the public space through high quality building design .																	

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<p>Where located along identified active frontages, require new built development and activities to provide a positive interface with the public space through:</p> <ol style="list-style-type: none"> 1. <u>Being built up to and oriented towards the front boundary of the site;</u> 2. <u>Providing verandahs or other adequate forms of pedestrian shelter;</u> 3. <u>Providing display windows and obvious public entrances; and</u> 4. <u>Requiring parking, storage and servicing areas to be visually unobtrusive and located within or to the rear of buildings.</u> 		
	New TCZ - Town Centre Zone	Introduce new Policy TCZ-P7	<table border="1"> <tr> <td><u>TCZ-P7</u></td> <td><u>Interface with Residential Zones and Open Space and Recreation Zones</u></td> </tr> </table> <p>Minimise the adverse effects from commercial activities and development on directly adjoining sites that are zoned Residential or Open Space and Recreation through:</p> <ol style="list-style-type: none"> 1. <u>Requiring new buildings and activities to be located and designed to manage any shading and privacy effects on neighbouring sites zoned Residential or Open Space and Recreation;</u> 2. <u>Limiting the height, bulk and form of new buildings along boundaries with sites zoned Residential or Open Space and Recreation to minimise dominance effects; and</u> 3. <u>Requiring the use of screening and landscaping to minimise adverse visual effects on adjoining sites zoned Residential or Open Space and Recreation.</u> 	<u>TCZ-P7</u>	<u>Interface with Residential Zones and Open Space and Recreation Zones</u>
<u>TCZ-P7</u>	<u>Interface with Residential Zones and Open Space and Recreation Zones</u>				
	New TCZ - Town Centre Zone	Introduce new Policy TCZ-P8	<table border="1"> <tr> <td><u>TCZ-P8</u></td> <td><u>Hydraulic neutrality</u></td> </tr> </table> <p><u><i>New buildings and development will be designed to achieve hydraulic neutrality.</i></u></p>	<u>TCZ-P8</u>	<u>Hydraulic neutrality</u>
<u>TCZ-P8</u>	<u>Hydraulic neutrality</u>				
	New TCZ - Town Centre Zone	Introduce new Rules Advice Note	<table border="1"> <tr> <td><u>Rules</u></td> </tr> </table>	<u>Rules</u>	
<u>Rules</u>					

		<p><u>Note: There may be a number of provisions that apply to an activity, building, structure or site. Resource consent may therefore be required under rules in this chapter as well as other chapters. Unless specifically stated in a rule, resource consent is required under each relevant rule. The steps to determine the status of an activity are set out in Chapter 2 How the Plan Works.</u></p> <p><u>Rules relating to subdivision are found in the SUB-GEN (General Subdivision Provisions that Apply in All Zones) and the SUB-CMU (Subdivision in Commercial and Mixed Use Zones) chapters.</u></p> <p><u>Each activity in the Town Centre Zone shall comply with the relevant qualifying matter area provisions and permitted activity standards in the district-wide matters of the Plan as listed below.</u></p> <table border="1" data-bbox="537 518 1070 1268"> <tr><td><u>District-wide matters</u></td></tr> <tr><td><u>NU – Network Utilities</u></td></tr> <tr><td><u>REG - Renewable Energy Generation</u></td></tr> <tr><td><u>TP – Transport and Parking</u></td></tr> <tr><td><u>CL – Contaminated Land</u></td></tr> <tr><td><u>HS - Hazardous Substances</u></td></tr> <tr><td><u>NH - Natural Hazards</u></td></tr> <tr><td><u>WM – Waste Management</u></td></tr> <tr><td><u>HH - Historical Heritage</u></td></tr> <tr><td><u>TREE - Notable Trees</u></td></tr> <tr><td><u>UTG - Urban Tree Groups</u></td></tr> <tr><td><u>ECO - Ecosystems and Indigenous Biodiversity</u></td></tr> <tr><td><u>NATC – Natural Character</u></td></tr> <tr><td><u>NFL - Natural Features and Landscapes</u></td></tr> <tr><td><u>PA – Public Access</u></td></tr> <tr><td><u>SUB - Subdivision</u></td></tr> <tr><td><u>DC – Development Contributions</u></td></tr> <tr><td><u>AIR - Air</u></td></tr> <tr><td><u>PK – Papakāinga</u></td></tr> </table>	<u>District-wide matters</u>	<u>NU – Network Utilities</u>	<u>REG - Renewable Energy Generation</u>	<u>TP – Transport and Parking</u>	<u>CL – Contaminated Land</u>	<u>HS - Hazardous Substances</u>	<u>NH - Natural Hazards</u>	<u>WM – Waste Management</u>	<u>HH - Historical Heritage</u>	<u>TREE - Notable Trees</u>	<u>UTG - Urban Tree Groups</u>	<u>ECO - Ecosystems and Indigenous Biodiversity</u>	<u>NATC – Natural Character</u>	<u>NFL - Natural Features and Landscapes</u>	<u>PA – Public Access</u>	<u>SUB - Subdivision</u>	<u>DC – Development Contributions</u>	<u>AIR - Air</u>	<u>PK – Papakāinga</u>
<u>District-wide matters</u>																					
<u>NU – Network Utilities</u>																					
<u>REG - Renewable Energy Generation</u>																					
<u>TP – Transport and Parking</u>																					
<u>CL – Contaminated Land</u>																					
<u>HS - Hazardous Substances</u>																					
<u>NH - Natural Hazards</u>																					
<u>WM – Waste Management</u>																					
<u>HH - Historical Heritage</u>																					
<u>TREE - Notable Trees</u>																					
<u>UTG - Urban Tree Groups</u>																					
<u>ECO - Ecosystems and Indigenous Biodiversity</u>																					
<u>NATC – Natural Character</u>																					
<u>NFL - Natural Features and Landscapes</u>																					
<u>PA – Public Access</u>																					
<u>SUB - Subdivision</u>																					
<u>DC – Development Contributions</u>																					
<u>AIR - Air</u>																					
<u>PK – Papakāinga</u>																					

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			<table border="1"> <tr><td><u>ASW - Activities on the Surface of Water</u></td></tr> <tr><td><u>EW - Earthworks</u></td></tr> <tr><td><u>LIGHT - Light</u></td></tr> <tr><td><u>NOISE - Noise</u></td></tr> <tr><td><u>SIGN - Signs</u></td></tr> <tr><td><u>TEMP - Temporary Activities</u></td></tr> </table>	<u>ASW - Activities on the Surface of Water</u>	<u>EW - Earthworks</u>	<u>LIGHT - Light</u>	<u>NOISE - Noise</u>	<u>SIGN - Signs</u>	<u>TEMP - Temporary Activities</u>
<u>ASW - Activities on the Surface of Water</u>									
<u>EW - Earthworks</u>									
<u>LIGHT - Light</u>									
<u>NOISE - Noise</u>									
<u>SIGN - Signs</u>									
<u>TEMP - Temporary Activities</u>									
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R1	<table border="1"> <tr> <td><u>TCZ-R1</u></td> <td><u>Buildings and structures, including additions and alterations</u></td> </tr> <tr> <td colspan="2"> <p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>The gross floor area of the new building does not exceed 1,000m²;</u></p> <p>b. <u>Any addition to an existing building does not result in the gross floor area of the building exceeding 1,000m²; and</u></p> <p>c. <u>Compliance is achieved with</u></p> <p>i. <u>TCZ-S1 (Height);</u></p> <p>ii. <u>TCZ-S2 (Height in Relation to Boundary);</u></p> <p>iii. <u>TCZ-S3 (Setbacks);</u></p> <p>iv. <u>TCZ-S4 (Active Frontages);</u></p> <p>v. <u>TCZ-S5 (Location of Residential Units);</u></p> <p>vi. <u>TCZ-S6 (Noise and Ventilation);</u></p> <p>vii. <u>TCZ-S7 (Outdoor Living Space);</u></p> <p>viii. <u>TCZ-S8 (Landscaping and Screening);</u></p> <p>ix. <u>TCZ-S9 (Water Supply, Stormwater and Wastewater); and</u></p> <p>x. <u>TCZ-S10 (Hydraulic neutrality).</u></p> </td> </tr> </table>	<u>TCZ-R1</u>	<u>Buildings and structures, including additions and alterations</u>	<p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>The gross floor area of the new building does not exceed 1,000m²;</u></p> <p>b. <u>Any addition to an existing building does not result in the gross floor area of the building exceeding 1,000m²; and</u></p> <p>c. <u>Compliance is achieved with</u></p> <p>i. <u>TCZ-S1 (Height);</u></p> <p>ii. <u>TCZ-S2 (Height in Relation to Boundary);</u></p> <p>iii. <u>TCZ-S3 (Setbacks);</u></p> <p>iv. <u>TCZ-S4 (Active Frontages);</u></p> <p>v. <u>TCZ-S5 (Location of Residential Units);</u></p> <p>vi. <u>TCZ-S6 (Noise and Ventilation);</u></p> <p>vii. <u>TCZ-S7 (Outdoor Living Space);</u></p> <p>viii. <u>TCZ-S8 (Landscaping and Screening);</u></p> <p>ix. <u>TCZ-S9 (Water Supply, Stormwater and Wastewater); and</u></p> <p>x. <u>TCZ-S10 (Hydraulic neutrality).</u></p>			
<u>TCZ-R1</u>	<u>Buildings and structures, including additions and alterations</u>								
<p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>The gross floor area of the new building does not exceed 1,000m²;</u></p> <p>b. <u>Any addition to an existing building does not result in the gross floor area of the building exceeding 1,000m²; and</u></p> <p>c. <u>Compliance is achieved with</u></p> <p>i. <u>TCZ-S1 (Height);</u></p> <p>ii. <u>TCZ-S2 (Height in Relation to Boundary);</u></p> <p>iii. <u>TCZ-S3 (Setbacks);</u></p> <p>iv. <u>TCZ-S4 (Active Frontages);</u></p> <p>v. <u>TCZ-S5 (Location of Residential Units);</u></p> <p>vi. <u>TCZ-S6 (Noise and Ventilation);</u></p> <p>vii. <u>TCZ-S7 (Outdoor Living Space);</u></p> <p>viii. <u>TCZ-S8 (Landscaping and Screening);</u></p> <p>ix. <u>TCZ-S9 (Water Supply, Stormwater and Wastewater); and</u></p> <p>x. <u>TCZ-S10 (Hydraulic neutrality).</u></p>									

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with TCZ-R1-1.a or TCZ-R1-1.b.</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the size and scale of the building is commensurate with the anticipated level of commercial activities and community services in the Town Centre Zone.</u> <u>The extent to which the size and scale of the building may adversely impact on the anticipated amenity of the Town Centre Zone or adjacent properties.</u> <u>Whether the building reflects the anticipated purpose, scale and context of the Town Centre Zone.</u> <u>Whether the building is well designed and contributes to an attractive urban environment.</u> <u>The effects of the size and scale of the building on the existing and anticipated function and role of the Town Centre Zone.</u> <u>The potential of the size and scale of the building to compromise activities that are enabled in the Town Centre Zone.</u> <u>The potential of the size and scale of the building to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the size and scale of the building can be avoided, or appropriately remedied or mitigated.</u> <p>b. <u>Compliance is not achieved with one or more of the standards under TCZ-R1-1.c.</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of any infringed standard.</u> <p>Notification:</p> <p><u>An application under this rule where compliance is not achieved with TCZ-S2, TCZ-S3, TCZ-S4, TCZ-S5, TCZ-S6 or TCZ-S8 is precluded from being publicly notified in accordance with section 95A of the RMA.</u></p> <p><u>An application under this rule where compliance is not achieved with TCZ-S7 is precluded from being publicly or limited notified in accordance with section 95A of the RMA</u></p>

IPI - PROPOSED AMENDMENTS																									
#	Chapter	Change	Track Change																						
	New TCZ - Local Centre Zone	Introduce new Rule TCZ-R2	<table border="1"> <tr> <td>TCZ-R2</td> <td>Minor structures</td> </tr> <tr> <td colspan="2">1. Activity status: Permitted</td> </tr> </table>	TCZ-R2	Minor structures	1. Activity status: Permitted																			
TCZ-R2	Minor structures																								
1. Activity status: Permitted																									
	New TCZ - Local Centre Zone	Introduce new Rule TCZ-R3	<table border="1"> <tr> <td>TCZ-R3</td> <td>Demolition</td> </tr> <tr> <td colspan="2">1. Activity status: Permitted</td> </tr> <tr> <td colspan="2">Note: Prior to demolition commencing, confirm whether rules in chapter HH-Historic Heritage apply.</td> </tr> </table>	TCZ-R3	Demolition	1. Activity status: Permitted		Note: Prior to demolition commencing, confirm whether rules in chapter HH-Historic Heritage apply.																	
TCZ-R3	Demolition																								
1. Activity status: Permitted																									
Note: Prior to demolition commencing, confirm whether rules in chapter HH-Historic Heritage apply.																									
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R4	<table border="1"> <tr> <td>TCZ-R4</td> <td>Retail Activity not exceeding 500m² gross floor area</td> </tr> <tr> <td colspan="2">1. Activity status: Permitted</td> </tr> <tr> <td colspan="2">Where:</td> </tr> <tr> <td colspan="2">a. Compliance is achieved with TCZ-S8 (Landscaping and Screening).</td> </tr> <tr> <td colspan="2">2. Activity status: Restricted discretionary</td> </tr> <tr> <td colspan="2">Where:</td> </tr> <tr> <td colspan="2">a. Compliance is not achieved with TCZ-R4-1.a</td> </tr> <tr> <td colspan="2">Matters of discretion are restricted to:</td> </tr> <tr> <td colspan="2">1. <u>The matters of discretion of the infringed standard.</u></td> </tr> <tr> <td colspan="2">Notification:</td> </tr> <tr> <td colspan="2"> <ul style="list-style-type: none"> An application under this rule is precluded from being publicly notified in accordance with section 95A of the RMA </td> </tr> </table>	TCZ-R4	Retail Activity not exceeding 500m² gross floor area	1. Activity status: Permitted		Where:		a. Compliance is achieved with TCZ-S8 (Landscaping and Screening).		2. Activity status: Restricted discretionary		Where:		a. Compliance is not achieved with TCZ-R4-1.a		Matters of discretion are restricted to:		1. <u>The matters of discretion of the infringed standard.</u>		Notification:		<ul style="list-style-type: none"> An application under this rule is precluded from being publicly notified in accordance with section 95A of the RMA 	
TCZ-R4	Retail Activity not exceeding 500m² gross floor area																								
1. Activity status: Permitted																									
Where:																									
a. Compliance is achieved with TCZ-S8 (Landscaping and Screening).																									
2. Activity status: Restricted discretionary																									
Where:																									
a. Compliance is not achieved with TCZ-R4-1.a																									
Matters of discretion are restricted to:																									
1. <u>The matters of discretion of the infringed standard.</u>																									
Notification:																									
<ul style="list-style-type: none"> An application under this rule is precluded from being publicly notified in accordance with section 95A of the RMA 																									
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R5	<table border="1"> <tr> <td>TCZ-R5</td> <td>Commercial Service Activity</td> </tr> <tr> <td colspan="2">1. Activity status: Permitted</td> </tr> <tr> <td colspan="2">Where:</td> </tr> <tr> <td colspan="2">a. The gross floor area per tenancy does not exceed 500m²; and</td> </tr> <tr> <td colspan="2">b. Compliance is achieved with TCZ-S8 (Landscaping and Screening).</td> </tr> </table>	TCZ-R5	Commercial Service Activity	1. Activity status: Permitted		Where:		a. The gross floor area per tenancy does not exceed 500m ² ; and		b. Compliance is achieved with TCZ-S8 (Landscaping and Screening).													
TCZ-R5	Commercial Service Activity																								
1. Activity status: Permitted																									
Where:																									
a. The gross floor area per tenancy does not exceed 500m ² ; and																									
b. Compliance is achieved with TCZ-S8 (Landscaping and Screening).																									

Commented [MM220]: S72.12 - Te Rūnanga o Toa Rangatira Inc

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with TCZ-R5-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Town Centre Zone or adjacent properties.</u> 2. <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Town Centre Zone.</u> 3. <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Town Centre Zone.</u> 4. <u>The potential of the location of the activity in the Town Centre Zone to undermine the role and function of the City Centre Zone.</u> 5. <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or <u>appropriately remedied or mitigated.</u></u> <p>b. Compliance is not achieved with TCZ-R5-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> • <u>An application under TCZ-R5-2.b is precluded from being publicly notified in accordance with section 95A of the RMA</u> 		
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R6	<table border="1"> <tr> <td>TCZ-R6</td> <td>Food and Beverage Activity</td> </tr> </table> <p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>The gross floor area per tenancy does not exceed 500m²; and</u></p> <p>b. <u>Compliance is achieved with TCZ-S8 (Landscaping and Screening).</u></p>	TCZ-R6	Food and Beverage Activity
TCZ-R6	Food and Beverage Activity				

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with TCZ-R6-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Town Centre Zone or adjacent properties.</u> 2. <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Town Centre Zone.</u> 3. <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Town Centre Zone.</u> 4. <u>The potential of the location of the activity in the Town Centre Zone to undermine the role and function of the City Centre Zone.</u> 5. <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or <u>appropriately remedied or mitigated.</u></u> <p>b. Compliance is not achieved with TCZ-R6-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> • <u>An application under TCZ-R6-2.b is precluded from being publicly notified in accordance with section 95A of the RMA</u> 		
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R7	<table border="1"> <tr> <td>TCZ-R7</td> <td>Community Facility</td> </tr> </table> <p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>The gross floor area per facility does not exceed 500m²; and</u></p> <p>b. <u>Compliance is achieved with TCZ-S8 (Landscaping and Screening).</u></p>	TCZ-R7	Community Facility
TCZ-R7	Community Facility				

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with TCZ-R7-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Town Centre Zone or adjacent properties.</u> 2. <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Town Centre Zone.</u> 3. <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Town Centre Zone.</u> 4. <u>The potential of the location of the activity in the Town Centre Zone to undermine the role and function of the City Centre Zone.</u> 5. <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or <u>appropriately remedied or mitigated.</u></u> <p>b. Compliance is not achieved with TCZ-R7-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> • <u>An application under TCZ-R7-2.b is precluded from being publicly notified in accordance with section 95A of the RMA</u> 				
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R8	<table border="1"> <tr> <td>TCZ-R8</td> <td>Healthcare Activity</td> </tr> <tr> <td colspan="2"> <p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>The gross floor area per tenancy does not exceed 500m²; and</u></p> <p>b. <u>Compliance is achieved with TCZ-S8 (Landscaping and Screening).</u></p> </td> </tr> </table>	TCZ-R8	Healthcare Activity	<p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>The gross floor area per tenancy does not exceed 500m²; and</u></p> <p>b. <u>Compliance is achieved with TCZ-S8 (Landscaping and Screening).</u></p>	
TCZ-R8	Healthcare Activity						
<p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>The gross floor area per tenancy does not exceed 500m²; and</u></p> <p>b. <u>Compliance is achieved with TCZ-S8 (Landscaping and Screening).</u></p>							

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with TCZ-R8-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Town Centre Zone or adjacent properties.</u> 2. <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Town Centre Zone.</u> 3. <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Town Centre Zone.</u> 4. <u>The potential of the location of the activity in the Town Centre Zone to undermine the role and function of the City Centre Zone.</u> 5. <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or <u>appropriately remedied or mitigated.</u></u> <p>b. Compliance is not achieved with TCZ-R8-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> • <u>An application under TCZ-R8-2.b is precluded from being publicly notified in accordance with section 95A of the RMA</u> 		
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R9	<table border="1"> <tr> <td>TCZ-R9</td> <td>Educational Facility, and Community Corrections Activity</td> </tr> </table> <p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>The gross floor area per facility does not exceed 500m²; and</u></p> <p>b. <u>Compliance is achieved with TCZ-S8 (Landscaping and Screening).</u></p>	TCZ-R9	Educational Facility, and Community Corrections Activity
TCZ-R9	Educational Facility, and Community Corrections Activity				

Commented [MM221]: S28.8 - Ara Poutama Aotearoa – Department of Corrections

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with TCZ-R9-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Town Centre Zone or adjacent properties.</u> 2. <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Town Centre Zone.</u> 3. <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Town Centre Zone.</u> 4. <u>The potential of the location of the activity in the Town Centre Zone to undermine the role and function of the City Centre Zone.</u> 5. <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or <u>appropriately remedied or mitigated.</u></u> <p>b. Compliance is not achieved with TCZ-R9-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> • <u>An application under TCZ-R9-2.b is precluded from being publicly notified in accordance with section 95A of the RMA</u> 		
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R10	<table border="1"> <tr> <td>TCZ-R10</td> <td>Office activity</td> </tr> </table> <p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>The gross floor area per tenancy does not exceed 250m²; and</u></p> <p>b. <u>Compliance is achieved with TCZ-S8 (Landscaping and Screening).</u></p>	TCZ-R10	Office activity
TCZ-R10	Office activity				

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with TCZ-R10-1.a</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Town Centre Zone or adjacent properties.</u> 2. <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Town Centre Zone.</u> 3. <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Town Centre Zone.</u> 4. <u>The potential of the location of the activity in the Town Centre Zone to undermine the role and function of the City Centre Zone.</u> 5. <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or <u>appropriately remedied or mitigated.</u></u> <p>b. Compliance is not achieved with TCZ-R10-1.b</p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> • <u>An application under TCZ-R10-2.b is precluded from being publicly notified in accordance with section 95A of the RMA</u> 				
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R11	<table border="1"> <tr> <td>TCZ-R11</td> <td>Visitor Accommodation</td> </tr> <tr> <td colspan="2"> <p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>The gross floor area per tenancy does not exceed 500m²;</u></p> <p>b. <u>All habitable rooms comply with TCZ-S5 (Location of Residential Units) and TCZ-S6 (Noise and Ventilation); and</u></p> </td> </tr> </table>	TCZ-R11	Visitor Accommodation	<p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>The gross floor area per tenancy does not exceed 500m²;</u></p> <p>b. <u>All habitable rooms comply with TCZ-S5 (Location of Residential Units) and TCZ-S6 (Noise and Ventilation); and</u></p>	
TCZ-R11	Visitor Accommodation						
<p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>The gross floor area per tenancy does not exceed 500m²;</u></p> <p>b. <u>All habitable rooms comply with TCZ-S5 (Location of Residential Units) and TCZ-S6 (Noise and Ventilation); and</u></p>							




IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<p>c. <u>Compliance is achieved with TCZ-S8 (Landscaping and Screening).</u></p> <p>2. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with TCZ-R11-1.a</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Town Centre Zone or adjacent properties.</u> <u>The effects of the intensity, size and scale of the activity on the existing and anticipated function and role of the Town Centre Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Town Centre Zone.</u> <u>The potential of the location of the activity in the Town Centre Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. <u>Compliance is not achieved with TCZ-R11-1.b or TCZ-R11-1.c</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> <u>An application under TCZ-R11-2.b is precluded from being publicly notified in accordance with section 95A of the RMA</u> 		
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R12	<table border="1"> <tr> <td><u>TCZ-R12</u></td> <td><u>Residential Activity</u></td> </tr> </table> <p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. <u>No more than six residential units occupy the site; and</u></p>	<u>TCZ-R12</u>	<u>Residential Activity</u>
<u>TCZ-R12</u>	<u>Residential Activity</u>				

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<p>b. <u>Compliance is achieved with</u></p> <ol style="list-style-type: none"> i. <u>TCZ-S5 (Location of Residential Units);</u> ii. <u>TCZ-S6 (Noise and Ventilation); and</u> iii. <u>TCZ-S7 (Outdoor Living Space).</u> <p>2. <u>Activity status: Restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with TCZ-R12-1.a</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The effects of the residential activity on the existing and anticipated function and role of the Town Centre Zone.</u> 2. <u>The potential of the residential activity to compromise activities that are enabled in the Town Centre Zone.</u> 3. <u>The amenity for the occupiers of the residential units.</u> <p>b. <u>Compliance is not achieved with TCZ-R12-1.b</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The matters of discretion of the infringed standard.</u> <p><u>Notification:</u></p> <p><u>An application under this rule where compliance is not achieved with LCZ-S5 or LCZ-S6 is precluded from being publicly notified in accordance with section 95A of the RMA.</u></p> <p><u>An application under this rule where compliance is not achieved with LCZ-S7 is precluded from being publicly or limited notified in accordance with section 95A of the RMA.</u></p>				
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R13	<table border="1"> <tr> <td><u>TCZ-R13</u></td> <td><u>Supermarket</u></td> </tr> <tr> <td colspan="2"> <p>1. <u>Activity status: Permitted</u></p> <p><u>Where:</u></p> </td> </tr> </table>	<u>TCZ-R13</u>	<u>Supermarket</u>	<p>1. <u>Activity status: Permitted</u></p> <p><u>Where:</u></p>	
<u>TCZ-R13</u>	<u>Supermarket</u>						
<p>1. <u>Activity status: Permitted</u></p> <p><u>Where:</u></p>							


IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<p>a. <u>The gross floor area does not exceed 1500m²; and</u></p> <p>b. <u>Compliance is achieved with TCZ-S7 (Landscaping and Screening).</u></p> <p>2. Activity status: Restricted Discretionary</p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with TCZ-R13-1.a</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the intensity, size and scale of the activity may adversely impact on the amenity of the Town Centre Zone or adjacent properties.</u> <u>The effects of the of the intensity, size and scale of the activity on the existing and anticipated function and role of the Town Centre Zone.</u> <u>The potential of the intensity, size and scale of the activity to compromise activities that are enabled in the Town Centre Zone.</u> <u>The potential of the location of the activity in the Town Centre Zone to undermine the role and function of the City Centre Zone.</u> <u>The extent to which the adverse effects of the intensity, size and scale of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>b. <u>Compliance is not achieved with TCZ-R13-1.b</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The matters of discretion of the infringed standard.</u> <p>Notification:</p> <ul style="list-style-type: none"> <u>An application under TCZ-R13-2.b is precluded from being publicly notified in accordance with section 95A of the RMA</u> 				
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R14	<table border="1"> <tr> <td>TCZ-R14</td> <td>Emergency Service Facility</td> </tr> <tr> <td colspan="2"> <p>1. Activity status: Restricted discretionary</p> <p><u>Where:</u></p> </td> </tr> </table>	TCZ-R14	Emergency Service Facility	<p>1. Activity status: Restricted discretionary</p> <p><u>Where:</u></p>	
TCZ-R14	Emergency Service Facility						
<p>1. Activity status: Restricted discretionary</p> <p><u>Where:</u></p>							

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<p>a. <u>Compliance is achieved with TCZ-S7 (Landscaping and Screening).</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The extent to which the activity may adversely impact on the amenity of the Town Centre Zone or adjacent properties.</u> 2. <u>The effects of the of the activity on the existing and anticipated function and role of the Town Centre Zone.</u> 3. <u>The potential of the activity to compromise activities that are enabled in the Town Centre Zone.</u> 4. <u>The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated.</u> 5. <u>The functional need or operational need for the Emergency Service Facility to be located in the Town Centre Zone.</u> <p>Notification:</p> <ul style="list-style-type: none"> • <u>An application under this rule is precluded from being publicly notified in accordance with section 95A of the RMA</u> 		
			<p>2. <u>Activity status: Discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with TCZ-R14-1.a</u></p>		
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R15	<table border="1"> <tr> <td>TCZ-R15</td> <td>Sport and Active Recreation</td> </tr> </table> <p>1. <u>Activity status: Restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>The gross floor area per tenancy does not exceed 500m²;</u></p> <p>b. <u>Compliance is achieved with TCZ-S7 (Landscaping and Screening).</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The extent to which the activity may adversely impact on the amenity of the Town Centre Zone or adjacent properties.</u> 2. <u>The effects of the of the activity on the existing and anticipated function and role of the Town Centre Zone.</u> 	TCZ-R15	Sport and Active Recreation
TCZ-R15	Sport and Active Recreation				

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<p>3. <u>The potential of the activity to compromise activities that are enabled in the Town Centre Zone.</u></p> <p>4. <u>The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated.</u></p> <p>2. <u>Activity status: Discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with TCZ-R15-1.a or TCZ-R15-1.b</u></p>				
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R16	<table border="1"> <tr> <td>TCZ-R16</td> <td>Entertainment Facility</td> </tr> <tr> <td>1.</td> <td>Activity status: Discretionary</td> </tr> </table>	TCZ-R16	Entertainment Facility	1.	Activity status: Discretionary
TCZ-R16	Entertainment Facility						
1.	Activity status: Discretionary						
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R17	<table border="1"> <tr> <td>TCZ-R17</td> <td>Large Format Retail Activity, excluding Supermarkets</td> </tr> <tr> <td>1.</td> <td>Activity status: Discretionary</td> </tr> </table>	TCZ-R17	Large Format Retail Activity, excluding Supermarkets	1.	Activity status: Discretionary
TCZ-R17	Large Format Retail Activity, excluding Supermarkets						
1.	Activity status: Discretionary						
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R18	<table border="1"> <tr> <td>TCZ-R18</td> <td>Drive-through Activity</td> </tr> <tr> <td>1.</td> <td>Activity status: Discretionary</td> </tr> </table>	TCZ-R18	Drive-through Activity	1.	Activity status: Discretionary
TCZ-R18	Drive-through Activity						
1.	Activity status: Discretionary						
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R19	<table border="1"> <tr> <td>TCZ-R19</td> <td>Retirement Village</td> </tr> <tr> <td>1.</td> <td>Activity status: Discretionary</td> </tr> </table>	TCZ-R19	Retirement Village	1.	Activity status: Discretionary
TCZ-R19	Retirement Village						
1.	Activity status: Discretionary						
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R20	<table border="1"> <tr> <td>TCZ-R20</td> <td>Any activity not otherwise listed as permitted, restricted discretionary, discretionary or non-complying</td> </tr> <tr> <td>1.</td> <td>Activity status: Discretionary</td> </tr> </table>	TCZ-R20	Any activity not otherwise listed as permitted, restricted discretionary, discretionary or non-complying	1.	Activity status: Discretionary
TCZ-R20	Any activity not otherwise listed as permitted, restricted discretionary, discretionary or non-complying						
1.	Activity status: Discretionary						
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R21	<table border="1"> <tr> <td>TCZ-R21</td> <td>Industrial Activity</td> </tr> <tr> <td>1.</td> <td>Activity status: Non-complying</td> </tr> </table>	TCZ-R21	Industrial Activity	1.	Activity status: Non-complying
TCZ-R21	Industrial Activity						
1.	Activity status: Non-complying						
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R22	<table border="1"> <tr> <td>TCZ-R22</td> <td>Yard Sale Activity / Trade Supplier</td> </tr> <tr> <td>1.</td> <td>Activity status: Non-complying</td> </tr> </table>	TCZ-R22	Yard Sale Activity / Trade Supplier	1.	Activity status: Non-complying
TCZ-R22	Yard Sale Activity / Trade Supplier						
1.	Activity status: Non-complying						

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R23	<table border="1"> <tr> <td>TCZ-R23</td> <td>Motorised Recreation</td> </tr> <tr> <td colspan="2">1. Activity status: Non-complying</td> </tr> </table>	TCZ-R23	Motorised Recreation	1. Activity status: Non-complying			
TCZ-R23	Motorised Recreation								
1. Activity status: Non-complying									
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R24	<table border="1"> <tr> <td>TCZ-R24</td> <td>Rural Industry</td> </tr> <tr> <td colspan="2">1. Activity status: Non-complying</td> </tr> </table>	TCZ-R24	Rural Industry	1. Activity status: Non-complying			
TCZ-R24	Rural Industry								
1. Activity status: Non-complying									
	New TCZ - Town Centre Zone	Introduce new Rule TCZ-R25	<table border="1"> <tr> <td>TCZ-R25</td> <td>Primary Production</td> </tr> <tr> <td colspan="2">1. Activity status: Non-complying</td> </tr> </table>	TCZ-R25	Primary Production	1. Activity status: Non-complying			
TCZ-R25	Primary Production								
1. Activity status: Non-complying									
	New TCZ - Town Centre Zone	Introduce new Standard TCZ-S1	<table border="1"> <tr> <th colspan="2">Standards</th> </tr> <tr> <td>TCZ-S1</td> <td>Height</td> </tr> <tr> <td> <p>1. Buildings must not exceed 26 metres in height, except that 50% of a building's roof in elevation, measured vertically from the junction between wall and roof, may exceed this height by 1 metre, where the entire roof slopes 15° or more, as shown on the following diagram:</p>  <p>2. Any fence or standalone wall along a side or rear boundary which adjoins a site zoned Residential or Open Space and Recreation must not exceed 2m in height.</p> <p>This standard does not apply to:</p> </td> <td> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>The location, design and appearance of the building or structure.</u> 2. <u>Any adverse effects on the streetscape.</u> 3. <u>Visual dominance, shading and loss of privacy for adjoining Residential or Open Space and Recreation zoned sites.</u> 4. <u>Compatibility with the planned built urban form of buildings, structures and activities in the surrounding area.</u> 5. <u>Whether the building height is commensurate with the anticipated level of commercial activities and community services in the Town Centre Zone.</u> 6. <u>Whether an increase in building height results from a response to natural hazard mitigation.</u> 7. <u>Whether topographical or other site constraints make compliance with the standard impractical.</u> </td> </tr> </table>	Standards		TCZ-S1	Height	<p>1. Buildings must not exceed 26 metres in height, except that 50% of a building's roof in elevation, measured vertically from the junction between wall and roof, may exceed this height by 1 metre, where the entire roof slopes 15° or more, as shown on the following diagram:</p>  <p>2. Any fence or standalone wall along a side or rear boundary which adjoins a site zoned Residential or Open Space and Recreation must not exceed 2m in height.</p> <p>This standard does not apply to:</p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>The location, design and appearance of the building or structure.</u> 2. <u>Any adverse effects on the streetscape.</u> 3. <u>Visual dominance, shading and loss of privacy for adjoining Residential or Open Space and Recreation zoned sites.</u> 4. <u>Compatibility with the planned built urban form of buildings, structures and activities in the surrounding area.</u> 5. <u>Whether the building height is commensurate with the anticipated level of commercial activities and community services in the Town Centre Zone.</u> 6. <u>Whether an increase in building height results from a response to natural hazard mitigation.</u> 7. <u>Whether topographical or other site constraints make compliance with the standard impractical.</u>
Standards									
TCZ-S1	Height								
<p>1. Buildings must not exceed 26 metres in height, except that 50% of a building's roof in elevation, measured vertically from the junction between wall and roof, may exceed this height by 1 metre, where the entire roof slopes 15° or more, as shown on the following diagram:</p>  <p>2. Any fence or standalone wall along a side or rear boundary which adjoins a site zoned Residential or Open Space and Recreation must not exceed 2m in height.</p> <p>This standard does not apply to:</p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>The location, design and appearance of the building or structure.</u> 2. <u>Any adverse effects on the streetscape.</u> 3. <u>Visual dominance, shading and loss of privacy for adjoining Residential or Open Space and Recreation zoned sites.</u> 4. <u>Compatibility with the planned built urban form of buildings, structures and activities in the surrounding area.</u> 5. <u>Whether the building height is commensurate with the anticipated level of commercial activities and community services in the Town Centre Zone.</u> 6. <u>Whether an increase in building height results from a response to natural hazard mitigation.</u> 7. <u>Whether topographical or other site constraints make compliance with the standard impractical.</u> 								

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<ul style="list-style-type: none"> a. <u>Solar water heating components provided these do not exceed the height by more than 1m.</u> b. <u>Chimney structures not exceeding 1.1m in width on any elevation and provided these do not exceed the height by more than 1m.</u> c. <u>Antennas, aerials, and flues provided these do not exceed the height by more than 1m.</u> d. <u>Satellite dishes (less than 1m in diameter) and architectural features (e.g. finials, spires) provided these do not exceed the height by more than 1m.</u> e. <u>Lift overruns provided these do not exceed the height by more than 1m.</u> 				
	New TCZ - Town Centre Zone	Introduce new Standard TCZ-S2	<table border="1"> <thead> <tr> <th><u>TCZ-S2</u></th> <th><u>Height in Relation to Boundary</u></th> </tr> </thead> <tbody> <tr> <td> <p>Where the side or rear boundary of a site adjoins a Residential Zone or Open Space and Recreation Zone the following Height in Relation to Boundary standard applies:</p> <p>1. Buildings must not project beyond a 60° recession plane measured from a point 4 metres vertically above ground level along all boundaries, as shown on the following diagram. Where the boundary forms part of a legal right of way, entrance strip, access site, or pedestrian access way, the height in relation to boundary applies from the farthest boundary of that legal right of way, entrance strip, access site, or pedestrian access way.</p> </td> <td> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Visual dominance, shading and loss of privacy for adjoining Residential or Open Space and Recreation zoned sites.</u> 2. <u>The location, design and appearance of the building or structure.</u> 3. <u>Whether an increase in height in relation to boundary results from a response to natural hazard mitigation.</u> 4. <u>Whether any architectural features or steps are proposed in the building façade to provide an attractive appearance when viewed from adjoining Residential or Open Space and Recreation zoned sites.</u> </td> </tr> </tbody> </table>	<u>TCZ-S2</u>	<u>Height in Relation to Boundary</u>	<p>Where the side or rear boundary of a site adjoins a Residential Zone or Open Space and Recreation Zone the following Height in Relation to Boundary standard applies:</p> <p>1. Buildings must not project beyond a 60° recession plane measured from a point 4 metres vertically above ground level along all boundaries, as shown on the following diagram. Where the boundary forms part of a legal right of way, entrance strip, access site, or pedestrian access way, the height in relation to boundary applies from the farthest boundary of that legal right of way, entrance strip, access site, or pedestrian access way.</p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Visual dominance, shading and loss of privacy for adjoining Residential or Open Space and Recreation zoned sites.</u> 2. <u>The location, design and appearance of the building or structure.</u> 3. <u>Whether an increase in height in relation to boundary results from a response to natural hazard mitigation.</u> 4. <u>Whether any architectural features or steps are proposed in the building façade to provide an attractive appearance when viewed from adjoining Residential or Open Space and Recreation zoned sites.</u>
<u>TCZ-S2</u>	<u>Height in Relation to Boundary</u>						
<p>Where the side or rear boundary of a site adjoins a Residential Zone or Open Space and Recreation Zone the following Height in Relation to Boundary standard applies:</p> <p>1. Buildings must not project beyond a 60° recession plane measured from a point 4 metres vertically above ground level along all boundaries, as shown on the following diagram. Where the boundary forms part of a legal right of way, entrance strip, access site, or pedestrian access way, the height in relation to boundary applies from the farthest boundary of that legal right of way, entrance strip, access site, or pedestrian access way.</p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Visual dominance, shading and loss of privacy for adjoining Residential or Open Space and Recreation zoned sites.</u> 2. <u>The location, design and appearance of the building or structure.</u> 3. <u>Whether an increase in height in relation to boundary results from a response to natural hazard mitigation.</u> 4. <u>Whether any architectural features or steps are proposed in the building façade to provide an attractive appearance when viewed from adjoining Residential or Open Space and Recreation zoned sites.</u> 						

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			 <p>This standard does not apply to:</p> <ol style="list-style-type: none"> <u>A boundary with a road.</u> <u>Existing or proposed internal boundaries within a site.</u> <u>Site boundaries where there is an existing common wall between 2 buildings on adjacent sites or where a common wall is proposed.</u> <u>Solar water heating components provided these do not exceed the height in relation to boundary by more than 1m.</u> <u>Chimney structures not exceeding 1.1m in width on any elevation and provided these do not exceed the height in relation to boundary by more than 1m.</u> <u>Antennas, aerials, satellite dishes (less than 1m in diameter), flues, and architectural features (e.g. finials, spires) provided these do not exceed the height in relation to boundary by more than 3m measured vertically.</u> 		
	New TCZ - Town Centre Zone	Introduce new Standard TCZ-S3	<table border="1"> <tr> <td><u>TCZ-S3</u></td> <td><u>Setback</u></td> </tr> </table>	<u>TCZ-S3</u>	<u>Setback</u>
<u>TCZ-S3</u>	<u>Setback</u>				

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			<p>Where the side or rear boundary of a site adjoins a Residential Zone or Open Space and Recreation Zone the following Setback standard applies:</p> <ol style="list-style-type: none"> Buildings must be set back from the relevant boundary by the minimum depth listed in the yards table below: <table border="1" data-bbox="600 539 869 641"> <thead> <tr> <th>Yard</th> <th>Minimum depth</th> </tr> </thead> <tbody> <tr> <td>Side</td> <td>1 metre</td> </tr> <tr> <td>Rear</td> <td>1 metre</td> </tr> </tbody> </table> This standard does not apply to site boundaries where there is an existing common wall between 2 buildings on adjacent sites or where a common wall is proposed. This standard does not apply to: <ol style="list-style-type: none"> Accessory buildings less than 2m in height. Fences and standalone walls. <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> <u>The visual amenity of adjoining Residential and Open Space and Recreation sites.</u> <u>The location, design and appearance of the building or structure.</u> <u>Whether any architectural features or steps are proposed in the building façade to provide an attractive appearance when viewed from adjoining Residential or Open Space and Recreation sites.</u> <u>Any benefits, including the extent to which the reduced setback will result in a more efficient, practical and better use of the balance of the site.</u> 	Yard	Minimum depth	Side	1 metre	Rear	1 metre
Yard	Minimum depth								
Side	1 metre								
Rear	1 metre								
	New TCZ - Town Centre Zone	Introduce new Standard TCZ-S4	<table border="1" data-bbox="533 890 1666 1262"> <thead> <tr> <th>TCZ-S4</th> <th>Active Frontages</th> </tr> </thead> <tbody> <tr> <td> <ol style="list-style-type: none"> Along active frontages identified on the planning maps: <ol style="list-style-type: none"> All new buildings and ground level additions or alterations to existing buildings must be built up to and oriented towards the road or public space boundary; A veranda must be provided that: <ol style="list-style-type: none"> Extends along the entire length of the building frontage; Provides continuous shelter with any adjoining veranda; and </td> <td> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The effects on the amenity and quality of the streetscape. The design and appearance of the street frontage. The ability to reuse and adapt the building for a variety of activities. </td> </tr> </tbody> </table>	TCZ-S4	Active Frontages	<ol style="list-style-type: none"> Along active frontages identified on the planning maps: <ol style="list-style-type: none"> All new buildings and ground level additions or alterations to existing buildings must be built up to and oriented towards the road or public space boundary; A veranda must be provided that: <ol style="list-style-type: none"> Extends along the entire length of the building frontage; Provides continuous shelter with any adjoining veranda; and 	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The effects on the amenity and quality of the streetscape. The design and appearance of the street frontage. The ability to reuse and adapt the building for a variety of activities. 		
TCZ-S4	Active Frontages								
<ol style="list-style-type: none"> Along active frontages identified on the planning maps: <ol style="list-style-type: none"> All new buildings and ground level additions or alterations to existing buildings must be built up to and oriented towards the road or public space boundary; A veranda must be provided that: <ol style="list-style-type: none"> Extends along the entire length of the building frontage; Provides continuous shelter with any adjoining veranda; and 	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> The effects on the amenity and quality of the streetscape. The design and appearance of the street frontage. The ability to reuse and adapt the building for a variety of activities. 								

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<ul style="list-style-type: none"> iii. <u>Has a minimum setback of 500mm from any kerb face;</u> c. <u>At least 55% of the ground floor building frontage must be display windows or transparent glazing; and</u> d. <u>The principal public entrance to the building must be located on the front boundary.</u> 				
	New TCZ - Town Centre Zone	Introduce new Standard TCZ-S5	<table border="1"> <tr> <td>TCZ-S5</td> <td>Location of Residential Units</td> </tr> <tr> <td> <ul style="list-style-type: none"> 1. <u>Along active frontages identified on the planning maps all residential units must be located above ground floor level.</u> </td> <td> Matters of discretion are restricted to: <ul style="list-style-type: none"> 1. <u>The effects on the amenity and quality of the streetscape.</u> 2. <u>The amenity for the occupiers of the residential units.</u> </td> </tr> </table>	TCZ-S5	Location of Residential Units	<ul style="list-style-type: none"> 1. <u>Along active frontages identified on the planning maps all residential units must be located above ground floor level.</u> 	Matters of discretion are restricted to: <ul style="list-style-type: none"> 1. <u>The effects on the amenity and quality of the streetscape.</u> 2. <u>The amenity for the occupiers of the residential units.</u>
TCZ-S5	Location of Residential Units						
<ul style="list-style-type: none"> 1. <u>Along active frontages identified on the planning maps all residential units must be located above ground floor level.</u> 	Matters of discretion are restricted to: <ul style="list-style-type: none"> 1. <u>The effects on the amenity and quality of the streetscape.</u> 2. <u>The amenity for the occupiers of the residential units.</u> 						
	New TCZ - Town Centre Zone	Introduce new Standard TCZ-S6	<table border="1"> <tr> <td>TCZ-S6</td> <td>Noise and Ventilation</td> </tr> <tr> <td> <ul style="list-style-type: none"> 1. <u>All residential units must meet the following standards:</u> <ul style="list-style-type: none"> a. <u>All habitable rooms must be designed and constructed to meet internal sound insulation levels achieving $D_{nT,w}+C_{tr} >30dB$ with an acoustic design certificate signed by a qualified acoustic engineer stating compliance will be achieved; and</u> b. <u>All habitable rooms must have a positive supplementary source of fresh air ducted from outside. The supplementary source of air is to achieve a minimum of 7.5 litres per second per person.</u> </td> <td> Matters of discretion are restricted to: <ul style="list-style-type: none"> 1. <u>Any potential reverse sensitivity effects on the continued operation of non- residential activities.</u> 2. <u>The amenity for the occupiers of the residential units.</u> </td> </tr> </table>	TCZ-S6	Noise and Ventilation	<ul style="list-style-type: none"> 1. <u>All residential units must meet the following standards:</u> <ul style="list-style-type: none"> a. <u>All habitable rooms must be designed and constructed to meet internal sound insulation levels achieving $D_{nT,w}+C_{tr} >30dB$ with an acoustic design certificate signed by a qualified acoustic engineer stating compliance will be achieved; and</u> b. <u>All habitable rooms must have a positive supplementary source of fresh air ducted from outside. The supplementary source of air is to achieve a minimum of 7.5 litres per second per person.</u> 	Matters of discretion are restricted to: <ul style="list-style-type: none"> 1. <u>Any potential reverse sensitivity effects on the continued operation of non- residential activities.</u> 2. <u>The amenity for the occupiers of the residential units.</u>
TCZ-S6	Noise and Ventilation						
<ul style="list-style-type: none"> 1. <u>All residential units must meet the following standards:</u> <ul style="list-style-type: none"> a. <u>All habitable rooms must be designed and constructed to meet internal sound insulation levels achieving $D_{nT,w}+C_{tr} >30dB$ with an acoustic design certificate signed by a qualified acoustic engineer stating compliance will be achieved; and</u> b. <u>All habitable rooms must have a positive supplementary source of fresh air ducted from outside. The supplementary source of air is to achieve a minimum of 7.5 litres per second per person.</u> 	Matters of discretion are restricted to: <ul style="list-style-type: none"> 1. <u>Any potential reverse sensitivity effects on the continued operation of non- residential activities.</u> 2. <u>The amenity for the occupiers of the residential units.</u> 						
	New TCZ - Town Centre Zone	Introduce new Standard TCZ-S7	<table border="1"> <tr> <td>TCZ-S7</td> <td>Outdoor Living Space</td> </tr> <tr> <td> <ul style="list-style-type: none"> 1. <u>Each residential unit at ground floor level must have an outdoor living space that is at least 20 square metres and</u> </td> <td> Matters of discretion are restricted to: </td> </tr> </table>	TCZ-S7	Outdoor Living Space	<ul style="list-style-type: none"> 1. <u>Each residential unit at ground floor level must have an outdoor living space that is at least 20 square metres and</u> 	Matters of discretion are restricted to:
TCZ-S7	Outdoor Living Space						
<ul style="list-style-type: none"> 1. <u>Each residential unit at ground floor level must have an outdoor living space that is at least 20 square metres and</u> 	Matters of discretion are restricted to:						

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>that comprises ground floor, balcony, patio, or roof terrace space that,—</p> <p>a.— where located at ground level, has no dimension less than 3 metres; and</p> <p>b.— where provided in the form of a balcony, patio, or roof terrace, is at least 8 square metres and has a minimum dimension of 1.8 metres; and</p> <p>c.— is accessible from the residential unit; and</p> <p>d.— may be—</p> <p>i.— grouped cumulatively by area in 1 communally accessible location; or</p> <p>ii.— located directly adjacent to the unit; and</p> <p>e.— is free of buildings, parking spaces, and servicing and manoeuvring areas.</p> <p>2.— Each residential unit located above ground floor level must have an outdoor living space in the form of a balcony, patio, or roof terrace that—</p> <p>a.— is at least 8 square metres and has a minimum dimension of 1.8 metres; and</p> <p>b.— is accessible from the residential unit; and</p> <p>c.— may be—</p> <p>i.— grouped cumulatively by area in 1 communally accessible location, in which case it may be located at ground level; or</p> <p>ii.— located directly adjacent to the unit.</p> <p>3.— For multi-unit housing, the outdoor living space can be provided as private space and shared space where:</p> <ol style="list-style-type: none"> <u>Whether adequate useable space is provided to accommodate outdoor activities.</u> <u>Whether there are topographical or other site constraints that make compliance with the standard impractical.</u> <u>The proximity of the residential unit to accessible public open space.</u>

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change						
			<p>a. Each residential unit is provided with a private outdoor living space that has a minimum area of 8m² with a minimum dimension of 1.8m, that is directly accessible from the residential unit to which it relates;</p> <p>b. The shared outdoor living space has a minimum area of 20m² with a minimum dimension of 3m; and</p> <p>c. Any ground floor outdoor living space is free of buildings, parking spaces and manoeuvring areas;</p> <p><u>1. Each residential unit, including any dual key unit, must be provided with either a private outdoor living space or access to a communal outdoor living space;</u></p> <p><u>2. Where private outdoor living space is provided it must be:</u></p> <ul style="list-style-type: none"> i <u>For the exclusive use of residents;</u> ii <u>Directly accessible from a habitable room;</u> iii <u>A single contiguous space; and</u> iv <u>Of the minimum area and dimension specified in the table below;</u> <p><u>3. Where communal outdoor living space is provided it does not need to be in a single continuous space, but it must be:</u></p> <ul style="list-style-type: none"> i <u>Accessible from the residential units it serves;</u> ii <u>Of the minimum area and dimension specified in the table below; and</u> iii <u>Free of buildings, parking spaces, and servicing and manoeuvring areas.</u> <table border="1" data-bbox="539 1198 1070 1284"> <thead> <tr> <th data-bbox="539 1198 786 1257">Living Space Type</th> <th data-bbox="786 1198 920 1257">Minimum area</th> <th data-bbox="920 1198 1070 1257">Minimum dimension</th> </tr> </thead> <tbody> <tr> <td data-bbox="539 1257 786 1284">1. Private</td> <td data-bbox="786 1257 920 1284"></td> <td data-bbox="920 1257 1070 1284"></td> </tr> </tbody> </table>	Living Space Type	Minimum area	Minimum dimension	1. Private		
Living Space Type	Minimum area	Minimum dimension							
1. Private									

Commented [MM222]: S58.370 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS															
#	Chapter	Change	Track Change												
			<table border="1"> <tr> <td>i Studio unit & 1 bedroom unit</td> <td>5m²</td> <td>1.8m</td> </tr> <tr> <td>ii 2+ bedroom unit</td> <td>8m²</td> <td>1.8m</td> </tr> <tr> <td>3. Communal</td> <td></td> <td></td> </tr> <tr> <td>For every 5 units</td> <td>10m² (per residential unit)</td> <td>8m diameter</td> </tr> </table>	i Studio unit & 1 bedroom unit	5m ²	1.8m	ii 2+ bedroom unit	8m ²	1.8m	3. Communal			For every 5 units	10m ² (per residential unit)	8m diameter
i Studio unit & 1 bedroom unit	5m ²	1.8m													
ii 2+ bedroom unit	8m ²	1.8m													
3. Communal															
For every 5 units	10m ² (per residential unit)	8m diameter													
New TCZ - Town Centre Zone	Introduce new Standard TCZ-S8	<p>TCZ-S8</p> <p>Screening and Landscaping of Service Areas, Outdoor Storage Areas and Parking Areas</p> <p>1. Any on-site service areas, including rubbish collection areas, and areas for the outdoor storage of goods or materials must, without preventing the provision of an entry point to the site, be adequately screened by a fence or landscaping where they are visible from any:</p> <ol style="list-style-type: none"> Public road; Other public space; and Directly adjoining site zoned Residential or Open Space and Recreation. <p>2. Any on-site parking area must:</p> <ol style="list-style-type: none"> Be adequately screened by a fence or landscaping from any directly adjoining site zoned Residential or Open Space and Recreation. Where located along a street edge, provide a landscaping strip that extends at least 1.5m from the boundary with the road and comprise a mix of trees, shrubs and ground cover plants, without preventing the provision of an entry point to the site. This does 	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> Any adverse effects on the streetscape. The visual amenity of adjoining Residential and Open Space and Recreation zoned sites including shading. The service, storage and parking needs of the activity. The size and location of service, storage and any parking areas. 												

Commented [MM223]: S58.370 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<p><u>not apply to individual parking spaces for residential development, if provided.</u></p> <p>3. <u>Along active frontages identified on the planning maps any on-site service areas, including rubbish collection areas, and areas for the storage of goods or materials and any on-site ground level car parking must be:</u></p> <p>a. <u>Located within or at the rear of the building that they serve; and</u></p> <p>b. <u>Adequately screened by a fence or landscaping where they are visible from any public road, public space or directly adjoining site zoned Residential or Open Space and Recreation.</u></p>				
	New TCZ - Town Centre Zone	Introduce new Standard TCZ-S9	<table border="1"> <thead> <tr> <th>TCZ-S9</th> <th>Water Supply, Stormwater and Wastewater</th> </tr> </thead> <tbody> <tr> <td> <p>1. <u>All activities shall comply with the water supply, stormwater and wastewater standards in the Code of Practice for Civil Engineering Works.</u></p> </td> <td> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Whether the Water Supply, Stormwater and Wastewater infrastructure has sufficient capacity to accommodate the activity.</u> 2. <u>Any alternative measures proposed to mitigate adverse effects on the Water Supply, Stormwater and Wastewater infrastructure network.</u> 3. <u>Whether the additional demand generated will necessitate additional unplanned public investment in, or expansion of, the Water Supply, Stormwater and Wastewater infrastructure network or compromise its ability to service other activities permitted within the zone.</u> 4. <u>Whether the development can achieve hydraulic neutrality.</u> </td> </tr> </tbody> </table>	TCZ-S9	Water Supply, Stormwater and Wastewater	<p>1. <u>All activities shall comply with the water supply, stormwater and wastewater standards in the Code of Practice for Civil Engineering Works.</u></p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Whether the Water Supply, Stormwater and Wastewater infrastructure has sufficient capacity to accommodate the activity.</u> 2. <u>Any alternative measures proposed to mitigate adverse effects on the Water Supply, Stormwater and Wastewater infrastructure network.</u> 3. <u>Whether the additional demand generated will necessitate additional unplanned public investment in, or expansion of, the Water Supply, Stormwater and Wastewater infrastructure network or compromise its ability to service other activities permitted within the zone.</u> 4. <u>Whether the development can achieve hydraulic neutrality.</u>
TCZ-S9	Water Supply, Stormwater and Wastewater						
<p>1. <u>All activities shall comply with the water supply, stormwater and wastewater standards in the Code of Practice for Civil Engineering Works.</u></p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Whether the Water Supply, Stormwater and Wastewater infrastructure has sufficient capacity to accommodate the activity.</u> 2. <u>Any alternative measures proposed to mitigate adverse effects on the Water Supply, Stormwater and Wastewater infrastructure network.</u> 3. <u>Whether the additional demand generated will necessitate additional unplanned public investment in, or expansion of, the Water Supply, Stormwater and Wastewater infrastructure network or compromise its ability to service other activities permitted within the zone.</u> 4. <u>Whether the development can achieve hydraulic neutrality.</u> 						

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			5. <u>The extent to which the development incorporates stormwater management techniques or controls to mitigate any increase in pre-development peak stormwater runoff.</u>				
	New TCZ - Town Centre Zone	Introduce new Standard TCZ-S10	<table border="1"> <tr> <td>TCZ-S10</td> <td>Hydraulic neutrality</td> </tr> <tr> <td><u>New buildings and development must be designed to achieve hydraulic neutrality ensure that the stormwater runoff from all new impermeable surfaces will be disposed of or stored on-site and released at a rate that does not exceed the peak stormwater runoff when compared to the pre-development situation for the 10% and 1% rainfall Annual Exceedance Probability event.</u></td> <td> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> <u>1. Methods to avoid, remedy or mitigate any adverse effects resulting from any increase in pre-development peak stormwater runoff.</u> <u>2. Cumulative effects.</u> </td> </tr> </table>	TCZ-S10	Hydraulic neutrality	<u>New buildings and development must be designed to achieve hydraulic neutrality ensure that the stormwater runoff from all new impermeable surfaces will be disposed of or stored on-site and released at a rate that does not exceed the peak stormwater runoff when compared to the pre-development situation for the 10% and 1% rainfall Annual Exceedance Probability event.</u>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> <u>1. Methods to avoid, remedy or mitigate any adverse effects resulting from any increase in pre-development peak stormwater runoff.</u> <u>2. Cumulative effects.</u>
TCZ-S10	Hydraulic neutrality						
<u>New buildings and development must be designed to achieve hydraulic neutrality ensure that the stormwater runoff from all new impermeable surfaces will be disposed of or stored on-site and released at a rate that does not exceed the peak stormwater runoff when compared to the pre-development situation for the 10% and 1% rainfall Annual Exceedance Probability event.</u>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> <u>1. Methods to avoid, remedy or mitigate any adverse effects resulting from any increase in pre-development peak stormwater runoff.</u> <u>2. Cumulative effects.</u> 						
CCZ – City Centre Zone							
	CCZ - City Centre Zone	Amend Background	<p>CCZ - City Centre Zone</p> <p>Background</p> <p>Businesses within the City are located in the City Centre Zone (Central Business District – CBD), commercial and industrial areas, and suburban areas. Some parts of the business areas include hotels, tourist facilities and other activities.</p> <p>The City Centre Zone is the primary commercial centre of the city. It offers vibrant, attractive and high-quality public spaces and provides for a wide variety and diverse range of commercial, community, recreational, employment and residential opportunities.</p> <p>High-density development and intensification is enabled and encouraged while maintaining and improving recognising that amenity values develop and change over time in response to the diverse and changing needs of people, communities and future generations especially in the public realm. There is opportunity for redevelopment and intensification as many sites within the City Centre Zone are currently not being used as intensively as they could be.</p> <p>There are specific requirements along identified street frontages to create attractive frontages that contribute a vibrant and active streetscape and improve the quality and appeal of City Centre Zone. New buildings and development are well designed and reflect the high-quality urban environment planned urban built form of the City Centre Zone. While all new buildings require resource consent as a restricted discretionary activity, the relevant standards send a clear signal that maximum building heights and density of urban form are anticipated and encouraged. At the same time the restricted discretionary activity status for new</p>				

Commented [MM224]: S58.373 - Kianga Ora: Home and Communities.

Commented [MM225]: S64.119 - Retirement Villages Association of New Zealand.

Commented [MM226]: S64.119 - Retirement Villages Association of New Zealand.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p><u>buildings and substantial additions and alterations to existing buildings will allow for an assessment of the proposal to ensure that any new development is well designed, of high quality and consistent with the City Centre Design Guide.</u></p> <p><u>The City Centre Zone also encourages high-density residential developments such as apartments, to provide wider housing choices and increase vibrancy of the City Centre Zone. Residential units need to be located above ground floor along identified active frontages.</u></p> <p><u>Non-residential activities and development have the potential to generate adverse effects where they are directly adjoining residential and open space areas. To manage these potential effects buildings have to be set back from these boundaries and outdoor storage and parking areas need to be screened.</u></p>
	CCZ- City Centre Zone	Delete existing Resource Management Issues	<p><i>Resource Management Issues</i></p> <p>CCZ 11 — Adverse effects on amenity values and environmental quality resulting from commercial activities.</p> <p>Commercial activities in general, while vital to the well-being of the community, may have a range of adverse effects on the surrounding environment, including residential areas. These effects need to be identified and managed to ensure that amenity values are not diminished. The adverse environmental effects which commercial activities may have can include increases in traffic density, noise and odour, a decrease in sunlight, and loss of privacy and visual amenity.</p> <p>CCZ 12 — The adverse effects of commercial activities on the existing infrastructure and resources of the commercial areas.</p> <p>Activities in commercial areas can result in effects on the infrastructure and resources which have established there.</p> <p>The efficient use of the existing infrastructure and resources of the commercial areas, including new development, is considered to be an important resource management matter.</p> <p>CCZ 13 — Providing for a range of commercial activities which are readily accessible.</p> <p>The variety of activities which exist in the commercial areas contributes to the vitality and convenience of the City. A number of distinct commercial areas are found in the City. The City Centre Zone (CBD) has a range of retail activities, community and entertainment facilities, civic and cultural facilities, offices and businesses, and is a focal point for the City.</p> <p>CCZ 14 — The continued maintenance of an appropriate level of environmental quality within commercial areas.</p> <p>Commercial activities can generate traffic, smoke, noise, vibration, glare or other nuisances that can adversely affect other nearby activities. They also can have potential adverse effects on the natural environment, such as waterbodies and indigenous bush areas.</p>

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			Some commercial areas within the City are characterised by pedestrian orientated activities and amenities. Large scale industrial, warehousing and storage facilities, which are vehicle orientated, may adversely impact on the pedestrian environment of the City Centre Zone (CBD). It is therefore important to recognise the particular elements which affect the amenity values of an area.						
	CCZ- City Centre Zone	Amend Objective CCZ-01	<table border="1"> <thead> <tr> <th colspan="2">Objectives</th> </tr> <tr> <th>CCZ-01</th> <th>Purpose of the CCZ- City Centre Zone</th> </tr> </thead> <tbody> <tr> <td colspan="2"> <p>The City Centre is Upper Hutt's principal sustainable management of physical resources within the existing commercial areas of the City to protect and enhance their amenity values, civic and cultural centre. It is vibrant and attractive and accommodates a wide range of commercial, community, recreational and residential activities.</p> <p>This objective recognises the importance of particular elements and characteristics that define the commercial areas. Commercial activities and development can have both positive and adverse environmental effects on the areas that surround them. Any consideration of effects must take account of the need to provide sufficient areas for commercial development needs, and the maintenance of amenity values and character.</p> <p>The commercial areas within the City are divided into two specific zones to reflect the Plan's policies:</p> <p>(1) The Commercial Zone focuses on retail and service functions which support the local community. Commercial activities are provided for at Silverstream and other suburban areas. These areas provide for a limited range of shopping and business needs. The smaller neighbourhood shops, including dairies, provide for day to day convenience shopping.</p> <p>(2) The CCZ- City Centre Zone (CBD) accommodates a variety of activities in a compact, convenient layout which is characterised by pedestrian orientated traffic.</p> </td> </tr> </tbody> </table>	Objectives		CCZ-01	Purpose of the CCZ- City Centre Zone	<p>The City Centre is Upper Hutt's principal sustainable management of physical resources within the existing commercial areas of the City to protect and enhance their amenity values, civic and cultural centre. It is vibrant and attractive and accommodates a wide range of commercial, community, recreational and residential activities.</p> <p>This objective recognises the importance of particular elements and characteristics that define the commercial areas. Commercial activities and development can have both positive and adverse environmental effects on the areas that surround them. Any consideration of effects must take account of the need to provide sufficient areas for commercial development needs, and the maintenance of amenity values and character.</p> <p>The commercial areas within the City are divided into two specific zones to reflect the Plan's policies:</p> <p>(1) The Commercial Zone focuses on retail and service functions which support the local community. Commercial activities are provided for at Silverstream and other suburban areas. These areas provide for a limited range of shopping and business needs. The smaller neighbourhood shops, including dairies, provide for day to day convenience shopping.</p> <p>(2) The CCZ- City Centre Zone (CBD) accommodates a variety of activities in a compact, convenient layout which is characterised by pedestrian orientated traffic.</p>	
Objectives									
CCZ-01	Purpose of the CCZ- City Centre Zone								
<p>The City Centre is Upper Hutt's principal sustainable management of physical resources within the existing commercial areas of the City to protect and enhance their amenity values, civic and cultural centre. It is vibrant and attractive and accommodates a wide range of commercial, community, recreational and residential activities.</p> <p>This objective recognises the importance of particular elements and characteristics that define the commercial areas. Commercial activities and development can have both positive and adverse environmental effects on the areas that surround them. Any consideration of effects must take account of the need to provide sufficient areas for commercial development needs, and the maintenance of amenity values and character.</p> <p>The commercial areas within the City are divided into two specific zones to reflect the Plan's policies:</p> <p>(1) The Commercial Zone focuses on retail and service functions which support the local community. Commercial activities are provided for at Silverstream and other suburban areas. These areas provide for a limited range of shopping and business needs. The smaller neighbourhood shops, including dairies, provide for day to day convenience shopping.</p> <p>(2) The CCZ- City Centre Zone (CBD) accommodates a variety of activities in a compact, convenient layout which is characterised by pedestrian orientated traffic.</p>									
	CCZ- City Centre Zone	Amend Objective CCZ-02	<table border="1"> <thead> <tr> <th>CCZ-02</th> <th>Character and Qualities of the CCZ- City Centre Zone</th> </tr> </thead> <tbody> <tr> <td colspan="2"> <p>The City Centre is characterised by a promotion of a compact, convenient and attractive pedestrian orientated Central Business District built form that reflects the high-density urban environment. Buildings and open spaces are of high quality, well-designed and create an attractive place to visit, work or live. Active and attractive street frontages create a lively environment with a strong pedestrian focus.</p> <p>The role of the CCZ- City Centre Zone (CBD), as a commercial and community focus of the City, relies on the accessibility and attractiveness of the area. Retail activities within the area are sustained by its pedestrian focus.</p> </td> </tr> </tbody> </table>	CCZ-02	Character and Qualities of the CCZ- City Centre Zone	<p>The City Centre is characterised by a promotion of a compact, convenient and attractive pedestrian orientated Central Business District built form that reflects the high-density urban environment. Buildings and open spaces are of high quality, well-designed and create an attractive place to visit, work or live. Active and attractive street frontages create a lively environment with a strong pedestrian focus.</p> <p>The role of the CCZ- City Centre Zone (CBD), as a commercial and community focus of the City, relies on the accessibility and attractiveness of the area. Retail activities within the area are sustained by its pedestrian focus.</p>			
CCZ-02	Character and Qualities of the CCZ- City Centre Zone								
<p>The City Centre is characterised by a promotion of a compact, convenient and attractive pedestrian orientated Central Business District built form that reflects the high-density urban environment. Buildings and open spaces are of high quality, well-designed and create an attractive place to visit, work or live. Active and attractive street frontages create a lively environment with a strong pedestrian focus.</p> <p>The role of the CCZ- City Centre Zone (CBD), as a commercial and community focus of the City, relies on the accessibility and attractiveness of the area. Retail activities within the area are sustained by its pedestrian focus.</p>									

IPI - PROPOSED AMENDMENTS											
#	Chapter	Change	Track Change								
			Council feels that the location of churches in the CCZ – City Centre Zone (CBD) needs to be controlled, as they may conflict with its retail function.								
	CCZ- City Centre Zone	Amend Objective CCZ-O3	<table border="1"> <tr> <td>CCZ-O3</td> <td>Interface with Residential or Open Space and Recreation Zones</td> </tr> <tr> <td colspan="2"><i>Use and development within the CCZ- City Centre Zone manage potential The avoidance, remedying, or mitigation of the adverse effects of commercial activities on the amenity values of surrounding neighbourhoods–adjoining sites in Residential or Open Space and Recreation Zones.</i></td> </tr> <tr> <td colspan="2">The effects generated by the wide range of activities provided for in the CCZ – City Centre Zone, such as smoke, noise, vibration, glare or other nuisances, can have adverse effects on areas beyond the CCZ – City Centre Zone boundaries.</td> </tr> </table>	CCZ-O3	Interface with Residential or Open Space and Recreation Zones	<i>Use and development within the CCZ- City Centre Zone manage potential The avoidance, remedying, or mitigation of the adverse effects of commercial activities on the amenity values of surrounding neighbourhoods–adjoining sites in Residential or Open Space and Recreation Zones.</i>		The effects generated by the wide range of activities provided for in the CCZ – City Centre Zone, such as smoke, noise , vibration, glare or other nuisances, can have adverse effects on areas beyond the CCZ – City Centre Zone boundaries.			
CCZ-O3	Interface with Residential or Open Space and Recreation Zones										
<i>Use and development within the CCZ- City Centre Zone manage potential The avoidance, remedying, or mitigation of the adverse effects of commercial activities on the amenity values of surrounding neighbourhoods–adjoining sites in Residential or Open Space and Recreation Zones.</i>											
The effects generated by the wide range of activities provided for in the CCZ – City Centre Zone, such as smoke, noise , vibration, glare or other nuisances, can have adverse effects on areas beyond the CCZ – City Centre Zone boundaries.											
	CCZ- City Centre Zone	Insert new Objective CCZ-O4	<table border="1"> <tr> <td>CCZ-O4</td> <td>Hydraulic neutrality</td> </tr> <tr> <td colspan="2"><i>There is no increase in the peak demand on stormwater management systems and increase in flooding from subdivision and development.</i></td> </tr> </table>	CCZ-O4	Hydraulic neutrality	<i>There is no increase in the peak demand on stormwater management systems and increase in flooding from subdivision and development.</i>					
CCZ-O4	Hydraulic neutrality										
<i>There is no increase in the peak demand on stormwater management systems and increase in flooding from subdivision and development.</i>											
	CCZ- City Centre Zone	Amend Policy CCZ-P1	<table border="1"> <tr> <td colspan="2">Policies</td> </tr> <tr> <td>CCZ-P1</td> <td>Appropriate Activities</td> </tr> <tr> <td colspan="2"> <ol style="list-style-type: none"> <i>To promote the location of retail. Enable a wide range of activities in patterns which do not adversely affect the that are compatible with the anticipated purpose, character planned urban built form, and amenity values of the CCZ- City Centre Zone (Central Business District), and to limit the establishment of retail activities within the General Industrial Zone.</i> <i>Encourage activities with a strong pedestrian focus to locate along roads with active street frontage requirements to create a vibrant interface and active public spaces.</i> </td> </tr> <tr> <td colspan="2">The CCZ – City Centre Zone (CBD) is the focus of many retail and service activities that, in combination, give this area a special and unique character as the centre of the City. The focusing and clustering of activities within the CCZ – City Centre Zone (CBD) is an important part of the vitality, character and amenity of the City. This policy seeks to recognise the role of the CCZ – City Centre Zone (CBD) by promoting its amenity characteristics and recognising its overall</td> </tr> </table>	Policies		CCZ-P1	Appropriate Activities	<ol style="list-style-type: none"> <i>To promote the location of retail. Enable a wide range of activities in patterns which do not adversely affect the that are compatible with the anticipated purpose, character planned urban built form, and amenity values of the CCZ- City Centre Zone (Central Business District), and to limit the establishment of retail activities within the General Industrial Zone.</i> <i>Encourage activities with a strong pedestrian focus to locate along roads with active street frontage requirements to create a vibrant interface and active public spaces.</i> 		The CCZ – City Centre Zone (CBD) is the focus of many retail and service activities that, in combination, give this area a special and unique character as the centre of the City. The focusing and clustering of activities within the CCZ – City Centre Zone (CBD) is an important part of the vitality, character and amenity of the City. This policy seeks to recognise the role of the CCZ – City Centre Zone (CBD) by promoting its amenity characteristics and recognising its overall	
Policies											
CCZ-P1	Appropriate Activities										
<ol style="list-style-type: none"> <i>To promote the location of retail. Enable a wide range of activities in patterns which do not adversely affect the that are compatible with the anticipated purpose, character planned urban built form, and amenity values of the CCZ- City Centre Zone (Central Business District), and to limit the establishment of retail activities within the General Industrial Zone.</i> <i>Encourage activities with a strong pedestrian focus to locate along roads with active street frontage requirements to create a vibrant interface and active public spaces.</i> 											
The CCZ – City Centre Zone (CBD) is the focus of many retail and service activities that, in combination, give this area a special and unique character as the centre of the City. The focusing and clustering of activities within the CCZ – City Centre Zone (CBD) is an important part of the vitality, character and amenity of the City. This policy seeks to recognise the role of the CCZ – City Centre Zone (CBD) by promoting its amenity characteristics and recognising its overall											

Commented [MM227]: S58.380 - Kainga Ora - Homes and Communities.

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<p>economic viability, but this policy does not seek to preclude retail development in other parts of the City such as in neighbourhood centres. This in turn promotes the sustainable management of the CCZ – City Centre Zone (CBD).</p> <p>Yard-orientated retail activities and large format retail activities tend to adversely affect pedestrian amenity values. It is therefore important to encourage them to locate in areas where a lower level of pedestrian amenity is acceptable such as in the General industrial zone. Establishment of retail activity in the General industrial zone is however controlled in order to enable the assessment of the scale and character of retail activity. Retail activity in the General industrial zone can detract from other retail areas of the City and can generate adverse traffic effects. Retail activity can also conflict with other land uses within the General industrial zone. Large format retail development should be located in a manner complementary to the existing retail development of the City and in a manner that is complementary to, and does not detract from, the vitality and viability of the CCZ – City Centre Zone (CBD).</p> <p>Specific provision is made for large format retailing to establish on the former South Pacific Tyres site being a location that is considered to be complementary to the CBD and which can contain a number of large format retail activities in an integrated manner, complementary to established activities on Park Street. The site has been identified as being appropriate for large format retailing through the development of the Upper Hutt Urban Growth Strategy.</p> <p>The concentration of activities in established areas results in the provision of a wide range of services and the promotion of amenity values of the established business areas. It also encourages better use of community resources such as the City Library or recreation facilities which are more convenient when located centrally.</p>		
	CCZ- City Centre Zone	Replace Policy CCZ-P2	<table border="1"> <tr> <td>CCZ-P2</td> <td><u>Residential Activity</u></td> </tr> </table> <p><u>1. To promote a high level of CCZ – City Centre Zone (Central Business District) amenity, including weather protection in Main Street and the minimisation of conflict with motor vehicles. Provide for high-density residential activity and development where:</u></p> <ol style="list-style-type: none"> a. <u>Residential units are located above ground floor;</u> b. <u>Residential units are designed to</u> <ol style="list-style-type: none"> i. <u>Ensure appropriate indoor noise and ventilation levels; and</u> ii. <u>Provide amenity values for occupants;</u> c. <u>Reverse sensitivity effects on commercial activities are minimised; and</u> d. <u>It is consistent with the City Centre Design Guide.</u> 	CCZ-P2	<u>Residential Activity</u>
CCZ-P2	<u>Residential Activity</u>				

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<p><u>2. Only allow for the location of residential units on the ground floor where:</u></p> <ol style="list-style-type: none"> a. <u>It is not located along an Active Street Frontage identified on the planning maps.</u> b. <u>It does not preclude a positive interface with the public space;</u> c. <u>It will not compromise amenity values for residents;</u> d. <u>It will not result in reverse sensitivity effects on existing or anticipated and enabled non-residential activities in the City Centre Zone; and</u> e. <u>It will not compromise the function and role of the City Centre Zone.</u> <p>4.3. Avoid the location of residential units on the ground floor along Active Street Frontages identified on the planning maps.</p> <p>This policy promotes the protection and enhancement of the environmental quality of the CCZ – City Centre Zone (CBD), and provision for the needs of pedestrians. A lack of weather protection can detract from the amenity and pleasantness of the area. Verandahs will be required for buildings along Main Street. Council also seeks to enhance the amenity of the CCZ – City Centre Zone (CBD) by traffic management measures and the provision of street furniture.</p>				
	CCZ- City Centre Zone	Amend Policy CCZ-P3	<table border="1"> <thead> <tr> <th>CCZ-P3</th> <th>Other Activities</th> </tr> </thead> <tbody> <tr> <td colspan="2"> <p>To ensure that <u>Only allow for other activities in the CCZ – City Centre Zone do not unduly detract from the character and amenity of neighbouring areas where:</u></p> <ol style="list-style-type: none"> 1. <u>Any adverse effects, including reverse sensitivity effects on existing or anticipated activities, can be managed;</u> 2. <u>The scale and intensity of the activity is consistent with the anticipated high-density character and amenity values of the City Centre Zone;</u> 3. <u>The scale and intensity of the activity does not compromise other activities that are anticipated and enabled within the City Centre Zone; and</u> 4. <u>The design and layout of the activity does not compromise the streetscape, amenity values or safety of the City Centre Zone.</u> </td> </tr> </tbody> </table>	CCZ-P3	Other Activities	<p>To ensure that <u>Only allow for other activities in the CCZ – City Centre Zone do not unduly detract from the character and amenity of neighbouring areas where:</u></p> <ol style="list-style-type: none"> 1. <u>Any adverse effects, including reverse sensitivity effects on existing or anticipated activities, can be managed;</u> 2. <u>The scale and intensity of the activity is consistent with the anticipated high-density character and amenity values of the City Centre Zone;</u> 3. <u>The scale and intensity of the activity does not compromise other activities that are anticipated and enabled within the City Centre Zone; and</u> 4. <u>The design and layout of the activity does not compromise the streetscape, amenity values or safety of the City Centre Zone.</u> 	
CCZ-P3	Other Activities						
<p>To ensure that <u>Only allow for other activities in the CCZ – City Centre Zone do not unduly detract from the character and amenity of neighbouring areas where:</u></p> <ol style="list-style-type: none"> 1. <u>Any adverse effects, including reverse sensitivity effects on existing or anticipated activities, can be managed;</u> 2. <u>The scale and intensity of the activity is consistent with the anticipated high-density character and amenity values of the City Centre Zone;</u> 3. <u>The scale and intensity of the activity does not compromise other activities that are anticipated and enabled within the City Centre Zone; and</u> 4. <u>The design and layout of the activity does not compromise the streetscape, amenity values or safety of the City Centre Zone.</u> 							

Commented [MM228]: Clause 16(2) Schedule 1 RMA correction.

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<p>This policy recognises the potential for business activities to impact adversely on adjoining areas and consequently aims to preserve the amenity values of areas adjacent to the CCZ- City Centre Zone.</p>				
	CCZ- City Centre Zone	Amend Policy CCZ-P5	<table border="1"> <tr> <td>CCZ-P4</td> <td>Built Development</td> </tr> <tr> <td colspan="2"> <p>To control the size and scale of buildings and the visual appearance of sites within the CCZ- City Centre Zone</p> <p><u>Provide for and encourage high-density and high quality built development that:</u></p> <ol style="list-style-type: none"> <u>Acknowledges and reflects the purpose of the City Centre Zone as being the main commercial centre and focal point for Upper Hutt;</u> <u>Realises as much development capacity as possible, to maximise the benefits of intensification;</u> <u>Reflects the anticipated compact, high-density built environment of the City Centre Zone;</u> <u>Is well designed and contributes to creating safe and vibrant public spaces;</u> <u>Provides active and attractive street frontages;</u> and <u>Is accessible to active and public transport; and</u> <u>Is consistent with the City Centre Design Guide.</u> <p>This policy aims to preserve amenity values within the CCZ- City Centre Zone. Buildings and sites need to be attractive and be of a size or type that is compatible with the neighbourhood.</p> </td> </tr> </table>	CCZ-P4	Built Development	<p>To control the size and scale of buildings and the visual appearance of sites within the CCZ- City Centre Zone</p> <p><u>Provide for and encourage high-density and high quality built development that:</u></p> <ol style="list-style-type: none"> <u>Acknowledges and reflects the purpose of the City Centre Zone as being the main commercial centre and focal point for Upper Hutt;</u> <u>Realises as much development capacity as possible, to maximise the benefits of intensification;</u> <u>Reflects the anticipated compact, high-density built environment of the City Centre Zone;</u> <u>Is well designed and contributes to creating safe and vibrant public spaces;</u> <u>Provides active and attractive street frontages;</u> and <u>Is accessible to active and public transport; and</u> <u>Is consistent with the City Centre Design Guide.</u> <p>This policy aims to preserve amenity values within the CCZ- City Centre Zone. Buildings and sites need to be attractive and be of a size or type that is compatible with the neighbourhood.</p>	
CCZ-P4	Built Development						
<p>To control the size and scale of buildings and the visual appearance of sites within the CCZ- City Centre Zone</p> <p><u>Provide for and encourage high-density and high quality built development that:</u></p> <ol style="list-style-type: none"> <u>Acknowledges and reflects the purpose of the City Centre Zone as being the main commercial centre and focal point for Upper Hutt;</u> <u>Realises as much development capacity as possible, to maximise the benefits of intensification;</u> <u>Reflects the anticipated compact, high-density built environment of the City Centre Zone;</u> <u>Is well designed and contributes to creating safe and vibrant public spaces;</u> <u>Provides active and attractive street frontages;</u> and <u>Is accessible to active and public transport; and</u> <u>Is consistent with the City Centre Design Guide.</u> <p>This policy aims to preserve amenity values within the CCZ- City Centre Zone. Buildings and sites need to be attractive and be of a size or type that is compatible with the neighbourhood.</p>							
	CCZ- City Centre Zone	Amend Policy CCZ-P6	<table border="1"> <tr> <td>CCZ-P5</td> <td>Public Space Interface and Active Street Frontages</td> </tr> <tr> <td colspan="2"> <p>To identify and maintain amenity values that the community wishes to protect. Require new development to create a positive interface with the public space through high quality building design.</p> <p><u>Encourage parking, storage and servicing areas to be visually unobtrusive and located preferably within or to the rear of buildings.</u></p> <p><u>Where located along identified active frontages, require new built development and activities to:</u></p> </td> </tr> </table>	CCZ-P5	Public Space Interface and Active Street Frontages	<p>To identify and maintain amenity values that the community wishes to protect. Require new development to create a positive interface with the public space through high quality building design.</p> <p><u>Encourage parking, storage and servicing areas to be visually unobtrusive and located preferably within or to the rear of buildings.</u></p> <p><u>Where located along identified active frontages, require new built development and activities to:</u></p>	
CCZ-P5	Public Space Interface and Active Street Frontages						
<p>To identify and maintain amenity values that the community wishes to protect. Require new development to create a positive interface with the public space through high quality building design.</p> <p><u>Encourage parking, storage and servicing areas to be visually unobtrusive and located preferably within or to the rear of buildings.</u></p> <p><u>Where located along identified active frontages, require new built development and activities to:</u></p>							

- Commented [MM229]:** S50.24 - Waka Kotahi - New Zealand Transport Agency.
- Commented [MM230]:** S50.24 - Waka Kotahi - New Zealand Transport Agency.
- Commented [MM231]:** S50.24 - Waka Kotahi - New Zealand Transport Agency.

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<p>1. <u>Provide a positive interface with the public space through:</u></p> <ol style="list-style-type: none"> <u>Being built up to and oriented towards the front boundary of the site;</u> <u>Providing verandahs or other adequate forms of pedestrian shelter;</u> <u>Providing display windows and obvious public entrances; and</u> <u>Requiring parking, storage and servicing areas to be visually unobtrusive and located within or to the rear of buildings.</u> <p>2. <u>Be consistent with the City Centre Design Guide</u></p> <p><u>Avoid new built development and activities that prevent or interrupt a continuous active street frontage along identified active frontages.</u></p> <p>Amenity values are those features or aspects about an area which enhance it or make it pleasant to be in. They can include access to sunlight, landscaping and visual qualities. They may also include important public features, such as parks and reserves. Activities which can adversely affect the amenities of an area must be managed, while also recognising the rights of individuals to use their own properties and the need for utilities to operate effectively and safely.</p> <p>A particular concern of the Upper Hutt community relates to the effects of the establishment and use of what are commonly referred to as gang fortifications. These are sometimes accompanied by an increase in antisocial behaviour. It is Council's view that the adverse effects of these fortifications on the environment, in particular in respect of the social, economic, aesthetic and cultural conditions of the Upper Hutt people and community, and the amenity values of the Upper Hutt environment, are such that these activities should not be permitted. The activity is therefore prohibited anywhere in Upper Hutt City.</p>		
	CCZ- City Centre Zone	Amend Policy CCZ-P4	<table border="1"> <tr> <td>CCZ-P6</td> <td><u>Inappropriate Activities</u></td> </tr> </table> <p><u>To promote the development of a safer and more secure environment for the community. Avoid activities that are incompatible with the anticipated purpose, character and amenity values of the City Centre Zone.</u></p> <p>Part of the environmental amenity of urban areas is dependent on the degree to which pedestrians feel comfortable moving from place to place. Buildings, roads and the network of pedestrian accessways within the built environment can significantly affect the way people feel about where they live and work, and their ease of movement, safety and security. For example, pedestrian amenity is promoted by the inclusion of some protection from the elements in the design of commercial premises.</p>	CCZ-P6	<u>Inappropriate Activities</u>
CCZ-P6	<u>Inappropriate Activities</u>				

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
	CCZ- City Centre Zone	Introduce new Policy CCZ-P7	<table border="1"> <tr> <td>CCZ-P7</td> <td>Interface with Residential or Open Space and Recreation Zones</td> </tr> <tr> <td colspan="2"><i>Minimise the adverse effects from commercial activities and high-density development on directly adjoining sites that are zoned Residential or Open Space and Recreation through:</i></td> </tr> <tr> <td colspan="2"> <ol style="list-style-type: none"> <i>Requiring new buildings and activities to be located and designed to manage any shading and privacy effects on neighbouring sites zoned Residential or Open Space and Recreation;</i> <i>Limiting the height, bulk and form of new buildings along boundaries with sites zoned Residential or Open Space and Recreation to minimise dominance effects; and</i> <i>Requiring the use of landscaping and screening to minimise adverse visual effects on adjoining sites zoned Residential or Open Space and Recreation.</i> </td> </tr> </table>	CCZ-P7	Interface with Residential or Open Space and Recreation Zones	<i>Minimise the adverse effects from commercial activities and high-density development on directly adjoining sites that are zoned Residential or Open Space and Recreation through:</i>		<ol style="list-style-type: none"> <i>Requiring new buildings and activities to be located and designed to manage any shading and privacy effects on neighbouring sites zoned Residential or Open Space and Recreation;</i> <i>Limiting the height, bulk and form of new buildings along boundaries with sites zoned Residential or Open Space and Recreation to minimise dominance effects; and</i> <i>Requiring the use of landscaping and screening to minimise adverse visual effects on adjoining sites zoned Residential or Open Space and Recreation.</i> 	
CCZ-P7	Interface with Residential or Open Space and Recreation Zones								
<i>Minimise the adverse effects from commercial activities and high-density development on directly adjoining sites that are zoned Residential or Open Space and Recreation through:</i>									
<ol style="list-style-type: none"> <i>Requiring new buildings and activities to be located and designed to manage any shading and privacy effects on neighbouring sites zoned Residential or Open Space and Recreation;</i> <i>Limiting the height, bulk and form of new buildings along boundaries with sites zoned Residential or Open Space and Recreation to minimise dominance effects; and</i> <i>Requiring the use of landscaping and screening to minimise adverse visual effects on adjoining sites zoned Residential or Open Space and Recreation.</i> 									
	CCZ- City Centre Zone	Introduce new Policy CCZ-P8	<table border="1"> <tr> <td>CCZ-P8</td> <td>Hydraulic neutrality</td> </tr> <tr> <td colspan="2"><i>New buildings and development will be designed to achieve hydraulic neutrality.</i></td> </tr> </table>	CCZ-P8	Hydraulic neutrality	<i>New buildings and development will be designed to achieve hydraulic neutrality.</i>			
CCZ-P8	Hydraulic neutrality								
<i>New buildings and development will be designed to achieve hydraulic neutrality.</i>									
	CCZ- City Centre Zone	Amend Rules Advice Note	<p>Rules (CBD)</p> <p>District-wide matters</p> <p>Note: There may be a number of provisions that apply to an activity, building, structure or site. Resource consent may therefore be required under rules in this chapter as well as other chapters. Unless specifically stated in a rule, resource consent is required under each relevant rule. The steps to determine the status of an activity are set out in Chapter 2 How the Plan Works.</p> <p>Rules relating to subdivision are found in the SUB-GEN (General Subdivision Provisions that Apply in All Zones) and the SUB-CMU (Subdivision in Commercial and Mixed Use Zones) chapters.</p> <p>Each activity in the CCZ- City Centre Zone shall comply with the relevant qualifying matter area provisions and permitted activity standards in the District-wide matters of the Plan as listed below.</p> <table border="1"> <tr> <td>District-wide matters</td> </tr> <tr> <td>NU – Network Utilities</td> </tr> <tr> <td>REG - Renewable Energy Generation</td> </tr> <tr> <td>TP – Transport and Parking</td> </tr> </table>	District-wide matters	NU – Network Utilities	REG - Renewable Energy Generation	TP – Transport and Parking		
District-wide matters									
NU – Network Utilities									
REG - Renewable Energy Generation									
TP – Transport and Parking									

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change																					
			<table border="1"> <tr><td>CL – Contaminated Land</td></tr> <tr><td>HS - Hazardous Substances</td></tr> <tr><td>NH - Natural Hazards</td></tr> <tr><td>WM – Waste Management</td></tr> <tr><td>HH - Historical Heritage</td></tr> <tr><td>TREE - Notable Trees</td></tr> <tr><td>UTG - Urban Tree Groups</td></tr> <tr><td>ECO - Ecosystems and Indigenous Biodiversity</td></tr> <tr><td>NATC – Natural Character</td></tr> <tr><td>NFL - Natural Features and Landscapes</td></tr> <tr><td>PA – Public Access</td></tr> <tr><td>SUB - Subdivision</td></tr> <tr><td>DC – Development Contributions</td></tr> <tr><td>AIR - Air</td></tr> <tr><td><u>PK – Papakāinga</u></td></tr> <tr><td>ASW - Activities on the Surface of Water</td></tr> <tr><td>EW - Earthworks</td></tr> <tr><td>LIGHT - Light</td></tr> <tr><td>NOISE - Noise</td></tr> <tr><td>SIGN - Signs</td></tr> <tr><td>TEMP - Temporary Activities</td></tr> </table>	CL – Contaminated Land	HS - Hazardous Substances	NH - Natural Hazards	WM – Waste Management	HH - Historical Heritage	TREE - Notable Trees	UTG - Urban Tree Groups	ECO - Ecosystems and Indigenous Biodiversity	NATC – Natural Character	NFL - Natural Features and Landscapes	PA – Public Access	SUB - Subdivision	DC – Development Contributions	AIR - Air	<u>PK – Papakāinga</u>	ASW - Activities on the Surface of Water	EW - Earthworks	LIGHT - Light	NOISE - Noise	SIGN - Signs	TEMP - Temporary Activities
CL – Contaminated Land																								
HS - Hazardous Substances																								
NH - Natural Hazards																								
WM – Waste Management																								
HH - Historical Heritage																								
TREE - Notable Trees																								
UTG - Urban Tree Groups																								
ECO - Ecosystems and Indigenous Biodiversity																								
NATC – Natural Character																								
NFL - Natural Features and Landscapes																								
PA – Public Access																								
SUB - Subdivision																								
DC – Development Contributions																								
AIR - Air																								
<u>PK – Papakāinga</u>																								
ASW - Activities on the Surface of Water																								
EW - Earthworks																								
LIGHT - Light																								
NOISE - Noise																								
SIGN - Signs																								
TEMP - Temporary Activities																								
	CCZ- City Centre Zone	Amend Permitted and	<p>Activities Tables <i>Policies CCZ P1, NU P4,</i></p>																					

IPI - PROPOSED AMENDMENTS																		
#	Chapter	Change	Track Change															
		Controlled Activities Tables	<table border="1"> <tr> <td colspan="2">Permitted Activities</td> <td></td> </tr> <tr> <td>CCZ-R1</td> <td> <p>All Commercial Service Activities other than those identified below are</p> <p>1. Activity status: Permitted provided they meet the standards specified in the Plan for permitted activities</p> </td> <td>PER</td> </tr> <tr> <td>CCZ-R2</td> <td> <p>Any <u>Retail</u> activities.</p> <p>1. Activity unless otherwise provided for below status: Permitted</p> </td> <td>PER</td> </tr> <tr> <td>CCZ-R3</td> <td> <p>Office activity The following retail activities:</p> <p>(1) The sale and maintenance of heavy machinery;</p> <p>(2) Garden centres;</p> <p>(3) Building improvement centres;</p> <p>(4) Yard oriented retail activities;</p> <p>(5) The sale of goods manufactured on the site, provided that the retail component is ancillary to the manufacturing activity;</p> <p>The sale of kit set buildings and framing.</p> <p>1. Activity status: Permitted</p> </td> <td>PER</td> </tr> <tr> <td>CCZ-R4</td> <td> <p>Visitor Accommodation</p> <p>1. Activity status: Permitted</p> <p>Where:</p> <p>a. Compliance is achieved with</p> <p>i. CCZ-S3 (Location of Habitable Rooms); and</p> </td> <td>PER</td> </tr> </table>	Permitted Activities			CCZ-R1	<p>All Commercial Service Activities other than those identified below are</p> <p>1. Activity status: Permitted provided they meet the standards specified in the Plan for permitted activities</p>	PER	CCZ-R2	<p>Any <u>Retail</u> activities.</p> <p>1. Activity unless otherwise provided for below status: Permitted</p>	PER	CCZ-R3	<p>Office activity The following retail activities:</p> <p>(1) The sale and maintenance of heavy machinery;</p> <p>(2) Garden centres;</p> <p>(3) Building improvement centres;</p> <p>(4) Yard oriented retail activities;</p> <p>(5) The sale of goods manufactured on the site, provided that the retail component is ancillary to the manufacturing activity;</p> <p>The sale of kit set buildings and framing.</p> <p>1. Activity status: Permitted</p>	PER	CCZ-R4	<p>Visitor Accommodation</p> <p>1. Activity status: Permitted</p> <p>Where:</p> <p>a. Compliance is achieved with</p> <p>i. CCZ-S3 (Location of Habitable Rooms); and</p>	PER
Permitted Activities																		
CCZ-R1	<p>All Commercial Service Activities other than those identified below are</p> <p>1. Activity status: Permitted provided they meet the standards specified in the Plan for permitted activities</p>	PER																
CCZ-R2	<p>Any <u>Retail</u> activities.</p> <p>1. Activity unless otherwise provided for below status: Permitted</p>	PER																
CCZ-R3	<p>Office activity The following retail activities:</p> <p>(1) The sale and maintenance of heavy machinery;</p> <p>(2) Garden centres;</p> <p>(3) Building improvement centres;</p> <p>(4) Yard oriented retail activities;</p> <p>(5) The sale of goods manufactured on the site, provided that the retail component is ancillary to the manufacturing activity;</p> <p>The sale of kit set buildings and framing.</p> <p>1. Activity status: Permitted</p>	PER																
CCZ-R4	<p>Visitor Accommodation</p> <p>1. Activity status: Permitted</p> <p>Where:</p> <p>a. Compliance is achieved with</p> <p>i. CCZ-S3 (Location of Habitable Rooms); and</p>	PER																

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>ii. <u>CCZ-S5 (Noise and Ventilation).</u></p>
			<p>CCZ-R5</p> <p>Community Facility Residential accommodation for a caretaker, where the caretaker is required to live on the site</p> <p>1. Activity status: Permitted</p> <p style="text-align: right;">PER</p>
			<p>CCZ-R6</p> <p>Residential Activity accommodation not otherwise provided for in this table</p> <p>1. Activity status: Permitted</p> <p>Where:</p> <p>a. Compliance is achieved with CCZ-S3 (Location of Residential Units); and</p> <p>b. Compliance is achieved with CCZ-S5 (Noise and Ventilation); and</p> <p>c. <u>Compliance is achieved with CCZ-S10 (Outdoor living space)</u></p> <p>2. Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. Compliance is not achieved with CCZ-R6-1.a; and</p> <p>b. <u>The residential units are not located along an Active Frontage identified on the planning maps.</u></p> <p>Matters of discretion are restricted to:</p> <p>1. <u>The matters of discretion of the infringed standard.</u></p> <p>2. <u>Consistency with the City Centre Design Guide.</u></p> <p>Notification:</p> <ul style="list-style-type: none"> <u>An application under this rule is precluded from being publicly notified in accordance with section 95A of the RMA</u> <p style="text-align: right;">PER</p>

Commented [MM232]: Consequential amendment to correct omission of outdoor living space standard within CCZ in response to matters raised by submissions S58.270, S58.216, and S58.319 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>3. <u>Activity status: Restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with CCZ-R6-1.b</u></p> <p><u>Matters of discretion are restricted to:</u></p> <p>1. <u>The matters of discretion of the infringed standard.</u></p> <p>Notification:</p> <ul style="list-style-type: none"> An application under this rule is precluded from being publicly notified in accordance with section 95A of the RMA
			<p>4. <u>Activity status: restricted discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>compliance is not achieved with CCZ-R6-1.c</u></p> <p><u>Matters of discretion are restricted to:</u></p> <p>1. <u>The matters of discretion of the infringed standard.</u></p>
			<p>4.5. <u>Activity status: Non-complying</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with CCZ-R6-1.a; and</u></p> <p>b. <u>The residential units are located along an Active Frontage identified on the planning maps.</u></p>
		CCZ-R7	<p>PER</p> <p><u>Erection, Construction and Development of Additions to Existing Buildings - Minor Structures</u></p> <p>1. <u>Activity status: Permitted</u></p> <p><u>Where:</u></p> <p>a. <u>The gross floor area of the additions is less than 5% of the gross floor area of the</u></p>

Commented [MM233]: Consequential amendment to correct omission of outdoor living space standard within CCZ in response to matters raised by submissions S58.270, S58.216, and S58.319 - Kianga Ora: Homes and Communities.

Commented [MM234]: Consequential amendment to correct omission of outdoor living space standard within CCZ in response to matters raised by submissions S58.270, S58.216, and S58.319 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p><u>existing building; and</u></p> <p>b. <u>Compliance is achieved with CCZ-S8 (Active Street Frontages).</u></p> <hr/> <p>2. Activity status: Restricted discretionary</p> <p>Where:</p> <p>a. <u>Compliance is not achieved with CCZ-R14-7-1.a; and</u></p> <p>b. <u>Compliance is achieved with</u></p> <ul style="list-style-type: none"> i. <u>CCZ-S1 (Fences and Standalone Walls);</u> ii. <u>CCZ-S2 (Setback);</u> iii. <u>CCZ-S3 (Location of Residential Units);</u> iv. <u>CCZ-S4 (Height in Relation to Boundary);</u> v. <u>CCZ-S5 (Noise and Ventilation);</u> vi. <u>CCZ-S6 (Water Supply, Stormwater and Wastewater);</u> vii. <u>CCZ-S7 (Landscaping and Screening); and</u> viii. <u>CCZ-S9 (Hydraulic neutrality).</u> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The extent to which the addition may adversely impact on the anticipated built form, character and amenity of the CCZ- City Centre Zone.</u> 2. <u>Whether the addition reflects the purpose scale and context of the CCZ- City Centre Zone.</u> 3. <u>The extent to which the addition aligns with the anticipated compact, high-density built environment anticipated for the CCZ- City Centre Zone and realises as much development capacity as possible, to maximise the benefits of intensification.</u> 4. <u>Whether the addition is well designed and contributes to the creation of safe and vibrant public spaces.</u>

Commented [MM235]: S58.397 - Kainga Ora: Homes and Communities.


IPI - PROPOSED AMENDMENTS						
#	Chapter	Change	Track Change			
			<p>5. <u>Whether the addition creates an active street frontage.</u></p> <p>6. <u>Whether the addition provides visual interest by using a variety of building forms, materials and colours.</u></p> <p>7. <u>Consistency with the City Centre Design Guide.</u></p> <p>Notification:</p> <ul style="list-style-type: none"> <u>An application under this rule is precluded from being publicly notified in accordance with section 95A of the RMA</u> <p>3. <u>Activity status: Discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with one or more of the standards under CCZ-R14-2.b</u></p>			
			<p>Controlled Activities</p> <table border="1"> <tr> <td> <p>CCZ-R8 <i>Policies</i> CCZ-P3, CCZ-P4</p> </td> <td> <p>Entertainment Activity-Churches</p> <p>Council may impose conditions on:</p> <p>(1) Avoiding, remedying or mitigating adverse effects on the business function of the area.</p> <p>(2) Location and nature of activities within the site.</p> <p>(3) Traffic generation, car parking, access arrangements and on site vehicle movements.</p> <p>(4) Bulk, location, design and appearance of buildings.</p> <p>(5) Hours of operation.</p> <p>(6) Landscaping and screening.</p> <p>(7) Noise.</p> </td> <td> <p>CON</p> </td> </tr> </table>	<p>CCZ-R8 <i>Policies</i> CCZ-P3, CCZ-P4</p>	<p>Entertainment Activity-Churches</p> <p>Council may impose conditions on:</p> <p>(1) Avoiding, remedying or mitigating adverse effects on the business function of the area.</p> <p>(2) Location and nature of activities within the site.</p> <p>(3) Traffic generation, car parking, access arrangements and on site vehicle movements.</p> <p>(4) Bulk, location, design and appearance of buildings.</p> <p>(5) Hours of operation.</p> <p>(6) Landscaping and screening.</p> <p>(7) Noise.</p>	<p>CON</p>
<p>CCZ-R8 <i>Policies</i> CCZ-P3, CCZ-P4</p>	<p>Entertainment Activity-Churches</p> <p>Council may impose conditions on:</p> <p>(1) Avoiding, remedying or mitigating adverse effects on the business function of the area.</p> <p>(2) Location and nature of activities within the site.</p> <p>(3) Traffic generation, car parking, access arrangements and on site vehicle movements.</p> <p>(4) Bulk, location, design and appearance of buildings.</p> <p>(5) Hours of operation.</p> <p>(6) Landscaping and screening.</p> <p>(7) Noise.</p>	<p>CON</p>				

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(8) Lighting.</p> <p>(9) Signage.</p> <p>(10) Provision of and effects on utilities and/or services.</p> <p>Financial contributions:</p> <p>1. Activity status: Permitted</p>
		<p>CCZ-R9 Policy CCZ-P4</p>	<p>CCZ-R9 Large Format Retail Establishment of a relocated building from another site</p> <p>Council may impose conditions on:</p> <p>(1) Reinstatement works to the condition and appearance of the building relating to:</p> <p>(a) Works to the exterior fabric of the building to repair, replace or renovate damaged, defective or substandard elements;</p> <p>(b) Painting and/or cleaning of the exterior fabric of the building if necessary;</p> <p>(c) Cladding or other means of enclosing open subfloor areas below the building;</p> <p>(d) *Alterations required to ensure that the reinstated exterior of any relocated building is not likely to detract from the amenity values of the surrounding area.</p> <p>(2) The timeframe for the work to be completed;</p> <p>(3) Landscaping, screening and boundary treatment;</p> <p>(4) Execution of a performance bond to provide security for exterior reinstatement works required as a condition of resource consent.</p> <p>(5) Provision of and effects on utilities and/or services.</p>

CON

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(6) Standard, construction and layout of vehicular access.</p> <p><u>Notes in respect of (4):</u></p> <ul style="list-style-type: none"> • A bond is not mandatory. It will only be required when Council considers it necessary in view of the scale and/or nature of exterior reinstatement works required. The requirement for a bond and its value will be determined in the context of the building assessment report submitted at resource consent stage. • The bond shall be executed at the time application is made for a building consent, and security shall be in the form of either money or a guarantee by an institution approved by Council as guarantor. <p>The bond shall be cancelled upon completion of exterior reinstatement works required in the conditions of the resource consent. The verification method for completion of these works shall be the issuing of a full or interim Code Compliance Certificate as defined in the Building Act. In the event that conditions relating to exterior reinstatement works are not complied with, the bond may be used in whole or in part to complete the works.</p> <p>1. Activity status: Permitted</p> <p><u>Where:</u></p> <p>a. Compliance is achieved with:</p> <ul style="list-style-type: none"> i. <u>CCZ-S7 (Landscaping and Screening); and</u> ii. <u>CCZ-S8 (Active Street Frontages).</u> <p>2. Activity status: Restricted Discretionary</p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with one or more of the standards under CCZ-R9-1.a.</u></p> <p><u>Matters of discretion are restricted to:</u></p>

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<div style="border: 1px solid black; padding: 5px;"> <ol style="list-style-type: none"> 1. <u>The matters of discretion of the infringed standard.</u> 2. <u>Consistency with the City Centre Design Guide.</u> <p>Notification:</p> <ul style="list-style-type: none"> • <u>An application under this rule is precluded from being publicly notified in accordance with section 95A of the RMA</u> </div> <p>Controlled activities – restrictions on notification Subject to sections 95A(2)(b), 95A(2)(c), 95A(4) and 95C of the Act, a resource consent application for a controlled activity is precluded from public notification under section 95A and, subject to section 95B(3), is precluded from limited notification under section 95B(2) of the Act.</p>		
	CCZ- City Centre Zone	Delete existing Standards for Permitted and Controlled Activities	<p>Standards for Permitted and Controlled Activities</p> <p>Note: The following standards for Permitted and Controlled Activities apply to all properties in the CCZ – City Centre Zone unless otherwise specified in the text of the standard in question.</p>		
		CCZ- City Centre Zone Introduce new Standards	<table border="1"> <tr> <td style="vertical-align: top;"> <p>CCZ-S1 Policies CCZ-P1, CCZ-P2, TP-P5</p> </td> <td style="vertical-align: top;"> <p>Access standards for land use activities</p> <ol style="list-style-type: none"> (1) All accessways and manoeuvring areas shall be formed and surfaced in accordance with the Code of Practice for Civil Engineering Works. Exemption – the requirement for accessways serving sites solely occupied by unstaffed utilities shall be that the accessway shall be surfaced with permanent all weather surfacing for a minimum length of 5m from the edge of the road carriageway seal. (2) All sites shall have practical vehicle access to car parking and loading spaces, in accordance with the Code of Practice for Civil Engineering Works. This requirement does not apply to sites solely occupied by unstaffed utilities, provided that vehicles associated with utilities shall not obstruct the footpath or create a traffic hazard on the road. (3) Adequate vehicular access shall be made available to the rear of every new building in accordance with the Code of Practice for Civil Engineering Works. (4) Vehicular access to a corner allotment shall be located no closer than 8m from the street corner. Where a site is located on an intersection of a primary or secondary arterial traffic route (as identified </td> </tr> </table>	<p>CCZ-S1 Policies CCZ-P1, CCZ-P2, TP-P5</p>	<p>Access standards for land use activities</p> <ol style="list-style-type: none"> (1) All accessways and manoeuvring areas shall be formed and surfaced in accordance with the Code of Practice for Civil Engineering Works. Exemption – the requirement for accessways serving sites solely occupied by unstaffed utilities shall be that the accessway shall be surfaced with permanent all weather surfacing for a minimum length of 5m from the edge of the road carriageway seal. (2) All sites shall have practical vehicle access to car parking and loading spaces, in accordance with the Code of Practice for Civil Engineering Works. This requirement does not apply to sites solely occupied by unstaffed utilities, provided that vehicles associated with utilities shall not obstruct the footpath or create a traffic hazard on the road. (3) Adequate vehicular access shall be made available to the rear of every new building in accordance with the Code of Practice for Civil Engineering Works. (4) Vehicular access to a corner allotment shall be located no closer than 8m from the street corner. Where a site is located on an intersection of a primary or secondary arterial traffic route (as identified
<p>CCZ-S1 Policies CCZ-P1, CCZ-P2, TP-P5</p>	<p>Access standards for land use activities</p> <ol style="list-style-type: none"> (1) All accessways and manoeuvring areas shall be formed and surfaced in accordance with the Code of Practice for Civil Engineering Works. Exemption – the requirement for accessways serving sites solely occupied by unstaffed utilities shall be that the accessway shall be surfaced with permanent all weather surfacing for a minimum length of 5m from the edge of the road carriageway seal. (2) All sites shall have practical vehicle access to car parking and loading spaces, in accordance with the Code of Practice for Civil Engineering Works. This requirement does not apply to sites solely occupied by unstaffed utilities, provided that vehicles associated with utilities shall not obstruct the footpath or create a traffic hazard on the road. (3) Adequate vehicular access shall be made available to the rear of every new building in accordance with the Code of Practice for Civil Engineering Works. (4) Vehicular access to a corner allotment shall be located no closer than 8m from the street corner. Where a site is located on an intersection of a primary or secondary arterial traffic route (as identified 				

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>in the Transport and Parking (TP) Chapter) the siting of the vehicular access shall be located as far as practicable from the corner of the street. The 8 metre setback shall be measured from where the two front boundaries of the site (refer to the definition of a corner allotment) join, or in accordance with the diagram below.</p>  <p>The diagram shows a corner allotment at a street intersection. A building is situated within the allotment, with a driveway leading to the road. The road reserve is shown on both sides of the road. A red hatched area indicates the setback zone, which is 8 meters wide and measured from the corner of the road reserve. The setback is shown as a red area extending 8m from the corner of the road reserve.</p> <ol style="list-style-type: none"> (1) Where a corner allotment is located at an intersection of a national, primary or secondary arterial traffic route, as identified in the Transport and Parking (TP) Chapter, no building, fence or other structure is to be erected and no vegetation allowed to grow so as to obstruct a traffic sight line. (2) At the intersection of a road or rail level crossing, no building, fence or other obstructions which block sight lines for trains shall be erected, placed or grown in the hatched area marked in TP-Diagram 1 in the Transport and Parking (TP) Chapter. (3) Land use activities with direct access to a State Highway shall comply with the access and visibility standards set out in TP-Diagrams 2 to 9 in the Transport and Parking (TP) Chapter. <div style="border: 1px solid black; padding: 5px; margin-top: 10px;"> <ol style="list-style-type: none"> 1. Any fence or standalone wall along a side or rear boundary which adjoins a site zoned High Density Residential, General Residential, or Open Space and Recreation must not exceed 2m in height. </div>
			<p>CCZ-S2 Policies CCZ-P3,</p>

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			<p><i>CCZ-P4</i></p> <p>Properties within the CCZ – City Centre Zone are exempt from all setback requirements, except where sites adjoins a High Density Residential Zone, General Residential Zone, or Open Space Zone, then the following Setback requirements shall standard applies along the adjoining boundary:</p> <p>(a) Side and rear boundaries adjoining a General Residential or Open Space Zone – 3m</p> <p>1. Buildings must be set back from the relevant boundary by the minimum depth listed in the yards table below:</p> <table border="1"> <thead> <tr> <th>Yard</th> <th>Minimum depth</th> </tr> </thead> <tbody> <tr> <td>Side</td> <td>1 metre</td> </tr> <tr> <td>Rear</td> <td>1 metre</td> </tr> </tbody> </table> <p>2. This standard does not apply to site boundaries where there is an existing common wall between 2 buildings on adjacent sites or where a common wall is proposed.</p> <p>3. This standard does not apply to:</p> <ol style="list-style-type: none"> Accessory buildings less than 2m in height. <u>Fences and standalone walls.</u> 	Yard	Minimum depth	Side	1 metre	Rear	1 metre
Yard	Minimum depth								
Side	1 metre								
Rear	1 metre								
			<p>CCZ-S3 <i>Policy</i> <i>CCZ-P4</i></p> <p>Building height</p> <p>The maximum height above ground level of any building in the following areas shall not exceed:</p> <ol style="list-style-type: none"> CCZ – City Centre Zone (except for northern side of Main Street) ————— 40m CCZ – City Centre Zone (northern side of Main Street only) ————— 20m <p>1. All residential units must be located above ground floor level.</p>						
			<p>CCZ-S4 <i>Policies</i> <i>GRZ-P4,</i> <i>CCZ-P3</i></p> <p>For Where the side or rear boundary of a sites within the CCZ – City Centre Zone, all buildings shall comply with the height control planes defined in GRZ-S8 along all boundaries adjoining a High Density Residential Zone, General Residential Zone, or Open Space and Recreation Zone, or along all boundaries</p>						

IPI - PROPOSED AMENDMENTS															
#	Chapter	Change	Track Change												
			<p><i>CCZ-P4</i></p> <p>which face and are within 25 metres of a site within the General Residential or Open Space Zone the following Height in Relation to Boundary standard applies:</p> <p>1. Buildings must not project beyond a 60° recession plane measured from a point 4 metres vertically above ground level along all boundaries. Where the boundary forms part of a legal right of way, entrance strip, access site, or pedestrian access way, the height in relation to boundary applies from the farthest boundary of that legal right of way, entrance strip, access site, or pedestrian access way.</p> <p>This standard does not apply to:</p> <ol style="list-style-type: none"> A boundary with a road. Existing or proposed internal boundaries within a site. Site boundaries where there is an existing common wall between 2 buildings on adjacent sites or where a common wall is proposed. 												
			<p>CCZ-S5 <i>Policies CCZ-P2, CCZ-P3</i></p> <p>Loading provisions</p> <p>1. The number of loading spaces needed for any building in the CCZ – City Centre Zone shall be as follows:</p> <table border="1"> <thead> <tr> <th></th> <th>Floor area</th> <th>Loading spaces required</th> </tr> </thead> <tbody> <tr> <td>(a)</td> <td>Between 100m² and 1000m²</td> <td>1 space</td> </tr> <tr> <td>(b)</td> <td>Between 1001m² and 2000m²</td> <td>2 spaces</td> </tr> <tr> <td>(c)</td> <td>More than 2000m²</td> <td>2 spaces or 4 spaces if the building is used as a retail store</td> </tr> </tbody> </table> <p>Notes</p> <ul style="list-style-type: none"> Every loading space requires a manoeuvring space for ingress and egress. The extent of the manoeuvring space is to be in accordance with the Code of Practice for Civil Engineering Works. Loading areas must be kept clear and must be available at all times for vehicles used in association with the building during which time the building is being used for the activity to which the car parking and loading spaces relate. Direct access to each loading space may be allowed from any vested service lane 		Floor area	Loading spaces required	(a)	Between 100m ² and 1000m ²	1 space	(b)	Between 1001m ² and 2000m ²	2 spaces	(c)	More than 2000m ²	2 spaces or 4 spaces if the building is used as a retail store
	Floor area	Loading spaces required													
(a)	Between 100m ² and 1000m ²	1 space													
(b)	Between 1001m ² and 2000m ²	2 spaces													
(c)	More than 2000m ²	2 spaces or 4 spaces if the building is used as a retail store													

IPI - PROPOSED AMENDMENTS																							
#	Chapter	Change	Track Change																				
			<ul style="list-style-type: none"> All loading spaces are required to be formed and surfaced in accordance with the Code of Practice for Civil Engineering Works. <table border="1"> <tr> <td colspan="2">Noise and Ventilation</td> </tr> <tr> <td> 1. All residential units must meet the following standards: <ol style="list-style-type: none"> All habitable rooms must be designed and constructed to meet internal sound insulation levels achieving $DnT,w+Ctr >30dB$ with an acoustic design certificate signed by a qualified acoustic engineer stating compliance will be achieved; and All habitable rooms must have a positive supplementary source of fresh air ducted from outside. The supplementary source of air is to achieve a minimum of 7.5 litres per second per person. </td> <td> Matters of discretion are restricted to: <ol style="list-style-type: none"> Any potential reverse sensitivity effects on the continued operation of non- residential activities. The amenity for the occupiers of the residential units. </td> </tr> </table> <table border="1"> <tr> <td colspan="2">CCZ-S6 Policies NATC-P1</td> </tr> <tr> <td colspan="2">Water Supply, Stormwater and Wastewater</td> </tr> <tr> <td> 1. All activities shall comply with the water supply, stormwater and wastewater standards in the Code of Practice for Civil Engineering Works. </td> <td> Matters of discretion are restricted to: <ol style="list-style-type: none"> Methods to avoid, remedy or mitigate adverse effects. </td> </tr> </table> <table border="1"> <tr> <td colspan="2">CCZ-S7 Policies CCZ-P3 CCZ-P5</td> </tr> <tr> <td colspan="2">Screening</td> </tr> <tr> <td colspan="2">(1) Sites adjoining a Residential or Open Space Zone shall be fenced on the common boundary by a solid 2m high fence.</td> </tr> <tr> <td colspan="2">Service Areas, Outdoor Storage Areas and Parking Areas</td> </tr> <tr> <td> 1. Any on-site service areas, including rubbish collection areas, and areas for the outdoor storage of goods or materials must, without </td> <td> Matters of discretion are restricted to: <ol style="list-style-type: none"> Any adverse effects on the streetscape. </td> </tr> </table>	Noise and Ventilation		1. All residential units must meet the following standards: <ol style="list-style-type: none"> All habitable rooms must be designed and constructed to meet internal sound insulation levels achieving $DnT,w+Ctr >30dB$ with an acoustic design certificate signed by a qualified acoustic engineer stating compliance will be achieved; and All habitable rooms must have a positive supplementary source of fresh air ducted from outside. The supplementary source of air is to achieve a minimum of 7.5 litres per second per person. 	Matters of discretion are restricted to: <ol style="list-style-type: none"> Any potential reverse sensitivity effects on the continued operation of non- residential activities. The amenity for the occupiers of the residential units. 	CCZ-S6 Policies NATC-P1		Water Supply, Stormwater and Wastewater		1. All activities shall comply with the water supply, stormwater and wastewater standards in the Code of Practice for Civil Engineering Works.	Matters of discretion are restricted to: <ol style="list-style-type: none"> Methods to avoid, remedy or mitigate adverse effects. 	CCZ-S7 Policies CCZ-P3 CCZ-P5		Screening		(1) Sites adjoining a Residential or Open Space Zone shall be fenced on the common boundary by a solid 2m high fence.		Service Areas, Outdoor Storage Areas and Parking Areas		1. Any on-site service areas, including rubbish collection areas, and areas for the outdoor storage of goods or materials must, without	Matters of discretion are restricted to: <ol style="list-style-type: none"> Any adverse effects on the streetscape.
Noise and Ventilation																							
1. All residential units must meet the following standards: <ol style="list-style-type: none"> All habitable rooms must be designed and constructed to meet internal sound insulation levels achieving $DnT,w+Ctr >30dB$ with an acoustic design certificate signed by a qualified acoustic engineer stating compliance will be achieved; and All habitable rooms must have a positive supplementary source of fresh air ducted from outside. The supplementary source of air is to achieve a minimum of 7.5 litres per second per person. 	Matters of discretion are restricted to: <ol style="list-style-type: none"> Any potential reverse sensitivity effects on the continued operation of non- residential activities. The amenity for the occupiers of the residential units. 																						
CCZ-S6 Policies NATC-P1																							
Water Supply, Stormwater and Wastewater																							
1. All activities shall comply with the water supply, stormwater and wastewater standards in the Code of Practice for Civil Engineering Works.	Matters of discretion are restricted to: <ol style="list-style-type: none"> Methods to avoid, remedy or mitigate adverse effects. 																						
CCZ-S7 Policies CCZ-P3 CCZ-P5																							
Screening																							
(1) Sites adjoining a Residential or Open Space Zone shall be fenced on the common boundary by a solid 2m high fence.																							
Service Areas, Outdoor Storage Areas and Parking Areas																							
1. Any on-site service areas, including rubbish collection areas, and areas for the outdoor storage of goods or materials must, without	Matters of discretion are restricted to: <ol style="list-style-type: none"> Any adverse effects on the streetscape. 																						

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
			<p><u>preventing the provision of an entry point to the site, be adequately screened by a fence or landscaping where they are visible from any:</u></p> <ul style="list-style-type: none"> a. <u>Public road;</u> b. <u>Other public space; and</u> c. <u>Directly adjoining site zoned Residential or Open Space and Recreation.</u> <p>2. <u>Any on-site parking area must:</u></p> <ul style="list-style-type: none"> a. <u>Be adequately screened by a fence or landscaping from any directly adjoining site zoned Residential or Open Space and Recreation.</u> b. <u>Where located along a street edge, provide a landscaping strip that extends at least 1.5m from the boundary with the road and comprise a mix of trees, shrubs and ground cover plants, without preventing the provision of an entry point to the site. This does not apply to individual parking spaces for residential development, if provided.</u> <p>3. <u>Along active frontages identified on the planning maps any on-site service areas, including rubbish collection areas, and areas for the storage of goods or materials and any on-site ground level car parking must be:</u></p> <ul style="list-style-type: none"> a. <u>Located within or at the rear of the building that they serve; and</u> b. <u>Screened from view by a fence or landscaping where they are visible from any public road, public space or directly adjoining</u> <ul style="list-style-type: none"> 2. <u>The visual amenity of adjoining Residential and Open Space and Recreation zoned sites including shading.</u> 3. <u>The service, storage and parking needs of the activity.</u> 4. <u>The size and location of service, storage and any parking areas.</u> 5. <u>Consistency with the City Centre Design Guide.</u>

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change						
			<table border="1"> <tr> <td data-bbox="533 371 685 459"></td> <td data-bbox="685 371 1668 459"> <p><u>site zoned Residential or Open Space and Recreation.</u></p> </td> </tr> <tr> <td data-bbox="533 459 685 1230"> <p>CCZ-S8 <i>Policies</i> <i>CCZ-P2,</i> <i>CCZ-P3,</i> <i>CCZ-P4</i></p> </td> <td data-bbox="685 459 1668 1230"> <p>Landscaping</p> <p>(1) If a building is required to be set back from the road boundary, the set back area between the road boundary and the building shall be landscaped unless it is used for access or car parking purposes. If car parking or accessways are provided between the road boundary and the building, a landscape strip with a minimum width of 0.6m shall be provided within the site along the road boundary.</p> <p>(2) Where a site adjoins a Residential, Rural, Open Space or Special Activity Zone (excluding road boundaries) or is within 25m of a General Residential or Open Space Zone, a landscape buffer with a minimum width of 0.6m shall be provided within the site between the zone boundary and the buildings.</p> <p>Active Frontages</p> <table border="1"> <tr> <td data-bbox="685 786 1171 1230"> <p>1. Along active frontages identified on the planning maps:</p> <p>a. <u>All new buildings and ground level additions or alterations to existing buildings must be built up to and oriented towards the road or public space boundary;</u></p> <p>b. <u>A veranda must be provided that:</u></p> <p>i. <u>Extends along the entire length of the building frontage;</u></p> <p>ii. <u>Provides continuous shelter with any adjoining veranda; and</u></p> <p>iii. <u>Has a minimum setback of 500mm from any kerb face;</u></p> </td> <td data-bbox="1171 786 1668 1230"> <p>Matters of discretion are restricted to:</p> <p>1. <u>The effects on the amenity and quality of the streetscape.</u></p> <p>2. <u>The design and appearance of the street frontage.</u></p> <p>3. <u>The ability to reuse and adapt the building for a variety of activities.</u></p> <p>4. <u>Consistency with the City Centre Design Guide.</u></p> </td> </tr> </table> </td> </tr> </table>		<p><u>site zoned Residential or Open Space and Recreation.</u></p>	<p>CCZ-S8 <i>Policies</i> <i>CCZ-P2,</i> <i>CCZ-P3,</i> <i>CCZ-P4</i></p>	<p>Landscaping</p> <p>(1) If a building is required to be set back from the road boundary, the set back area between the road boundary and the building shall be landscaped unless it is used for access or car parking purposes. If car parking or accessways are provided between the road boundary and the building, a landscape strip with a minimum width of 0.6m shall be provided within the site along the road boundary.</p> <p>(2) Where a site adjoins a Residential, Rural, Open Space or Special Activity Zone (excluding road boundaries) or is within 25m of a General Residential or Open Space Zone, a landscape buffer with a minimum width of 0.6m shall be provided within the site between the zone boundary and the buildings.</p> <p>Active Frontages</p> <table border="1"> <tr> <td data-bbox="685 786 1171 1230"> <p>1. Along active frontages identified on the planning maps:</p> <p>a. <u>All new buildings and ground level additions or alterations to existing buildings must be built up to and oriented towards the road or public space boundary;</u></p> <p>b. <u>A veranda must be provided that:</u></p> <p>i. <u>Extends along the entire length of the building frontage;</u></p> <p>ii. <u>Provides continuous shelter with any adjoining veranda; and</u></p> <p>iii. <u>Has a minimum setback of 500mm from any kerb face;</u></p> </td> <td data-bbox="1171 786 1668 1230"> <p>Matters of discretion are restricted to:</p> <p>1. <u>The effects on the amenity and quality of the streetscape.</u></p> <p>2. <u>The design and appearance of the street frontage.</u></p> <p>3. <u>The ability to reuse and adapt the building for a variety of activities.</u></p> <p>4. <u>Consistency with the City Centre Design Guide.</u></p> </td> </tr> </table>	<p>1. Along active frontages identified on the planning maps:</p> <p>a. <u>All new buildings and ground level additions or alterations to existing buildings must be built up to and oriented towards the road or public space boundary;</u></p> <p>b. <u>A veranda must be provided that:</u></p> <p>i. <u>Extends along the entire length of the building frontage;</u></p> <p>ii. <u>Provides continuous shelter with any adjoining veranda; and</u></p> <p>iii. <u>Has a minimum setback of 500mm from any kerb face;</u></p>	<p>Matters of discretion are restricted to:</p> <p>1. <u>The effects on the amenity and quality of the streetscape.</u></p> <p>2. <u>The design and appearance of the street frontage.</u></p> <p>3. <u>The ability to reuse and adapt the building for a variety of activities.</u></p> <p>4. <u>Consistency with the City Centre Design Guide.</u></p>
	<p><u>site zoned Residential or Open Space and Recreation.</u></p>								
<p>CCZ-S8 <i>Policies</i> <i>CCZ-P2,</i> <i>CCZ-P3,</i> <i>CCZ-P4</i></p>	<p>Landscaping</p> <p>(1) If a building is required to be set back from the road boundary, the set back area between the road boundary and the building shall be landscaped unless it is used for access or car parking purposes. If car parking or accessways are provided between the road boundary and the building, a landscape strip with a minimum width of 0.6m shall be provided within the site along the road boundary.</p> <p>(2) Where a site adjoins a Residential, Rural, Open Space or Special Activity Zone (excluding road boundaries) or is within 25m of a General Residential or Open Space Zone, a landscape buffer with a minimum width of 0.6m shall be provided within the site between the zone boundary and the buildings.</p> <p>Active Frontages</p> <table border="1"> <tr> <td data-bbox="685 786 1171 1230"> <p>1. Along active frontages identified on the planning maps:</p> <p>a. <u>All new buildings and ground level additions or alterations to existing buildings must be built up to and oriented towards the road or public space boundary;</u></p> <p>b. <u>A veranda must be provided that:</u></p> <p>i. <u>Extends along the entire length of the building frontage;</u></p> <p>ii. <u>Provides continuous shelter with any adjoining veranda; and</u></p> <p>iii. <u>Has a minimum setback of 500mm from any kerb face;</u></p> </td> <td data-bbox="1171 786 1668 1230"> <p>Matters of discretion are restricted to:</p> <p>1. <u>The effects on the amenity and quality of the streetscape.</u></p> <p>2. <u>The design and appearance of the street frontage.</u></p> <p>3. <u>The ability to reuse and adapt the building for a variety of activities.</u></p> <p>4. <u>Consistency with the City Centre Design Guide.</u></p> </td> </tr> </table>	<p>1. Along active frontages identified on the planning maps:</p> <p>a. <u>All new buildings and ground level additions or alterations to existing buildings must be built up to and oriented towards the road or public space boundary;</u></p> <p>b. <u>A veranda must be provided that:</u></p> <p>i. <u>Extends along the entire length of the building frontage;</u></p> <p>ii. <u>Provides continuous shelter with any adjoining veranda; and</u></p> <p>iii. <u>Has a minimum setback of 500mm from any kerb face;</u></p>	<p>Matters of discretion are restricted to:</p> <p>1. <u>The effects on the amenity and quality of the streetscape.</u></p> <p>2. <u>The design and appearance of the street frontage.</u></p> <p>3. <u>The ability to reuse and adapt the building for a variety of activities.</u></p> <p>4. <u>Consistency with the City Centre Design Guide.</u></p>						
<p>1. Along active frontages identified on the planning maps:</p> <p>a. <u>All new buildings and ground level additions or alterations to existing buildings must be built up to and oriented towards the road or public space boundary;</u></p> <p>b. <u>A veranda must be provided that:</u></p> <p>i. <u>Extends along the entire length of the building frontage;</u></p> <p>ii. <u>Provides continuous shelter with any adjoining veranda; and</u></p> <p>iii. <u>Has a minimum setback of 500mm from any kerb face;</u></p>	<p>Matters of discretion are restricted to:</p> <p>1. <u>The effects on the amenity and quality of the streetscape.</u></p> <p>2. <u>The design and appearance of the street frontage.</u></p> <p>3. <u>The ability to reuse and adapt the building for a variety of activities.</u></p> <p>4. <u>Consistency with the City Centre Design Guide.</u></p>								

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<p>c. <u>At least 55% of the ground floor building frontage must be display windows or transparent glazing; and</u></p> <p>d. <u>The principal public entrance to the building must be located on the front boundary.</u></p>		
		<p>CCZ-S9 <i>Policies</i> <i>CCZ-P2,</i> <i>CCZ-P4</i></p>	<p>Hydraulic neutrality</p> <table border="1"> <tr> <td> <p>New buildings and development must be designed to achieve hydraulic neutrality ensure that the stormwater runoff from all new impermeable surfaces will be disposed of or stored on site and released at a rate that does not exceed the peak stormwater runoff when compared to the pre-development situation for the 10% and 1% rainfall Annual Exceedance Probability event.</p> </td> <td> <p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Methods to avoid, remedy or mitigate any adverse effects resulting from any increase in pre-development peak stormwater runoff.</u> 2. <u>Cumulative effects.</u> </td> </tr> </table> <p>Requirements for buildings on sites adjoining Main Street</p> <ol style="list-style-type: none"> (1) All buildings on sites adjoining Main Street shall provide continuous building frontage onto the boundary with Main Street. (2) All yards, outdoor storage, outdoor retail areas, or other unbuilt areas on a site shall not be located adjoining the boundary with Main Street. (3) All buildings fronting Main Street shall ensure that at least 50% of the ground floor frontage is glazed. (4) For sites fronting onto Main Street, all vehicle access or egress shall be via alternative streets or service lanes or other accesses which do not connect on to Main Street. 	<p>New buildings and development must be designed to achieve hydraulic neutrality ensure that the stormwater runoff from all new impermeable surfaces will be disposed of or stored on site and released at a rate that does not exceed the peak stormwater runoff when compared to the pre-development situation for the 10% and 1% rainfall Annual Exceedance Probability event.</p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Methods to avoid, remedy or mitigate any adverse effects resulting from any increase in pre-development peak stormwater runoff.</u> 2. <u>Cumulative effects.</u>
<p>New buildings and development must be designed to achieve hydraulic neutrality ensure that the stormwater runoff from all new impermeable surfaces will be disposed of or stored on site and released at a rate that does not exceed the peak stormwater runoff when compared to the pre-development situation for the 10% and 1% rainfall Annual Exceedance Probability event.</p>	<p>Matters of discretion are restricted to:</p> <ol style="list-style-type: none"> 1. <u>Methods to avoid, remedy or mitigate any adverse effects resulting from any increase in pre-development peak stormwater runoff.</u> 2. <u>Cumulative effects.</u> 				
		<p>CCZ-S10 <i>Policies</i> <i>CCZ-P2,</i> <i>CCZ-P4</i></p>	<p>Main Street verandahs</p> <ol style="list-style-type: none"> (1) Buildings fronting Main Street shall provide verandahs for pedestrian cover, meeting the following standards: 		

Commented [MM236]: S58.409 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change																
			<p>(a) The lowest part of a verandah, not including signage, shall be at least 2.9m above the footpath.</p> <p>(b) The verandah shall extend for the full length of the frontage of the site.</p> <p>(c) The verandah shall cover the full width of the footpath less 500mm.</p> <p>(d) Any new or refurbished verandah shall provide in its design for a visual continuity between any existing adjoining verandah(s) and the proposed verandah.</p> <table border="1"> <thead> <tr> <th>CCZ-S10</th> <th>Outdoor Living Space</th> </tr> </thead> <tbody> <tr> <td> <p>1. <u>Each residential unit, including any dual key unit, must be provided with either a private outdoor living space or access to a communal outdoor living space;</u></p> <p>2. <u>Where private outdoor living space is provided it must be:</u></p> <ul style="list-style-type: none"> i <u>For the exclusive use of residents;</u> ii <u>Directly accessible from a habitable room;</u> iii <u>A single contiguous space; and</u> iv <u>Of the minimum area and dimension specified in the table below;</u> <p>3. <u>Where communal outdoor living space is provided it does not need to be in a single continuous space, but it must be:</u></p> <ul style="list-style-type: none"> i <u>Accessible from the residential units it serves;</u> ii <u>Of the minimum area and dimension specified in the table below; and</u> iii <u>Free of buildings, parking spaces, and servicing and manoeuvring areas.</u> <table border="1"> <thead> <tr> <th><u>Living Space Type</u></th> <th><u>Minimum area</u></th> <th><u>Minimum dimension</u></th> </tr> </thead> <tbody> <tr> <td><u>1. Private</u></td> <td></td> <td></td> </tr> <tr> <td>i <u>Studio unit & 1 bedroom unit</u></td> <td><u>5m²</u></td> <td><u>1.8m</u></td> </tr> <tr> <td>ii <u>2+ bedroom unit</u></td> <td><u>8m²</u></td> <td><u>1.8m</u></td> </tr> </tbody> </table> </td> <td> <p><u>Matters of discretion are restricted to:</u></p> <ul style="list-style-type: none"> 1. <u>Whether adequate useable space is provided to accommodate outdoor activities.</u> 2. <u>Whether there are topographical or other site constraints that make compliance with the standard impractical.</u> 3. <u>The proximity of the residential unit to accessible public open space.</u> </td> </tr> </tbody> </table>	CCZ-S10	Outdoor Living Space	<p>1. <u>Each residential unit, including any dual key unit, must be provided with either a private outdoor living space or access to a communal outdoor living space;</u></p> <p>2. <u>Where private outdoor living space is provided it must be:</u></p> <ul style="list-style-type: none"> i <u>For the exclusive use of residents;</u> ii <u>Directly accessible from a habitable room;</u> iii <u>A single contiguous space; and</u> iv <u>Of the minimum area and dimension specified in the table below;</u> <p>3. <u>Where communal outdoor living space is provided it does not need to be in a single continuous space, but it must be:</u></p> <ul style="list-style-type: none"> i <u>Accessible from the residential units it serves;</u> ii <u>Of the minimum area and dimension specified in the table below; and</u> iii <u>Free of buildings, parking spaces, and servicing and manoeuvring areas.</u> <table border="1"> <thead> <tr> <th><u>Living Space Type</u></th> <th><u>Minimum area</u></th> <th><u>Minimum dimension</u></th> </tr> </thead> <tbody> <tr> <td><u>1. Private</u></td> <td></td> <td></td> </tr> <tr> <td>i <u>Studio unit & 1 bedroom unit</u></td> <td><u>5m²</u></td> <td><u>1.8m</u></td> </tr> <tr> <td>ii <u>2+ bedroom unit</u></td> <td><u>8m²</u></td> <td><u>1.8m</u></td> </tr> </tbody> </table>	<u>Living Space Type</u>	<u>Minimum area</u>	<u>Minimum dimension</u>	<u>1. Private</u>			i <u>Studio unit & 1 bedroom unit</u>	<u>5m²</u>	<u>1.8m</u>	ii <u>2+ bedroom unit</u>	<u>8m²</u>	<u>1.8m</u>	<p><u>Matters of discretion are restricted to:</u></p> <ul style="list-style-type: none"> 1. <u>Whether adequate useable space is provided to accommodate outdoor activities.</u> 2. <u>Whether there are topographical or other site constraints that make compliance with the standard impractical.</u> 3. <u>The proximity of the residential unit to accessible public open space.</u>
CCZ-S10	Outdoor Living Space																		
<p>1. <u>Each residential unit, including any dual key unit, must be provided with either a private outdoor living space or access to a communal outdoor living space;</u></p> <p>2. <u>Where private outdoor living space is provided it must be:</u></p> <ul style="list-style-type: none"> i <u>For the exclusive use of residents;</u> ii <u>Directly accessible from a habitable room;</u> iii <u>A single contiguous space; and</u> iv <u>Of the minimum area and dimension specified in the table below;</u> <p>3. <u>Where communal outdoor living space is provided it does not need to be in a single continuous space, but it must be:</u></p> <ul style="list-style-type: none"> i <u>Accessible from the residential units it serves;</u> ii <u>Of the minimum area and dimension specified in the table below; and</u> iii <u>Free of buildings, parking spaces, and servicing and manoeuvring areas.</u> <table border="1"> <thead> <tr> <th><u>Living Space Type</u></th> <th><u>Minimum area</u></th> <th><u>Minimum dimension</u></th> </tr> </thead> <tbody> <tr> <td><u>1. Private</u></td> <td></td> <td></td> </tr> <tr> <td>i <u>Studio unit & 1 bedroom unit</u></td> <td><u>5m²</u></td> <td><u>1.8m</u></td> </tr> <tr> <td>ii <u>2+ bedroom unit</u></td> <td><u>8m²</u></td> <td><u>1.8m</u></td> </tr> </tbody> </table>	<u>Living Space Type</u>	<u>Minimum area</u>	<u>Minimum dimension</u>	<u>1. Private</u>			i <u>Studio unit & 1 bedroom unit</u>	<u>5m²</u>	<u>1.8m</u>	ii <u>2+ bedroom unit</u>	<u>8m²</u>	<u>1.8m</u>	<p><u>Matters of discretion are restricted to:</u></p> <ul style="list-style-type: none"> 1. <u>Whether adequate useable space is provided to accommodate outdoor activities.</u> 2. <u>Whether there are topographical or other site constraints that make compliance with the standard impractical.</u> 3. <u>The proximity of the residential unit to accessible public open space.</u> 						
<u>Living Space Type</u>	<u>Minimum area</u>	<u>Minimum dimension</u>																	
<u>1. Private</u>																			
i <u>Studio unit & 1 bedroom unit</u>	<u>5m²</u>	<u>1.8m</u>																	
ii <u>2+ bedroom unit</u>	<u>8m²</u>	<u>1.8m</u>																	

Commented [MM237]: Consequential amendment to correct omission of outdoor living space standard within CCZ in response to matters raised by submissions S58.270, S58.216, and S58.319 - Kianga Ora: Homes and Communities.

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			<table border="1"> <tr> <td><u>2. Communal</u></td> <td></td> <td></td> </tr> <tr> <td><u>For every 5 units</u></td> <td><u>10m² (per residential unit)</u></td> <td><u>8m diameter</u></td> </tr> </table>	<u>2. Communal</u>			<u>For every 5 units</u>	<u>10m² (per residential unit)</u>	<u>8m diameter</u>
<u>2. Communal</u>									
<u>For every 5 units</u>	<u>10m² (per residential unit)</u>	<u>8m diameter</u>							
			<p>CCZ-S11 <i>Policies</i> CCZ-P2, CCZ-P3</p> <p>Car parking areas</p> <p>(1) Any car parking provided on a site shall be primarily for the purposes of meeting the car parking demand generated by the use of that site.</p>						
			<p>CCZ-S12 <i>Policy</i> CCZ-P3</p> <p>Hours of operation for activities adjoining the General Residential Zone</p> <p>(1) Any activity which is open to the public (including licenced premises, places of assembly, shops, restaurants and takeaway food outlets) and adjoins a site which is zoned Residential, shall not be open to the public outside the hours of 7am – 11pm Sunday to Thursday (inclusive) and until 1am the following day on Friday, Saturday, Christmas Eve and New Year's Eve.</p>						
	CCZ- City Centre Zone	Delete existing Restricted Discretionary Activities Table	<p>Restricted Discretionary Activities</p> <p>CCZ-R10 <i>Policies</i> CCZ-P2, CCZ-P3, CCZ-P4</p> <p>Food and Beverage Activity Buildings which do not comply with permitted or controlled activity standards</p> <p>Buildings which do not comply with the standards for permitted and controlled activities.</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <p>(1) Height, boundary setbacks and sunlight access.</p> <p>(2) Provision of and effects on utilities and/or services.</p> <p>(3) Landscaping and screening.</p> <p>(4) Standard, construction and layout of vehicular access.</p> <p>(5) Car parking.</p> <p>(6) Effects on adjoining residential properties.</p> <p>(7) Effects on the amenity of the surrounding area.</p> <p style="text-align: right;">RDIS</p>						

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(8) Requirements for buildings on sites adjoining Main Street.</p> <p>Financial contributions.</p> <p>1. Activity status: Permitted</p>
			<p>CCZ-R11 <i>Policy</i> <i>TP-P3</i></p> <p>Healthcare Activity Activities otherwise permitted or controlled which do not comply with the access standards in CCZ-S1</p> <p>Council will restrict its discretion to, and may impose conditions on:</p> <p>(1) The extent to which the activity will adversely affect traffic and pedestrian safety.</p> <p>The extent to which the activity will adversely affect the efficient functioning of the roading network.</p> <p>1. Activity status: Permitted</p> <p style="text-align: right;">RDIS</p>
	CCZ- City Centre Zone	Amend existing Discretionary Activities table	<p>Discretionary Activities</p> <p>CCZ-R12</p> <p>Demolition Warehouses</p> <p>1. Activity status: Permitted</p> <p>Note: Prior to demolition commencing, confirm whether rules in chapter HH-Historic Heritage apply.</p> <p style="text-align: right;">DIS</p> <p>CCZ-R13</p> <p>Redevelopment, Alteration and Repair of Existing Buildings Service stations and motor vehicle garages</p> <p>1. Activity status: Permitted</p> <p>Where:</p> <p>a. The external building form (floor area and height) of the existing building remains unchanged; and</p> <p style="text-align: right;">DIS</p>

Commented [MM238]: S72.12 - Te Rūnanga o Toa Rangatira Inc

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
			<p data-bbox="772 387 1355 411">b. <u>Compliance is achieved with CCZ-S8 (Active Street Frontages).</u></p> <p data-bbox="723 440 1115 464">2. Activity status: <u>Restricted discretionary</u></p> <p data-bbox="772 480 837 504"><u>Where:</u></p> <p data-bbox="772 520 1386 544">a. <u>Compliance is not achieved with CCZ-R13-1.a or CCZ-R13-1.b; and</u></p> <p data-bbox="772 560 1066 584">b. <u>Compliance is achieved with</u></p> <ul style="list-style-type: none"> <li data-bbox="819 600 1200 624">i. <u>CCZ-S1 (Fences and Standalone Walls);</u> <li data-bbox="819 639 1021 663">ii. <u>CCZ-S2 (Setback);</u> <li data-bbox="819 679 1200 703">iii. <u>CCZ-S3 (Location of Residential Units);</u> <li data-bbox="819 719 1223 743">iv. <u>CCZ-S4 (Height in Relation to Boundary);</u> <li data-bbox="819 759 1133 783">v. <u>CCZ-S5 (Noise and Ventilation);</u> <li data-bbox="819 799 1368 823">vi. <u>CCZ-S6 (Water Supply, Stormwater and Wastewater); and</u> <li data-bbox="819 839 1178 863">vii. <u>CCZ-S7 (Landscaping and Screening).</u> <p data-bbox="772 871 1104 895"><u>Matters of discretion are restricted to:</u></p> <ul style="list-style-type: none"> <li data-bbox="772 911 1559 959">1. <u>The extent to which the redevelopment, alteration or repair may adversely impact on the anticipated built character and amenity of the City Centre Zone.</u> <li data-bbox="772 975 1581 1023">2. <u>Whether the redevelopment, alteration or repair reflects the purpose scale and context of the City Centre Zone.</u> <li data-bbox="772 1038 1581 1142">3. <u>The extent to which the redevelopment, alteration or repair aligns with the anticipated compact, high-density built environment anticipated for the City Centre Zone and realises as much development capacity as possible, to maximise the benefits of intensification.</u> <li data-bbox="772 1158 1581 1206">4. <u>Whether the redevelopment, alteration or repair is well designed and contributes to the creation of safe and vibrant public spaces.</u> <li data-bbox="772 1222 1536 1246">5. <u>Whether the redevelopment, alteration or repair creates an active street frontage.</u> <li data-bbox="772 1262 1536 1286">6. <u>Whether the redevelopment, alteration or repair provides visual interest by using a</u>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>variety of building forms, materials and colours.</p> <p>7. <u>Consistency with the City Centre Design Guide.</u></p> <p>Notification:</p> <ul style="list-style-type: none"> An application under this rule is precluded from being publicly notified in accordance with <u>section 95A of the RMA</u> <p>3. <u>Activity status: Discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with one or more of the standards under CCZ-R13-2.b.</u></p>
		CCZ-R14	<p>Public car parks</p> <p>DIS</p>
		CCZ-R15	<p>Educational Facility, and Community Correction Activity The sale and hire of motor vehicles, boats, caravans and motor vehicle spare part</p> <p>1. <u>Activity status: Permitted</u></p> <p>DIS</p>
		CCZ-R16	<p>New Buildings and Structures Residential accommodation at ground floor level</p> <p>1. <u>Activity status: Restricted Discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is achieved with:</u></p> <ol style="list-style-type: none"> <u>CCZ-S1 (Fences and Standalone Walls);</u> <u>CCZ-S2 (Setback);</u> <u>CCZ-S3 (Location of Residential Units);</u> <u>CCZ-S4 (Height in Relation to Boundary);</u> <p>DIS</p>

Commented [MM239]: S28.8 - Ara Poutama Aotearoa – Department of Corrections

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>v. <u>CCZ-S5 (Noise and Ventilation);</u></p> <p>vi. <u>CCZ-S6 (Water Supply, Stormwater and Wastewater);</u></p> <p>vii. <u>CCZ-S7 (Landscaping and Screening);</u></p> <p>viii. <u>CCZ-S8 (Active Street Frontages); and</u></p> <p>ix. <u>CCZ-S9 – (Hydraulic neutrality).</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>The extent to which the building may adversely impact on the anticipated built form, character and amenity of the City Centre Zone.</u> 2. <u>Whether the building reflects the anticipated purpose scale and context of the City Centre Zone.</u> 3. <u>The extent to which the building aligns with the anticipated compact, high-density built environment anticipated for the City Centre Zone.</u> 4. <u>Whether the building is well designed and contributes to the creation of safe and vibrant public spaces.</u> 5. <u>Whether the building creates an active street frontage.</u> 6. <u>Whether the building provides visual interest by using a variety of building forms, materials and colours.</u> 7. <u>Consistency with the City Centre Design Guide.</u> 8. <u>The matters of discretion listed under the relevant standard.</u> <p><u>Notification:</u></p> <ul style="list-style-type: none"> • <u>An application under this rule is precluded from being publicly notified in accordance with section 95A of the RMA</u> <p>2. <u>Activity status: Discretionary</u></p> <p><u>Where:</u></p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>a. <u>Compliance is not achieved with one or more of the standards under CCZ-R16-1.a</u></p>
			<p>CCZ-R17</p> <p>Emergency Service Facility Activities otherwise permitted or controlled, which do not comply with the requirements of the Plan</p> <p>DIS</p> <p>1. Activity status: <u>Restricted Discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is achieved with CCZ-S7 (Landscaping and Screening).</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> <u>The extent to which the activity may adversely impact on the anticipated character and amenity values of the City Centre Zone.</u> <u>The effects of the activity on the existing and anticipated function and role of the City Centre Zone.</u> <u>The potential of the activity to compromise other activities that are enabled in the City Centre Zone.</u> <u>The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated.</u> <u>The functional need or operational need for the emergency service facility to be located in the City Centre Zone.</u> <p>Notification:</p> <ul style="list-style-type: none"> <u>An application under this rule is precluded from being publicly notified in accordance with section 95A of the RMA</u> <p>2. Activity status: <u>Discretionary</u></p> <p><u>Where:</u></p> <p>a. <u>Compliance is not achieved with CCZ-R17-1.a</u></p>

IPI - PROPOSED AMENDMENTS															
#	Chapter	Change	Track Change												
	CCZ- City Centre Zone	Amend existing Non-complying Activities Table	<p>Non-Complying Activities</p> <table border="1"> <tr> <td>CCZ-R18</td> <td> <p>Sport and Active Recreation-Motor vehicle wrecking</p> <p>1. Activity status: Restricted Discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is achieved with CCZ-S7 (Landscaping and Screening).</p> <p><u>Matters of discretion are restricted to:</u></p> <p>1. The extent to which the activity may adversely impact on the anticipated character and amenity values of the City Centre Zone.</p> <p>2. The effects of the activity on the existing and anticipated function and role of the City Centre Zone.</p> <p>3. The potential of the activity to compromise other activities that are enabled in the <u>zone</u>.</p> <p>4. The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated.</p> </td> <td rowspan="2">NG</td> </tr> <tr> <td></td> <td> <p>2. Activity status: Discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with one or more of the standards under CCZ-R18-1.a</p> </td> </tr> <tr> <td></td> <td></td> <td></td> <td> <table border="1"> <tr> <td>CCZ-R19</td> <td> <p>Retirement Village Every activity listed as an offensive trade in the third schedule of the Health Act 1956</p> <p>1. Activity status: Restricted Discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is achieved with</p> </td> <td>NG</td> </tr> </table> </td> </tr> </table>	CCZ-R18	<p>Sport and Active Recreation-Motor vehicle wrecking</p> <p>1. Activity status: Restricted Discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is achieved with CCZ-S7 (Landscaping and Screening).</p> <p><u>Matters of discretion are restricted to:</u></p> <p>1. The extent to which the activity may adversely impact on the anticipated character and amenity values of the City Centre Zone.</p> <p>2. The effects of the activity on the existing and anticipated function and role of the City Centre Zone.</p> <p>3. The potential of the activity to compromise other activities that are enabled in the <u>zone</u>.</p> <p>4. The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated.</p>	NG		<p>2. Activity status: Discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with one or more of the standards under CCZ-R18-1.a</p>				<table border="1"> <tr> <td>CCZ-R19</td> <td> <p>Retirement Village Every activity listed as an offensive trade in the third schedule of the Health Act 1956</p> <p>1. Activity status: Restricted Discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is achieved with</p> </td> <td>NG</td> </tr> </table>	CCZ-R19	<p>Retirement Village Every activity listed as an offensive trade in the third schedule of the Health Act 1956</p> <p>1. Activity status: Restricted Discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is achieved with</p>	NG
CCZ-R18	<p>Sport and Active Recreation-Motor vehicle wrecking</p> <p>1. Activity status: Restricted Discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is achieved with CCZ-S7 (Landscaping and Screening).</p> <p><u>Matters of discretion are restricted to:</u></p> <p>1. The extent to which the activity may adversely impact on the anticipated character and amenity values of the City Centre Zone.</p> <p>2. The effects of the activity on the existing and anticipated function and role of the City Centre Zone.</p> <p>3. The potential of the activity to compromise other activities that are enabled in the <u>zone</u>.</p> <p>4. The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated.</p>	NG													
	<p>2. Activity status: Discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is not achieved with one or more of the standards under CCZ-R18-1.a</p>														
			<table border="1"> <tr> <td>CCZ-R19</td> <td> <p>Retirement Village Every activity listed as an offensive trade in the third schedule of the Health Act 1956</p> <p>1. Activity status: Restricted Discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is achieved with</p> </td> <td>NG</td> </tr> </table>	CCZ-R19	<p>Retirement Village Every activity listed as an offensive trade in the third schedule of the Health Act 1956</p> <p>1. Activity status: Restricted Discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is achieved with</p>	NG									
CCZ-R19	<p>Retirement Village Every activity listed as an offensive trade in the third schedule of the Health Act 1956</p> <p>1. Activity status: Restricted Discretionary</p> <p><u>Where:</u></p> <p>a. Compliance is achieved with</p>	NG													

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<p>i. <u>CCZ-S3 (Location of Habitable Rooms);</u></p> <p>ii. <u>CCZ-S5 (Noise and Ventilation); and</u></p> <p>iii. <u>CCZ-S7 (Landscaping and Screening).</u></p> <p><u>Matters of discretion are restricted to:</u></p> <ol style="list-style-type: none"> 1. <u>Whether any adverse effects, including reverse sensitivity effects on the continued operation of established activities, can be avoided, remedied or mitigated.</u> 2. <u>Whether on-site amenity for residents is provided, which reflects the nature of and diverse needs of residents of the retirement village.</u> 3. <u>The extent to which the activity may adversely impact on the anticipated character and amenity values of the City Centre Zone.</u> 4. <u>The effects of the activity on the existing and anticipated function and role of the City Centre Zone.</u> 5. <u>The potential of the activity to compromise other activities that are enabled in the City Centre Zone.</u> 6. <u>The extent to which the adverse effects of the activity can be avoided, or appropriately remedied or mitigated.</u> <p>2. <u>Activity status: Discretionary</u></p> <p><u>Where:</u></p> <ol style="list-style-type: none"> a. <u>Compliance is not achieved with one or more of the standards under CCZ-R19-1.a</u> 				
	CCZ- City Centre Zone	Delete existing Matters for Consideration	<p>Matters for Consideration</p> <p>Matters that may be relevant in the consideration of any Discretionary or Non-Complying Activity resource consent may include the following:</p> <table border="1"> <tr> <td>CCZ-MC1</td> <td>Access</td> </tr> <tr> <td></td> <td>(1) Accessibility for public transport, cyclists and pedestrians.</td> </tr> </table>	CCZ-MC1	Access		(1) Accessibility for public transport, cyclists and pedestrians.
CCZ-MC1	Access						
	(1) Accessibility for public transport, cyclists and pedestrians.						

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(2) Compliance with the Code of Practice for Civil Engineering Works.</p> <p>(3) Whether the topography, size or shape of the site or the location of any natural or built feature(s) on the site or other requirements such as easements, rights of way or restrictive covenants impose constraints that make compliance impracticable.</p> <p>(4) Whether the activities proposed will not generate a demand for servicing facilities.</p> <p>(5) Whether suitable alternative provision for servicing can be made.</p> <p>(6) Whether the nature of adjacent roads is such that the entry, exit and manoeuvring of vehicles can be conducted safely.</p>
			<p><u>CCZ-MC2</u> Site Layout</p> <p>(1) The arrangement of buildings, car parks and vehicle movements on site.</p> <p>(2) The nature and extent of landscaping and screening.</p> <p>(3) Whether the topography of the site has been taken into account.</p> <p>(4) Whether a better standard of development can be achieved by varying the design.</p>
			<p><u>CCZ-MC3</u> Bulk and location of buildings</p> <p>(1) Whether the buildings will cause a loss of privacy, interfere with sunlight access or create shadows on residential units on adjoining Residentially zoned sites.</p> <p>(2) Whether the building design, appearance and scale will detrimentally affect the character of the surrounding area.</p>
			<p><u>CCZ-MC4</u> Traffic generation</p> <p>(1) Whether activities which generate significant traffic flows have the necessary access, do not adversely impact upon the street environment, and maintain public safety.</p>
			<p><u>CCZ-MC5</u> Non-business activities</p> <p>(1) Whether the buildings, structures or other works are of an appropriate scale having regard to the local amenity.</p>

IPI - PROPOSED AMENDMENTS													
#	Chapter	Change	Track Change										
			<table border="1"> <tr> <td></td> <td>(2) The extent to which the amenities and the quality of the business environment can be maintained and enhanced.</td> </tr> <tr> <td>CCZ-MC6</td> <td>Nuisance (1) The potential impacts of noise, dust, glare, vibration, fumes, smoke, other discharges or pollutants or the excavation or deposition of earth</td> </tr> <tr> <td>CCZ-MC7</td> <td>Infrastructure (1) The existing capacity of the infrastructure.</td> </tr> <tr> <td>CCZ-MC8</td> <td>Cumulative effects (1) Whether cumulative effects such as pollution, risks to public safety and nuisances have been assessed.</td> </tr> <tr> <td>CCZ-MC9</td> <td>Retail activities (1) The effects of retail activities on the vitality and economic viability of the CCZ – City Centre Zone (Central Business District), and neighbourhood centres. (2) Whether the nature and scale of retail activities complements activities occurring on surrounding sites</td> </tr> </table>		(2) The extent to which the amenities and the quality of the business environment can be maintained and enhanced.	CCZ-MC6	Nuisance (1) The potential impacts of noise, dust, glare, vibration, fumes, smoke, other discharges or pollutants or the excavation or deposition of earth	CCZ-MC7	Infrastructure (1) The existing capacity of the infrastructure.	CCZ-MC8	Cumulative effects (1) Whether cumulative effects such as pollution, risks to public safety and nuisances have been assessed.	CCZ-MC9	Retail activities (1) The effects of retail activities on the vitality and economic viability of the CCZ – City Centre Zone (Central Business District), and neighbourhood centres. (2) Whether the nature and scale of retail activities complements activities occurring on surrounding sites
	(2) The extent to which the amenities and the quality of the business environment can be maintained and enhanced.												
CCZ-MC6	Nuisance (1) The potential impacts of noise, dust, glare, vibration, fumes, smoke, other discharges or pollutants or the excavation or deposition of earth												
CCZ-MC7	Infrastructure (1) The existing capacity of the infrastructure.												
CCZ-MC8	Cumulative effects (1) Whether cumulative effects such as pollution, risks to public safety and nuisances have been assessed.												
CCZ-MC9	Retail activities (1) The effects of retail activities on the vitality and economic viability of the CCZ – City Centre Zone (Central Business District), and neighbourhood centres. (2) Whether the nature and scale of retail activities complements activities occurring on surrounding sites												
	CCZ- City Centre Zone	Delete existing Prohibited Activities table	<table border="1"> <tr> <td colspan="2">Prohibited Activities</td> </tr> <tr> <td>CCZ-R20</td> <td>Gang fortifications</td> </tr> </table>	Prohibited Activities		CCZ-R20	Gang fortifications						
Prohibited Activities													
CCZ-R20	Gang fortifications												
	CCZ- City Centre Zone	Introduce new Rule CCZ-R20	<table border="1"> <tr> <td>CCZ-R20</td> <td>Drive-through Activity</td> </tr> <tr> <td>1.</td> <td>Activity status: Discretionary</td> </tr> </table>	CCZ-R20	Drive-through Activity	1.	Activity status: Discretionary						
CCZ-R20	Drive-through Activity												
1.	Activity status: Discretionary												
	CCZ- City Centre Zone	Introduce new Rule CCZ-R21	<table border="1"> <tr> <td>CCZ-R21</td> <td>Any activity not otherwise listed as permitted, restricted discretionary, discretionary or non-complying</td> </tr> <tr> <td>1.</td> <td>Activity status: Discretionary</td> </tr> </table>	CCZ-R21	Any activity not otherwise listed as permitted, restricted discretionary, discretionary or non-complying	1.	Activity status: Discretionary						
CCZ-R21	Any activity not otherwise listed as permitted, restricted discretionary, discretionary or non-complying												
1.	Activity status: Discretionary												
	CCZ- City Centre Zone	Introduce new Rule CCZ-R22	<table border="1"> <tr> <td>CCZ-R22</td> <td>Industrial Activity</td> </tr> </table>	CCZ-R22	Industrial Activity								
CCZ-R22	Industrial Activity												

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			1. Activity status: Non-complying				
	CCZ- City Centre Zone	Introduce new Rule CCZ-R23	<table border="1"> <tr> <td>CCZ-R23</td> <td>Yard Sale Activity / Trade Supplier</td> </tr> <tr> <td colspan="2">1. Activity status: Non-complying</td> </tr> </table>	CCZ-R23	Yard Sale Activity / Trade Supplier	1. Activity status: Non-complying	
CCZ-R23	Yard Sale Activity / Trade Supplier						
1. Activity status: Non-complying							
	CCZ- City Centre Zone	Introduce new Rule CCZ-R24	<table border="1"> <tr> <td>CCZ-R24</td> <td>Motorised Recreation</td> </tr> <tr> <td colspan="2">1. Activity status: Non-complying</td> </tr> </table>	CCZ-R24	Motorised Recreation	1. Activity status: Non-complying	
CCZ-R24	Motorised Recreation						
1. Activity status: Non-complying							
	CCZ- City Centre Zone	Introduce new Rule CCZ-R25	<table border="1"> <tr> <td>CCZ-R25</td> <td>Primary Production</td> </tr> <tr> <td colspan="2">1. Activity status: Non-complying</td> </tr> </table>	CCZ-R25	Primary Production	1. Activity status: Non-complying	
CCZ-R25	Primary Production						
1. Activity status: Non-complying							
	CCZ- City Centre Zone	Introduce new Rule CCZ-R26	<table border="1"> <tr> <td>CCZ-R26</td> <td>Rural Industries</td> </tr> <tr> <td colspan="2">1. Activity status: Non-complying</td> </tr> </table>	CCZ-R26	Rural Industries	1. Activity status: Non-complying	
CCZ-R26	Rural Industries						
1. Activity status: Non-complying							
	CCZ- City Centre Zone	Delete existing Advice Note	<p>Advice note</p> <p>For any activity within the Stream/River Corridor, Overflow Path, Ponding Area or Erosion Hazard Area, applicants are advised to consult the Wellington Regional Council to determine if regional consent is also required.</p>				
	CCZ- City Centre Zone	Delete existing Methods	<p>Methods</p> <p>CCZ M1 District Plan provisions consisting of the following:</p> <p style="padding-left: 40px;">(1) Commercial Zones identifying the commercial environments within the City. These are the Commercial Zone and the CCZ – City Centre Zone.</p> <p style="padding-left: 40px;">(2) Rules and performance standards to avoid, remedy or mitigate adverse effects.</p> <p>CCZ M2 Code of Practice for Civil Engineering Works.</p> <p>CCZ M3 Abatement notices and enforcement orders may be issued where it is necessary to enforce the performance standards and mitigate any adverse effects of activities.</p> <p>CCZ M4 Consultation with businesses and landowners to promote new developments which avoid, remedy or mitigate the potential adverse effects of all activities.</p>				

IPI - PROPOSED AMENDMENTS																										
#	Chapter	Change	Track Change																							
			<p>CCZ M5 Management Plans prepared under relevant legislation.</p> <p>CCZ M6 District Plan rules setting standards to protect adjacent properties from adverse shading effects.</p> <p>CCZ M7 District Plan rules prohibiting gang fortifications because of their adverse effects on the environment.</p>																							
	CCZ- City Centre Zone	Delete existing Anticipated Environmental Results	<p>Anticipated environmental results</p> <p>The following results are expected to be achieved by the objectives, policies and methods of this chapter. The means of monitoring whether this Plan achieves the anticipated environmental results are also set out below.</p> <table border="1"> <thead> <tr> <th>Anticipated environmental results</th> <th>Monitoring indicators</th> <th>Data source</th> </tr> </thead> <tbody> <tr> <td>CCZ-AER1</td> <td>Development within the CCZ – City Centre Zone which reflects the location, scale and intensity of development in the surrounding environment</td> <td>Density within the CCZ – City Centre Zone Number of resource consents by type</td> <td>Council records</td> </tr> <tr> <td>CCZ-AER2</td> <td>Management of the CCZ – City Centre Zone so that activities do not unduly affect adjacent land users</td> <td>Number of resource consents by type Complaints and abatement/enforcement proceedings</td> <td>Council records Complaints register</td> </tr> <tr> <td>CCZ-AER3</td> <td>A CBD which is safe, convenient and attractive</td> <td>Complaints and abatement/enforcement proceedings</td> <td>Complaints register Field work</td> </tr> <tr> <td>CCZ-AER4</td> <td>A consolidated CCZ – City Centre Zone that continues to maximise resources and existing infrastructure</td> <td>Density within the CCZ – City Centre Zone Number of resource consents by type</td> <td>Council records</td> </tr> <tr> <td>CCZ-AER5</td> <td>Retail activities are appropriately located to not adversely affect the economic viability of the CBD and to ensure that the industrial land resource of the City is used primarily for industrial purposes</td> <td>Number of resource consents by type The spatial development of retail activities The use, occupation and vacancy rate of industrial land and buildings</td> <td>Council records Field work</td> </tr> </tbody> </table>	Anticipated environmental results	Monitoring indicators	Data source	CCZ-AER1	Development within the CCZ – City Centre Zone which reflects the location, scale and intensity of development in the surrounding environment	Density within the CCZ – City Centre Zone Number of resource consents by type	Council records	CCZ-AER2	Management of the CCZ – City Centre Zone so that activities do not unduly affect adjacent land users	Number of resource consents by type Complaints and abatement/enforcement proceedings	Council records Complaints register	CCZ-AER3	A CBD which is safe, convenient and attractive	Complaints and abatement/enforcement proceedings	Complaints register Field work	CCZ-AER4	A consolidated CCZ – City Centre Zone that continues to maximise resources and existing infrastructure	Density within the CCZ – City Centre Zone Number of resource consents by type	Council records	CCZ-AER5	Retail activities are appropriately located to not adversely affect the economic viability of the CBD and to ensure that the industrial land resource of the City is used primarily for industrial purposes	Number of resource consents by type The spatial development of retail activities The use, occupation and vacancy rate of industrial land and buildings	Council records Field work
Anticipated environmental results	Monitoring indicators	Data source																								
CCZ-AER1	Development within the CCZ – City Centre Zone which reflects the location, scale and intensity of development in the surrounding environment	Density within the CCZ – City Centre Zone Number of resource consents by type	Council records																							
CCZ-AER2	Management of the CCZ – City Centre Zone so that activities do not unduly affect adjacent land users	Number of resource consents by type Complaints and abatement/enforcement proceedings	Council records Complaints register																							
CCZ-AER3	A CBD which is safe, convenient and attractive	Complaints and abatement/enforcement proceedings	Complaints register Field work																							
CCZ-AER4	A consolidated CCZ – City Centre Zone that continues to maximise resources and existing infrastructure	Density within the CCZ – City Centre Zone Number of resource consents by type	Council records																							
CCZ-AER5	Retail activities are appropriately located to not adversely affect the economic viability of the CBD and to ensure that the industrial land resource of the City is used primarily for industrial purposes	Number of resource consents by type The spatial development of retail activities The use, occupation and vacancy rate of industrial land and buildings	Council records Field work																							

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			<table border="1"> <tr> <td>CGZ AER6</td> <td>A built environment which supports the health and safety of the City's residents</td> <td>Resource consents and type and effect on health and safety issues Consultation and community initiatives</td> <td>Council records</td> </tr> </table>	CGZ AER6	A built environment which supports the health and safety of the City's residents	Resource consents and type and effect on health and safety issues Consultation and community initiatives	Council records
CGZ AER6	A built environment which supports the health and safety of the City's residents	Resource consents and type and effect on health and safety issues Consultation and community initiatives	Council records				
INDUSTRIAL ZONES							
GIZ – General Industrial Zone							
	GIZ – General Industrial Zone	Consequential Amendment	<p>GIZ – General Industrial Zone</p> <p>Background</p> <p>Businesses within the City are located in the <u>City Centre Zone</u> Central Business District (CBD), commercial, <u>mixed use</u> and industrial areas, and suburban areas. Some parts of the business areas include hotels, tourist facilities and other activities</p>				
	GIZ – General Industrial Zone	Consequential Amendment	<p>Objectives</p> <p>GIZ-O1 <i>The sustainable management of physical resources within the existing industrial areas of the City to protect and enhance their amenity values.</i></p> <p>This objective recognises the importance of particular elements and characteristics that define the commercial areas. Commercial activities and development can have both positive and adverse environmental effects on the areas that surround them. Any consideration of effects must take account of the need to provide sufficient areas for commercial development needs, and the maintenance of amenity values and character.</p> <p>The General Industrial Zone incorporates land which is used for a range of industrial and commercial activities, but in particular larger scale industrial, warehousing, storage and commercial activities which are vehicle rather than pedestrian orientated. There are limited retail activities within these areas and the environmental standards are less stringent than those within the Commercial and Mixed Use zones.</p>				
			<p>Policies</p> <p>GIZ-P1 <i>To promote the location of retail activities in patterns which do not adversely affect the amenity values of the City Centre Zone (Central Business District), and to limit the establishment of retail activities within the General Industrial Zone.</i></p> <p>The City Centre Zone (CBD) is the focus of many retail and service activities that, in combination, give this area a special and unique character as the centre of the City. The focusing and clustering of activities within the City Centre Zone (CBD)</p>				

IPI - PROPOSED AMENDMENTS									
#	Chapter	Change	Track Change						
			<p>is an important part of the vitality, character and amenity of the City. This policy seeks to recognise the role of the City Centre Zone (CBD) by promoting its amenity characteristics and recognising its overall economic viability, but this policy does not seek to preclude retail development in other parts of the City such as in neighbourhood centres. This in turn promotes the sustainable management of the City Centre Zone (CBD).</p> <p>Yard-orientated retail activities and large format retail activities tend to adversely affect pedestrian amenity values. It is therefore important to encourage them to locate in areas where a lower level of pedestrian amenity is acceptable such as in the General industrial zone. Establishment of retail activity in the General industrial zone is however controlled in order to enable the assessment of the scale and character of retail activity. Retail activity in the General industrial zone can detract from other retail areas of the City and can generate adverse traffic effects. Retail activity can also conflict with other land uses within the General industrial zone. Large format retail development should be located in a manner complementary to the existing retail development of the City and in a manner that is complementary to, and does not detract from, the vitality and viability of the City Centre Zone (CBD).</p> <p>Specific provision is made for large format retailing to establish on the former South Pacific Tyres site being a location that is considered to be complementary to the City Centre Zone (CBD) and which can contain a number of large format retail activities in an integrated manner, complementary to established activities on Park Street. The site has been identified as being appropriate for large format retailing through the development of the Upper Hutt Urban Growth Strategy.</p> <p>The concentration of activities in established areas results in the provision of a wide range of services and the promotion of amenity values of the established business areas. It also encourages better use of community resources such as the City Library or recreation facilities which are more convenient when located centrally.</p>						
	GIZ – General Industrial Zone	Consequential Amendment – Delete reference to GIZ-Figure1 (rezoned to MUZ)	<table border="1"> <thead> <tr> <th colspan="3">Permitted Activities</th> </tr> </thead> <tbody> <tr> <td>GIZ-R2</td> <td>Large format retail activities on land identified in GIZ Figure1</td> <td>PER</td> </tr> </tbody> </table>	Permitted Activities			GIZ-R2	Large format retail activities on land identified in GIZ Figure1	PER
Permitted Activities									
GIZ-R2	Large format retail activities on land identified in GIZ Figure1	PER							
	GIZ – General Industrial Zone	Consequential Amendment	<table border="1"> <thead> <tr> <th colspan="2">Standards for Permitted and Controlled Activities</th> </tr> </thead> <tbody> <tr> <td colspan="2">Note: The following standards for Permitted and Controlled Activities apply to all properties throughout the general industrial Zone unless otherwise specified in the text of the standard in question.</td> </tr> <tr> <td>GIZ-S2</td> <td>Setbacks from boundaries</td> </tr> </tbody> </table>	Standards for Permitted and Controlled Activities		Note: The following standards for Permitted and Controlled Activities apply to all properties throughout the general industrial Zone unless otherwise specified in the text of the standard in question.		GIZ-S2	Setbacks from boundaries
Standards for Permitted and Controlled Activities									
Note: The following standards for Permitted and Controlled Activities apply to all properties throughout the general industrial Zone unless otherwise specified in the text of the standard in question.									
GIZ-S2	Setbacks from boundaries								

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p><i>Policies GIZ-P2, GIZ-P3</i></p> <p>(1) The setback distance for buildings from boundaries shall be not less than:</p> <p>(a) Front boundary 8m</p> <p>(b) Side and rear boundaries except where adjoining a General Residential, <u>High Density Residential</u>, or Open Space Zone 0m</p> <p>(c) Side and rear boundaries adjoining a General Residential, <u>High Density Residential</u>, or Open Space Zone 5.5m</p> <p>Exemptions:</p> <p>(2) Service station ...</p> <p>(3) Pole signs ...</p> <p>(4) Within the Business Industrial zone ...</p>
	GIZ – General Industrial Zone	Consequential Amendment	<p>GIZ-S4</p> <p><i>Policies GRZ-P4, GIZ-P2, GIZ-P3</i></p> <p>Sunlight access</p> <p>(1) All buildings on sites adjoining, or separated by a road from a site in the General Residential, <u>High Density Residential</u>, or Open Space Zone, shall comply with the height control planes defined in relation to boundary standard in GRZ-S8 along the adjoining boundary or the boundary or boundaries separated by a road.</p>
	GIZ – General Industrial Zone	Consequential Amendment	<p>GIZ-S7</p> <p><i>Policies GIZ-P2, GIZ-P5</i></p> <p>Screening</p> <p>(1) Sites adjoining a General Residential, <u>High Density Residential</u>, or Open Space Zone shall be fenced on the common boundary by a solid 2m high fence.</p>
	GIZ – General Industrial Zone	Consequential Amendment	<p>GIZ-S8</p> <p><i>Policies GIZ-P2, GIZ-P3, CCZ-P2</i></p> <p>Landscaping</p> <p>(1) If a building is</p> <p>(2) Where a site adjoins a Residential, Rural, Open Space or Special Activity Zone (excluding road boundaries) or is within 25m of a General Residential, <u>High Density Residential</u>, or Open Space Zone, a</p>

IPI - PROPOSED AMENDMENTS						
#	Chapter	Change	Track Change			
			landscape buffer with a minimum width of 0.6m shall be provided within the site between the zone boundary and the buildings .			
	GIZ – General Industrial Zone	Consequential Amendment	GIZ-S10 Hours of operation for activities adjoining the General Residential or High Density Residential Zone (1) Any activity which is open to the public ... <i>Policies</i> <i>GIZ-P1</i>			
	GIZ – General Industrial Zone	Consequential Amendment Delete reference to GIZ-Figure1 (rezoned to MUZ)	Discretionary Activities <table border="1"> <tr> <td>GIZ-R14</td> <td>Any other retail activity on land identified in GIZ-Figure1, unless otherwise provided for below</td> <td>DIS</td> </tr> </table>	GIZ-R14	Any other retail activity on land identified in GIZ-Figure1, unless otherwise provided for below	DIS
GIZ-R14	Any other retail activity on land identified in GIZ-Figure1, unless otherwise provided for below	DIS				
			GIZ-Figure1 Former South Pacific Tyres site 			

IPI - PROPOSED AMENDMENTS													
#	Chapter	Change	Track Change										
OPEN SPACE AND RECREATION ZONES													
OSZ – Open Space Zone													
	OSZ – Open Space Zone	Consequential Amendment	<p>Standards for Permitted and Controlled Activities</p> <p>Zone-wide provisions (including Speedway Area) Unless otherwise specified, all permitted and controlled activities within the Open Space Zone shall comply with the standards specified below.</p> <table border="1"> <tr> <td>OSZ-S2</td> <td>Sunlight access</td> </tr> <tr> <td><i>Policies</i> GRZ-P4, OSZ-P2, OSZ-P4</td> <td>(1) All buildings on sites adjoining, or separated by a road from a site in the Residential or Open Space Zone, shall comply with the height control planes in relation to boundary standard defined in GRZ-S8 along the adjoining boundary or the boundary or boundaries separated by a road.</td> </tr> </table>	OSZ-S2	Sunlight access	<i>Policies</i> GRZ-P4, OSZ-P2, OSZ-P4	(1) All buildings on sites adjoining, or separated by a road from a site in the Residential or Open Space Zone, shall comply with the height control planes in relation to boundary standard defined in GRZ-S8 along the adjoining boundary or the boundary or boundaries separated by a road .						
OSZ-S2	Sunlight access												
<i>Policies</i> GRZ-P4, OSZ-P2, OSZ-P4	(1) All buildings on sites adjoining, or separated by a road from a site in the Residential or Open Space Zone, shall comply with the height control planes in relation to boundary standard defined in GRZ-S8 along the adjoining boundary or the boundary or boundaries separated by a road .												
	OSZ – Open Space Zone	Consequential Amendment	<p>Zone wide provisions (excluding Speedway Area) Unless otherwise specified, all permitted and controlled activities within the Open Space Zone (outside the Speedway Area) shall comply with the standards specified below.</p> <table border="1"> <tr> <td>OSZ-S5</td> <td> <p>Setbacks from boundaries</p> <p>(1) The setback distance for buildings from boundaries shall be not less than:</p> <table border="0"> <tr> <td>(a) Front boundary</td> <td>6m</td> </tr> <tr> <td>(b) Boundaries adjoining a General Residential <u>or High Density Residential Zone</u></td> <td>3m</td> </tr> <tr> <td>(c) All other boundaries</td> <td>0m</td> </tr> </table> <p>Exemptions:</p> <p>(2) Eaves, ...</p> <p>(3) Non-enclosed ...</p> </td> </tr> <tr> <td><i>Policies</i> OSZ-P2</td> <td></td> </tr> </table>	OSZ-S5	<p>Setbacks from boundaries</p> <p>(1) The setback distance for buildings from boundaries shall be not less than:</p> <table border="0"> <tr> <td>(a) Front boundary</td> <td>6m</td> </tr> <tr> <td>(b) Boundaries adjoining a General Residential <u>or High Density Residential Zone</u></td> <td>3m</td> </tr> <tr> <td>(c) All other boundaries</td> <td>0m</td> </tr> </table> <p>Exemptions:</p> <p>(2) Eaves, ...</p> <p>(3) Non-enclosed ...</p>	(a) Front boundary	6m	(b) Boundaries adjoining a General Residential <u>or High Density Residential Zone</u>	3m	(c) All other boundaries	0m	<i>Policies</i> OSZ-P2	
OSZ-S5	<p>Setbacks from boundaries</p> <p>(1) The setback distance for buildings from boundaries shall be not less than:</p> <table border="0"> <tr> <td>(a) Front boundary</td> <td>6m</td> </tr> <tr> <td>(b) Boundaries adjoining a General Residential <u>or High Density Residential Zone</u></td> <td>3m</td> </tr> <tr> <td>(c) All other boundaries</td> <td>0m</td> </tr> </table> <p>Exemptions:</p> <p>(2) Eaves, ...</p> <p>(3) Non-enclosed ...</p>	(a) Front boundary	6m	(b) Boundaries adjoining a General Residential <u>or High Density Residential Zone</u>	3m	(c) All other boundaries	0m						
(a) Front boundary	6m												
(b) Boundaries adjoining a General Residential <u>or High Density Residential Zone</u>	3m												
(c) All other boundaries	0m												
<i>Policies</i> OSZ-P2													
	OSZ – Open Space Zone	Consequential Amendment	<table border="1"> <tr> <td>OSZ-S7</td> <td>Sunlight access</td> </tr> </table>	OSZ-S7	Sunlight access								
OSZ-S7	Sunlight access												

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p><i>Policies GRZ-P4, OSZ-P2, OSZ-P4</i></p> <p>(1) All buildings shall comply with the height control planes <u>height control planes in relation to boundary standard</u> defined in GRZ-S8.</p>

SPECIAL PURPOSE ZONES

SAZ – Special Activity Zone			
	SAZ – Special Activity Zone	Amend Background	<p>Background</p> <p>The main characteristics of the Special Activity Zone are the form and scale of building development, the nature and intensity of activities on the sites and their effects on the environment.</p> <p>Major activities in the Zone include Trentham Military Camp, Rimutaka Prison, New Zealand International Campus (the former Central Institute of Technology (CIT) complex), St Patrick’s College, Trentham Racecourse, Heretaunga Golf Course and the Silver Stream Railway. These activities make an important and positive economic, social and cultural contribution to the City.</p> <p>The area adjoining and including St Patrick’s College covers approximately 65 hectares of land, 45 hectares of which is undeveloped. This land is referred to in the Plan as the St Patrick’s Estate Area. The land borders the Hutt River and forms part of the flood plain.</p> <p>The Hutt City Council have a designation for an excess wastewater flow storage facility adjacent to the Eastern Hutt Road.</p>
	SAZ – Special Activity Zone	Amend Issue	<p>Issues</p> <p>SAZ-14 <i>Potential detractor from the visual amenity resulting from development on the St Patrick’s Estate Area.</i></p> <p>The St Patrick’s Estate Area is currently mainly pasture and is part of the open vista entrance to Upper Hutt. This open character is a feature when entering the City from the south. To recognise and respect the “gateway” function of the area and maintain its visual amenity, building development should be relatively low-profile with an emphasis on landscaping.</p>
	SAZ – Special Activity Zone	Amend Issue	<p>SAZ-15 <i>The threat to the St Patrick’s Estate Precinct and St Patrick’s College Area from potential inundation from the Hutt River and the Mawaihakona Stream.</i></p> <p>As this is a flood plain, a number of restrictions have to be placed on the location and construction of buildings and structures.</p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	SAZ – Special Activity Zone	Amend Objective	<p>Objectives</p> <p>SAZ-O3 <i>Provision for a range of activities on the St Patrick’s Estate Area which avoids, remedies or mitigates any adverse effects on its visual amenity, on the neighbouring community, services and roading infrastructure, and takes into account the flooding hazards.</i></p> <p>St Patrick’s Estate Precinct is an area of land with potential for a wide range of development options that adjoins the St Patrick’s College Area. This Precinct area is dealt with under a specific policy framework within the Special Activity Mixed Use Zone. The St Patrick’s Estate contains two distinct areas for future development, which are identified on the Planning Maps:</p> <p>(1) The St Patrick’s College Area provides for future education expansion under the Special Activity Zone provisions.</p> <p>(2) The Managed Development Area for a range of other uses.</p> <p>Controls are required to prevent development in close proximity to the Hutt River and Mawaihakona Stream.</p>
	SAZ – Special Activity Zone	Amend Policy	<p>Policies</p> <p>SAZ-P4 <i>To provide for a range of activities within the St Patrick’s Estate College Area which best suit the characteristics and constraints of the existing environment.</i></p> <p>Two distinct The areas provides for a range of commercial, open space and educational activities appropriate to the environmental character and constraints of the land and surrounding area. These have been based on previous policies for the land and negotiation with the landowners and other parties. Linkages to the Hutt River walkway and the Silverstream Railway Station may be important components of future development.</p> <p>The rules for these areas require that any development be serviced with appropriate access to existing services and roads. In a major flood event, structures could impede the flood flow, putting buildings, roads or services in danger and causing additional problems. Accordingly, activities that are relatively free of structures are appropriate for the part of the site in the flood plain. However, special requirements are also included in relation to building floor levels, roads and services, so that structures may be developed as long as they are designed for protection from future floods with a 1 in 100 year return period.</p>
	SAZ – Special Activity Zone	Amend Policy	<p>SAZ-P6 <i>To identify and maintain amenity values that the community wishes to protect.</i></p> <p>Amenity values are those features or aspects about an area which enhance it or make it pleasant to be in. They can include access to sunlight, landscaping and visual qualities. They may also include important public features, such as parks and reserves. Activities which can adversely affect the amenities of an area must be managed, while also</p>

IPI - PROPOSED AMENDMENTS																																				
#	Chapter	Change	Track Change																																	
			<p>recognising the rights of individuals to use their own properties and the need for utilities to operate effectively and safely.</p> <p>A particular concern of the Upper Hutt community relates to the effects of the establishment and use of what are commonly referred to as gang fortifications. These are sometimes accompanied by an increase in antisocial behaviour.</p> <p>It is Council's view that the adverse effects of these fortifications on the environment, in particular in respect of the social, economic, aesthetic and cultural conditions of the Upper Hutt people and community, and the amenity values of the Upper Hutt environment, are such that these activities should not be permitted. The activity is therefore prohibited anywhere in Upper Hutt City.</p>																																	
	SAZ – Special Activity Zone	Amend Rule	<table border="1"> <thead> <tr> <th colspan="3">Permitted Activities</th> </tr> <tr> <th colspan="3">Zone-wide (excluding the St Patrick's Estate College Area)</th> </tr> </thead> <tbody> <tr> <td>SAZ-R1</td> <td>Activities relating to ...</td> <td>PER</td> </tr> <tr> <td>SAZ-R2</td> <td>Activities relating to ...</td> <td>PER</td> </tr> <tr> <td>SAZ-R3</td> <td>Activities relating to educational ...</td> <td>PER</td> </tr> <tr> <td>SAZ-R4</td> <td>Visitor accommodation, tourist facilities, ...</td> <td>PER</td> </tr> <tr> <td>SAZ-R5</td> <td>Activities relating to the Police ...</td> <td>PER</td> </tr> <tr> <td>SAZ-R6</td> <td>Railway museum and ...</td> <td>PER</td> </tr> <tr> <td>SAZ-R7</td> <td>Active and passive recreation and ...</td> <td>PER</td> </tr> <tr> <td>SAZ-R8</td> <td>Removal of a building ...</td> <td>PER</td> </tr> <tr> <td>SAZ-R9</td> <td>Minor Structures</td> <td>PER</td> </tr> </tbody> </table>	Permitted Activities			Zone-wide (excluding the St Patrick's Estate College Area)			SAZ-R1	Activities relating to ...	PER	SAZ-R2	Activities relating to ...	PER	SAZ-R3	Activities relating to educational ...	PER	SAZ-R4	Visitor accommodation, tourist facilities, ...	PER	SAZ-R5	Activities relating to the Police ...	PER	SAZ-R6	Railway museum and ...	PER	SAZ-R7	Active and passive recreation and ...	PER	SAZ-R8	Removal of a building ...	PER	SAZ-R9	Minor Structures	PER
Permitted Activities																																				
Zone-wide (excluding the St Patrick's Estate College Area)																																				
SAZ-R1	Activities relating to ...	PER																																		
SAZ-R2	Activities relating to ...	PER																																		
SAZ-R3	Activities relating to educational ...	PER																																		
SAZ-R4	Visitor accommodation, tourist facilities, ...	PER																																		
SAZ-R5	Activities relating to the Police ...	PER																																		
SAZ-R6	Railway museum and ...	PER																																		
SAZ-R7	Active and passive recreation and ...	PER																																		
SAZ-R8	Removal of a building ...	PER																																		
SAZ-R9	Minor Structures	PER																																		
	SAZ – Special Activity Zone	Amend Rules	<table border="1"> <thead> <tr> <th colspan="3">St Patrick's Estate College Area only</th> </tr> </thead> <tbody> <tr> <td>SAZ-R10</td> <td>Passive recreation</td> <td>PER</td> </tr> <tr> <td>SAZ-R11</td> <td>Removal of a building from a site</td> <td>PER</td> </tr> <tr> <td>SAZ-R12</td> <td>Educational facilities, early childhood centres (St Patrick's College Area* only)</td> <td>PER</td> </tr> <tr> <td>SAZ-R13</td> <td>Residential units and visitor accommodation (St Patrick's College Area* only)</td> <td>PER</td> </tr> </tbody> </table>	St Patrick's Estate College Area only			SAZ-R10	Passive recreation	PER	SAZ-R11	Removal of a building from a site	PER	SAZ-R12	Educational facilities, early childhood centres (St Patrick's College Area* only)	PER	SAZ-R13	Residential units and visitor accommodation (St Patrick's College Area* only)	PER																		
St Patrick's Estate College Area only																																				
SAZ-R10	Passive recreation	PER																																		
SAZ-R11	Removal of a building from a site	PER																																		
SAZ-R12	Educational facilities, early childhood centres (St Patrick's College Area* only)	PER																																		
SAZ-R13	Residential units and visitor accommodation (St Patrick's College Area* only)	PER																																		

Commented [MM240]: 5.32 - Bob Anker.

IPI - PROPOSED AMENDMENTS																																													
#	Chapter	Change	Track Change																																										
			<table border="1"> <tr> <td>SAZ-R14</td> <td>Minor Structures</td> <td>PER</td> </tr> <tr> <td colspan="3">* Identified on the Planning Maps</td> </tr> </table>	SAZ-R14	Minor Structures	PER	* Identified on the Planning Maps																																						
SAZ-R14	Minor Structures	PER																																											
* Identified on the Planning Maps																																													
	SAZ – Special Activity Zone	Amend Rule	<table border="1"> <tr> <td colspan="3">Controlled Activities</td> </tr> <tr> <td colspan="3">Zone-wide (including the St Patrick's Estate College Area)</td> </tr> <tr> <td colspan="3">St Patrick's Estate College Area only</td> </tr> <tr> <td>SAZ-R16</td> <td>Car parks (not including buildings)</td> <td>CON</td> </tr> <tr> <td><i>Policies</i></td> <td>Council may impose conditions over the following matters:</td> <td></td> </tr> <tr> <td>SAZ-P2</td> <td>(1) Bulk, location and design of the buildings.</td> <td></td> </tr> <tr> <td>SAZ-P3</td> <td>(2) Design and layout of car parks, loading, manoeuvring, pedestrian links and access.</td> <td></td> </tr> <tr> <td>NU-P3</td> <td>(3) Provision of and effects on utilities and/or services.</td> <td></td> </tr> <tr> <td></td> <td>(4) Landscaping.</td> <td></td> </tr> <tr> <td></td> <td>(5) Flood mitigation measures.</td> <td></td> </tr> <tr> <td></td> <td>(6) Screening.</td> <td></td> </tr> <tr> <td></td> <td>(7) Financial contributions.</td> <td></td> </tr> <tr> <td></td> <td>(8) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-SAZ-R7 covers subdivision within the Electricity Transmission Corridor</td> <td></td> </tr> <tr> <td></td> <td>(9) The outcome of consultation with the owner or operator of consented or existing renewable energy generation activities located on or in proximity to the site.</td> <td></td> </tr> </table>	Controlled Activities			Zone-wide (including the St Patrick's Estate College Area)			St Patrick's Estate College Area only			SAZ-R16	Car parks (not including buildings)	CON	<i>Policies</i>	Council may impose conditions over the following matters:		SAZ-P2	(1) Bulk, location and design of the buildings .		SAZ-P3	(2) Design and layout of car parks, loading, manoeuvring, pedestrian links and access.		NU-P3	(3) Provision of and effects on utilities and/or services.			(4) Landscaping.			(5) Flood mitigation measures.			(6) Screening.			(7) Financial contributions.			(8) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-SAZ-R7 covers subdivision within the Electricity Transmission Corridor			(9) The outcome of consultation with the owner or operator of consented or existing renewable energy generation activities located on or in proximity to the site .	
Controlled Activities																																													
Zone-wide (including the St Patrick's Estate College Area)																																													
St Patrick's Estate College Area only																																													
SAZ-R16	Car parks (not including buildings)	CON																																											
<i>Policies</i>	Council may impose conditions over the following matters:																																												
SAZ-P2	(1) Bulk, location and design of the buildings .																																												
SAZ-P3	(2) Design and layout of car parks, loading, manoeuvring, pedestrian links and access.																																												
NU-P3	(3) Provision of and effects on utilities and/or services.																																												
	(4) Landscaping.																																												
	(5) Flood mitigation measures.																																												
	(6) Screening.																																												
	(7) Financial contributions.																																												
	(8) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-SAZ-R7 covers subdivision within the Electricity Transmission Corridor																																												
	(9) The outcome of consultation with the owner or operator of consented or existing renewable energy generation activities located on or in proximity to the site .																																												
	SAZ – Special Activity Zone	Delete Rule	<table border="1"> <tr> <td>SAZ-R17</td> <td>Commercial development, excluding retailing</td> <td>CON</td> </tr> <tr> <td><i>Policies</i></td> <td>Council may impose conditions over the following matters:</td> <td></td> </tr> <tr> <td>SAZ-P2</td> <td>(1) Bulk, location and design of the buildings.</td> <td></td> </tr> <tr> <td>SAZ-P3</td> <td>(2) Design and layout of car parks, loading, manoeuvring, pedestrian links and access.</td> <td></td> </tr> <tr> <td>NU-P3</td> <td></td> <td></td> </tr> </table>	SAZ-R17	Commercial development, excluding retailing	CON	<i>Policies</i>	Council may impose conditions over the following matters:		SAZ-P2	(1) Bulk, location and design of the buildings.		SAZ-P3	(2) Design and layout of car parks, loading, manoeuvring, pedestrian links and access.		NU-P3																													
SAZ-R17	Commercial development, excluding retailing	CON																																											
<i>Policies</i>	Council may impose conditions over the following matters:																																												
SAZ-P2	(1) Bulk, location and design of the buildings.																																												
SAZ-P3	(2) Design and layout of car parks, loading, manoeuvring, pedestrian links and access.																																												
NU-P3																																													

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(3) Provision of and effects on utilities and/or services.</p> <p>(4) Landscaping.</p> <p>(5) Flood mitigation measures.</p> <p>(6) Screening.</p> <p>(7) Financial contributions.</p> <p>(8) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-SAZ-R7 covers subdivision within the Electricity Transmission Corridor</p> <p>(9) The outcome of consultation with the owner or operator of consented or existing renewable energy generation activities located on or in proximity to the site.</p>
	SAZ – Special Activity Zone	Delete Rule	<p>SAZ-R18</p> <p><i>Policies</i></p> <p>SAZ-P2</p> <p>SAZ-P3</p> <p>NU-P3</p> <p>Business and professional offices</p> <p>Council may impose conditions over the following matters:</p> <p>(1) Bulk, location and design of the buildings.</p> <p>(2) Design and layout of car parks, loading, manoeuvring, pedestrian links and access.</p> <p>(3) Provision of and effects on utilities and/or services.</p> <p>(4) Landscaping.</p> <p>(5) Flood mitigation measures.</p> <p>(6) Screening.</p> <p>(7) Financial contributions.</p> <p>(8) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-SAZ-R7 covers subdivision within the Electricity Transmission Corridor</p> <p>(9) The outcome of consultation with the owner or operator of consented or existing renewable energy generation activities located on or in proximity to the site.</p> <p>CON</p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	SAZ – Special Activity Zone	Delete Rule	<p>SAZ R19</p> <p><i>Policies</i> SAZ P2 SAZ P3 NU P3</p> <p>Active recreation and places of entertainment</p> <p>Council may impose conditions over the following matters:</p> <p>(1) Bulk, location and design of the buildings.</p> <p>(2) Design and layout of car parks, loading, manoeuvring, pedestrian links and access.</p> <p>(3) Provision of and effects on utilities and/or services.</p> <p>(4) Landscaping.</p> <p>(5) Flood mitigation measures.</p> <p>(6) Screening.</p> <p>(7) Financial contributions.</p> <p>(8) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule 22.18 22.15 SUB SAZ R7 covers subdivision within the Electricity Transmission Corridor</p> <p>(9) The outcome of consultation with the owner or operator of consented or existing renewable energy generation activities located on or in proximity to the site.</p>
	SAZ – Special Activity Zone	Delete Rule	<p>SAZ R20</p> <p><i>Policies</i> SAZ P2 SAZ P3 NU P3</p> <p>Places of assembly (including community facilities), and conference centres</p> <p>Council may impose conditions over the following matters:</p> <p>(1) Bulk, location and design of the buildings.</p> <p>(2) Design and layout of car parks, loading, manoeuvring, pedestrian links and access.</p> <p>(3) Provision of and effects on utilities and/or services.</p> <p>(4) Landscaping.</p> <p>(5) Flood mitigation measures.</p> <p>(6) Screening.</p> <p>(7) Financial contributions.</p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>(8) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-SAZ-R7 covers subdivision within the Electricity Transmission Corridor</p> <p>(9) The outcome of consultation with the owner or operator of consented or existing renewable energy generation activities located on or in proximity to the site.</p>
	SAZ – Special Activity Zone	Delete Rule	<p>SAZ-R21</p> <p><i>Policies</i></p> <p>SAZ-P2</p> <p>SAZ-P3</p> <p>NU-P3</p> <p>Garden centres</p> <p>Council may impose conditions over the following matters:</p> <p>(1) Bulk, location and design of the buildings.</p> <p>(2) Design and layout of car parks, loading, manoeuvring, pedestrian links and access.</p> <p>(3) Provision of and effects on utilities and/or services.</p> <p>(4) Landscaping.</p> <p>(5) Flood mitigation measures.</p> <p>(6) Screening.</p> <p>(7) Financial contributions.</p> <p>(8) The outcome of consultation with the owner or operator of regionally significant network utilities (excluding the National Grid) located on or in proximity to the site. Note: Rule SUB-SAZ-R7 covers subdivision within the Electricity Transmission Corridor</p> <p>(9) The outcome of consultation with the owner or operator of consented or existing renewable energy generation activities located on or in proximity to the site.</p> <p>CON</p>
	SAZ – Special Activity Zone	Insert New Rule	<p><u>SAZ-R26A</u></p> <p><u>Buildings that do not comply with SAZ-S6 within the Special Activity Zone Height Overlay.</u></p> <p><u>Council will restrict its discretion to, and may impose conditions on:</u></p> <ol style="list-style-type: none"> <u>The location, design and appearance of the building or structure.</u> <u>Any adverse effects on the streetscape.</u> <p><u>RDIS</u></p>

IPI - PROPOSED AMENDMENTS												
#	Chapter	Change	Track Change									
			<ol style="list-style-type: none"> 3. Visual dominance, shading and loss of privacy for adjoining Residential or Open Space and Recreation zoned sites. 4. Compatibility with the planned built urban form of buildings, structures and activities in the surrounding area. 5. Whether an increase in building height results from a response to natural hazard mitigation. 6. Whether topographical or other site constraints make compliance with the standard impractical. 7. Reverse sensitivity effects. 									
SAZ – Special Activity Zone	Amend Standard	<p>Standards for Permitted and Controlled Activities</p> <p>Zone-wide (including St. Patrick’s Estate College Area)</p> <p>SAZ-S2</p> <p><i>Policies</i> GRZ-P4 SAZ-P2 SAZ-P3</p> <p>Sunlight access</p> <p>(1) All buildings on sites adjoining, or separated by a road from a site in the Residential or Open Space Zone, shall comply with the height control planes in relation to boundary standard defined in GRZ-S8 along the adjoining boundary or the boundary or boundaries separated by a road.</p>										
SAZ – Special Activity Zone	Amend Standard	<p>Zone-wide (excluding St. Patrick’s Estate College Area)</p> <p>St Patrick’s Estate College Area only</p> <p>In addition to compliance with the zone-wide provisions and the Citywide rules, all permitted activities within the St Patrick’s Estate College Area shall also comply with the following standards.</p> <p>SAZ-S8</p> <p><i>Policies</i> SAZ-P3 SAZ-P4</p> <p>Setbacks from boundaries</p> <p>(1) The setback distance for buildings shall not be less than:</p> <table border="1"> <thead> <tr> <th></th> <th>Managed Development Area*</th> <th>St Patrick’s College Area*</th> </tr> </thead> <tbody> <tr> <td>(a) Front boundary - Fergusson Drive</td> <td>10m</td> <td>10m</td> </tr> <tr> <td>(b) Any other front boundary</td> <td>5m</td> <td>5m</td> </tr> </tbody> </table>		Managed Development Area*	St Patrick’s College Area*	(a) Front boundary - Fergusson Drive	10m	10m	(b) Any other front boundary	5m	5m	
	Managed Development Area*	St Patrick’s College Area*										
(a) Front boundary - Fergusson Drive	10m	10m										
(b) Any other front boundary	5m	5m										

IPI - PROPOSED AMENDMENTS											
#	Chapter	Change	Track Change								
			<table border="1"> <tr> <td>(c)</td> <td>Side boundary</td> <td>5m</td> <td>10m</td> </tr> <tr> <td>(d)</td> <td>Rear boundary</td> <td>10m</td> <td>10m</td> </tr> </table> <p><i>* Identified on Planning Maps</i></p>	(c)	Side boundary	5m	10m	(d)	Rear boundary	10m	10m
(c)	Side boundary	5m	10m								
(d)	Rear boundary	10m	10m								
	SAZ – Special Activity Zone	Amend Standard	<p>SAZ-S9</p> <p><i>Policies</i> SAZ-P3 SAZ-P4</p> <p>Building coverage</p> <p>(1) The <u>maximum building coverage by buildings</u> on a site shall not exceed <u>10%</u>.</p> <table border="1"> <tr> <td></td> <td>Managed Development Area*</td> <td>St Patrick's College Area*</td> </tr> <tr> <td><u>Maximum building coverage</u></td> <td>40%</td> <td>10%</td> </tr> </table> <p><i>* Identified on Planning Maps</i></p>		Managed Development Area*	St Patrick's College Area*	<u>Maximum building coverage</u>	40%	10%		
	Managed Development Area*	St Patrick's College Area*									
<u>Maximum building coverage</u>	40%	10%									
	SAZ – Special Activity Zone	Amend Standard	<p>SAZ-S10</p> <p><i>Policies</i> SAZ-P3 SAZ-P4</p> <p>Building Height</p> <p>(1) The maximum height above ground level of any building shall not exceed <u>8m</u>.</p> <table border="1"> <tr> <td></td> <td>Managed Development Area*</td> <td>St Patrick's College Area*</td> </tr> <tr> <td><u>Maximum building height</u></td> <td>8m</td> <td>8m</td> </tr> </table> <p><i>* Identified on Planning Maps</i></p>		Managed Development Area*	St Patrick's College Area*	<u>Maximum building height</u>	8m	8m		
	Managed Development Area*	St Patrick's College Area*									
<u>Maximum building height</u>	8m	8m									
	SAZ – Special Activity Zone	Retain Standard	<p>SAZ-S11</p> <p><i>Policies</i> SAZ-P3 SAZ-P5</p> <p>Screening</p> <p>(1) Outdoor storage areas shall be screened by a close-boarded fence, a solid wall or dense planting</p>								
	SAZ – Special Activity Zone	Amend Standard	<p>SAZ-S12</p> <p><i>Policies</i> SAZ-P3 SAZ-P5</p> <p>Landscaping</p> <p>(1) Front boundary setback areas along Fergusson Drive and County Lane shall be landscaped into a partial screen through earth shaping and permanent plantings of trees and shrubs.</p> <p>(2) If parking or accessways are provided between the road boundary and the building, a landscape strip with a minimum width of 0.6m shall be provided within the St Patrick's Estate <u>College</u> site along the road boundary.</p>								

IPI - PROPOSED AMENDMENTS																		
#	Chapter	Change	Track Change															
	SAZ – Special Activity Zone	Amend and Retain Standard	<table border="1"> <tr> <td>SAZ-S13</td> <td>Building restriction</td> <td></td> </tr> <tr> <td><i>Policies</i></td> <td>(1) No building, structure or earthworks shall be located or undertaken within 200m of the southern bank of the Hutt River and to the north of the Mawaihakona Stream.</td> <td></td> </tr> <tr> <td><i>NIH-P1</i></td> <td></td> <td></td> </tr> <tr> <td><i>NIH-P2</i></td> <td></td> <td></td> </tr> </table>	SAZ-S13	Building restriction		<i>Policies</i>	(1) No building, structure or earthworks shall be located or undertaken within 200m of the southern bank of the Hutt River and to the north of the Mawaihakona Stream.		<i>NIH-P1</i>			<i>NIH-P2</i>					
SAZ-S13	Building restriction																	
<i>Policies</i>	(1) No building, structure or earthworks shall be located or undertaken within 200m of the southern bank of the Hutt River and to the north of the Mawaihakona Stream.																	
<i>NIH-P1</i>																		
<i>NIH-P2</i>																		
	SAZ – Special Activity Zone	Amend Rule Table Heading	<table border="1"> <tr> <td colspan="3">Discretionary Activities</td> </tr> <tr> <td colspan="3">Zone-wide (excluding the St Patrick's Estate College Area)</td> </tr> <tr> <td>SAZ-R27</td> <td>Activities which do not comply with the permitted and ...</td> <td>DIS</td> </tr> </table>	Discretionary Activities			Zone-wide (excluding the St Patrick's Estate College Area)			SAZ-R27	Activities which do not comply with the permitted and ...	DIS						
Discretionary Activities																		
Zone-wide (excluding the St Patrick's Estate College Area)																		
SAZ-R27	Activities which do not comply with the permitted and ...	DIS																
	SAZ – Special Activity Zone	Amend Rule Table Heading	<table border="1"> <tr> <td colspan="3">Non-complying Activities</td> </tr> <tr> <td colspan="3">Zone-wide (excluding the St Patrick's Estate College Area)</td> </tr> <tr> <td>SAZ-R28</td> <td>Buildings or structures within 12m of high voltage (110kV or greater) electricity transmission lines as shown on the Planning Maps *(refer to the definition of transmission line)</td> <td>NC</td> </tr> <tr> <td>SAZ-R29</td> <td>Activities which are not listed in this table unless otherwise covered in the District-wide matters of the Plan</td> <td>NC</td> </tr> </table>	Non-complying Activities			Zone-wide (excluding the St Patrick's Estate College Area)			SAZ-R28	Buildings or structures within 12m of high voltage (110kV or greater) electricity transmission lines as shown on the Planning Maps *(refer to the definition of transmission line)	NC	SAZ-R29	Activities which are not listed in this table unless otherwise covered in the District-wide matters of the Plan	NC			
Non-complying Activities																		
Zone-wide (excluding the St Patrick's Estate College Area)																		
SAZ-R28	Buildings or structures within 12m of high voltage (110kV or greater) electricity transmission lines as shown on the Planning Maps *(refer to the definition of transmission line)	NC																
SAZ-R29	Activities which are not listed in this table unless otherwise covered in the District-wide matters of the Plan	NC																
	SAZ – Special Activity Zone	Amend Rules	<table border="1"> <tr> <td colspan="3">St Patrick's Estate College Area only</td> </tr> <tr> <td>SAZ-R30</td> <td>Retailing excluding garden centres</td> <td>NC</td> </tr> <tr> <td>SAZ-R31</td> <td>Activities which do not comply with the permitted or controlled activity standards or which are not listed in this table unless otherwise covered in the District-wide matters of the Plan</td> <td>NC</td> </tr> <tr> <td>SAZ-R32</td> <td>Medical facilities (St Patrick's College Area* only)</td> <td>NC</td> </tr> <tr> <td colspan="3">* Identified on the Planning Maps</td> </tr> </table>	St Patrick's Estate College Area only			SAZ-R30	Retailing excluding garden centres	NC	SAZ-R31	Activities which do not comply with the permitted or controlled activity standards or which are not listed in this table unless otherwise covered in the District-wide matters of the Plan	NC	SAZ-R32	Medical facilities (St Patrick's College Area* only)	NC	* Identified on the Planning Maps		
St Patrick's Estate College Area only																		
SAZ-R30	Retailing excluding garden centres	NC																
SAZ-R31	Activities which do not comply with the permitted or controlled activity standards or which are not listed in this table unless otherwise covered in the District-wide matters of the Plan	NC																
SAZ-R32	Medical facilities (St Patrick's College Area* only)	NC																
* Identified on the Planning Maps																		
	SAZ – Special Activity Zone	Amend Rule	<table border="1"> <tr> <td colspan="3">Prohibited Activities</td> </tr> <tr> <td colspan="3">Zone-wide (including the St Patrick's Estate College Area)</td> </tr> <tr> <td>SAZ-R33</td> <td>Gang fortifications</td> <td>PR</td> </tr> </table>	Prohibited Activities			Zone-wide (including the St Patrick's Estate College Area)			SAZ-R33	Gang fortifications	PR						
Prohibited Activities																		
Zone-wide (including the St Patrick's Estate College Area)																		
SAZ-R33	Gang fortifications	PR																
	SAZ – Special Activity Zone	Amend Method	Methods															

IPI - PROPOSED AMENDMENTS					
#	Chapter	Change	Track Change		
			<p>SAZ-M1 District Plan provisions consisting of the following:</p> <ol style="list-style-type: none"> (1) A Special Activity Zone containing special land uses and environments within the City. Rules and standards reflect environmental standards so that adverse effects can be avoided, remedied or mitigated. (2) For the St Patrick's Estate Area two special areas are identified. These are the Managed Development Area, which provides for a range of development options, and tThe St Patrick's College Area which promotes the development of educational facilities. These areas are identified on the Planning Maps. (3) Rules controlling vegetation clearance, setbacks, earthworks, minimum allotment size, noise and other nuisances, and building. 		
SAZ – Special Activity Zone	Amend Anticipated Environmental Results	Anticipated environmental results			
		SAZ-AER3	Development on the St Patrick's Estate College Area which has due regard to the flood hazards, the environmental characteristics of the site and the compatibility of a diverse range of activities	Monitoring indicators Resource consents by type Change in land cover and use Development in identified natural hazard areas	Data source Council resource consent records
		SAZ-AER4	A built environment which ...	Resource consents and type and ... Consultation and ...	Council records
DEVELOPMENT AREAS					
Development Area 1 - Wallaceville Structure Plan Development Area					
Development Area 1 - Wallaceville Structure Plan Development Area			This chapter contains provisions which relate to the Wallaceville Structure Plan Development Area . These provisions apply in addition to the underlying zone rules of the General Residential Zone , High Density Residential Zone , and the Commercial Local Centre Local Centre Zone and relevant District-wide Matters. Where there is any conflict between the provisions the Wallaceville Structure Plan Development Area provisions shall prevail. Subdivision provisions for the Wallaceville Structure Plan Development Area are located in the Subdivision Chapter (SUB).		
Development Area 1 - Wallaceville			Objectives Wallaceville Living Precinct Area A, Wallaceville Living Precinct Area B, Urban Precinct and Grants Bush Precinct		

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	Structure Plan Development Area		The following objective relates to the Wallaceville Living Precinct Area A, the Wallaceville Living Precinct Area B, the Urban Precinct and the Grants Bush Precinct of the Wallaceville Structure Plan Development Area . It applies in addition to the objectives of the underlying General Residential Zone or High Density Residential Zone and provides additional guidance specific to the identified areas of the Structure Plan.
	Development Area 1 - Wallaceville Structure Plan Development Area		Gateway Precinct The following objective relates to the Gateway Precinct of the Wallaceville Structure Plan Development Area and applies in addition to the objectives of the underlying Commercial Local Centre Zone . It provides additional guidance specific to the Gateway Precinct of the Structure Plan.
	Development Area 1 - Wallaceville Structure Plan Development Area		Policies Wallaceville Living Precinct Area A, Wallaceville Living Precinct Area B, Urban Precinct and Grants Bush Precinct The following policies apply to the Wallaceville Living Precinct Area A, the Wallaceville Living Precinct Area B, the Urban Precinct and the Grants Bush Precinct of the Wallaceville Structure Plan Development Area , in addition to the policies of the underlying General Residential Zone or High Density Residential Zone . They provide additional guidance specific to the identified areas of the Structure Plan.
	Development Area 1 - Wallaceville Structure Plan Development Area		DEV1-P1 <i>To ensure that non-residential activities within residential areas do not cause significant adverse environmental effects.</i> While provided for as a Discretionary Activity, it is recognised that commercial development may take place in the Urban Precinct of the Wallaceville Structure Plan, which may include the commercial redevelopment of the farm management building and dairy building , provided that significant adverse environmental effects on the Commercial Local Centre Zone (the Gateway Precinct), residential activities and other areas of Upper Hutt City can be avoided or mitigated. This does not preclude other potential development options for the Urban Precinct being developed that are compatible with residential activities . Resource consent applications for any commercial development not consistent with the Wallaceville Structure Plan will need to be carefully assessed against Policies DEV-P1 in particular.
	Development Area 1 - Wallaceville Structure Plan Development Area		DEV1-P4 <i>To encourage higher density housing through the provision of reduced net site area standards and in the form of Comprehensive Residential Developments in identified areas of the City.</i> The Plan identifies areas considered suitable for higher density residential development. These areas are located surrounding the central business district, around the Trentham neighbourhood centre located at Camp Street, near

IPI - PROPOSED AMENDMENTS												
#	Chapter	Change	Track Change									
			<p>the Wallaceville railway station from Ward Street to Lane Street and within the Urban Precinct and Grants Bush Precinct of the Wallaceville Structure Plan Development Area.</p> <p>These areas are in close proximity to retail and service facilities as well as the availability of major transport points, including rail and bus services, and a major bus terminal in the CBD.</p>									
	Development Area 1 - Wallaceville Structure Plan Development Area		<p>Gateway Precinct</p> <p>The following policies apply within the Gateway Precinct of the Wallaceville Structure Plan Development Area. They apply in addition to the underlying policies of the Commercial <u>Local Centre</u> Zone and provide additional guidance specific to the Gateway Precinct of the Structure Plan.</p>									
	Development Area 1 - Wallaceville Structure Plan Development Area		<p>DEV1-P7 <i>To control the size and scale of buildings and the visual appearance of sites within the Commercial <u>Local Centre</u> Zone.</i></p> <p>...</p>									
	Development Area 1 - Wallaceville Structure Plan Development Area		<p>Rules</p> <p>Wallaceville Living Precinct Area A, Wallaceville Living Precinct Area B, Urban Precinct and Grants Bush Precinct</p> <p>The following provisions relate to the Wallaceville Living Precinct Area A, the Wallaceville Living Precinct Area B, the Urban Precinct and the Grants Bush Precinct of the Wallaceville Structure Plan Development Area. They apply in addition to the provisions of the underlying General Residential Zone or High Density Residential Zone. Where there is any conflict between the provisions the Wallaceville Structure Plan Development Area provisions shall prevail</p>									
	Development Area 1 - Wallaceville Structure Plan Development Area		<table border="1"> <thead> <tr> <th colspan="3">Restricted Discretionary Activities</th> </tr> </thead> <tbody> <tr> <td>DEV1-R1</td> <td>Comprehensive Residential Development on a site within the Residential Centres Precinct complying with the standards and terms of GRZ-PREC1-S10</td> <td>RDIS</td> </tr> <tr> <td><i>Policies</i> GRZ-P1, GRZ-P2, GRZ-PREC1-P1, DEV1-P2, GRZ-P4, DEV1-P4,</td> <td> <p>The following provisions apply in addition to the requirements of GRZ-PREC1-R2</p> <p>In considering a resource consent application, Council's discretion is also restricted to an assessment against the Wallaceville Structure Plan.</p> <p>Restriction on notification</p> <p>For Comprehensive Residential Development in the Wallaceville Structure Plan Development Area, in respect of this rule, and subject to sections 95A(2)(b), 95A(4) and 95C of the Act, an application which</p> </td> <td></td> </tr> </tbody> </table>	Restricted Discretionary Activities			DEV1-R1	Comprehensive Residential Development on a site within the Residential Centres Precinct complying with the standards and terms of GRZ-PREC1-S10	RDIS	<i>Policies</i> GRZ-P1, GRZ-P2, GRZ-PREC1-P1, DEV1-P2, GRZ-P4, DEV1-P4,	<p>The following provisions apply in addition to the requirements of GRZ-PREC1-R2</p> <p>In considering a resource consent application, Council's discretion is also restricted to an assessment against the Wallaceville Structure Plan.</p> <p>Restriction on notification</p> <p>For Comprehensive Residential Development in the Wallaceville Structure Plan Development Area, in respect of this rule, and subject to sections 95A(2)(b), 95A(4) and 95C of the Act, an application which</p>	
Restricted Discretionary Activities												
DEV1-R1	Comprehensive Residential Development on a site within the Residential Centres Precinct complying with the standards and terms of GRZ-PREC1-S10	RDIS										
<i>Policies</i> GRZ-P1, GRZ-P2, GRZ-PREC1-P1, DEV1-P2, GRZ-P4, DEV1-P4,	<p>The following provisions apply in addition to the requirements of GRZ-PREC1-R2</p> <p>In considering a resource consent application, Council's discretion is also restricted to an assessment against the Wallaceville Structure Plan.</p> <p>Restriction on notification</p> <p>For Comprehensive Residential Development in the Wallaceville Structure Plan Development Area, in respect of this rule, and subject to sections 95A(2)(b), 95A(4) and 95C of the Act, an application which</p>											

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>DEV1-P5, NU-P3</p> <p>meets the relevant standards and terms will be decided without the need for public notification under section 95A and any application that is consistent with the Wallaceville Structure Plan will be decided without the need for limited notification under section 95B.</p>
	Development Area 1 - Wallaceville Structure Plan Development Area		<p>Restricted Discretionary Activity Standards</p> <p>DEV1-S9</p> <p>Comprehensive Residential Development</p> <p>The following provisions apply in addition to the requirements of GRZ-PREC1-S10</p> <p>Additional standards and terms for Comprehensive Residential Development within the Wallaceville Structure Plan Development Area:</p> <p>(1) Compliance with noise insulation and ventilation standards of DEV1-S6 and DEV1-S7</p> <p>(2) Compliance with the fencing standards of DEV1-S8</p> <p>Policies GRZ-P1, GRZ-P2, GRZ-PREC1-P1, DEV1-P2, GRZ-P4, DEV1-P4, DEV1-P5, NU-P3</p>
		DEV1-S1	<p>Standards for Permitted and Controlled Activities</p> <p>DEV1-S1</p> <p>Access standards for land use activities</p> <p>The following standards apply in addition to the requirements of GRZ-S1</p> <p>(1) ...</p> <p>Policies GRZ-P2, GRZ-PREC1-P1, GRZ-PREC1-P2, GRZ-P7, DEV1-P4</p>
	Urban Precinct - Wallaceville Structure Plan Development Area	DEV1-S4	<p>Standards for Permitted and Controlled Activities</p> <p>DEV1-S4</p> <p>Building height</p> <p>The following exemption applies to the requirements of GRZ-S7</p> <p>(1) New buildings as part of a Comprehensive Residential Development in the Urban Precinct of the Wallaceville Structure Plan Development Area where the maximum height above ground level of any building shall not exceed 10m</p> <p>Policies GRZ-P2, GRZ-PREC1-P1, DEV1-P2, GRZ-P4</p>
	Urban Precinct - Wallaceville	DEV1-S5	<p>Standards for Permitted and Controlled Activities</p> <p>DEV1-S5</p> <p>Sunlight access</p>

Commented [MM241]: S46.10 - Blue Mountains Campus Development Limited Partnership.

Commented [MM242]: S46.13 - Blue Mountains Campus Development Limited Partnership.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
	Structure Plan Development Area		<p><i>Policies</i> GRZ-P2, GRZ-PREC1-P1, DEV1-P2, GRZ-P4</p> <p>The following exemption applies to the requirements of GRZ-S8</p> <p>Exemptions: (1) In the Urban Precinct of the Wallaceville Structure Plan Development Area, for semi-detached residential units the sunlight access provisions shall not apply on the shared common wall.</p>
	Gateway Precinct - Wallaceville Structure Plan Development Area		<p>Gateway Precinct The following provisions apply to the Gateway Precinct of the Wallaceville Structure Plan Development Area. They apply in addition to the provisions of the underlying Commercial Local Centre Zone. Where there is any conflict between the provisions the Wallaceville Structure Plan Development Area provisions shall prevail.</p>
	Gateway Precinct - Wallaceville Structure Plan Development Area	Delete DEV1-S10	<p>Standards for Permitted and Controlled Activities</p> <p>DEV1-S10 Loading Provisions</p> <p><i>Policies</i> COMZ-P1, CCZ-P2</p> <p>(1) Loading spaces required under COMZ-S6 do not apply to the floor area of residential activities located in the Gateway Precinct of the Wallaceville Structure Plan Development Area.</p>
	Gateway Precinct - Wallaceville Structure Plan Development Area	Amend DEV1-S12	<p>Standards for Permitted and Controlled Activities</p> <p>DEV1-S12 Screening</p> <p><i>Policies</i> COMZ-P1, COMZ-P2</p> <p>(1) The land identified in in the Gateway Precinct of the Wallaceville Structure Plan Development Area is exempt from the screening specified in COMZ-S8.</p>
	Gateway Precinct - Wallaceville Structure Plan Development Area	Delete DEV1-S13	<p>Standards for Permitted and Controlled Activities</p> <p>DEV1-S12 Landscaping</p> <p><i>Policies</i> COMZ-P1, DEV1-P2, CCZ-P2</p> <p>(1) The land identified in in the Gateway Precinct of the Wallaceville Structure Plan Development Area is exempt from the landscaping specified in COMZ-S9 (2).</p>
	Development Area 1 - Wallaceville Structure Plan Development Area	Amend restriction on notification clause within DEV1-R5	<p>Restriction on notification In respect of this rule, and subject to sections 95A(2)(b), 95A(2)(c), 95A(4) and 95C of the Act, an application which meets the relevant standards and terms will be decided without the need for public notification under section 95A and any application that is consistent with the Wallaceville Structure Plan, without the need for limited notification under Section 95B and for new buildings</p>

Commented [MM243]: S46.14 - Blue Mountains Campus Development Limited Partnership.

Commented [MM244]: S46.3 - Blue Mountains Campus Development Limited Partnership.

Commented [MM245]: S46.4 - Blue Mountains Campus Development Limited Partnership.

Commented [MM246]: S46.5 - Blue Mountains Campus Development Limited Partnership.

Commented [MM247]: S46.6 - Blue Mountains Campus Development Limited Partnership.

IPI - PROPOSED AMENDMENTS							
#	Chapter	Change	Track Change				
			within the heritage covenant area limited notification will only be served on Heritage New Zealand (unless affected party approval is provided) under section 95B of the Act.				
	Development Area 1 - Wallaceville Structure Plan Development Area	Amend DEV1-R6 rule references	<table border="1"> <thead> <tr> <th colspan="2">Discretionary Activities</th> </tr> </thead> <tbody> <tr> <td>DEV1-R6</td> <td>Garden centres and all activities other than retail activity, restaurants, offices, early childhood centres, and residential accommodation above ground level and not otherwise provided for as non-complying in COMZ R20 and COMZ R21 the Local Centre Zone in the Gateway Precinct of the Wallaceville Structure Plan Development Area.</td> </tr> </tbody> </table>	Discretionary Activities		DEV1-R6	Garden centres and all activities other than retail activity, restaurants, offices, early childhood centres, and residential accommodation above ground level and not otherwise provided for as non-complying in COMZ R20 and COMZ R21 the Local Centre Zone in the Gateway Precinct of the Wallaceville Structure Plan Development Area .
Discretionary Activities							
DEV1-R6	Garden centres and all activities other than retail activity, restaurants, offices, early childhood centres, and residential accommodation above ground level and not otherwise provided for as non-complying in COMZ R20 and COMZ R21 the Local Centre Zone in the Gateway Precinct of the Wallaceville Structure Plan Development Area .						
	Wallaceville Living Precinct Area A, Wallaceville Living Precinct Area B, Urban Precinct and Grants Bush Precinct - Wallaceville Structure Plan Development Area	DEV1-MC1	<table border="1"> <thead> <tr> <th colspan="2">Standards for Permitted and Controlled Activities</th> </tr> </thead> <tbody> <tr> <td>DEV1-MC1</td> <td>Development in the Wallaceville Structure Plan Development Area (1) Relevant matters GRZ-MC1 to GRZ-MC10 and GRZ-PREC1-MC1 to GRZ-PREC1-MC2</td> </tr> </tbody> </table>	Standards for Permitted and Controlled Activities		DEV1-MC1	Development in the Wallaceville Structure Plan Development Area (1) Relevant matters GRZ-MC1 to GRZ-MC10 and GRZ-PREC1-MC1 to GRZ-PREC1-MC2
Standards for Permitted and Controlled Activities							
DEV1-MC1	Development in the Wallaceville Structure Plan Development Area (1) Relevant matters GRZ-MC1 to GRZ-MC10 and GRZ-PREC1-MC1 to GRZ-PREC1-MC2						
	Development Area 1 - Wallaceville Structure Plan Development Area		<p>Methods</p> <p>DEV1-M1 District Plan provisions consisting of a General Residential Zone and High Density Residential Zone identifying the residential environments within the City, including the Conservation and Hill Areas Precincts, and the Residential Centres Precinct and the Wallaceville Structure Plan Development Area. Rules and standards apply to activities so that adverse effects are avoided, remedied or mitigated. Consent application procedures provide for the consideration of effects on a case by- case basis and the imposition of appropriate conditions when necessary.</p>				
	Development Area 1 - Wallaceville Structure Plan Development Area		<p>Wallaceville Structure Plan</p> <p>1 PRECINCT DESCRIPTIONS, INTENTIONS AND OUTCOMES</p> <p>1.3 Gateway Precinct</p> <p>1.3.2 Outcomes</p> <p>(1) Re-use of existing buildings and ...</p> <p>(2) New tree planting to ...</p> <p>(3) Fencing along ...</p>				

Commented [MM248]: S46.7 - Blue Mountains Campus Development Limited Partnership

Commented [MM249]: S46.15 - Blue Mountains Campus Development Limited Partnership.

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
			<ul style="list-style-type: none"> (4) Provision of a neighbourhood ... (5) Main public road ... (6) A simple, grid structure, ... (7) signage and advertising ... (8) Materials and colours ... (9) Retention of existing ... (10) Naming of streets to ... (11) Height of new buildings to ... (12) Residential development that is consistent with the Design Guide for the Residential Centres Precinct. <p>1.4 Urban Precinct</p> <p>1.4.1 Intentions</p> <ul style="list-style-type: none"> (1) A compact and attractive high density residential precinct, making efficient use of the land resource in this location and providing a transition from the Commercial <u>Local Centre</u> Zone to other residential areas. <p>1.4.2 Outcomes</p> <ul style="list-style-type: none"> (1) A height limit to allow ... (2) A simple, grid structure, ... (3) A range of housing types, ... (4) Some business/... (5) Retention of healthy ... (6) Subdivision and development to ... (7) New tree planting ... (8) Utilisation of a ... (9) Provides active ... (10) Active frontage and ... (11) Development that ... (12) Residential development that is consistent with the Design Guide for Residential Centres Precinct <p>1.5 Grants Bush Precinct</p> <p>1.5.2 Outcomes</p> <ul style="list-style-type: none"> (1) A range of housing types ... (2) A simple, grid structure, ... (3) Road frontage to ... (4) Active edges to ... (5) A main public park ...

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<ul style="list-style-type: none"> (6) Grants Bush covenant ... (7) Landscaping character ... (8) Variation in building ... (9) Low level front fencing ... (10) Front boundaries along ... (11) Subdivision and ... (12) Pedestrian/cycle connection ... (13) Pedestrian connection through ... (14) Protection of the ... (15) Active frontage and ... (16) Development that incorporates ... (17) Residential development that is consistent with the Design Guide for the Residential Centres Precinct.

PART 4 – APPENDICES AND MAPS

APPENDICES

Appendix 1 – Medium and High Density Design Guide


Design Guide for the Residential Centres Precinct	Delete Design Guide for the Residential Centres Precinct.	<p>Design Guide for the Residential Centres Precinct</p> <p>The Design Guide</p> <p>The purpose of the design guide is to provide design criteria that will direct the delivery of well designed, good quality higher density housing in an Upper Hutt specific context. The guide applies specifically to Comprehensive Residential Development and subdivision that produces small lots. These developments, because of their higher density and potential effect on residential amenity, will require resource consents. Applications will be required to demonstrate how the design of the development has addressed the criteria in this Design Guide, in addition to meeting the relevant standards and objectives and policies of the District Plan.</p> <p>This design guideline is structured in three parts. The first focuses on the specific requirements of Comprehensive Residential Developments and the second concentrates on small site design – most relevant to infill style subdivision, or developments of small scale stand alone residential unit. The two parts should be read as a whole, and the guidance provided should be considered to achieve improved urban outcomes for all forms of residential development.</p> <p>The third part of the Design Guide contains Character Statements for the Residential Centres Precinct, to assist in understanding the elements of character in those areas and responding positively to the Design Guide with these in mind.</p>
---	---	--

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>What is Comprehensive Residential Development?</p> <p>Comprehensive residential development is a way of providing a greater degree of choice in housing in Upper Hutt. It involves developing sites in a planned and efficient way with a greater density of housing than has been done in the past. It delivers an alternative to traditional development patterns of houses on large sections, and is a way to make efficient use of land while still providing houses that are attractive, private and often, more affordable to buy and through improved design, providing lower cost of living. Different forms of housing also provide choice for those who do not want or need larger houses or sections, especially if they wish to remain in a community they have come to like.</p> <p>Across the residential areas of Upper Hutt, several areas called the Residential Centres Precinct has been specifically identified as suitable locations for this sort of development to occur. These areas are in proximity to local amenities and public transport, and are ideal locations for housing developments at a greater density</p> <p>As density increases, more thought needs to be given to creating good quality living spaces alongside pleasing streets and townscape. Higher density housing is often thought to lead to poor urban quality, overcrowding and reduced space standards. However, poor quality outcomes are often a result of poorly conceived or inflexible design rather than just increased density. The best sorts of outcomes are achieved by examining context and designing a carefully considered, specific solution for each site.</p> <p>The design of higher density residential development needs to respond to the qualities of the street and the area, and to provide for the needs of the inhabitants. Good quality housing will meet current and future demand, and cater for the needs of the city's changing population.</p> <p>Aims for comprehensive residential developments:</p> <ul style="list-style-type: none"> ➤ Houses and open space are located and arranged on the site in an integrated and comprehensive manner. ➤ New development contributes positively to the character of the neighbourhood. ➤ Reasonable privacy for the residents and neighbours is provided through well considered siting and design of buildings. ➤ Housing provides a high quality and efficient living environment (both internal and external) for occupants. <p><i>Note: Where a development incorporates an existing house(s) the requirements of this Guide shall apply equally to that house(s).</i></p> <p>What is a 'small site'?</p> <p>Within the Residential Centres Precinct, the District Plan provides for a lower minimum net site area than in other residential areas. Such small lots present design challenges, and simply 'miniaturising' more commonly seen forms of development may not produce the best outcomes for amenity either on site or for the wider area. A careful approach is needed to ensure that small lots continue to create sites that are both developable, and able to accommodate houses that are well designed and afford good amenity to occupants.</p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>Aims for small site design:</p> <ul style="list-style-type: none"> ➤ Lots are of an adequate width and suitable shape to accommodate a residential dwelling. ➤ Lots are oriented for access to sunlight and to take advantage of solar gain to internal spaces. ➤ Lots are designed to ensure that useable outdoor space will be readily accessible from future dwelling sites. ➤ Lots are laid out and designed, and building sites identified, so as to provide for the retention of significant trees and vegetation. ➤ Access to lots is designed so as to minimise its visual impact and dominance. ➤ Lots and residential unit sites are located and shaped to minimise adverse impact on existing development surrounding the site, and potential future development. <p>COMPREHENSIVE RESIDENTIAL DEVELOPMENTS</p> <p>Integrated Buildings and Spaces</p> <p>As housing density increases there is a corresponding need to make sure that buildings are arranged carefully across sites and that spaces around them fulfil useful and sensible functions. In Upper Hutt, the sense of space around buildings is valued as part of the townscape, so new developments should aim to enhance this wherever possible.</p> <p>However, this does not mean that all houses need to be physically separate and have space on all sides. Well designed attached housing can provide both on-site amenity and value to the wider area, by employing careful consideration of how buildings are arranged and outdoor spaces are allocated from the outset of the design process. The ability to accommodate landscaping on-site (particularly vegetation that grows to a mature height above fence level) will also have an impact on both the sense of spaciousness around houses and the character of the wider neighbourhood.</p> <p>How vehicles are accommodated on sites also has an impact on amenity outcomes. Site design should aim to consider buildings, the spaces surrounding them, vehicles and landscaping as part of a comprehensive whole at the outset of the design process.</p> <p>Guidelines</p> <ul style="list-style-type: none"> ➤ The siting of buildings and open space should be designed in an integrated way so that buildings can connect with useful outdoor space that has reasonable privacy, good access to sunlight, and a sense of openness. (See figure 1)


IPI - PROPOSED AMENDMENTS


#	Chapter	Change	Track Change
			<div data-bbox="824 373 1348 663" data-label="Image"> </div> <p data-bbox="584 683 1592 703"><i>Figure 1: Carefully considered layout of buildings on sites helps to contribute to a more pleasant living environment.</i></p> <ul data-bbox="607 722 1659 770" style="list-style-type: none"> ➤ <i>Each unit should have its own private outdoor space, for use exclusively as outdoor recreational space. Shared spaces as the principal means of providing outdoor living areas will only be considered in special circumstances.</i> <p data-bbox="613 790 1659 863"><i>Outdoor space within the site needs to be planned for at the design stage to ensure it is useable rather than residual to the buildings. It also needs to be easily accessible and connected to main living areas, and should not have any part of its area used for any other required function for the site i.e. as part of the on-site parking or manoeuvring requirements.</i></p> <p data-bbox="613 882 1659 978"><i>Shared spaces may be considered in situations such as for comprehensively planned elderly persons' housing, sheltered/community housing or papakainga. Such instances will be individually assessed to ensure the space provided is of the best quality possible and will meet the specific needs of residents, while also ensuring reasonable privacy to interior living spaces.</i></p> <ul data-bbox="607 997 1659 1201" style="list-style-type: none"> ➤ <i>The outdoor living area allocated to each residential unit should have within it a 'principal area' that is:</i> <ul style="list-style-type: none"> — <i>Directly accessible from the main indoor living area of that dwelling;</i> — <i>Positioned to have regard to shelter from the prevailing wind, or be detailed so as to minimise the worst effects of that wind;</i> — <i>Oriented with a northerly aspect to take advantage of natural sunlight;</i> — <i>Able to accommodate a square of 4m x 4m;</i> — <i>Nominally flat, with a gradient of no greater than 1 in 12;</i> — <i>Not located between the residential unit and any public street.</i> <p data-bbox="613 1220 1659 1294"><i>The allocation of a 'principal area' within the overall requirement of outdoor living space ensures that a minimum amount of the outdoor space for a residential unit is carefully considered, and of the highest quality for usability, access and privacy. Although one larger space is preferred, two or more smaller spaces will be considered acceptable where it is</i></p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p><i>possible to demonstrate that this leads to a better outcome in terms of providing quality, useable outdoor living space. (See figure 2)</i></p>  <p><i>Figure 2: Different types of spaces can all contribute to creating a pleasant outdoor living environment.</i></p> <ul style="list-style-type: none"> ➤ Landscaping of outdoor spaces should be comprehensively planned as part of the overall site design from an early stage. <p><i>Landscaping can play a role in helping to define spaces on a site. Landscaping plans should ideally be submitted as part of a resource consent application so the outcomes can be considered as part of a comprehensive whole.</i></p> <ul style="list-style-type: none"> ➤ Where units are at first floor level or above, balconies or roof terraces may be appropriate to provide for outdoor space, subject to careful consideration of privacy. If adequate privacy cannot be obtained by orientation of the spaces or the placement of windows, screening should be used. ➤ Where there are common outdoor areas on a site, these should connect with the built development by ensuring windows overlook the space, doors to units open on to the space and the dominance of the area by garage doors or parked cars is avoided. <p><i>Common areas or shared spaces can contribute positively to the enjoyment of development. They can be used for meeting places, barbeque areas and a place to kick a ball around. These spaces can be made more enjoyable and safe if people inside units can oversee activity in them. The dominance of cars within these areas will detract from their ability to be used for these activities and the amenity of the development.</i></p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>➤ Outdoor rubbish, clothes drying, recycling and storage space should be located so that these facilities are not visually obtrusive, are not located within the 'principal area', do not dominate the entry to residences and are easily accessible to the unit which they serve.</p> <p><i>Rubbish enclosures and storage can detract from the appearance of the development and the neighbourhood as well as the amenity of outdoor spaces and as with most existing houses, is most appropriately located in less visible areas and away from locations used for outdoor living.</i></p> <p><i>Outdoor rubbish areas should be screened if they are located within sight of the principal outdoor area.</i></p> <p><i>For terraced houses, where front yard rubbish/recycling storage may be the most appropriate to avoid the need to move these items through the interior of the house, a carefully designed enclosure with adequate ventilation, incorporated into the overall landscaping plan, will usually be the best solution.</i></p> <p>Fitting in with the neighbourhood</p> <p>Many areas of Upper Hutt have a well-developed sense of character. Much of the city's residential area (and the locations in which redevelopment is most likely to occur) is located on the flat valley floor. Older housing stock is often single-storey, set back from the street edge and located near the centre of a large rectangular site. Housing displays a wide variety of architectural styles, and mature vegetation contributes to the sense of established neighbourhoods.</p> <p>Comprehensive residential developments will introduce housing at a greater density into established neighbourhoods. In order for this to be successful, the essential elements of character in a neighbourhood must be understood, and where those elements create a positive contribution, they should be respected (but not necessarily replicated) in the new design. Understanding the key building patterns of the area will help guide new development so that it can sit comfortably within an established area and retain the amenity enjoyed by the neighbourhood and its residents.</p> <p>Guidelines</p> <p>➤ The siting and layout of buildings should respect the existing character and building patterns of the neighbourhood. This pattern may consist of the distance of elements such as front yard setbacks, the spacing between buildings, height and width of buildings, materials used, and types of buildings.</p> <p><i>Respecting existing patterns in new development can be demonstrated by adopting similar patterns while not necessarily exactly replicating the detailed design of buildings in the neighbourhood. (See figure 3).</i></p>


IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
			 <p data-bbox="817 730 1361 754"><i>Figure 3: New houses respect the patterns set by existing ones.</i></p> <p data-bbox="607 770 1668 847">➤ Where the development is in an area of single houses on single sites, the greater building bulk associated with comprehensive residential development should be arranged in terms of layout and form to relate to the scale of the neighbouring housing.</p> <p data-bbox="645 863 869 887">This may be achieved by:</p> <ul data-bbox="660 903 1668 1082" style="list-style-type: none"> — Modulating the appearance of larger buildings by using setbacks in alignment; — Varying the roof design to reduce the perception of bulk; — Varying the size of units to reflect the variation of house size in the neighbourhood where this exists; — Varying the height and form of units to avoid a large or dominant form at the boundary; — Using complementary/contrasting materials or colours on exteriors to relieve the appearance of bulk; — Retaining existing mature trees and vegetation on the site, where possible, to assist the integration of the new development within the site and the neighbourhood. <p data-bbox="660 1086 1594 1110"><i>New developments can fit into existing neighbourhoods by paying attention to existing details and patterns.</i></p> <p data-bbox="660 1126 1668 1174"><i>Mature trees benefit neighbourhood amenity beyond the development site and are often highly valued by the community. Unless they unreasonably hinder development or are in poor health they should be retained.</i></p> <p data-bbox="607 1190 1668 1238">➤ Residential units within a larger development should be designed and detailed to provide a sense of individuality, and provide opportunities for personalisation.</p>


IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>Most people like to identify their homes by some sense of individuality and this also adds to the visual interest of the development. Where design elements are replicated across a development, providing opportunities for individualisation of houses is important.</p> <p>➤ Sites with wide frontages should have more than one connection to the adjoining road.</p> <p><i>Vehicle and pedestrian access to sites in most established neighbourhoods is provided at regular intervals along the street edge. The benefits of this are providing good access to and from the street, and creating interesting and active 'fronts' along the street edge. Sites with wide frontages (or amalgamated sites) with shared/fewer driveways need to be carefully considered to ensure that the design will continue to provide these benefits. (See figure 4).</i></p>  <p><i>Figure 4: Multiple entrances activate site edges</i></p> <p>➤ Houses on corner allotments with frontage to two roads should be designed to provide interest and opportunities for passive surveillance on both facades.</p> <p><i>Buildings on corner sites should have one front/primary façade facing the street. Attention should be given to ensuring that the other street facing façade does not present a blank wall to a public space. Secondary façades could include things like bedroom or dining room windows.</i></p> <p>➤ Dwellings and garages should be designed so that blank walls do not face the street. Any other large surfaces facing the street (e.g. fences) should be either minimised or suitably modulated.</p> <p><i>Large blank walls usually have a detrimental effect on streetscape. While being generally unattractive to look at, they also restrict opportunities for passive surveillance of public spaces.</i></p> <p>➤ Where an existing residential unit is proposed to form a part of a Comprehensive Residential Development, consideration should be given to the integration of the existing residential unit into the development through the specific consideration of the factors outlined in this section.</p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>Whilst an existing residential unit can form a part of a Comprehensive Residential Development, this may not always be desirable where the existing residential unit cannot be adequately integrated into the proposed development. Factors such as architectural style, bulk and form, and the use of particular materials may affect the ability of a residential unit to be integrated.</p> <p>Accommodating vehicles on sites</p> <p>The accommodation of vehicles on sites can have a significant impact on external amenity. Driveways and paving, garages and garage doors all have the potential to dominate if not carefully considered with the view to minimising visual impact.</p> <p>Driveways and paved areas within larger developments should be designed and detailed so that they are able to function more like 'shared spaces', where vehicles and people have equal priority. This will ensure that both visual amenity and vehicle and pedestrian safety are enhanced.</p> <p>Note: The Code of Practice for Civil Engineering Works gives the specific technical requirements relating to the length, width, gradient and other geometric and construction aspects of driveways and parking spaces. Once these have been met, consideration should be given to the following guidelines.</p> <p>Guidelines</p> <ul style="list-style-type: none"> ➤ Accessways and vehicle manoeuvring spaces should be designed to ensure cars enter and leave the site slowly. <li style="padding-left: 20px;">To ensure the safety of people within the development, it is important that the layout and landscaping requires vehicles to move slowly within the area and when coming and going. Areas used by cars should be designed so that it is clear to drivers that the spaces are shared with other activities. ➤ Open parking or vehicle manoeuvring areas should be designed and landscaped as an integral part of the development. ➤ Expanses of driveway and access areas should be relieved by contrasting patterns and materials to give interest, moderate the apparent scale of paving and add to the visual quality of the development. <li style="padding-left: 20px;">Reducing the dominance of vehicle paving is particularly important on larger sites, and on narrow sites where a greater proportion of the width of the site must be dedicated to access and manoeuvring. Long driveways should be detailed with contrasting paving to break up the expanse of hard surfacing. ➤ The layout of buildings on the site should ensure that garages and car parking spaces are not visually dominant on either the street frontage or within the site.

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			 <p><i>Figure 5: Eliminating blank walls and rows of garages creates a more pleasant streetscape.</i></p> <p><i>A row of garages at the street edge tends to block visibility between the buildings and the street. This usually has a negative impact on a site's attractiveness and reduces the ability of the residents to oversee the street and thereby contribute to the safety and liveliness of the area. The monotony of a line of garages can also conflict with the pattern of existing development. (See figure 5).</i></p> <ul style="list-style-type: none"> ➤ The design and materials of carports and garages should be integrated into the design of the overall development. <i>Garages should not be regarded as separate from the development or of lesser design importance.</i> ➤ Car parking spaces and garages should be conveniently located for the residential unit they serve. ➤ Any open parking spaces not allocated to a dwelling should have adequate passive surveillance. <i>Open parking areas and visitor parking needs to be both convenient and safe.</i> ➤ Access and circulation paths around the site should take into account the need to accommodate rubbish and recycling on collection days, without creating danger or nuisance to either pedestrians or vehicles. <p>Privacy and Safety</p> <p>Residential privacy is a valued commodity in Upper Hutt. Past development patterns characterised by single-storey houses located near the centre of large flat sites, with outdoor space to the rear means that many houses enjoy high levels of both visual and acoustic privacy within both the residential unit and typically, for the rear yard.</p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>Medium density housing can be well designed to protect privacy both within the development site and to adjacent sites. Careful consideration of the placement of doors, windows and internal uses within the residential unit can continue to maintain highly reasonable levels of privacy while still allowing a pleasant outlook, opportunities for passive surveillance and adequate opportunities for solar gain.</p> <p>Guidelines</p> <ul style="list-style-type: none"> ➤ Front doors should be oriented to face the street where possible, or to face common areas within the development. ➤ Position windows adjacent to common areas so that they provide an outlook while maintaining privacy within the residential units. <p><i>While privacy is important, locating entrances and windows adjacent to public or shared space means that residents can contribute to making the space active and safe. (See figure 6)</i></p>  <p><i>Figure 6: Window placement can enhance passive surveillance of public spaces.</i></p> <ul style="list-style-type: none"> ➤ For residential units that have a ground floor level, position the main living areas on the ground floor. This will help maintain privacy to the outdoor areas of adjoining sites. ➤ Wherever possible, each unit should have its own entry that provides a sheltered threshold. It should be well lit and highly visible as the entrance to the unit. The entry should be able to provide for personalisation by the occupant, and should not be dominated by service areas. <p><i>Particularly, rubbish or wheeled bin storage should not be located adjacent to the front door due to potential smell, leakage or pest nuisance.</i></p>

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
			<p>➤ Position windows or otherwise restrict or direct outlook so that the short range view from the main indoor living area of one residential unit is not directly into the main indoor living area of any adjacent residential unit, either within the site or on adjacent sites.</p> <p><i>Internal living rooms within dwellings are the most frequently used spaces and should have the highest consideration of privacy afforded to them (See figure 7).</i></p>  <p><i>Figure 7: Window positioning can help maintain privacy</i></p> <p>➤ The design and siting of buildings should take into account the potential for development on adjacent sites. The design of a development should therefore aim to maintain privacy and amenity on the site and at the boundaries taking into consideration possible future comprehensive residential development on adjacent sites.</p> <p><i>It is important to consider what is permitted or could be developed on adjacent sites. They too could be redeveloped and the same issues of sunlight and privacy will be relevant.</i></p> <p>➤ Housing should be clearly numbered both from the public street and within the site, to assist legibility for both visitors and emergency services.</p> <p>➤ Front fences and walls should be designed of materials compatible with the overall development and should ideally incorporate opportunities for visual connection with the adjacent street.</p> <p><i>Fences can enhance both the attractiveness of developments, and the ability to provide passive surveillance. The design of fences adjacent to the public street is particularly important (See figure 8).</i></p>

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
			<div data-bbox="920 371 1245 719" data-label="Image"> </div> <p data-bbox="786 735 1391 759"><i>Figure 8: The front entry of a residential unit should be clearly visible.</i></p> <ul data-bbox="591 775 1644 799" style="list-style-type: none"> ➤ Provide lighting as required for night time way finding and in situations where personal safety is likely to be important. <p data-bbox="613 815 1644 887"><i>Lighting for night time visibility should be energy efficient, low glare lighting along paths and accessways within the development and around shared areas. The design and placement of lighting should be included at the stage of developing a landscape plan.</i></p> <ul data-bbox="591 903 1644 951" style="list-style-type: none"> ➤ Mail boxes should be located in accordance with the requirements of NZ Post. Where houses do not have frontage to a public road, the mail boxes should be grouped in a visible location (See figure 9). <div data-bbox="936 970 1234 1169" data-label="Image"> </div> <p data-bbox="658 1185 1518 1209"><i>Figure 9: Grouped letter boxes at the front of a site can help strengthen the visibility of an entrance.</i></p> <p data-bbox="533 1225 808 1249">Sustainable Development</p>

IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>The inclusion of Overlay Areas in the District Plan aims to ensure that new higher density housing will be located in the most efficient locations, close to local amenities and public transport. New housing design can also contribute to local infrastructure efficiency by being designed in a way that reduces service infrastructure requirements.</p> <p>The topography and existing development pattern of much of Upper Hutt provides good opportunities for designing housing that is site responsive and takes advantage of solar gain, energy efficiency measures and promoting alternative forms of transport such as walking and cycling.</p> <p>Guidelines</p> <ul style="list-style-type: none"> ➤ The orientation and construction methodology of new houses should maximise opportunities for passive solar gain in winter and adequate shade in summer, particularly to the main living areas and private outdoor spaces. <p><i>The main indoor living area of a dwelling should ideally receive midwinter sun for at least four hours per day, ideally falling on an interior surface that incorporates thermal mass.</i></p> <ul style="list-style-type: none"> ➤ Opportunities for on site disposal/soakage of stormwater should be included in the landscaping design. <p><i>Developments of multiple units often increase the amount of hard surfacing over a site area by a significant amount. On site soakage of stormwater reduces the impact of multiple sites on stormwater infrastructure. On site soakage can be provided by garden areas and lawns, or by using materials such as water permeable paving or loose chip.</i></p> <ul style="list-style-type: none"> ➤ Noise sensitive areas of residential units (such as bedrooms) should be located away from noise generating activities on adjacent sites (i.e. major roads, railway lines or non residential uses). ➤ Attached residential units should employ appropriate noise resistant wall, ceiling and floor materials and construction details. ➤ The principles of Crime Prevention through Environmental Design should be applied to all developments. <p><i>Refer to Upper Hutt City Design Guidelines for Crime Prevention through Environmental Design, July 2009).</i></p> <p>SMALL SITE DESIGN AND DEVELOPMENT</p>



IPI - PROPOSED AMENDMENTS			
#	Chapter	Change	Track Change
			<p>Within the Residential Centres Precinct, the District Plan provides for a lower minimum net site area than in other residential areas. As part of the resource consent process for the subdivision of sites in these areas, or for the development of more than one residential unit on a site in these areas, some basic design considerations should be made and assessed against the criteria of this design guide.</p> <p>Smaller sites require greater care and attention in the design of developments to ensure appropriate standards of on site, streetscape and townscape amenity are maintained.</p> <p>These guidelines can also be considered in other areas as a means to ensure fundamental 'good practice' aspects of site design are addressed.</p> <p>Guidelines</p> <p>Lot shape and size</p> <ul style="list-style-type: none"> ➤ Lots should be designed to be predominantly square or rectangular in shape, and following this, avoiding the creation of areas and shapes that do not contribute to the usability of the lot. ➤ Lots should be designed to consider the location of outdoor living spaces and to ensure that these will be easily accessible from future buildings. <p>Site context</p> <ul style="list-style-type: none"> ➤ The design and siting of buildings should take into account the existing and future potential for development on adjacent sites. The design of a development should therefore aim to maintain privacy, sunlight access and amenity on the site and at the boundaries taking into consideration existing and possible future residential development on adjacent sites. <p><i>It is important to consider what is permitted or could be developed on adjacent sites. They too could be redeveloped and the same issues of sunlight and privacy will be relevant.</i></p> <p>On-site amenity</p> <ul style="list-style-type: none"> ➤ Small site design and development should meet the matters contained in the guidelines for Comprehensive Residential Developments in respect of: <ul style="list-style-type: none"> — Outdoor living areas (qualitative attributes only); — Landscaping, including retention of existing trees, fences, walls, and planting; — Servicing and storage facilities; — Accommodating vehicles on site; — Privacy and safety;

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
			<p style="text-align: center;">— Sustainable development.</p> <p style="text-align: center;">Many of the quality issues relating to residential development are common to proposals irrespective of whether they are Comprehensive Residential Development or small site development. The same guidelines can be applied for both the sake of consistency, and to ensure that an equally high standard of development and amenity is achieved by small site proposals as is expected of Comprehensive Residential Development.</p> <div style="border: 1px solid black; padding: 10px;"> <div style="display: flex; justify-content: space-between;"> <div style="width: 30%; border: 1px solid black; padding: 5px;"> <p>Character Assessment: CENTRAL AREA</p> <p>The Central Residential Centres Precinct surrounds the CBD of Upper Hutt and represents a key opportunity for higher density redevelopment.</p> <p>Residential development at an increased density around the Central Business District would create a variety of housing types close to the city centre, attracting and supporting a wide cross-section of the population to live and work in Upper Hutt.</p> <p>The CBD offers a good range of attractions, from shops and bars to businesses and public services. Increasing the density of housing in the surrounding area would contribute to enlivening the CBD and providing a thriving centre to Upper Hutt.</p> <p>The Central Area has a number of existing character elements that any new development should seek to maintain and enhance through good design and planning:</p> <ul style="list-style-type: none"> ▲ Connection ▲ Dwelling Types ▲ Avenues ▲ Public spaces </div> <div style="width: 65%;">  <p>Connection</p> <p>The Central Area surrounds the CBD of Upper Hutt City and is therefore close to the numerous businesses and services located in the city centre.</p> <p>The area is well-served by local bus connections and Upper Hutt Railway Station is within walking distance, connecting the city to Lower Hutt and Wellington.</p> <p>The roadways in the Central Area are flat and wide and provide ample room for cycling and on-street parking. The openness and spaciousness of the streets is an attractive element of the City Centre.</p> <p>Many of the streets in the Central Area are tree-lined and this quality should be maintained and amplified through any new development.</p> <p>Development should also seek to improve connections and promote sustainable methods of transport.</p>  <p>Streets & Open Space & Public Space</p> <p>The Central area has a strong grid pattern of streets, with many short streets, parks and walking links enhancing the area's walkability and ease of access. New development should capitalise on these links and assist with providing passive surveillance.</p> <p>Double Storey Development</p> <p>Two-storey houses are frequently seen in the Central Area. This element of the existing character presents an opportunity to develop 1.5 or 2-storey development on smaller building footprints.</p> <p>Dwelling Type</p> <p>The Central Area is comprised of a range of different housing types from small cottage style development to large double-storey detached houses, multi-dwelling units and estate style development, mostly for the elderly and vulnerable.</p> <p>The range of housing types is an important quality of the CBD and new development should seek to maintain this in order to offer a wide range of housing options. It also offers options for diversity in the style of new developments.</p> <p>CBD Avenues</p> <p>The roads leading into the CBD are an important aspect of the 'sense of arrival' in the CBD, and present an opportunity to develop multi-unit apartment residential units close to the amenities of the city centre. Development here could be more 'urban' in appearance, with buildings creating a more positive street edge, use of more contemporary materials and of a similar scale to the retail and light industrial buildings that are present in the area.</p> </div> </div> <div style="display: flex; justify-content: space-between; margin-top: 10px;"> <div style="width: 30%; border: 1px solid black; padding: 5px;">  <p><small>Residential development in the Central Area</small></p> </div> <div style="width: 65%; border: 1px solid black; padding: 5px;">  </div> </div> </div>

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
			<div data-bbox="548 391 896 829"> <p>Character Assessment: TRENTHAM</p> <p>Trentham is a suburb located 3km southwest of the CBD. The area comprising the Residential Centres Precinct is located directly north of the railway station between Stafford Street and Fergusson Drive, from Ranfurly Street in the east to Bathurst Street in the west.</p> <p>The general character of Trentham is a pleasant suburb with good local amenities such as Trentham Memorial Park, Trentham Racecourse and convenient access to public transport services.</p> <p>Further to these amenities, Trentham has a number of existing character elements that any new development should seek to maintain and enhance through good design and planning:</p> <ul style="list-style-type: none"> ▲ Connection ▲ Dwelling Style / Materials ▲ Layout ▲ Dwelling Type ▲ Boundaries </div> <div data-bbox="907 391 1254 462"> </div> <div data-bbox="907 478 1624 638"> <p>Connection</p> <p>The train connects Trentham to Upper Hutt CBD in 5 minutes and southern connections to Lower Hutt and Wellington are regular, with travel times of around 30mins and 40mins respectively.</p> <p>To the south of the train line is the Trentham Racecourse, and to the north of Fergusson Drive is Trentham Memorial Park which provides both local landscape amenity, sports grounds and local recreation activities.</p> <p>The streets around Trentham are tree-lined, wide and open, which allows for good views to the north and south and visual links to the park and the racecourse. Opportunities exist to improve these links and the quality of public space with high quality developments and good street design.</p> <p>Style Materials</p> <p>There are a number of well-maintained cottage-style properties in the area that could inform a general style for any future development in Trentham. This style incorporates timber construction clad in weatherboards, with pitched roofs, bargeboards and carved detailing.</p> <p>Site boundaries</p> <p>A large number of existing properties along Ararino Street have a high fence adjacent to the street boundary. This is a feature that should be discouraged in future as it creates an inactive edge to the public space and reduces the opportunity for passive surveillance of the street.</p> <p>Dwelling Type</p> <p>Variety in the type of housing in Trentham is not great and any new development should seek to provide a range of housing types to encourage a wider diversity of people to live in Trentham.</p> <p>Layout</p> <p>The main Trentham shops are located on Camp Street but there are additional shops and businesses on Ararino Street and along Fergusson Drive, interspersed with housing. Any future development of the area should seek to encourage and support one of these areas to develop into a more coherent centre. A key opportunity would be to provide a greater density of housing within the walking catchment of shops.</p> </div> <div data-bbox="548 837 896 965"> </div> <div data-bbox="548 973 896 1077"> </div> <div data-bbox="907 965 1624 1093"> <p>Local shops on the corner of Selington Dr. and Fergusson Dr. (left) and Inactive edges along Ararino Dr. on Camp St. (right)</p> </div>

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
			<div data-bbox="555 395 907 454" data-label="Section-Header"> <p>Character Assessment: WALLACEVILLE</p> </div> <div data-bbox="555 475 907 550" data-label="Text"> <p>The Wallaceville Area within the Residential Centres Precinct is located to the south of the Upper Hutt CBD on the south side of the train line. The area is comprised of a mix of residential and industrial uses.</p> </div> <div data-bbox="555 555 907 590" data-label="Text"> <p>Assessment of Wallaceville has identified a number of local characteristics that should influence future development.</p> </div> <div data-bbox="555 595 907 646" data-label="Text"> <p>The assessment identified the following elements as having particular qualities that are important to the character of Wallaceville:</p> </div> <div data-bbox="582 651 683 718" data-label="List-Group"> <ul style="list-style-type: none"> ▲ Setting ▲ Connections ▲ Housing </div> <div data-bbox="555 722 907 774" data-label="Text"> <p>Any future development of sites in this area should seek to retain the following qualities through good design and planning:</p> </div> <div data-bbox="555 818 683 837" data-label="Section-Header"> <p>Style and Materials</p> </div> <div data-bbox="555 842 1220 893" data-label="Text"> <p>There is no particular architectural style that can be attributed to the Wallaceville area. The housing stock is varied in scale, style, type, material and detailing. The variation of styles and materials allows for individuality within the street scene which should be retained.</p> </div> <div data-bbox="555 914 660 933" data-label="Section-Header"> <p>Dwelling Type</p> </div> <div data-bbox="555 938 1601 973" data-label="Text"> <p>Current housing stock includes many small to medium sized one-storey residential units, some of which have been converted into flats. Smaller dwellings are therefore common in the area and this housing type can be encouraged in new forms in the future.</p> </div> <div data-bbox="555 978 638 997" data-label="Section-Header"> <p>Setbacks</p> </div> <div data-bbox="555 1002 1064 1093" data-label="Text"> <p>The large majority of properties have generous building setbacks from the front boundary, which has given rise to a prevalence of activity occurring in front yards. This gives the streets in this area a unique sense of vitality and should be encouraged in any future development. Front boundaries are generally marked with low level wooden fences, which allow for surveillance and further contribute to a general feeling of openness and space.</p> </div> <div data-bbox="1025 383 1406 475" data-label="Image"> </div> <div data-bbox="936 486 974 502" data-label="Section-Header"> <p>Setting</p> </div> <div data-bbox="936 510 1601 566" data-label="Text"> <p>Physical features play an important part in the character of Wallaceville. Views of the hillsides are prominent to the north and, even more so, the south. Seddon Street and Wilford Street are long, straight roads that run east-west with clear sight lines and minimal signage.</p> </div> <div data-bbox="936 571 1310 646" data-label="Text"> <p>Views of the hills to the south of Wallaceville are visible between the houses on Seddon Street and through and over the residential units on Wilford Street. This is an important part of the character and amenity of the area and any future development should seek to maximise this aspect from both public and private locations.</p> </div> <div data-bbox="936 662 1019 678" data-label="Section-Header"> <p>Connections</p> </div> <div data-bbox="936 686 1310 774" data-label="Text"> <p>The area is well served by public transport links and is within walking distance of the Upper Hutt CBD. The road layout is simple and legible, with street trees and a wide carriageway and footpaths. Development should seek to improve connections and encourage sustainable methods of travel within the area such as walking and cycling.</p> </div> <div data-bbox="1326 561 1617 805" data-label="Image"> </div> <div data-bbox="1236 817 1594 901" data-label="Image"> </div> <div data-bbox="1131 976 1482 1104" data-label="Image"> </div>

	New Medium and High Density Design Guide	Introduce new Medium and High Density Design Guide	<h2 style="text-align: center;">TABLE OF CONTENTS</h2> <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 5%;">1.</td> <td style="width: 85%;">Purpose</td> <td style="width: 10%; text-align: right;">1</td> </tr> <tr> <td>2.</td> <td>Design Guide Structure</td> <td style="text-align: right;">2</td> </tr> <tr> <td>3.</td> <td>Using this guide as a part of a resource consent application</td> <td style="text-align: right;">3</td> </tr> <tr> <td>4.</td> <td>Typologies</td> <td style="text-align: right;">4</td> </tr> <tr> <td>5.</td> <td>Design Principles</td> <td style="text-align: right;">5</td> </tr> <tr> <td>6.</td> <td>Design Elements</td> <td style="text-align: right;">7</td> </tr> <tr> <td>6.1</td> <td>Site Layout</td> <td></td> </tr> <tr> <td></td> <td>- Setback & frontage</td> <td></td> </tr> <tr> <td></td> <td>- Access & car parking</td> <td></td> </tr> <tr> <td></td> <td>- Outdoor living space, (communal) open space</td> <td></td> </tr> <tr> <td></td> <td>- Stormwater management</td> <td></td> </tr> <tr> <td></td> <td>- Storage, waste & service areas</td> <td></td> </tr> <tr> <td>6.2</td> <td>Built Form & Design</td> <td style="text-align: right;">13</td> </tr> <tr> <td></td> <td>- Building mass and height</td> <td></td> </tr> <tr> <td></td> <td>- Building entrances & balconies</td> <td></td> </tr> <tr> <td></td> <td>- Garages</td> <td></td> </tr> <tr> <td></td> <td>- Building design & materials</td> <td></td> </tr> <tr> <td></td> <td>- Building diversity</td> <td></td> </tr> <tr> <td>6.3</td> <td>Amenity & Sustainability</td> <td style="text-align: right;">19</td> </tr> <tr> <td></td> <td>- Landscape treatment</td> <td></td> </tr> <tr> <td></td> <td>- Sunlight access</td> <td></td> </tr> <tr> <td></td> <td>- Energy efficiency</td> <td></td> </tr> <tr> <td></td> <td>- Privacy & safety</td> <td></td> </tr> </table>	1.	Purpose	1	2.	Design Guide Structure	2	3.	Using this guide as a part of a resource consent application	3	4.	Typologies	4	5.	Design Principles	5	6.	Design Elements	7	6.1	Site Layout			- Setback & frontage			- Access & car parking			- Outdoor living space, (communal) open space			- Stormwater management			- Storage, waste & service areas		6.2	Built Form & Design	13		- Building mass and height			- Building entrances & balconies			- Garages			- Building design & materials			- Building diversity		6.3	Amenity & Sustainability	19		- Landscape treatment			- Sunlight access			- Energy efficiency			- Privacy & safety	
1.	Purpose	1																																																																						
2.	Design Guide Structure	2																																																																						
3.	Using this guide as a part of a resource consent application	3																																																																						
4.	Typologies	4																																																																						
5.	Design Principles	5																																																																						
6.	Design Elements	7																																																																						
6.1	Site Layout																																																																							
	- Setback & frontage																																																																							
	- Access & car parking																																																																							
	- Outdoor living space, (communal) open space																																																																							
	- Stormwater management																																																																							
	- Storage, waste & service areas																																																																							
6.2	Built Form & Design	13																																																																						
	- Building mass and height																																																																							
	- Building entrances & balconies																																																																							
	- Garages																																																																							
	- Building design & materials																																																																							
	- Building diversity																																																																							
6.3	Amenity & Sustainability	19																																																																						
	- Landscape treatment																																																																							
	- Sunlight access																																																																							
	- Energy efficiency																																																																							
	- Privacy & safety																																																																							

1 | PURPOSE

The purpose of this guide is to provide urban design guidance to inform the design of new medium and high density residential development (generally referred to as intensive residential development for the purposes of this guide) that responds to the Upper Hutt context. Such development includes townhouses as well as terraced, multi-unit housing and apartments.



Who is it for?

The guide applies to anyone involved in the design and construction of intensive residential development in the city, including architects, designers, developers and property owners. It will also be used by Upper Hutt City Council staff to assess new intensive residential development proposals to ensure that they are responsive to the local context and result in buildings and associated spaces that are liveable and attractive.

Why?

With a heightened emphasis on higher density living to meet the city's future growth needs, ensuring that good quality design outcomes are also delivered becomes increasingly important. As Upper Hutt continues to change and adapt to cater for these needs it is critical that the potential visual, privacy and/or amenity impacts of larger scale development is properly managed, particularly on sites or in neighbourhoods that are spatially constrained.

Where does it apply?

To provide greater lifestyle choice the Upper Hutt District Plan includes provisions that enable more intensive development in the city's residential areas. The design guidance that follows applies to residential development within the General Residential Zone and High Density Residential Zone as identified in the plan.

2 | DESIGN GUIDE STRUCTURE

The guide does not prescribe development requirements but instead supports and complements the design outcomes sought for residential development in the Upper Hutt District Plan (e.g. form and appearance, amenity). It outlines the key features that characterises intensive residential development and offers practical advice to guide such development using best practice principles and relevant examples.

Supporting photographic examples and indicative diagrammatic interpretations are provided showing how these considerations can be met.

The guidelines apply to any area that is defined as suitable for medium density and high density residential development in the Upper Hutt District Plan. As the guidelines are based on a relatively universal set of urban design principles, most are applicable to residential development at a variety of scales.

Key design considerations are divided into fourteen contributory elements split across three themes as follows:

- **Site Layout** covers the design elements that are related to effects of development at a site scale.
- **Built Form & Character** covers elements related to the appropriateness of the building design.
- **Sustainability and amenity** cover the elements that contribute to living comfort and environment

6 DESIGN ELEMENTS

6.1 SITE LAYOUT

Context & purpose

The composition of a development on a site needs to consider its relationship to the surrounding context and its contribution to the overall character and amenity of the area. This includes the building's form, scale, and materials, as well as its relationship to the surrounding landscape and public realm. The building's form and scale should be appropriate to the site and its context, and its materials should be of high quality and contribute to the overall character and amenity of the area.

Guidelines

1. Where possible, buildings should be orientated with the sun of the building's long side facing the street or public space.
2. Where possible, buildings should be orientated with the sun of the building's long side facing the street or public space.
3. Public, semi-public and private spaces should be clearly defined and separated by a minimum of one storey between public and private spaces. This also provides a measure of passive surveillance of public and semi-public spaces. Private spaces should be oriented to the rear of the site, depending on the shape and context.
4. Where a building of three or more storeys is built to the street edge, consider building the upper storeys to maintain a human scale in ground level and increase privacy for upper levels.
5. Special considerations should be given to any mixed use development to the appearance, of the ground floor and relationship with the street and pedestrian network. The building should be clearly identified, preferably with a combination of signage and contribute to the overall character.

Typology indicator

- U Up to three storeys
- H Four or more storeys

Example photos

~~Mixed use considerations~~

2 | UPPER HUTT RESIDENTIAL DESIGN GUIDE

3 USING THIS GUIDE AS A PART OF A RESOURCE CONSENT APPLICATION

The district plan contains a number of objectives and policies that will be relevant in the context of higher density residential development. This design guide is intended to assist with the consideration of whether a development is consistent with these objectives and policies. The design guide is also referred to as a Matter of Discretion within a number of District Plan rules.

Preparation of a Design Statement

Where this design guide is relevant to a resource consent application, it is expected that a Design Statement will be included within the resource consent application to explain how the proposal meets the principles and guidelines contained within the design guide.

The design guide aims to recognise that all development proposals will be unique and that only those guidelines that are relevant to the site, activity or development proposal should be applied. The Design Statement provides applicants with the opportunity to explain which guidelines are relevant to the proposal, and how they have been applied.

A Design Statement will include:

- » A description of the proposal;
- » An overarching statement that explains how the proposal meets the design principles outlined in the design guide;
- » A description of how the proposal meets each relevant design guideline;
- » Where the proposal does not meet a design guideline, a description of:
 - » the alternative approach taken;
 - » why this is appropriate; and
 - » how the alternative approach enables the proposal to meet the overarching design principles.

4 TYPOLOGIES



Single dwelling

Single dwellings on either a conventional or infill site - this is the predominant residential development type in the city. They can also be a contributor to medium density development, providing diversity and increased housing choice.



Dual occupancy

Two dwellings that are fully or partly attached. They can be duplex dwellings that share a common wall or include a unit that occupies an upper storey. Units in dual occupancy generally have their own separate entry.



Multi dwelling housing / townhouses

Three or more dwellings on a single site, each with separate access at ground level and private open space. They can either be fully attached (terraced) or a collection of semi-detached buildings. Dwelling frontages generally align with an adjacent public road or internal street.



~~Multi-unit dwelling~~

~~A single building, with one or more entries, that contains three or more units up to a maximum of four storeys. These units can have (a combination of) private and/or shared open space.~~




High density / apartments

A multi-storey apartment building or group of buildings between 5.4 to 10 storeys that contains multiple units, often with shared open space ~~and the potential for mixed use on ground floor.~~

General Residential - Permitted up to three dwellings of three storeys - Design Guide applies when resource consent is required.



High Density - Permitted up to 24.5m 20m height - Design Guide applies when resource consent is required.



How we design our buildings and the relationship they have with the street and surrounding neighbourhood has a considerable bearing on the way we live, work and meet. The following design principles have been developed to encourage high quality design that contributes to the future character of Upper Hutt and provides an attractive and comfortable living environment for users, residents and visitors.

F

POSITIVELY RESPOND TO FUTURE CONTEXT

- » Contribute positively to the natural and built environment of the area in line with its anticipated and evolving future context
- » Recognise and positively respond to the existing and anticipated future character of the streetscape and neighbourhood

B

APPLY APPROPRIATE BUILT FORM & DESIGN

- » Achieve a scale, bulk and height appropriate to the existing and anticipated future character of the street and surrounding buildings
- » Provide a suitable balance between built form and design through maintaining a good composition of elements, internal layout, building materials and colours
- » Enable natural surveillance of the public domain while providing for visual privacy to residents

A

PROVIDE AMENITY

- » Contribute to creating positive living environments that enrich residents wellbeing
- » Ensure building orientation enables appropriate access to sunlight, outlook, attractive indoor and outdoor spaces
- » Establish a well-designed green space that positively contributes to the (social) living experience and surrounding landscape character
- » Provide good accessibility that caters for all age groups and degrees of mobility

D

FOSTER DIVERSITY & SOCIAL INTERACTION

- » Provide a range of housing choice to serve the needs of different cultural groups, ages and stages, lifestyles and household budgets
- » Respond to the social context by encouraging a range of dwelling sizes to suit the existing and future mix of residents
- » Provide opportunities for social interactions through communal open space and an attractive and social interface with the street

S

ENCOURAGE SUSTAINABILITY BY PASSIVE DESIGN

- » Improve the liveability for residents by providing natural ventilation and sufficient sunlight access
- » Reduce energy usage and cost by carefully considering building location, orientation and design to allow for passive solar gains and natural ventilation
- » Allow landscape elements to enhance the environmental performance of the site, contributing to an integrated and sustainable green network

This matrix identifies the key relationships and interactions between the Design Principles and the Design Elements in the Guide.

DESIGN PRINCIPLES	POSITIVELY RESPOND TO FUTURE CONTEXT F	APPLY APPROPRIATE BUILT FORM & DESIGN B	PROVIDE AMENITY A	FOSTER DIVERSITY & SOCIAL INTERACTION D	ENCOURAGE SUSTAINABILITY BY PASSIVE DESIGN S
SITE LAYOUT					
Setback & frontage	■	■		■	■
Access & car parking		■	■	■	
Outdoor living & (communal) open space			■	■	
Stormwater management					■
Storage, waste & service areas			■		■
BUILT FORM & DESIGN					
Building mass and height	■	■			■
Building entrances & balconies		■		■	
Garages	■	■			
Building design & materials	■	■	■	■	■
Building diversity	■	■		■	
AMENITY & SUSTAINABILITY					
Landscape treatment			■	■	■
Sunlight access		■	■		■
Energy efficiency			■		■
Privacy & safety		■	■		

6 DESIGN ELEMENTS

6.1 SITE LAYOUT




DIAGRAM 1- FRONTAGE AND BUILDING ORIENTATION

- A Dwellings should have a clear frontage that addresses the street/public space along with a clear area to the rear
- B A clear delineation between private and public space
- C Front yard acts as a buffer between private and public space
- D Access directly from the street with a visible house number and letter box



PHOTO 1- AMBERLEY GARDENS (SILVERSTREAM, UPPER HUTT)

~~MAX 2.0M~~
~~E. If a taller consideration should be given in any situation the design team to plan separation of the ground floor of dwellings to with the street and pedestrian traffic. The facade should be visually permeable to the street with a ground floor appearance and the ability to create an active street edge.~~

Setback & frontage

The configuration of a development on a site, and its relation to adjoining public space, is an important consideration to ensure good amenity and reduce **overshadowing** and privacy effects on adjoining sites. Having a defined front and back, as well as a clear delineation between public, semi-public and private spaces contributes to the legibility of the site and street.

The setback and frontage of a building also contribute to a socially active and safe environment, while the front yard provides additional amenity for residents and a setting for the dwelling.

1. Where possible, buildings should be orientated with the front of the dwelling(s) facing the street or public space. M H
2. Where possible, dwellings should be configured so that there are habitable spaces located at the front of the building, with ground and upper storey windows or balconies providing an outlook that enables passive surveillance. M H
3. Public, semi-public and private spaces should be clearly defined through planted landscaping, hard landscaping or fencing, and front yards kept to a minimum. Yards not only provide amenity or outdoor living space for residents but act as a buffer between public and private space – they also provide a means of passive surveillance of public and communal open spaces. Private spaces generally contained by taller solid fencing or vegetation should be located to the rear or the side, depending on site shape and orientation. M
4. Avoid tall solid fencing between outdoor living spaces and the street or other public spaces. M H
5. Where a private outdoor living space fronts a street or other public space, a taller fence may be appropriate, but this should be designed to be at least 50% visually permeable. M H
6. Where a building of three or more storeys is built to the street edge, consider setting back the upper storeys to maintain a human scale at ground level and increase privacy for upper storey units. M H



DIAGRAM 2 - GROUND FLOORS DESIGNED TO SUPPORT A HUMAN SCALE AT STREET LEVEL.

- A Upper storeys are set back to reduce the perceived density on a street level
- B Landscaping in between buildings increases an intimacy and creates a softer people oriented space



PHOTO 2 - ON STREET PARKING ALONG INTERNAL STREET (MILLBROOK, OTAGO)



PHOTO 3 - LANDSCAPING AND RAIN GARDENS IN CENTRALISED PARKING (PICTON)

Access & car parking

The location, type and design of pedestrian and vehicle access points can have a significant bearing on the streetscape, and site layout and building facade design. Considering alternative modes of transport and maximising opportunities for cyclists (e.g. bicycle parking) can also help ease pressure on car parking.

Circulation networks should be legible and provide a safe environment for pedestrians and cyclists.

7. If on street parking is provided it should not conflict with active mode infrastructure (e.g. walking, cycling). On street parking reduces the number of footpath crossings, increases pedestrian safety, and enables available parking space to be flexibly used by a variety of users. M H
8. Provision of off street parking between buildings and the street is discouraged as it reduces the dominance and presence of individual dwellings and the overall visual coherence of the streetscape. M H
9. On site parking for medium density, high density or mixed use developments is encouraged to be below grade. Any parking provided above grade should be screened from the street view by evergreen planting. M H
10. Outdoor centralised parking should be landscaped to provide amenity, and be designed to offer safe and comfortable pedestrian routes. M H
11. Hard surface parking or large impermeable surface areas should be minimised to reduce visual dominance. M H
12. Where parking is proposed adjacent to a street, the use of landscaping is encouraged to prevent car parking dominating views from the street. M H
13. Pedestrian access should be differentiated from vehicle access through variation in surface treatment or texture. Preferably, pedestrian and vehicle access should also be separated by a buffer such as vegetation or a raised surface. M
14. Multi-unit developments on large or deep sites should preferably be accessed from new streets and lanes, rather than long driveways. The frontage of dwellings along internal streets should be treated in a similar fashion to frontage onto a public street. M H



DIAGRAM 3 - PROVIDE ON STREET CAR PARKING WHERE POSSIBLE




DIAGRAM 4 - ON SITE CAR PARKING INTEGRATED INTO DESIGN

- A** On street car parking enables parking spaces to be re-used by different users
- B** Clear separation in surface treatment between driveways and pedestrian access
- C** Landscaping can be used to soften the outlook onto hard surfaces

- 15. Large building blocks should create pedestrian connections between streets where possible. A fine grained block pattern encourages more intensive pedestrian use and enables the development of comfortable and sheltered public open spaces or walking routes. M H
- 16. Internal streets or rear lanes providing access to parking should be designed to be safe for active modes of transport (e.g. pedestrians, cyclists) and contribute to the amenity and attractiveness of the site. This can be achieved by incorporating landscape elements, bollards and variation in paving treatment into the design. M H

MIXED USE

- ~~17. Pedestrian circulation should be given particular design consideration in any mixed use development, including provision of inviting and suitably sized gathering spaces.~~ M H

Outdoor living & (communal) open space

Outdoor open space is an important consideration when designing intensive residential developments and should be considered early on in the design process to ensure it is an integral part of the development.

Higher densities often result in a reduction in the amount of outdoor space available to residents, influencing the sense of privacy and level of individual amenity experienced. Outdoor space allows residents to be able to enjoy a range of activities, express personal and creative identity around their property and, in the case of communal open space, provide for casual social interactions.

- 18. Where possible, provide good direct access from primary habitable living spaces (such as lounge or dining areas) to private or communal outdoor spaces (or outlook in the case of upper floor apartments). This adds to internal amenity and sense of space and encourages the use of available outdoor areas. M H




DIAGRAM 5 - ENSURE THAT OUTDOOR OPEN SPACES ARE USABLE AND OF AN APPROPRIATE SIZE

- A Good access from indoor to outdoor, with integration of ramps into the design where necessary
- B Where possible link indoor habitable spaces with outdoor space
- C Practical dimensions that allow for recreation or seating



PHOTO 4 - COMMUNAL OUTDOOR SPACE (KUPE STREET HOUSES, AUCKLAND)

- 19. Consider using decks or balconies as outdoor living space where access to ground floor private open space is not possible. Taller developments are encouraged to consider use of the roof as communal outdoor open space, enabling increased access to available sunlight and views. M H
- 20. Outdoor spaces should offer privacy to users, and be orientated to maximise sunlight access that enables a comfortable outdoor environment that can be enjoyed throughout the year. M H
- 21. Allow outdoor space to be optimally used by carefully considering the dimensions and location of the space. Wide or square spaces (i.e. ones that allow for the placement of outdoor furniture) are more efficient than long and narrow spaces. M H
- 22. Include screening devices and strategic landscaping to increase privacy, limit outlook into adjacent private properties or prevent the space from being directly overlooked by neighbouring properties. M H
- 23. The size of any communal space should correspond to the number of residents it is intended to serve, be equally accessible to use by all units. It should also encourage opportunities for social interactions between users by incorporating seating, barbecue, sporting or play equipment into the design. M H



PHOTO 5 - COURTYARD AS OUTDOOR OPEN SPACE FOR APARTMENT UNITS (BEAUMONT QUARTER, AUCKLAND)




DIAGRAM 6 - INCORPORATING STORMWATER MANAGEMENT



PHOTO 6 - RAIN GARDEN (ROLLESTON)



PHOTO 7 - PERMEABLE PAVING (WELLINGTON)

Stormwater management

Stormwater is rain that runs off hard surfaces such as parking lots, driveways or rooftops and flows into stormwater drains or natural streams. Incorporating low impact stormwater measures into the design reduces the potential for this runoff to be contaminated and reduces the pressure on Council owned stormwater infrastructure during peak stormwater discharges.

Best practice water management considers water sensitive urban design measures at all stages of the building process. Early consideration during the design phase can help to enhance their cost effectiveness.

In large scale subdivisions (e.g. greenfield) stormwater management is best dealt with at a catchment level.

S

- 24. Minimise the use of impermeable surfaces to manage and dispose of on-site stormwater. The use of permeable paving in locations such as parking spaces/areas is encouraged. M H
- 25. Where possible, consider the use of swales, green roofs or rain gardens to collect, treat or reduce stormwater. M H

Storage, waste & service areas

Integrating storage, waste and service areas into the overall site design can have a beneficial effect on the amenity and quality of a development. Considering how waste is managed, stored and collected, as well as the location of storage and service areas, helps to minimise visible clutter that could create lower standards of amenity and poorer impressions of an area.

A S

- 26. Outdoor storage space should be provided that is proportionate to the size of the dwelling. Providing opportunities for outdoor storage of recreational and maintenance equipment and/or other large household items can increase the efficient utilisation of indoor storage space. M




DIAGRAM 7 - SERVICE AREAS INCLUDED IN THE DESIGN




DIAGRAM 8 - SERVICE AREAS INCLUDED IN THE DESIGN



DIAGRAM 9 - SERVICE AND DELIVERY AREAS FOR MIXED USE PREFERABLY LOCATED AWAY FROM PEOPLE ORIENTED AREAS

27. Ensure that the location and size of storage, waste and service areas does not restrict onsite pedestrian movement or create potential health and/or safety risks. M H
28. Integrate waste and personal storage areas into the building design and ensure that they are of a sufficient size relative to the number of units. Waste areas should be able to accommodate all waste bins and have a clear connection to the collection area. M H
29. Position storage and service areas in locations that are obscured from public view. Storage in any areas set aside for car manoeuvring should also be discouraged. M H
30. Areas set aside for wheeled bins or rubbish storage and collection should be integrated into the development in a way that is visually discrete and be located away from commonly used areas to prevent the impact of odour or leakage. On sites where access to the side or rear of a dwelling is limited, locating the rubbish storage area to the front of the site can provide a useful alternative provided visibility from the street is mitigated by appropriate landscaping or screening. M H
31. Communal storage spaces should be accessible from common circulation spaces such as hallways or laundry rooms. M H

MIXED USE

- ~~32. Delivery and rubbish collection areas for commercial activities should preferably be located at the rear or side of the building, away from residential activities or pedestrian movements.~~ M H

6.2 BUILT FORM & DESIGN



DIAGRAM 10 - BUILDING HEIGHT AND ROOFTYPES



PHOTO 9 - BREAK UP OF MASS THROUGH FACADE AND ROOF ARTICULATION (WALLACEVILLE, UPPER HUTT)




DIAGRAM 11 - BUILDING MASS FOR TALL BUILDINGS BROKEN DOWN INTO A 'BASE', 'MIDDLE', 'TOP'

F B S

Building mass and height

Building height contributes to achieving more intensive residential development as it can enable more effective utilisation of a site while maintaining a low ecological footprint. A visually attractive design can help to mitigate any potential adverse effects arising as a result of building height and/or bulk.

33. Building mass/bulk and height should be designed to create visual interest and minimise physical dominance or potential shading or privacy effects on neighbouring properties.

M H

34. Minimise the potential impact of building bulk by reducing the floor area of upper levels or stepping them back from the street. Building mass can also be visually reduced by introducing variation in façade treatment (for example, balconies, shading devices or porches) or the effective use of landscaping.

M H

35. Reduce the effect of building mass by breaking the form of the building up into a 'base', a 'middle' and a 'top'. Setting back the upper storeys from the base helps to create a pedestrian scale at street level and also reduces wind turbulence at ground level.

H

36. A varied roof form that is integrated with the design of the upper storey can further reduce the bulk and visual impact of the building and can provide a visually diverse building silhouette.

M H

(Also refer guideline 56)

37. To reduce visual monotony long linear or blank walls without windows, doors or associated design features should be avoided. Long continuous roof ridgelines are also discouraged.

M H

38. Increasing building height on corner sites emphasises the corner and creates a focal point, providing visual interest that supports legibility and way finding without unduly affecting adjacent buildings.

M H

(Also refer guideline 54)



PHOTO 10 - PROVISION OF A CLEAR ENTRANCE AND BALCONY FRONTING THE STREET (NORTHWOOD, CHRISTCHURCH)



PHOTO 11 - DIFFERENCE IN ENTRANCE DESIGN BETWEEN RESIDENTIAL AND COMMERCIAL ACTIVITIES (PETONE, LOWER HUTT)

Building entrances & balconies

B D

The entrance to a building makes an important contribution to the way a building is experienced. Balconies and entrances provide visual interest by breaking up a façade; they also add a human scale to intensive residential developments and can positively contribute to the overall appearance of a building when designed well. Visible activity on the ground floor and street facing façade enhances public safety through passive surveillance and creates opportunities for social interaction.

Balconies also offer a good way of providing outdoor open space on a street facing façade and contribute to reducing the noticeable bulk effect of a building.

39. Where there are multiple dwellings on a site consider subtle variation to entrances (e.g. colour, design), or enable occupants to personalise in order to differentiate units and increase legibility. M
40. Ensure entrances (as well as address and letterbox) are clearly defined and visible from the street to enable them to be easily located and accessed. M H
41. Entrances that serve high density development should provide sufficient space for people to gather (e.g. small entry plaza) and include signage and landscape treatment that enhances the legibility of the entrance location. Indoor lobby spaces should have a clear visual and physical connection to the street. H
42. Entrances should be designed to provide all weather shelter (e.g. canopies or overhangs) with suitable lighting incorporated into the design. M H
43. Ensure privacy and weather protection are considered when providing any outdoor balcony space. M H
44. Provide screening where unit balconies adjoin to increase privacy. M H



45. Solid screening should be considered for any balconies large enough to be used for storage of bicycles and/or large items. M H

~~MIXED USE~~
~~46. Entries to any ground-floor commercial activities should have a distinct appearance and design in a way that differentiates them from entrances to residential units.~~ M H




DIAGRAM 12 - GARAGE SET BACK FROM THE BUILDING FRONT



PHOTO 12 - CONSISTENT PATTERN OF GARAGES WITHOUT DISRUPTING PEDESTRIAN MOVEMENT ALONG THE FOOTPATH (HOBSONVILLE, AUCKLAND)

Garages F B
 Garages should be sensitively integrated into any development as they can have a significant impact on its overall layout and design as well as on the associated streetscape.

47. Any garaging forming part of an overall development should be designed to be consistent with the style of the dwelling(s). M

48. Garages and carports should be set back from the front façade of any dwelling to minimise visual dominance and increase visibility of main pedestrian entries. Designing garaging that is narrow and visually recessive can also help to reduce the extent to which it dominates the associated dwelling. M

49. Where possible, garages, carports and associated driveways should: M
 a. reflect the rhythm and consistency of the street frontage
 b. be located to minimise interruption of pedestrian movements along footpaths



PHOTO 14 - VARIATION IN COLOUR, ROOF TYPES AND MATERIALS (HOBSONVILLE, AUCKLAND)



PHOTO 12 - CHOICE OF MATERIALS AS AN INTEGRAL PART OF THE DESIGN (WHITEMANS VALLEY, UPPER HUTT)



PHOTO 15 - PONSONBY, AUCKLAND
DIFFERENCE IN TREATMENT OF GROUND LEVEL AND UPPER STOREYS IN RESPONSE TO PEDESTRIAN SCALE



PHOTO 18 - PETONE, LOWER HUTT
DIFFERENCE IN TREATMENT OF GROUND LEVEL AND UPPER STOREYS IN RESPONSE TO PEDESTRIAN SCALE

E B A D S

Building design & materials

Building design and use of materials make an important contribution to the effective integration of intensive residential development into an existing street environment.

The main factors that influence the appearance of a building are scale, modulation and the articulation of its form and façade. The choice of materials used can also affect the appearance of a development, how well it performs and endures over time and its ongoing sustainability and resilience.

50. The design, type and location of the building on a site, as well as the choice of materials used, should recognise and reflect the level of intensification planned for the surrounding area. In relation to the surrounding environment, consideration should be given to:

- a. setback from the street;
- b. scale and bulk;
- c. roofline;
- d. complementary materials and colours;
- e. planting; and
- f. presence of heritage.

51. Building features and elements should be integrated and considered as part of a single, coherent design. This includes elements such as roofline, articulation of the façade (including balconies and frequency of windows and doors), maintenance systems and service spaces.

52. Consider lighting and signage elements as an integral part of the design early in the design process.

53. Consider views of the rear and side façades of the building, particularly where there is a transition to a lower density environment.

54. Consider increasing the visual prominence of buildings on corner sites through the use of different materials, colours or roofline.

(Also refer guideline 38)

M H
M H
M H
M H



PHOTO 17 - ROOF FORM INTEGRATED WITHIN THE DESIGN OF THE TOP STOREY

55. Use robust materials that are easy to maintain and retain their long term appearance. This is particularly important in areas that are prone to increased wear such as communal spaces.

56. Rooflines can have a significant impact on the composition of a building and can provide variety and a sense of identity when applied to a row of dwellings. The roof form (pitched, flat or a combination) should complement the existing or emerging character of the surrounding area.

(Also refer guideline 36)

MIXED USE

57. Where a mix of uses are proposed, the ground level treatment and appearance of the building should respond to the physical context at street level and positively contribute to the pedestrian experience.

M H

M H

M H



DIAGRAM 13 - LEGIBLE ENTRANCE AND BALCONIES CONTRIBUTE TO ATTRACTIVE BUILDING DESIGN




DIAGRAM 14- REDUCE BULK BY ADDING VARIETY TO THE ROOFLINE



DIAGRAM 15- VARIATION IN BUILDING SIZE AND TYPE



PHOTO 18 - PROVISION OF A RANGE OF BUILDING SIZES AND TYPES CATERING TO A VARIETY OF DIFFERENT LIFESTYLES (DELAMAIN, CHRISTCHURCH)

F B D

Building diversity

Providing diversity of dwelling type and size offers increased accommodation choice catering to a variety of needs ranging from income level and household size through to demographic and cultural requirements. Units that appeal to a broad range of ages and stages are also more likely to withstand significant changes in the market.

Additionally, diversity provides improved opportunities for existing residents to move within their local community as and when their housing needs and requirements change.

The development of apartments or multi-unit housing can be an effective way of achieving higher density while retaining sufficient space for outdoor use, particularly on sites with size constraints.

58. Dwelling and unit sizes should be carefully considered and suit the context. Where possible, a range of dwelling or unit sizes should be considered (providing a variety in number of rooms or housing typologies) to cater for a variety of financial, demographic or accommodation needs.

M

59. Consider developing buildings that are adaptable and that can be flexibly used or reconfigured over time without the need for major change.

M H

6.3 AMENITY & SUSTAINABILITY



DIAGRAM 18 - LANDSCAPING USED TO SOFTEN HARD EDGES AND IMPROVE OUTLOOK



PHOTO 19 - APPROPRIATE LANDSCAPING CAN HELP TO MITIGATE NEGATIVE EFFECTS OF FENCING OR BLANK WALLS (REGENT PARK, WELLINGTON)

A D S

Landscape treatment

Landscape design can greatly improve the amenity, experience and integration of intensive residential development into a street or neighbourhood. The implementation of carefully considered landscape design can help to enhance different design elements, such as the screening or softening of hardstanding areas (driveways, parking, services areas), mitigate the effects of building bulk and offer amenity and environmental benefits.

Coordinating landscaping early in the building and site design process can increase opportunities to more effectively integrate landscape treatment into outdoor open space, traffic circulation routes, service locations and the interface between the public and private domain.

- 60. Where possible, existing mature and healthy vegetation should be retained and integrated into the site development. M H
- 61. Use planting to improve the outlook from dwellings and the street and to soften hard surface areas such as car parks, service areas or along internal site boundaries and driveways/shared accessways. M H
- 62. Use hedges or climbing plants where space is constrained and larger vegetation where sufficient space and access to rainwater is available. M H
- 63. Choose plants that are appropriate to the climatic conditions and character of the area; planting species that require low maintenance and attract local bird life is also encouraged. M H
- 64. Deciduous trees provide shade in summer and light in winter, but careful consideration should be given to species selection in heavily shaded areas to ensure survivability. M H
- 65. Use of hard landscape elements such as low walls, kerbs or raised beds is encouraged as these can provide protection to plants and, where integrated into the site design, can add to the visual amenity of outdoor spaces. M H




DIAGRAM 17 - ORIENTATION TO MAXIMISE SUNLIGHT ACCESS

- A Ideal orientation along a east-west axis with living areas facing north
- B Small and/or high level windows in service or storage spaces, ideally facing south
- C Narrow buildings benefit from tall windows in north facing façades for optimal sunlight penetration




DIAGRAM 18 - HIGH LEVEL WINDOWS, SKYLIGHTS AND/OR ATRIUMS CAN IMPROVE SUNLIGHT PENETRATIONS

B A S

Sunlight access

Adequate access to natural light is an important consideration in designing the layout of a site, particularly any opportunities to capitalise on a northern aspect.

It is also a key consideration in siting and designing the internal layout of associated dwellings as it not only provides a warm and pleasant internal living environment but helps to increase energy efficiency.

- 66. Design dwellings with habitable spaces facing north, west or east to maximise sunlight access. M H
- 67. Buildings that are relatively deep and narrow, or that have limited north facing frontage, benefit from larger floor-to-ceiling heights; where this occurs consider the use of taller windows to ensure deeper sunlight penetration. M H
- 68. On narrow sites place balconies and windows in habitable spaces to the front or the rear of the building to allow for daylight access, outlook and privacy. M H
- 69. Consider the use of skylights, atriums or light wells to provide sunlight access to internal spaces with no external walls. M H
- 70. In order to maintain sunlight access, high level windows or louvres should be considered where privacy is an issue or to restrict views of service or storage areas; however, their use should be minimised in façades that face the street or public areas. M H




DIAGRAM 19 - SUNLIGHT ACCESS, EAVES AND INTERNAL VENTILATION

- A** Large windows on the sunny side, smaller windows on the side that gets the least sun hours
- B** Eaves blocking sunlight in the summer while allowing sunlight access in winter months
- C** Windows in opposite sides of the building allow for natural ventilation



PHOTO 20 - OVERHANGING BALCONIES PROVIDE SHADE IN SUMMER (CLEARWATER GOLD RESORT, CHRISTCHURCH)

Energy efficiency

An energy efficient home promotes sustainable living, limits the impact on the environment by relying on sustainable energy sources and can produce long term cost savings to residents.

Integrating efficient passive design into a building contributes to a more comfortable indoor environment by increasing the thermal stability, reducing indoor condensation and promoting natural ventilation; it also helps reduce energy usage.

Energy efficiency should be considered during all phases of development, from planning and design (e.g. internal layout and building systems) through to construction (e.g. minimising waste) and long term maintenance (e.g. using durable materials).

- 71. Where possible, site long buildings on an east-west axis, with living areas orientated to the north to optimise solar access. M
- 72. Consider locating opening windows on opposite sides of a dwelling to enable natural cross ventilation; the total window surface on south facing façades should also be limited to prevent heat loss in winter. M
- 73. Use of eaves is encouraged as they can help limit the duration of sunlight penetration in summer, preventing indoor spaces (particularly those with a northern aspect) from becoming too warm. M
- 74. When designing large scale developments, consider installing a communal (solar) hot water heating facility as it has the potential to offer greater efficiencies compared to heating sources in individual units. M H



PHOTO 21- AMBERLEY GARDENS, SILVERSTREAM




DIAGRAM 20 - BALANCE PRIVACY AND NATURAL SURVEILLANCE

- A** Prevent placing windows immediately opposite windows in a neighbouring property
- B** Living areas with large windows in the front of the building to provide for natural surveillance
- C** Soft landscaping or porous fencing to create natural surveillance while retaining privacy

Privacy and safety

The orientation of dwellings and their interface with public and communal open spaces are important safety and privacy considerations. In designing for safety and privacy, adequate account needs to be taken of the relationship of new and adjoining buildings to ensure a successful balance is achieved between protecting private amenity and providing opportunities for passive surveillance.

75. Where possible, locate habitable spaces (e.g. kitchen, dining or lounge) in multi-unit developments to face the street or an adjoining open space as this will enable passive surveillance of these areas while maintaining privacy in main living spaces.

76. Solid, blank walls facing any public open space or pedestrian pathways should be avoided.

77. Where possible, orientate windows to public spaces to provide for passive surveillance; privacy between dwellings can be maintained by screening upper level windows or balconies to limit opportunities for residents to directly overlook adjacent properties.

78. Consider staggering façades relative to each other to limit direct views into adjoining habitable rooms.

79. Consider a larger setback between taller buildings to improve privacy for residents (and also to contribute to daylight access and outlook).

80. Locate habitable spaces that are more sensitive to privacy issues (e.g. bedrooms) to the front or the rear of buildings on narrow sites.

81. Use soft landscape elements and visually permeable materials to achieve an appropriate balance between maintaining privacy and enabling passive surveillance.

B A

M

M H

M H

M H

M H

M H

M H




PHOTO 22 - STAGGERED BALCONIES MAXIMISE PRIVACY WHILE RETAINING OUTLOOK AND SUNLIGHT ACCESS (WELLINGTON)

- 82. Clearly delineate boundaries between private, communal and public spaces as this increases user perceptions of safety and helps to identify intruders. M H
- 83. Use lighting, planting and fencing to enhance the safety of residents and visitors and incorporate these elements into the design process; also consider low level planting or trees with higher canopies to minimise the risk of light sources becoming obscured by landscape elements, particularly around sensitive areas. M H
- 84. Elevating dwelling floors, patios and decks slightly above the street level for buildings that have no or minimal setback can provide privacy to residents while maintaining outlook onto the street. M H
- 85. Strategically locate communal open space to encourage passive surveillance within the development and of adjoining sites. M H

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
---	---------	--------	--------------

Appendix 2 – City Centre Zone Design Guide

	New CCZ Design Guide	Introduce new Design Guide for the CCZ	<p style="text-align: center;">UPPER HUTT CITY CENTRE DESIGN GUIDE</p>
--	----------------------	--	---

TABLE OF CONTENTS

1.	Purpose	1
2.	Design Guide Structure	2
3.	Using this guide as a part of a resource consent application	3
4.	Design Principles	4
5.	Design Elements	6
5.1	Site Layout	6
	• Sitting and alignment	
	• Connectivity	
	• Car parking, storage and servicing	
	• Balconies	
5.2	Built Form and Appearance	10
	• Bulk and form	
	• Visual Interest / facade modulation	
	• Building design and materials	
	• Building top design	
	• Privacy, daylight and outlook	
	• Wind and sunlight	
5.3	Street level	16
	• Street frontage	
	• Public open space	
	• Access and entrances	
	• Landscape treatment	

UPPER HUTT CITY CENTRE DESIGN GUIDE

1 | PURPOSE

The purpose of this guide is to support the interpretation and application of the urban design provisions relating to the City Centre Zone of the Upper Hutt District Plan. It provides urban design guidance to inform the design of new, high quality development that responds to the Upper Hutt context. An emphasis is placed on how buildings and spaces respond to an anticipated transformation in density and contribute to enhancing the vibrancy and welcoming nature of the City Centre.




Who is it for?

The guide applies to anyone involved in the design and construction of development in the City Centre Zone, including architects, designers, developers and property owners. It will also be used by Upper Hutt City Council staff to assess new development proposals in the City Centre Zone to ensure that they are responsive to the local context and result in buildings and associated spaces that are liveable and attractive.

Why?

With a heightened emphasis on higher density development to meet the city's future growth needs, ensuring that good quality design outcomes are also delivered becomes increasingly important. As Upper Hutt continues to change and adapt to cater for these needs it is critical that the potential visual, privacy and/or amenity impacts of larger scale development are properly managed.



2 DESIGN GUIDE STRUCTURE

The guide does not prescribe development requirements but instead supports and complements the design outcomes sought for city centre development in the Upper Hutt District Plan (e.g. form and appearance, amenity). It outlines the key features that characterise centres development and offers practical advice to guide such development using best practice principles and relevant examples.

The guide uses supporting photographic examples and indicative diagrammatic interpretations to communicate the desired outcomes that are sought by a series of associated Design Principles (see page 4).

Key design considerations are divided into fourteen design elements that can be grouped into three themes as follows:

The guidelines apply to any area that is defined as City Centre Zone in the Upper Hutt District Plan. As the guidelines are based on a relatively universal set of urban design principles, most are applicable to centres development at a variety of scales.

- › **Site Layout** covers design elements that are related to the effects of development at a site scale.
- › **Built Form & Appearance** covers elements related to the appropriateness of the building design.
- › **Street level** covers elements that contribute to the way the development interacts with the public domain at street level.

Reference to associated design principles

Context and purpose of the design element

Explanatory diagrams

Guidelines

Captions highlighting guidelines in practice

Typology indicator Applies to residential tower storages Applies to residential on ground floor
 All others (no indicator) Applies to all developments

Example photos

2 | UPPER HUTT CITY CENTRE DESIGN GUIDE

3 | USING THIS GUIDE AS A PART OF A RESOURCE CONSENT APPLICATION

The district plan contains a number of objectives and policies that will be relevant in the context of higher density residential, commercial and mixed-use development. This design guide is intended to assist with the consideration of whether a development is consistent with these objectives and policies. The design guide is also referred to as a Matter of Discretion within a number of District Plan rules.

Preparation of a Design Statement

Where this design guide is relevant to a resource consent application, it is expected that a Design Statement will be included within the resource consent application to explain how the proposal meets the principles and guidelines contained within the design guide.

The design guide aims to recognise that all development proposals will be unique and that only those guidelines that are relevant to the site, activity or development proposal should be applied. The Design Statement provides applicants with the opportunity to explain which guidelines are relevant to the proposal, and how they have been applied.

A Design Statement will include:

- » A description of the proposal;
- » An overarching statement that explains how the proposal meets the design principles outlined in the design guide;
- » A description of how the proposal meets each relevant design guideline;
- » Where the proposal does not meet a design guideline, a description of:
 - » the alternative approach taken;
 - » why this is appropriate; and
 - » how the alternative approach enables the proposal to meet the overarching design principles.

4 | DESIGN PRINCIPLES

How we design our buildings and the relationship they have with the street and public space within the Upper Hutt city centre has a considerable bearing on the way we live, work and meet. The following design principles have been developed to encourage high quality design that contributes to transforming the future character of the city centre and provides an attractive and comfortable environment for users, residents and visitors alike.

P

CREATE A FOCAL POINT FOR COMMUNITY

- » Promote the city centre as a vibrant economic destination of employment and retail activity
- » Provide quality civic spaces that enable a wide range of residents and visitors to participate in the city's activity

C

PROVIDE CONNECTIVITY AND ACCESS

- » Create an accessible city centre, utilising principles of universal design that cater to all age groups and degrees of mobility
- » Encourage multi-modal transport options that prioritise connectivity to the train station adjacent to the city centre
- » Enable efficient pedestrian connectivity within the City Centre Zone and to the local surroundings
- » Create a legible and identifiable network of streets and lanes with clear wayfinding

F

PREPARE FOR THE FUTURE

- » Enable buildings to be adapted to accommodate a diverse use over time
- » Design innovative buildings that use sustainable and passive building materials and that transform the future character of the city centre
- » Ensure building orientation enables appropriate access to sunlight and outlook while providing attractive indoor and outdoor spaces
- » Integrate new buildings into the existing environment as the city undergoes its transformative stages
- » Create a city centre that is resilient and able to positively respond to changing intensification and environmental conditions

W

BE WELCOMING AND COMFORTABLE

- » Encourage design that supports safe and inclusive streets and laneways
- » Celebrate the city's diverse cultural identity through public art and building design in the city centre
- » Design public spaces that are attractive and comfortable by responding to climatic conditions, and maximising sun access while providing shade and shelter from the wind and rain
- » Contribute to a quality street environment that considers the human scale and prioritises pedestrian movement

A

ACTIVATE THE STREET

- » Provide public and open spaces that are inviting to residents and visitors alike
- » Create interesting and attractive streetscapes which provide visual interest
- » Respond to a street hierarchy that rationalises different traffic flows through the city centre
- » Ensure street edges, including associated building frontages and footpaths, are activated and encourage social interaction
- » Use setbacks and street edges to define open spaces



[This matrix identifies the key relationships and interactions between the Design Principles and the Design Elements in the Guide.](#)

DESIGN PRINCIPLES	FOCAL POINT FOR COMMUNITY P	CONNECTIVITY AND ACCESS C	PREPARE FOR THE FUTURE F	WELCOMING AND COMFORTABLE W	ACTIVATE THE STREET A
SITE LAYOUT					
Siting and alignment		■	■	■	■
Connectivity	■	■	■	■	■
Car parking, storage and servicing		■	■		■
Balconies			■	■	■
BUILT FORM & APPEARANCE					
Bulk and form			■	■	■
Visual interest / Façade modulation	■			■	■
Building design and materials	■		■		
Building top design			■	■	
Privacy, daylight and outlook			■	■	
Wind and sunlight	■		■	■	■
STREET LEVEL					
Street frontage	■		■	■	■
Public open space	■	■	■	■	■
Access and entrances		■		■	■
Landscape treatment		■		■	■

5 DESIGN ELEMENTS

5.1 SITE LAYOUT



PHOTO 1 - BUILDINGS TO STREET EDGE WITH CLEARLY DELINEATED MID-BLOCK CONNECTIONS, WEST END CHRISTCHURCH



DIAGRAM 1 - CREATE ACTIVE EDGES ALONG STREETS AND (NEW) MID-BLOCK CONNECTIONS TO ENCOURAGE VIBRANCY AND SAFETY




DIAGRAM 2 - A SETBACK CAN BE USED AS GATHERING SPACE IN FRONT OF THE ENTRANCE WHERE APPLICABLE (E.G. BUILDINGS WITH A CIVIC PURPOSE)

C F W A

Siting and alignment

The configuration of a building on a site and its relationship to the street and adjoining public space are important considerations to ensure good amenity. Having a defined front and back, as well as a clear delineation between public, semi-public and private spaces contributes to the legibility of the site and street.

An active frontage of a building also contributes to a socially active and safe environment and provides amenity for visitors and residents.

1. Consider the placement, orientation and form of the building to ensure it fits within the general pattern and network of the City Centre Zone and contributes to the legibility, permeability and functionality of the wider block structure.
2. Buildings should align with, and be orientated towards, any street, footpath or public space and contribute to the general continuity of frontage along the street.
3. The appearance of the ground floor should reinforce the relationship between the building with the street and pedestrian network. The façade should be visually interesting, preferably with a transparent appearance and contribute to encouraging activity along the street edge.
4. Use setbacks to create open space where applicable, particularly adjacent to buildings that perform a civic purpose (e.g. museums, educational facilities, libraries, community halls etc).
5. Open space should only be provided where it serves a clear public purpose to ensure that spaces contribute to the centre's environment in a positive way.



PHOTO 2 - MID-BLOCK CONNECTION WITH ACTIVE FRONTAGES, CHRISTCHURCH




DIAGRAM 3 - ENABLE MID-BLOCK LINKS TO CONNECT WITH THE WIDER TRAFFIC AND OPEN SPACE NETWORK




DIAGRAM 4 - PEDESTRIAN CONNECTIONS CAN CONNECT THE SHOPPING STREET WITH ADJACENT (PARKING) AREAS

P C W A

Connectivity

A connected network can reduce travel times and contribute to attractive, safe and legible environments that cater for people of all ages and mobilities.

Considering a good pedestrian and cycling experience in the design process can help to create safe, attractive and healthy communities.

Circulation networks should be legible and provide a safe environment for pedestrians and cyclists alike.

6. Extend and enhance existing pedestrian connections such as Centre Walk, and create new mid-block links where they enhance the connection with the wider pedestrian and open space network.
7. Reduce the scale of blocks where possible by providing new streets, mid-block connections, footpaths, courtyards, and plazas that connect with neighbouring streets and public or common open space areas.
8. Where appropriate, along identified frontages activate the frontages on mid-block connections with entrances and display windows to create safe and comfortable pedestrian environments.
9. Locate bicycle parking close to building entrances and open space at grade, especially when combined with amenities like bike repair/sales or other complementary commercial activities. Promoting cycle use reduces the need for vehicle parking, and promotes active street life.
10. Ensure that developments allow for sufficient space and seating around transit stops to encourage the use of public transport.



DIAGRAM 6 - CREATE ACTIVE EDGES ALONG STREETS AND (NEW) MID-BLOCK CONNECTIONS TO ENCOURAGE VIBRANCY AND SAFETY



PHOTO 1 - CAR PARKING INTEGRATED INTO THE LANDSCAPE DESIGN OF THE PUBLIC REALM WEST END CHRISTCHURCH




DIAGRAM 5 - SERVICE AND DELIVERY AREAS FOR MIXED USE PREFERABLY LOCATED AWAY FROM PEOPLE ORIENTED AREAS

Car parking, storage and servicing

Integrating car parking, storage, waste and service areas into the overall site design can have a beneficial effect on the amenity and quality of a development. Considering how waste is managed, stored and collected, as well as the location of storage and service areas, including areas that are dedicated to loading and unloading, can help to minimise visible clutter and result in higher levels of amenity and improved impressions of an area.

Considering alternative modes of transport and maximising opportunities for cyclists (e.g. cycle parking) can help ease pressure on car parking.

11. If on street parking is provided, care should be taken to ensure it does not conflict with active mode infrastructure (e.g. walking, cycling). On street parking or larger centralised off-street parking areas reduce the number of footpath crossings, increase pedestrian safety, and enable available parking space to be flexibly used by a variety of users.
12. On site parking for high density or mixed use development is encouraged to be below grade or positioned away from the street frontage (e.g. to be accessed by service lanes such as Bradley Lane). Any parking provided above grade should be screened from the street or public open space by evergreen planting.
13. Outdoor centralised parking should be landscaped to provide amenity, and be designed to offer safe and comfortable pedestrian access.
14. Car parking and loading or service areas should not impede access to adjacent buildings or compromise the quality and continuity of the street edge.
15. Integrate waste and storage areas into the building design and ensure that they are of a sufficient size relative to the number of units serviced. Waste areas should be able to accommodate all waste bins and have a clear connection to the collection area.
16. Delivery and rubbish collection areas should preferably be located at the rear or side of the building and away from pedestrian environments or residential activities.
17. Where loading docks or similar utilitarian built features are required, consider making provision for them to be adapted for alternative purposes (e.g. for seating or events, or as outdoor workspace).




DIAGRAM 7 - OUTLOOK FROM BALCONIES CAN PROVIDE PASSIVE SURVEILLANCE AND INCREASE SAFETY ON THE STREET



PHOTO 6 - STRATEGICALLY INTEGRATING BALCONIES INTO THE DESIGN CAN ENHANCE THE SENSE OF PRIVACY

E W A

Balconies

Higher densities often result in a reduction in the amount of outdoor space available to residents and other users, influencing the sense of privacy and level of individual amenity experienced.

Balconies and rooftops are an important consideration when designing intensive development and should be integrated into the design at an early stage in the design process.

Balconies also contribute to reducing the noticeable bulk effect of a building.

- 18. Consider using decks or balconies as outdoor living space where access to ground floor private open space is not possible. Taller developments are encouraged to consider use of the roof as communal outdoor open space, enabling increased access to available sunlight and views. Ⓢ
- 19. Balconies should offer privacy and weather protection to users, and be orientated to maximise sunlight access that enables a comfortable outdoor environment. c Ⓢ
- 20. Provide strategically placed screening where unit balconies adjoin to increase the sense of privacy. Ⓢ
- 21. Solid screening should be considered for larger balconies that can be used for the storage of cycles and/or large items. Ⓢ

5.2 BUILT FORM & APPEARANCE



PHOTO 8 - BULK OF THE BUILDINGS BROKEN DOWN BY A BOTTOM, MIDDLE AND TOP, CHRISTCHURCH.




DIAGRAM 8 - BUILDING MASS FOR TALL BUILDINGS BROKEN DOWN INTO A 'BASE,' 'MIDDLE,' 'TOP'



DIAGRAM 9 - VARIATION IN FACADE TREATMENT CAN VISUALLY BREAK DOWN BULK

F W A

Bulk and form

The development pattern in the Upper Hutt City Centre generally consists of narrow lots which, when redeveloped, are likely to encourage development with a predominantly vertically oriented built form. To reduce the bulk of tall buildings, an increased focus should be directed towards horizontally composed design with strong base - this will help to achieve a human scale at street level.

A building that relates to the Centre's fabric, to its immediate context, and adjacent human activity will help to unify the character of the area. The relationship between lower density areas and those with higher, large-scaled buildings can be more harmonious if the transition in building height and mass between these areas is intentionally managed in a sensitive manner.

22. Minimise the potential impact of building bulk by either reducing the floor area of upper levels or stepping them back from the street to maintain a human scale at ground level and increase the privacy of upper storey units.
23. Building mass can also be visually reduced by introducing variation in façade treatment (e.g. by balconies, shading devices or porches) or the effective use of landscaping.
24. Building mass and height should be designed to create visual interest and minimise physical dominance on public space.
25. Reduce the effect of building mass by visually breaking the form of the building up into a 'base', a 'middle' and a 'top'. This helps to create a pedestrian scale at street level and also reduces the extent of ground level wind turbulence.
26. Positively reinforce the shape of the street or public space with the building through designing it in a way that helps to define the street and frame views.



P W A

Visual interest and façade modulation

The main factors that influence the appearance of a building are scale, modulation and the articulation of its form and façade.

Façades composed of long expanses of monotonous surfaces create streetscapes that lack the sense of scale, visual interest, and character. Façades designed as three-dimensional ensembles create frontages that can be engaging and can enhance the experience of the pedestrian and road users.

Manipulation of light and shadow in the façade can make the scale of a building and its associated components appear more vivid.

Additionally, balconies and entrances provide visual interest by breaking up a façade and add a human scale to more intensive development - this positively contributes to the overall appearance of a building when designed well. Visible activity on the ground floor and street facing façade enhances public safety through passive surveillance and creates opportunities for social interaction.




DIAGRAM 10 - VIEWS OF ALL SIDES OF THE BUILDING NEED TO BE CONSIDERED

- 27. Avoid large expanses of undifferentiated blank surfaces. Relying solely on changes in colour or materials within the same plane rarely achieves sufficient levels of interest and articulation.
- 28. Where applicable, signage should be integrated into the overall design of the building and be of a size that is appropriate to the receiving environment and scale of the streetscape and building façade.
- 29. Consider views of the rear and side façades of the building, particularly where there is a transition to a lower density environment. The design of all visible façades should be given a similar degree of considerations as that applied to the primary façade.
- 30. Solid, blank walls facing any public open space, pedestrian pathways, residential or recreation zones should be avoided.
- 31. The design of building façades should respect neighbouring window and entrance patterns, including their type, proportions, scale, and frequency.



DIAGRAM 11 - VARIATION IN COLOURS, SCALE, PLACEMENT OF WINDOWS, ROOFLINES ETC CAN ENHANCE VISUAL INTEREST



PHOTO 7 - SIGNAGE SHOULD BE INTEGRATED AS PART OF A COHERENT DESIGN, HAWERA & PICTON

Building design and materials

P F

The building design and use of materials make an important contribution to the effective integration of intensive development into an existing environment.

The choice of materials used can affect the appearance of a development and how it contributes to the public realm. It can also affect how it performs and endures over time as well as its ongoing sustainability and resilience.

A visually attractive design can help to mitigate any potential adverse effects resulting from building height and/or bulk and enhance the city centre experience of visitors and residents alike.

32. The design of the building, as well as the choice of materials used, should recognise and reflect the level of intensification planned in the immediate and surrounding areas. In particular, consideration should be given to:
 - a. setback from the street / continuity along the street edge;
 - b. building age and style;
 - c. scale and bulk;
 - d. roofline;
 - e. placement of windows, entrances and other articulation in the façade.
33. Building features and elements should be integrated and considered as part of a single, coherent design. This includes elements such as façade modulation and articulation, with this also encompassing balconies and frequency of windows and doors. Variation of colour or materials in the same plane generally offers an insufficient means of adding visual interest.
34. Consider lighting and signage elements as an integral part of the design early in the design process. Lighting should reinforce pedestrian comfort at ground level but, in any residential context, should be designed to ensure neighbours are not disturbed.
35. Buildings should be designed to accommodate a range of uses and to enable change in use over time (e.g. by providing generous ceiling heights).
36. Use design opportunities to create distinctive points of identity along the street front to enhance wayfinding and promote the uniqueness of the Upper Hutt city centre.



PHOTO 8 - ROOF FORM INTEGRATED WITHIN THE DESIGN OF THE TOP STOREY, WELLINGTON




DIAGRAM 12 - REDUCE BULK BY ADDING VARIETY TO THE ROOFLINE

F W

Building top design

Viewed from the surrounding hills, the rooflines of the City Centre buildings are a highly visual element.

As the roofline of a building has a significant impact on its composition, when viewed across a number of buildings they collectively make a noticeable contribution to the variety and sense of identity of an area.

The shape that building roofs make with the sky can positively shape the city's skyline and reinforce the building's design intent. Roofs may also provide amenities such as common or private open space.

37. Consider integrating a varied roof form in the design of upper storeys as this can further reduce the bulk and visual impact of the building and provide a visually diverse building silhouette.
38. The roofline, as well as any rooftop maintenance systems and services spaces, should be integrated as part of a single, coherent design.
39. Encourage the use of roofs and walls to generate renewable energy (e.g. solar panels) and/or provide habitat-supportive vegetation.




PHOTO 9 - STAGGERED BALCONIES MAXIMISE PRIVACY WHILE RETAINING OUTLOOK AND SUNLIGHT ACCESS (WELLINGTON)

F W

Privacy, daylight and outlook

Adequate access to natural light is an important consideration in designing the layout of a site, particularly any opportunities to capitalise on a northern aspect.

It is also a key consideration in siting and designing the internal layout of buildings and any associated residential units as it not only provides a warm and pleasant internal living environment but helps to increase energy efficiency.

The orientation of dwellings and their interface with public and communal open space are important safety and privacy considerations. In designing for safety and privacy, adequate account needs to be taken of the relationship of new and adjoining buildings to ensure a successful balance is achieved between protecting private amenity and providing opportunities for passive surveillance.

40. Where privacy and overlooking is an issue, either high level windows or louvres should be considered to minimise direct views into sensitive areas. However, their use on façades that face the street or public areas should be minimised.
41. Where possible, orientate windows to public space to enable for passive surveillance.
42. Maintain privacy between upper storey units by screening upper level windows or balconies to limit opportunities for residents to directly overlook adjacent properties.
43. Consider incorporating a staggered façade profile into the building design to limit direct views into adjoining rooms or balconies.
44. Where residential units are provided on the ground floor, elevate dwelling floors, patios and decks slightly above the street level to provide privacy to residents while maintaining outlook onto the street.
45. Ensure living and working environments receive sufficient sunlight to connect people to the natural cycle of day and night and promote reduction in energy use.

U

U

C



P E W A

Wind and sunlight

Using natural resources like wind and sunlight can enhance the energy efficiency of a building and limits its impact on the environment through increased reliance on sustainable energy sources. This can also produce long term cost savings to occupants.

Integrating efficient passive design into a building contributes to a more comfortable indoor environment by increasing thermal stability and reducing indoor condensation.

While wind effects can be used for natural ventilation and energy generation, it can also potentially create downdrafts that can compromise the safety and comfort of the public realm.




DIAGRAM 13 - HIGH LEVEL WINDOWS, SKYLIGHTS AND/OR ATRIUMS CAN IMPROVE SUNLIGHT PENETRATIONS



PHOTO 10 - VERANDAH'S TO PROVIDE SHELTER, CHRISTCHURCH

- 46. Use solar exposure and local wind patterns to capitalise on natural forms of heating and ventilation and reduce the need for mechanical systems.
- 47. Consider the use of eaves or strategic screening to help limit the duration of sunlight penetration in summer, thus preventing indoor spaces (particularly those with a northern aspect) from overheating.
- 48. Design the mass of buildings to minimise shadow impacts on adjoining lower density residential areas, parks, and open space.
- 49. Modify tall buildings to minimise wind impacts at the street levels or provide strategic shelter as an integrated part of the design to mitigate any potential negative effects of downdraft at street level.

5.3 STREET LEVEL

P F W A

Street frontage

Buildings that provide an active and transparent interface between their interior uses and the street, public open space or laneway create an engaging and safe environment through natural surveillance. Visible ground floor retail combined with a variable street edge with setbacks and lobby entrances contribute to an attractive human scale street experience.




DIAGRAM 14 - GROUND FLOORS DESIGNED TO SUPPORT A HUMAN SCALE AT STREET LEVEL

- A Upper storeys are set back to reduce the perceived density on street level
- B Landscaping in between buildings increases an intimacy and creates a softer people oriented space



PHOTO 11 - PONSONBY, AUCKLAND



PHOTO 12 - PETONE, LOWER HUTT

DIFFERENCE IN TREATMENT OF GROUND LEVEL AND UPPER STOREYS IN RESPONSE TO PEDESTRIAN SCALE

50. Design all public building frontages to enable active and direct engagement with the street that supports pedestrian-oriented activity. Also consider the width of the footpath and the relationship between the anticipated use of the building and the footpath when designing the articulation of the street front.
51. Aim to activate the street frontage to the full width of the site; this will benefit optimal activation of the street edge and ground floor area.
52. The ground level treatment and appearance of the building should respond to the physical context at street level and positively contribute to the pedestrian experience.
53. Use lighting to enhance safety on the street frontage and incorporate these elements into the design process; when planting is a part of the design, minimise the risk of light sources becoming obscured by landscape elements, particularly around sensitive areas.
54. Where a forecourt or front setback is proposed ensure it is designed as an inviting spatial transitional element between the building frontage and the street environment.
55. Where residential activity is planned at ground level, provide an appropriate transition space between street and footpath to create an element of privacy (also refer Upper Hutt Residential Design Guide). Also minimise the height and opacity of front screens, fences, railings and gates to allow for natural surveillance.
56. Minimise frontages devoted to utilities, storage, services and parking access, and integrate with the overall articulation and fenestration of the façade. Where possible, locate rubbish areas below grade or to the rear of the building, and combine loading with vehicular access.

C





DIAGRAM 15 - HIGHLY VISIBLE AND ACCESSIBLE OPEN SPACE DUE TO ITS LOCATION AND DESIGN RESPONSE OF ADJACENT BUILDINGS



PHOTO 14 - SEATS AND LANDSCAPING CAN BE USED TO FRAME AND DEFINE ATTRACTIVE HUMAN-SCALE SPACES, CHRISTCHURCH



PHOTO 13 - ONLY PROVIDE LIGHTING IN OPEN SPACE WHERE NIGHT TIME ACTIVITY IS SAFE AND ACCEPTABLE, CHRISTCHURCH

P C F W A


Public open space

When integrated into the built environment, common open spaces, such as front setbacks, plazas, courtyards, and roof decks, enhance the quality of urban life.

Public open spaces are most welcoming when they act as an accessible extension of footpaths and adjacent buildings. Open space provides relief to the urban experience when thoughtfully incorporated with neighbouring uses.

Generally, the quality and design of an open space is more important than size.

- 57. Locate and orient open space to maximise direct solar exposure during parts of the day when the space is anticipated to be mostly used and to protect from the predominant wind direction.
- 58. Ensure that open space receives sufficient daylight throughout the day and that it is well connected, particularly in circumstances where it is the result of a building setback or recess.
- 59. Open space should be visible and accessible from the footpath for all users and support the ground floor use of the adjacent building wherever possible.
- 60. When designing outdoor public space, use design elements (e.g. shapes, patterns, structures) that are compatible with the design of adjacent buildings to create spaces that are unique and respond to their local context.
- 61. Provide seating and/or play elements that promote the activation of the space and cater for a variety of users (young and old).
- 62. Only provide lighting in public spaces that are intended to be used at night and that considered to be safe and secure after dark.
- 63. Use robust materials that are easy to maintain and retain their long term appearance. This is particularly important in public spaces that are prone to increased wear.



C W A

Access and entrances

The location, type and design of pedestrian and vehicle access points can have a significant bearing on the streetscape, site layout and building façade design.

The entrance to a building makes an important contribution to the way it is experienced. Entrances provide visual interest by breaking up a façade; they also add a human scale to more intensive developments and can positively contribute to the overall appearance of a building when designed well.

Visible activity on the ground floor and upper street façade levels enhances public safety through passive surveillance and creates opportunities for social interaction.



PHOTO 15 - DIFFERENCE IN ENTRANCE DESIGN BETWEEN RESIDENTIAL AND COMMERCIAL ACTIVITIES (PETONE, LOWER HUTT)




DIAGRAM 16 - ENTRY OR OPEN SPACE AT STREET ALIGNMENT

- 64. Ensure entrances are clearly defined and visible from the street to enable them to be easily located and accessed.
- 65. Entrances that serve high density developments should provide sufficient space for people to gather (e.g. small entry plaza) and include signage and landscape treatment that enhances the legibility of the entrance location. Indoor lobby spaces should have a clear visual and physical connection to the street.
- 66. Apply 'universal access' design standards to entrances of public buildings (e.g. consider entrance width and integration of ramps into the design). Wayfinding legibility can be improved by signalling doorways and access points (eg. by using colour signage themes).
- 67. Entry to any ground floor commercial activity should have a distinct appearance and be designed in a way that differentiates it from a residential unit entrance.
- 68. Mailboxes and other facilities used daily in a residential building should be placed in the lobby to increase internal pedestrian activity and reduce the potential for clutter in the public realm.
- 69. Entrances should be designed to provide all weather shelter (e.g. canopies or overhangs) with suitable lighting incorporated into the design. Verandahs should also be provided along active edges where possible.

⑩

⑩



PHOTO 16 - LANDSCAPE DESIGN IN AN OPEN SPACE SHOULD BE CONSIDERED AS AN INTEGRAL PART OF THE BUILDING DESIGN, CHRISTCHURCH



PHOTO 17 - LANDSCAPING CAN BREAK UP LARGE FORMS AND BRING VISUAL INTEREST TO THE STREET EDGE, CHRISTCHURCH



PHOTO 18 - LANDSCAPING CAN SOFTEN HARD SURFACES SUCH AS PARKING AREAS

C W A

Landscape treatment

Landscape design can greatly improve the amenity, experience and integration of more intensive forms of development into a street or neighbourhood. The implementation of carefully considered landscape design can help to enhance different design elements, such as the screening or softening of hardstanding areas (e.g. driveways, parking, service areas), mitigate the effects of building bulk and offer amenity and environmental benefits.

Coordinating landscaping early in the building and site design process can increase opportunities to more effectively integrate landscape treatment into outdoor open space, traffic circulation routes, service locations and the interface between the public and private domain.

70. Where possible, retain existing mature and healthy vegetation and integrate into the site development.
71. Use planting to improve the outlook from buildings and the street and to soften hard surface areas such as car parks or service areas.
72. Choose plants that are appropriate to the climatic conditions, scale and character of the area; planting species that require low maintenance and attract local bird life is also encouraged.
73. Deciduous trees provide shade in summer and light in winter, but careful consideration should be given to species selection in heavily shaded areas to ensure survivability.
74. Use of hard landscape elements such as low walls, kerbs or raised beds is encouraged as these can provide protection to plants and, where integrated into the site design, can add to the visual amenity of outdoor spaces.
75. Maximise opportunities for sustainable plantings and permeable surfaces in footpaths, roofs, courtyards, and rear yards. Also, decking and green/living roofs support a more visually compelling roof landscape and reduce air pollution, and the amount of water entering the stormwater system.

IPI - PROPOSED AMENDMENTS

#	Chapter	Change	Track Change
---	---------	--------	--------------

Appendix 3 – Precinct 2 – St Patrick's Estate Precinct Structure Plan

<p>New Appendix 3</p>	<p>Insert Structure Plan for St Patrick's Estate Precinct</p>	<p>Legend.</p> <ul style="list-style-type: none"> Property Boundary Megajot Boundary Landscaping / Gateway Treatment at Ferguson Drive Entrance Top of Bund Land Parcels <p>Road Hierarchy.</p> <ul style="list-style-type: none"> Internal Road Internal Road Including Active Transport Connection <p>Proposed Land Use Outcomes.</p> <p>ML-01 All activities provided for by the MLZ, and predominantly: - Retail, supermarket and large format related activities; - Commercial and office facilities; - Medical facilities, and/or - Residential</p> <p>ML-02 Predominantly the following activities: - Residential, and/or - Retirement village</p> <p>ML-03 and ML-04 Predominantly the following activities: - Residential, and/or - Retirement village, and/or - Small scale retail and non-residential activities</p> <p>Note: Secondary roading within megajots subject to final land use.</p> <p>St. Patrick's Estate Precinct. Structure Plan.</p> <p>Dw No: 1 Scale 1:2500 @A3</p>
---------------------------------------	---	---